# District I 1625 N. French Dr., Hobbs, NM 88240 District II 1301 W. Grand Avenue, Artesia, NM 88210 District III 1000 Rio Brazos Road, Aztec, NM 87410 District IV

# State of New Mexico Energy Minerals and Natural Resource EIVED

Form C-101 May 27, 2004

Oil Conservation Division SEP 1 6 2005 ubmit to appropriate District Office 1220 South St. Francis DrCCD-AFTERIA MENDED REPORT Santa Fe NM 87505

220 S. St. F	rancis Dr., Sa	nta Fe, NM	87505		Santa	Fe, NI	M 87505					
APP	LICATI	ON FO	R PERMIT	TO DRILL	., RE-E	ENTE	R, DEE	PEN,	PLUGBA	CK, OR A		ZONE
			•						14744			
			Mewbourne Oi Po Box : Hobbs, NM	5270 88240			30 - 015 - 34344					
Property Code Property							Name °Well No.					
<u> </u>	5104				Pecos Rive	r 11				<u> </u>	1	
(	Carlsk		Proposed Pool 1  Morrow		392				<sup>10</sup> Pro	posed Pool 2		
			, , , , , , , , , , , , , , , , , , ,	<sup>7</sup> S	urface I	Locati	ion					
L or lot no. J	Section 11	Township 22S	Range 27E	Lot Idn	Feet from 1415		North/South S	line	Feet from the 1980	East/West lin E	ne	County Eddy
			№8 Prop	osed Bottom H	ole Locat	tion If I	Different F	rom St	ırface			
or lot no.	Section	Township	Range	Lot Idin	Feet from	m the	North/South	line	Feet from the	East/West lir	ne	County
	<del></del>		<u> </u>	Additio	nal Wel	I Info	rmation	I	··· · · · · · · · · · · · · · · · · ·	<del></del> .		· · · · · ·
<sup>11</sup> Work	Type Code	$\neg$	12 Well Type Co	le	13 Cable/			14 L	ease Type Code	15		el Elevation
16.	N		G		R			P			3071'	
	fultiple	1	17 Proposed Dep 12200'	in	18 Form Morr			<sup>19</sup> Contractor TBA			<sup>20</sup> Spud Date ASAP	
pth to Grou				Distance from ne Less than 1000 f			vater well Distance from nearest surface water r wtr sources: 0 pts 1000' or more 0 pts			-		
	0 0 50		thick Clay	D': X/ 1 04000			D.'''- 1	6-4-1-T				
	Synthetic N		mick Clay []	Pit Volume:_24000	bbls		Drilling N				•	
Close	d-Loop Systen	<u> </u>	2	D					Diesel/Oil-based	Gas/Air		· · · · · · · · · · · · · · · · · · ·
				Proposed C	asing ar	na Cei	ment Pro	gram			· ·	
Hole			sing Size	Casing weight	t/foot	S	etting Depth		Sacks of Cement		Estimated TOC	
17 ½			3 3/8"	48#			400'		400			urface
12 ½			0 5/8"	40#			4500'		140	<del></del>	/	urface
8 3/	4"		5 ½"	17#			12200'		100	0	7500' abo	we Wolfcamp
escribe the leader of the lead	blowout prev n: 13 %" 2k #2A) from su	ention progr Hydril (see rface casing	ram, if any. Use a Exhibit #2) from to total depth. Re	to DEEPEN or PL dditional sheets if r surface casing to in otating head, PVT,	necessary. ntermediate flow monit	TD. Sci	haffer LWS mud gas Sep	or equiva	alent (Double-Ra	am Hydraulic)	11" 5000#	
id Progran	n: 0' to 400' 400' to 450 4500' to 98 9800' to TI	00' Brine 00' Fresh	Water and LCM Water, lime for 1	, lime for PH and I as needed for seepa PH and LCM as nee #/g, Caustic for PH	age. eded for see	epage.		CM as ne	G. Zo	AS AND Y	WATE	R BEARIN
	17 79			1	Г						-,, ·,	
				e and complete to t drilling pit will be		DE	<u></u> ₹/ 0	IL CC	NSERVA'	TION DIV	ISION	
nstructed	according to	NMOCD	guidelines X, a g	eneral permit 🗌		Approv	ed by:	10	Jem	W. A		w .
	ternative O	7	ed plan ∐.	nla				Les	fint-	IL S	Y	win
	: Kristi Gree	n / O	me of			Title:	^==				@ED	0 1 2000
Asac			oval, if duri	ng ———		Approv	val D <b>&amp;EP</b>	21	2005	Expiration Date	: <b>9</b>	2 1 2006
pit coi	nstruction				a conc	dition	of appi	oval,	<u>a</u> –			· · · · · · · · · · · · · · · · · · ·
			r seeps in p	its clo			ıust be s					
			OCD MUST		d appr	oved	prior to	the				
RF CO	<u>JNTAC</u>	ED IM	MEDIATE	Y! co	mmeno	cemer	at of clos	sure				

procedures.

DISTRICT I 1625 M. French Br., Hobbs, NM 88240 DISTRICT II 811 South Pirst, Artesia, NM 88210

1000 Rio Brazos Rd., Aztec, NM 87410 DISTRICT IV 2040 South Pacheco, Santa Pe, NM 87505

DISTRICT III

State of New Mexico Energy, Minerals and Natural Resources Department

FORM CTIVE Revised March 17, 1999 instruction on back Submit to Appropriate District Office State Lease - 4 Copies Pee Lease - 3 Copies

## OIL CONSERVATION DIVISION P.O. Box 2088

WELL LOCATION AND ACREAGE DEDICATION PLAT

☐ AMENDED REPORT

## Santa Fe, New Mexico 87504-2088

API Number	Pool Code		Pool Name
	73920	Carls Dad	norrow, East
Property Code	Pr	Weli Number	
	PECOS RIV	ER "11"	1
OGRID No.	Ор	erator Name	Elevation
14744	MEWBOURNE	OIL COMPANY	3071


## Surface Location

-	UL or lot No.	Section	Township	Range	Lot idn	Peet from the	North/South line	Feet from the	East/West line	County
	J	11	225	27E		1415	SOUTH	1980	EAST	EDDY

#### Bottom Hole Location If Different From Surface

ſ	UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
L										
Γ	Dedicated Acres	Joint of	r Insilii Co	nsolidation (	ode On	der No.				
ĺ	320		[		- [					

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION



660'

330'

## MULTI-POINT SURFACE USE AND OPERATIONS PLAN MEWBOURNE OIL COMPANY

Pecos River 11 #1 1415' FSL & 1980' FEL Section 11-T22S-R27E Eddy County, New Mexico

This plan is submitted with Form 3160-3, Application for Permit to Drill, Covering the above described well. The purpose of this plan is to describe the location of the proposed well, the proposed construction activities and operations plan, the magnitude of the surface disturbance involved, and the procedures to be followed in restoring the surface so that a complete appraisal can be made of the environmental impact associated with the proposed operations.

## 1. Existing Roads:

- A. Exhibit #3 is a road map showing the location of the proposed well. Exhibit #3A is a topographic map showing the location of the proposed well and access road. Existing roads are highlighted in red and proposed roads are highlighted in yellow.
- B. Directions to location from Carlsbad, NM: On Hwy 62/180 to just East of Carlsbad, turn right on US Refinery Rd (CR605) and go 3 miles to MOC lease road, continue 100' into new location.

## 2. Proposed Access Road:

- A No new road will be needed.
- B. The access to the location will be limited to 16' in width and will adequately drain runoff and control erosion as presently constructed.

## 3. Location of Existing and/or Proposed Facilities:

- A. There are no production facilities on this lease at the present time.
- B. In the event that the well is productive, production facilities will be located on the well pad.

## 4. Location and Type of Water Supply

The well will be drilled with a combination of fresh water and brine water based mud systems. The water will be obtained from commercial suppliers in the area and/or hauled to the location by transport trucks over existing and proposed roads as indicated in Exhibit #3.

#### 5. Source of Construction Materials

All material required for construction of the drill pad and access roads will be obtained from private, state, or federal pits. The construction contractor will be solely responsible for securing construction materials required for this operation and paying any royalties that may be required on those materials.

## 6. Methods of Handling Waste Disposal:

- A. Drill cuttings not retained for evaluation purposed will be disposed of in the reserve pit.
- B. Drilling fluids will be allowed to evaporate in the reserve pit prior to closure.
- C. Water produced during operations will be disposed of in the reserve pit.
- D. If any liquid hydrocarbons are produced during operations, those liquids will be stored in suitable tanks until sold.
- Current regulations regarding the proper disposal of human waste will be followed.
- F. All trash, junk, and other waste materials will be stored in proper containers to prevent dispersal and will be removed to an appropriate facility within one week of cessation of drilling and completion activities.

## 7. Ancillary Facilities

There are no ancillary facilities within the immediate vicinity of the proposed well site.

## 8. Well Site Layout

- A A diagram of the drill pad is shown in Exhibit #5. Dimensions of the pad, pits, and location of major rig components are shown.
- B. The reserve pit will be lined with a high quality plastic sheeting to prevent migration of fluids
- C. The pad dimension of 400' X 250' has been staked and flagged.

## 9. Plans for Restoration of Surface

- A. Upon cessation of the proposed operations, if the well is abandoned, the location and road will be ripped and re-seeded. The reserve pit area, after allowing to dry will be leveled. The entire location will be restored to the original contour as much as reasonable possible. All trash, garbage, and pit lining will be hauled to appropriate disposal to assure the location is aesthetically pleasing as reasonable possible. All restoration work will be completed within 180 days of cessation of activities.
- B. The disturbed area will be restored by re-seeding during the proper growing season.
- C. Three sides of the reserve pit will be fenced prior to and during drilling operations. The reserve pit will be fenced on the fourth side after the drilling rig is removed to prevent the endangerment of livestock. The fence will remain in place until the pit area has been leveled and restored.
- D. Upon cessation of the proposed operations, if the well is not abandoned, the reserve pit area will be restored as per OCD guidelines. Any additional caliche required for production facilities will be obtained from a source as described in Section 6.
- E. Within 90 days of cessation of drilling and completion operations, all equipment not necessary for production operations will be removed. The location will be cleaned of all trash and junk to assure the well site is left as aesthetically pleasing as reasonably possible.

MULTI-POINT SURFACE USE AND OPERATIONS PLAN MEWBOURNE OIL COMPANY Pecos River 11 #1 Page 3

## 10. Surface Ownership:

The surface is owned by:

Sammy D Clark 1617 Thomason Road Carlsbad, NM 88220 (505) 885-3280

#### 11. Other Information:

A. Topography: Refer to the archaeological report for a detailed description of flora, fauna,

soil characteristics, dwellings, and historical or cultural sites.

B. The primary use of the surface at the location is for grazing of livestock.

## 12. Operator's Representative:

A. Through APD approval, drilling, completion and production operations:

N.M. Young, District Manager Mewbourne Oil Company PO Box 5270 Hobbs, NM 88241 505-393-5905

#### 13. Certification

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access route; that I am familiar with the conditions which currently exist; that the statements made in this plan are to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed by Mewbourne Oil Company, its contractors and subcontractors, in accordance with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

Date: This green for NH Young Signature: 09/14/05\_\_\_\_

N.M. Young, District Manager Mewbourne Oil Company PO Box 5270 Hobbs, NM 88241 (505) 393-5905

## Hydrogen Sulfide Drilling Operations Plan

## Mewbourne Oil Company

Pecos River 11 #1 1415' FSL & 1980' FEL Section 11-T22S-R27E Eddy County, New Mexico

## 1. General Requirements

Rule 118 does not apply to this well because MOC has researched this area and no high concentrations of H2S were found. MOC will have on location and working all H2S safety equipment before the top of the Delaware 2108' for purposes of safety and insurance requirements.

## 2. Hydrogen Sulfide Training

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will have received training from a qualified instructor in the following areas prior to entering the drilling pad area of the well:

- 1. The hazards and characteristics of hydrogen sulfide gas.
- 2. The proper use of personal protective equipment and life support systems.
- 3. The proper use of hydrogen sulfide detectors, alarms, warning systems, briefing areas, evacuation procedures.
- 4. The proper techniques for first aid and rescue operations.

Additionally, supervisory personnel will be trained in the following areas:

- The effects of hydrogen sulfide on metal components. If high tensile tubular systems are utilized, supervisory personnel will be trained in their special maintenance requirements.
- 2 Corrective action and shut in procedures, blowout prevention, and well control procedures while drilling a well.
- 3 The contents of the Hydrogen Sulfide Drilling Operations Plan.

There will be an initial training session prior to encountering a know hydrogen sulfide source. The initial training session shall include a review of the site specific Hydrogen Sulfide Drilling Operations Plan.

## 3. Hydrogen Sulfide Safety Equipment and Systems

All hydrogen sulfide safety equipment and systems will be installed, tested, and operational prior to drilling below the intermediate casing.

## 1. Well Control Equipment

- A. Flare line with automatic igniter or continuous ignition source.
- B. Choke manifold with minimum of one adjustable choke.
- C. Blowout preventers equipped with blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit
- D. Auxiliary equipment including rotating head and annular type blowout preventer.

## 2. Protective Equipment for Essential Personnel

Thirty minute self contained work unit located at briefing area as indicated on wellsite diagram.

Hydrogen Sulfide Drilling Operations Plan Mewbourne Oil Company Pecos River 11 #1 Page 2

## 3. Hydrogen Sulfide Protection and Monitoring Equipment

Two portable hydrogen sulfide monitors positioned on location for optimum coverage and detection. The units shall have audible sirens to notify personnel when hydrogen sulfide levels exceed 20 ppm.

## 4. Visual Warning Systems

- A. Wind direction indicators as indicated on the wellsite diagram.
- B. Caution signs shall be posted on roads providing access to location. Signs shall be painted a high visibility color with lettering of sufficient size to be readable at reasonable distances from potentially contaminated areas.

## 4. Mud Program

The mud program has been designed to minimize the amount of hydrogen sulfide entrained in the mud system. Proper mud weight, safe drilling practices, and the use of hydrogen sulfide scavengers will minimize hazards while drilling the well.

## 5. Metallurgy

All tubular systems, wellheads, blowout preventers, drilling spools, kill lines, choke manifolds, and valves shall be suitable for service in a hydrogen sulfide environment when chemically treated.

#### 6. Communications

State & County Officials phone numbers are posted on rig floor and supervisors trailer. Communications in company vehicles and toolpushers are either two way radios or cellular phones.

## 7. Well Testing

Drill stem testing is not an anticipated requirement for evaluation of this well. A drill stem test is required, it will be conducted with a minimum number of personnel in the immediate vicinity. The test will be conducted during daylight hours only.


## Notes Regarding Blowout Preventer

**Mewbourne Oil Company** 

Pecos River 11 #1 1415' FSL & 1980' FEL Section 11-T22S-R27E Eddy County, New Mexico


- 1. Drilling nipple (bell nipple) to be constructed so that it can be removed without the use of a welder through the opening of the rotary table, with minimum internal diameter equal to blowout preventer bore.
- 2. Blowout preventer and all fittings must be in good condition with a minimum 5000 psi working pressure.
- 3. Safety valve must be available on the rig floor at all times with proper connections to install in the drill string. Valve must be full bore with minimum 5000 psi working pressure.
- 4. Equipment through which bit must pass shall be at least as large as internal diameter of the casing.
- 5. A kelly cock shall be installed on the kelly at all times.
- 6. Blowout preventer closing equipment to include and accumulator of at least 40 gallon capacity, two independent sources of pressure on closing unit, and meet all other API specifications.

## Mewbourne Oil Company **BOP Scematic for** 12 1/4" Hole




New Mexico

## Mewbourne Oil Company BOP Scematic for 8 3/4" or 7 7/8" Hole



Pecos River 11 #1 1415' FSL & 1980' FEL Sec 11-T22S-R27E Eddy, County New Mexico Continued on Page 12



SECTION 11, TOWNSHIP 22 SOUTH, RANGE 27 EAST, NMPM, EDDY COUNTY, NEW MEXICO.





Exhibit 3A

	1000'	0 Scale	1" = 1000	ooo.		<u>3</u> 000.
THE PREPARATION OF THIS PLAT AND THE PERFORMANCE OF THE SURVEY UPON WHICH IT IS BASED WERE DONE LINDER MY DIRECTION AND THE PLAT ACCURATELY DEPICTS THE BESULTS OF, SING SURVEY AND MEET THE REQUIREMENTS OF THE SAMBORDS FOR LAND SURVEYS IN NEW MEXICO AS	MEWBOU	IRNE	OIL	CO	MP	ANY
ADDITED BY THE NEW MENCE SHATT SOUND ON REGISTRATION FOR PROFESSIONAL ENGINEERS AND VANNUES BETT SOUND ON REGISTRATION FOR PROFESSIONAL ENGINEERS AND VANNUES BETT SOUND ON THE STATE OF THE SOUND OF THE STATE OF TH	"11" #1 WELL.	O ACCESS THE LOCATED IN SI 27 EAST, NMP	ECTION 11, T	OWNSHIP	22	
	Survey Date: 9/01/200	25	Sheet 1	of	1	Sheets
GENERAL SURVEXING COMPANY P.O. BOX 1928	Drawn By: Ed Blevins		W.O. Numb			
LOVINGTON, POFESSIONAL IN NEW MEXICO 88260	Date: 9/03/05		Scale 1" =	= 1000'	PECOS	RIVER

## Mewbourne Oil Company



Rig Location Schematic

## **Proposed Production Facilities Schematic**

