

Submit 1 Copy To Appropriate District Office
 District I - (575) 393-6161
 1625 N. French Dr., Hobbs, NM 88240
 District II - (575) 748-1283
 811 S. First St., Artesia, NM 88210
 District III - (505) 334-6178
 1000 Rio Brazos Rd., Aztec, NM 87410
 District IV - (505) 476-3460
 1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico
 Energy, Minerals and Natural Resources

Form C-103
 Revised August 1, 2011

OIL CONSERVATION DIVISION
 1220 South St. Francis Dr.
 Santa Fe, NM 87505

SUNDRY NOTICES AND REPORTS ON WELLS (DO NOT USE THIS FORM FOR PROPOSALS TO DRILL OR TO DEEPEN OR PLUG BACK TO A DIFFERENT RESERVOIR. USE "APPLICATION FOR PERMIT" (FORM C-101) FOR SUCH PROPOSALS.) 1. Type of Well: Oil Well <input checked="" type="checkbox"/> Gas Well <input type="checkbox"/> Other <input type="checkbox"/>		WELL API NO. 30-015-24423
2. Name of Operator Yates Petroleum Corporation		5. Indicate Type of Lease STATE <input type="checkbox"/> FEE <input checked="" type="checkbox"/>
3. Address of Operator 105 South Fourth Street, Artesia, NM 88210		6. State Oil & Gas Lease No.
4. Well Location Unit Letter <u>M</u> : <u>330</u> feet from the <u>South</u> line and <u>330</u> feet from the <u>West</u> line Section <u>13</u> Township <u>17S</u> Range <u>25E</u> NMPM <u>Eddy</u> County		7. Lease Name or Unit Agreement Name Jackson AT
11. Elevation (Show whether DR, RKB, RT, GR, etc.) 3465'GR		8. Well Number 17
9. OGRID Number 025575		10. Pool name or Wildcat Eagle Creek; San Andres

12. Check Appropriate Box to Indicate Nature of Notice, Report or Other Data

NOTICE OF INTENTION TO: PERFORM REMEDIAL WORK <input type="checkbox"/> PLUG AND ABANDON <input checked="" type="checkbox"/> TEMPORARILY ABANDON <input type="checkbox"/> CHANGE PLANS <input type="checkbox"/> PULL OR ALTER CASING <input type="checkbox"/> MULTIPLE COMPL <input type="checkbox"/> DOWNHOLE COMMINGLE <input type="checkbox"/> OTHER: <input type="checkbox"/>	SUBSEQUENT REPORT OF: REMEDIAL WORK <input type="checkbox"/> ALTERING CASING <input type="checkbox"/> COMMENCE DRILLING OPNS. <input type="checkbox"/> P AND A <input type="checkbox"/> CASING/CEMENT JOB <input type="checkbox"/> OTHER: <input type="checkbox"/>
--	---

13. Describe proposed or completed operations. (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work). SEE RULE 19.15.7.14 NMAC. For Multiple Completions: Attach wellbore diagram of proposed completion or recompletion.

Yates Petroleum Corporation plans to plug and abandon this well as follows:


- MIRU any safety equipment as needed. NU BOP. TOH with production equipment.
- RIH with bit and scraper to just below perfs at 1488' and circulate Class "C" cement to 500' with 115 sx. Note: If fill is tagged and you are unable to get across perfs then TOH and set a CIBP above perfs at 1230' before circulating cement to 500' (90 sx).
- Cut off wellhead and verify that there is cement behind all casing strings at surface. If so, cement to surface with 60 sx. If not then perforate and circulate cement to surface behind each casing string before cementing to surface inside production casing.
- Install dry hole marker and clean location.

Wellbore schematics attached

NOTE: Yates Petroleum Corporation will use steel pits and no earth pits

Spud Date:

Rig Release Date:



I hereby certify that the information above is true and complete to the best of my knowledge and belief.

SIGNATURE Tina Huerta TITLE Regulatory Reporting Supervisor DATE February 7, 2013

Type or print name Tina Huerta E-mail address: tinah@yatespetroleum.com PHONE: 575-748-4168


For State Use Only

APPROVED BY: J. R. Wade TITLE Dist. & Supervisor DATE 2/14/13

Conditions of Approval (if any): 90 days to P/A - Expires 5/14/13

Well Name: Jackson AT #17 Field: Eagle Creek
 Location: 330' FSL & 330' FWL Sec 13-17S-25E
 County: Eddy State: New Mexico
 GL: 3,465' Zero: KB:
 Spud Date: 3/8/1983 Completion Date: 3/27/1983
 Comments: API # 30015244230000

Casing Program	
Size/Wt/Grade	Depth Set
10 3/4" 40.5# K-55	342'
7" 23# K-55	1,200'
4 1/2" 9.5# K-55	1,490'




SKETCH NOT TO SCALE

DATE: 1/15/2013

Well Name: Jackson AT #17 Field: Eagle Creek
 Location: 330' FSL & 330' FWL Sec 13-17S-25E
 County: Eddy State: New Mexico
 GL: 3,465' Zero: KB:
 Spud Date: 3/8/1983 Completion Date: 3/27/1983
 Comments: API # 30015244230000

Casing Program	
Size/WVGrade	Depth Set
10 3/4" 40.5# K-55	342'
7" 23# K-55	1,200'
4 1/2" 9.5# K-55	1,490'



SKETCH NOT TO SCALE

DATE: 1/15/2013

NEW MEXICO OIL CONSERVATION DIVISION
DISTRICT 2 OFFICE
811 S. FIRST STREET
ARTESIA, NM 88210
(575)748-1283

CONDITIONS OF APPROVAL FOR PLUGGING & ABANDONMENT

Operator: Jates Pet.

Well Name & Number: Jackson AT #17

API #: 30-015-24423

1. Produced water **will not** be used during any part of the plugging & abandonment operation.
2. Notify NMOCD Dist. 2 office at least 24 hrs before beginning work.
3. Closed Loop System is to be used for entire plugging operation. Upon completion, contents of steel pit are to be hauled to a permitted disposal location.
4. Trucking companies being used to haul oilfield waste fluids to a disposal – commercial or private – shall have an approved NMOCD C-133 permit. A copy of this permit shall be available in each truck used to haul waste products. It is the responsibility of the operator, as well as the contractor, to verify that this permit is place prior to performing work. Drivers shall produce a copy upon request of NMOCD Field Inspectors.
5. A subsequent C-103 will serve as notification that the well bore has been plugged ONLY. A C-103 FINAL shall be filed before any bonding can be released on the well. Upon receipt of the Final, an inspection will be performed to verify that the location has been satisfactorily cleaned to NMOCD standards.
6. If work has not begun within 90 days of the approval of this procedure, an extension request must be filed, stating reason that well has not been plugged.
7. Every attempt must be made to clean the well bore out, to below the perms, before any plugs can be set, by whatever means possible.
8. **Cement Retainers may not be used.**

9. Squeeze pressures are not to exceed 500 PSI, unless approval is given by NMOCD.

10. Plugs may be combined after consulting with and getting approval from NMOCD.

11. Minimum WOC time for tag plugs will be 4 Hrs.

DATE: 02/20/2013

APPROVED BY: 