

UNORTHODOX LOCATION

ATS-13-1000

TOS
2-26-2014

Form 3160-3
(March 2012)

OCD Artesia

FORM APPROVED
OMB No. 1004-0137
Expires October 31, 2014

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

5. Lease Serial No. **LC063622**
NMNM0557729 SHL; NMLC063642-A **OH**

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		7. If Unit or CA Agreement, Name and No.
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		8. Lease Name and Well No. Rigel 20 Fed Com 8H 58797
2. Name of Operator Devon Energy Production Company, L.P.		9. API Well No. 30-015-42108
3a. Address 333 W. Sheridan Ave. Oklahoma City, OK 73102	3b. Phone No. (include area code) 405-235-3611	10. Field and Pool, or Exploratory Hackberry ; Bone Spring NW <29345>
4. Location of Well (Report location clearly and in accordance with any State requirements.)* At surface 635 FSL & 45 ^U FEL M PP: 870 FSL & 390 FEL SEC 20 At proposed prod. zone 400 FSL & 340 FWL M SEC 20		11. Sec., T. R. M. or Blk. and Survey or Area SEC 21 T19S R31E
14. Distance in miles and direction from nearest town or post office* 27 miles NE of Carlsbad, NM		12. County or Parish Eddy
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) See attached map		13. State NM
16. No. of acres in lease NMNM 0557729 320 ac NMLC063642-A 160 ac	17. Spacing Unit dedicated to this well NMNM0557729 SWSE. SESE 80 ac M.; C063642-A SWSW. SESW 80 ac	
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. See attached map	19. Proposed Depth 8050' TVD 12,940' MD	20. BLM/BIA Bond No. on file CO-1104; NMB-000801
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3487.4' GL	22. Approximate date work will start* 10/10/2013	23. Estimated duration 45 days

24. Attachments

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, must be attached to this form:

- | | |
|--|---|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be required by the BLM. |

25. Signature 	Name (Printed/Typed) Judy A. Barnett	Date 07/16/2013
---	---	--------------------

Title Sr. Regulatory Specialist

Approved by (Signature) /S/ STEPHEN J. CAFFEY	Name (Printed/Typed)	Date FEB 18 2014
--	----------------------	---------------------


Title FIELD MANAGER Office CARLSBAD FIELD OFFICE

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

APPROVAL FOR TWO YEARS

(Continued on page 2)



*(Instructions on page 2)

Capitan Controlled Water Basin

Approval Subject to General Requirements
& Special Stipulations Attached

**SEE ATTACHED FOR
CONDITIONS OF APPROVAL**


Certification

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access road proposed herein; that I am familiar with the conditions that presently exist; that I have full knowledge of State and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or Devon Energy Production Company, L.P. am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

I hereby also certify that I, or Devon Energy Production Company, L.P. have made a good faith effort to provide the surface owner with a copy of the Surface Use Plan of Operations and any Conditions of Approval that are attached to the APD.

Executed this 16th day of July, 2013.

Printed Name: Judy A. Barnett

Signed Name: 

Position Title: Sr. Regulatory Specialist

Address: 333 W. Sheridan, OKC OK 73102

Telephone: (405)-228-8699

Field Representative (if not above signatory):

Address (if different from above):

Telephone (if different from above):

District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720
District II
311 S. First St., Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720
District III
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-102
Revised August 1, 2011
Submit one copy to appropriate
District Office

AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

¹ API Number 30015-42108	² Pool Code 29345	³ Pool Name Hackberry; Bone Spring NW
⁴ Property Code 38797	⁵ Property Name RIGEL 20 FED COM	
⁷ OGRID No. 6137	⁸ Operator Name DEVON ENERGY PRODUCTION COMPANY, L.P.	⁶ Well Number 8H
		⁹ Elevation 3487.4

¹⁰ Surface Location

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
M	21	19 S	31 E		635	SOUTH	45	WEST	EDDY

¹¹ Bottom Hole Location If Different From Surface

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
M	20	19 S	31 E		400	SOUTH	340	WEST	EDDY

¹² Dedicated Acres 160	¹³ Joint or Infill	¹⁴ Consolidation Code	¹⁵ Order No.
---	-------------------------------	----------------------------------	-------------------------

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.

NOTE:
LATITUDE AND LONGITUDE COORDINATES ARE SHOWN USING THE NORTH AMERICAN DATUM OF 1983 (NAD83). LISTED NEW MEXICO STATE PLANE EAST COORDINATES ARE GRID (MADDS). BASIS OF BEARINGS AND DISTANCES USED ARE NEW MEXICO STATE PLANE EAST COORDINATES ADJUSTED TO THE SURFACE.

BOTTOM OF HOLE
LAT. = 32.6397309°N
LONG. = 103.8988655°W
NWSPE EAST (FT)
N = 598738.49
E = 675073.45

SURFACE LOCATION
LAT. = 32.6386573°N
LONG. = 103.8828175°W
NWSPE EAST (FT)
N = 596368.47
E = 680015.84

¹⁷ OPERATOR CERTIFICATION

I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

Signature: *Judy A. Barnett* Date: **7-10-13**

Judy A. Barnett, Regulatory Specialist

Printed Name
Judith.Barnett@dvn.com

E-mail Address

¹⁸ SURVEYOR CERTIFICATION

I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.

MAY 17, 2013

Date of Survey


Signature and Seal of Professional Surveyor: *[Signature]*

Certificate Number: **12797**

SURVEY NO. 1834

SECTION 21, TOWNSHIP 19 SOUTH, RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO
SITE MAP

NOTE: LATITUDE AND LONGITUDE COORDINATES ARE SHOWN USING THE NORTH AMERICAN DATUM OF 1983 (NAD83), LISTED NEW MEXICO STATE PLANE EAST COORDINATES ARE GRID (NAD83), BASIS OF BEARING AND DISTANCES USED ARE NEW MEXICO STATE PLANE EAST COORDINATES MODIFIED TO THE SURFACE



0 12 60 120 240

SCALE 1" = 120'

DIRECTIONS TO LOCATION
 FROM THE INTERSECTION OF CR 222 (SHUGART ROAD) AND CR 248 (LUSK PLANT ROAD) GO SOUTH ON CR 222 3.75 MILES TO CALICHE LEASE ROAD ON RIGHT, GO NORTH 0.75 MILES TO INTERSECTION, TAKE RIGHT GO EAST ALONG NORTH SIDE OF EXISTING PAD 0.45 MILES, ROAD ENDS AT EXISTING TANDEM ENERGY PAD. SITE LIES ABOUT 400 FT. NORTHWEST.


DEVON ENERGY PRODUCTION COMPANY, L.P.
RIGEL "20" FED COM #8H
 LOCATED 635 FT. FROM THE SOUTH LINE
 AND 45 FT. FROM THE WEST LINE OF
 SECTION 21, TOWNSHIP 19 SOUTH,
 RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO

NOVEMBER 5, 2013

SURVEY NO. 1834A

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO

SECTION 21, TOWNSHIP 19 SOUTH, RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO
 LOCATION VERIFICATION MAP



USGS QUAD MAP:
 HACKBERRY LAKE

NOT TO SCALE


DEVON ENERGY PRODUCTION COMPANY, L.P.
RIGEL "20" FED COM #8H
 LOCATED 635 FT. FROM THE SOUTH LINE
 AND 45 FT. FROM THE WEST LINE OF
 SECTION 21, TOWNSHIP 19 SOUTH,
 RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO

MAY 17, 2013

SURVEY NO. 1834

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
 (575) 234-3341

SECTION 21, TOWNSHIP 19 SOUTH, RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO
 VICINITY MAP



NOT TO SCALE

DEVON ENERGY PRODUCTION COMPANY, L.P.
RIGEL "20" FED COM #8H
 LOCATED 635 FT. FROM THE SOUTH LINE
 AND 45 FT. FROM THE WEST LINE OF
 SECTION 21, TOWNSHIP 19 SOUTH,
 RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO


DIRECTIONS TO LOCATION
 FROM THE INTERSECTION OF CR 222 (SHUGART ROAD) AND CR 248
 (LUSK PLANT ROAD) GO SOUTH ON CR 222 3.75 MILES TO CALICHE
 LEASE ROAD ON RIGHT. GO NORTH 0.75 MILES TO INTERSECTION,
 TAKE RIGHT GO EAST ALONG NORTH SIDE OF EXISTING PAD 0.45
 MILES. ROAD ENDS AT EXISTING TANDEM ENERGY PAD. SITE LIES
 ABOUT 400 FT. NORTHWEST.

MAY 17, 2013

SURVEY NO. 1834

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO

SECTION 21, TOWNSHIP 19 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
AERIAL PHOTO



NOT TO SCALE
AERIAL PHOTO:
GOOGLE EARTH
MARCH 2012

DEVON ENERGY PRODUCTION COMPANY, L.P.

RIGEL "20" FED COM #8H

LOCATED 635 FT. FROM THE SOUTH LINE

AND 45 FT. FROM THE WEST LINE OF

SECTION 21, TOWNSHIP 19 SOUTH,

RANGE 31 EAST, N.M.P.M.

EDDY COUNTY, STATE OF NEW MEXICO

MAY 17, 2013

SURVEY NO. 1834

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
(575) 234-3341

DRILLING PROGRAM

Devon Energy Production Company, LP

Rigel 20 Fed Com 8H

Surface Location: 635 FSL & 45 FWL, Unit M, Sec 21 T19S R31E, Eddy, NM

Bottom hole Location: 400 FSL & 340' FWL, Unit M, Sec 20 T19S R31E, Eddy, NM

1. Geologic Name of Surface Formation

a. Quaternarium Alluvium

2. Estimated Tops of Geological Markers & Depths of Anticipated Fresh Water, Oil or Gas:

a. Fresh Water	120'	water
b. Rustler Anhydrite	390'	Barren
c. Salt	655'	Barren
d. B/Salt	1955'	Barren
e. Yates	2095'	Oil
f. Seven Rivers	2315'	Oil
g. Capitan	2415'	Brine Water
h. Base Capitan	3810'	Brine Water
i. Delaware	4410'	Oil/Gas
j. Bone Spring	6700'	Oil/Gas
k. 2 nd Bone Spring Lm	8300'	Oil/Gas
Total Depth	12,940'	

Casing Program: All casing is new and API approved.

3.

<u>Hole Size</u>	<u>Hole Interval</u>	<u>OD Csg</u>	<u>Casing Interval</u>	<u>Weight</u>	<u>Collar</u>	<u>Grade</u>
26"	0 -440	20"	0-440	94#	BTC	J/K-55
17 1/2"	0' -2395	13 3/8"	0'-2395	68#	BTC	J/K-55
12 1/4"	0'-4100	9 5/8"	0-4100	40#	LTC	J-55
8 3/4"	4100'-7550	5 1/2"	0-7550	17#	LTC	HCP110
8 3/4"	7550-12940	5 1/2"	7550-12940	17#	BTC	HCP110

Design Parameter Factors:

<u>Casing Size</u>	<u>Collapse Design Factor</u>	<u>Burst Design Factor</u>	<u>Tension Design Factor</u>
20"	2.37	9.61	33.90
13 3/8"	1.54	2.72	7.00
9 5/8"	1.34	2.06	3.17
5 1/2" LTC	2.43	3.01	2.02
5 1/2" BTC	2.28	2.82	6.20

4. Cement Program:

String	Slurry	Amount and Type of Cement
Surface	Lead	485 sacks Class C Cement + 1% bwoc Calcium Chloride + 0.125 lbs/sack Cello Flake + 4% bwoc Bentonite + 81.1% Fresh Water, 13.5 ppg, 1.73 cf/sk
	Tail	300 sacks Class C Cement + 2% bwoc Calcium Chloride + 0.125 lbs/sack Cello Flake + 56.3% Fresh Water, 14.8 ppg, 1.35 cf/sk
13-3/8" Intermediate	Lead	1350 sacks (60:40) Poz (Fly Ash):Class C Cement + 5% bwow Sodium Chloride + 0.1% bwoc R-3 + 0.125 lbs/sack Cello Flake + 3 lbs/sack LCM-1 + 0.25% bwoc FL-52 + 1% bwoc Sodium Metasilicate + 83.4% Fresh Water, 12.8 ppg, 1.65 cf/sk
	Tail	450 sacks (60:40) Poz (Fly Ash):Class C Cement + 5% bwow Sodium Chloride + 0.125 lbs/sack Cello Flake + 0.5% bwoc Sodium Metasilicate + 0.5% bwoc BA-10A + 4% bwoc MPA-5 + 65.3% Fresh Water, 13.8 ppg, 1.38 cf/sk
<p><i>Self COA</i></p> <p>9-5/8" Intermediate</p>	1st STAGE	
	Lead	460 sacks (60:40) Poz (Fly Ash):Class C Cement + 5% bwow Sodium Chloride + 0.2% bwoc R-3 + 0.125 lbs/sack Cello Flake + 3 lbs/sack LCM-1 + 0.25% bwoc FL-52 + 1% bwoc Sodium Metasilicate + 89.6% Fresh Water, 12.6 ppg, 1.73 cf/sk
	Tail	300 sacks (60:40) Poz (Fly Ash):Class C Cement + 5% bwow Sodium Chloride + 0.125 lbs/sack Cello Flake + 0.5% bwoc Sodium Metasilicate + 0.5% bwoc BA-10A + 4% bwoc MPA-5 + 65.3% Fresh Water, 13.8 ppg, 1.38 cf/sk
	2nd STAGE (DV tool and ECP at 2,445 ft)	
	Lead	385 sacks (60:40) Poz (Fly Ash):Class C Cement + 5% bwow Sodium Chloride + 0.1% bwoc R-3 + 0.125 lbs/sack Cello Flake + 3 lbs/sack LCM-1 + 0.25% bwoc FL-52 + 1% bwoc Sodium Metasilicate + 83.4% Fresh Water, 12.8 ppg, 1.65 cf/sk
	Tail	150 sacks (60:40) Poz (Fly Ash):Class C Cement + 5% bwow Sodium Chloride + 0.125 lbs/sack Cello Flake + 0.5% bwoc Sodium Metasilicate + 0.5% bwoc BA-10A + 4% bwoc MPA-5 + 65.3% Fresh Water, 13.8 ppg, 1.38 cf/sk
	<p><i>Self COA</i></p> <p>Production</p>	Lead
Tail		1530 sacks (50:50) Poz (Fly Ash):Class H Cement + 5% bwow Sodium Chloride + 0.3% bwoc CD-32 + 0.5% bwoc FL-25 + 0.6% bwoc Sodium Metasilicate + 0.4% bwoc FL-52A + 57.3% Fresh Water, 14.2 ppg, 1.28 cf/sk
2nd STAGE (DV tool and ECP at 5,000 ft)		
Lead		250 sacks Class C Cement + 1% bwoc R-3 + 0.125 lbs/sack Cello Flake + 3% bwoc Sodium Metasilicate + 157% Fresh Water, 11.40 ppg, 2.88 cf/sk
Tail		150 sacks (60:40) Poz (Fly Ash):Class C Cement + 5% bwow Sodium Chloride + 0.125 lbs/sack Cello Flake + 0.1% bwoc Sodium Metasilicate + 4% bwoc MPA-5 + 65.4% Fresh Water, 13.80 ppg, 1.37 cf/sk

String	TOC
20" Surface	Surface
13-3/8" Intermediate	Surface
9-5/8" Intermediate	Surface
5-1/2" Production	2,350' (~65' above top of Capitan Reef)

The above cement volumes are based on 25% excess. Actual cement volumes could be adjusted based on fluid caliper and caliper log data.

5. Pressure Control Equipment:

The BOP system used to drill the 17-1/2" hole will consist of a 20" 2M Annular preventer. The BOP system will be tested as per BLM Onshore Oil and Gas Order 2 as a 2M system prior to drilling out the casing shoe.

A 3M 13-5/8" BOP system (Double Ram and Annular preventer) will be installed and tested prior to drilling out the surface casing shoe. The BOP system used to drill the intermediate hole will be tested per BLM Onshore Oil and Gas Order 2.

A 3M 13-5/8" BOP system (Double Ram and Annular preventer) will be installed and tested prior to drilling out the intermediate casing shoe. The BOP system used to drill the production hole will be tested per BLM Onshore Oil and Gas Order 2.

The pipe rams will be operated and checked each 24 hour period and each time the drill pipe is out of the hole. These tests will be logged in the daily driller's log. A 2" kill line and 3" choke line will be incorporated into the drilling spool below the ram BOP. In addition to the rams and annular preventer, additional BOP accessories include a kelly cock, floor safety valve, choke lines, and choke manifold rated at 3,000 psi WP.

*Sell
COA*

Devon requests a variance to use a flexible line with flanged ends between the BOP and the choke manifold (choke line); if an H&P rig drills this well. Otherwise no flex line is needed. The line will be kept as straight as possible with minimal turns.

6. Proposed Mud Circulation System

Depth Range	Mud Weight	Viscosity	Fluid Loss	Type System
0 - 440	8.4 - 9.0	28-34	NC	Fresh Water
440 - 2395	9.8 - 10	28-32	NC	Brine
2395 - 4100	8.4 - 9.0	28-32	NC	Fresh Water
4100 - 12940	8.4 - 9.0	28-32	NC-12	Fresh Water

The necessary mud products for weight addition and fluid loss control will be on location at all times. Visual mud monitoring equipment will be in place to detect volume changes indicating loss or gain of circulating fluid volume. If abnormal pressures are encountered, electronic/mechanical mud monitoring equipment will be installed.

7. Auxiliary Well Control and Monitoring Equipment:

- SM
CSA
- a. A Kelly cock will be in the drill string at all times.
 - b. A full opening drill pipe stabbing valve having the appropriate connections will be on the rig floor at all times.
 - c. Hydrogen Sulfide detection equipment will be in operation after drilling out the surface casing shoe until the 5 1/2" casing is cemented. Breathing equipment will be on location upon drilling the surface shoe until total depth is reached.

8. Logging, Coring, and Testing Program:

- a. Drill stem tests will be based on geological sample shows.
- b. If a drill stem test is anticipated; a procedure, equipment to be used and safety measures will be provided via sundry notice to the BLM.
- c. The open hole electrical logging program will be:
 - i. Total Depth to Intermediate Casing Dual Laterolog-Micro Laterolog with SP and Gamma Ray. Compensated Neutron – Z Density log with Gamma Ray and Caliper.
 - ii. Total Depth to Surface Compensated Neutron with Gamma Ray
 - iii. No coring program is planned
 - iv. Additional testing will be initiated subsequent to setting the 5 1/2" production casing. Specific intervals will be targeted based on log evaluation, geological sample shows and drill stem tests.

9. Potential Hazards:

No abnormal pressures or temperatures are expected. There is no known presence of H2S in this area. If H2S is encountered the operator will comply with the provisions of Onshore Oil and Gas Order No. 6. All personnel will be familiar with all aspects of safe operation of equipment being used to drill this well. Estimated BHP 3462 psi and Estimated BHT 129°. No H2S is anticipated to be encountered.

10. Anticipated Starting Date and Duration of Operations:

- a. Road and location construction will begin after the BLM has approved the APD. Anticipated spud date will be as soon after BLM approval and as soon as a rig will be available. Move in operations and drilling is expected to take 32 days. If production casing is run then an additional 30 days will be needed to complete well and construct surface facilities and/or lay flow lines in order to place well on production.



Weatherford®

Drilling Services

Proposal



devon

RIGEL 20 FED COM 8H

EDDY COUNTY, NM

WELL FILE: PLAN 1

JULY 9, 2013

Weatherford International, Ltd.

P.O. Box 61028
Midland, TX 79711 USA
+1.432.561.8892 Main
+1.432.561.8895 Fax
www.weatherford.com



Weatherford

Wft Plan Report X Y's.



Company: Devon Energy	Date: 7/9/2013	Time: 12:11:23	Page: 1
Field: Eddy Co. NM (NAD:83)	Co-ordinate(NE) Reference: Well: Rigel 20 Fed Com 8H	Grid: North	
Site: Rigel 20 Fed Com 8H	Vertical (TVD) Reference: SITE 3507.0		
Well: Rigel 20 Fed Com 8H	Section (VS) Reference: Well: (0:00N 0:00E 266.95Azi)		
Wellpath: 1	Survey Calculation Method: Minimum Curvature		Db: Sybase

Plan: Plan #1	Date Composed: 6/12/2013	Version: 1
Principal: Yes	Tied-to: From Surface	

Site: Rigel 20 Fed Com 8H

Site Position:	Northing: 597003.60 ft	Latitude: 32 38 25.437 N	
From: Map	Easting: 680056.48 ft	Longitude: 103 52 57.653 W	
Position Uncertainty: 0.00 ft		North Reference: Grid	
Ground Level: 3487.00 ft		Grid Convergence: 0.24 deg	

Well: Rigel 20 Fed Com 8H Slot Name:

Well Position: +N/-S 0.00 ft	Northing: 597003.60 ft	Latitude: 32 38 25.437 N	
+E/-W 0.00 ft	Easting: 680056.48 ft	Longitude: 103 52 57.653 W	
Position Uncertainty: 0.00 ft			

Wellpath: 1

Current Datum: SITE	Height 3507.00 ft	Drilled From: Surface	
Magnetic Data: 11/30/2013		Tie-on Depth: 0.00 ft	
Field Strength: 48612 nT		Above System Datum: Mean Sea Level	
Vertical Section: Depth From (TVD)		Declination: 7.46 deg	
ft	+N/-S ft	Mag Dip Angle: 60.46 deg	
		+E/-W ft	Direction deg
0.00	0.00	0.00	266.95

Plan Section Information

MD	Incl	Azim	TVD	+N/-S	+E/-W	DLS	Build	Turn	TFO	Target
ft	deg	deg	ft	ft	ft	deg/100ft	deg/100ft	deg/100ft	deg	
0.00	0.00	266.95	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
7676.39	0.00	266.95	7676.39	0.00	0.00	0.00	0.00	0.00	0.00	
8437.39	91.32	266.95	8153.73	-25.95	-487.77	12.00	12.00	0.00	266.95	
12940.20	91.32	266.95	8050.00	-265.11	-4983.03	0.00	0.00	0.00	0.00	PBHL

Survey

MD	Incl	Azim	TVD	N/S	E/W	VS	DLS	MapN	MapE	Comment
ft	deg	deg	ft	ft	ft	ft	deg/100ft	ft	ft	
7600.00	0.00	266.95	7600.00	0.00	0.00	0.00	0.00	597003.60	680056.48	
7676.39	0.00	266.95	7676.39	0.00	0.00	0.00	0.00	597003.60	680056.48	KOP
7700.00	2.83	266.95	7699.99	-0.03	-0.58	0.58	12.00	597003.57	680055.90	
7800.00	14.83	266.95	7798.62	-0.85	-15.89	15.91	12.00	597002.75	680040.59	
7900.00	26.83	266.95	7891.92	-2.73	-51.34	51.41	12.00	597000.87	680005.14	
8000.00	38.83	266.95	7975.79	-5.61	-105.38	105.53	12.00	596997.99	679951.10	
8100.00	50.83	266.95	8046.57	-9.35	-175.66	175.91	12.00	596994.25	679880.82	
8200.00	62.83	266.95	8101.18	-13.78	-259.10	259.46	12.00	596989.82	679797.38	
8300.00	74.83	266.95	8137.22	-18.73	-352.05	352.55	12.00	596984.87	679704.43	
8400.00	86.83	266.95	8153.13	-23.97	-450.45	451.09	12.00	596979.63	679606.03	
8437.39	91.32	266.95	8153.73	-25.95	-487.77	488.46	12.00	596977.65	679568.71	LP
8500.00	91.32	266.95	8152.29	-29.28	-550.28	551.06	0.00	596974.32	679506.20	
8600.00	91.32	266.95	8149.98	-34.59	-650.11	651.03	0.00	596969.01	679406.37	
8700.00	91.32	266.95	8147.68	-39.90	-749.94	751.00	0.00	596963.70	679306.54	
8800.00	91.32	266.95	8145.37	-45.21	-849.78	850.98	0.00	596958.39	679206.70	
8900.00	91.32	266.95	8143.07	-50.52	-949.61	950.95	0.00	596953.08	679106.87	
9000.00	91.32	266.95	8140.77	-55.83	-1049.44	1050.92	0.00	596947.77	679007.04	
9100.00	91.32	266.95	8138.46	-61.14	-1149.27	1150.90	0.00	596942.46	678907.21	
9200.00	91.32	266.95	8136.16	-66.46	-1249.11	1250.87	0.00	596937.14	678807.37	
9300.00	91.32	266.95	8133.86	-71.77	-1348.94	1350.85	0.00	596931.83	678707.54	
9400.00	91.32	266.95	8131.55	-77.08	-1448.77	1450.82	0.00	596926.52	678607.71	
9500.00	91.32	266.95	8129.25	-82.39	-1548.60	1550.79	0.00	596921.21	678507.88	
9600.00	91.32	266.95	8126.95	-87.70	-1648.43	1650.77	0.00	596915.90	678408.05	



Weatherford

Wft Plan Report X Y's.



Company: Devon Energy	Date: 7/9/2013	Time: 12:11:23	Page: 2
Field: Eddy Co. NM (NAD 83)	Co-ordinate(NE) Reference: Well: Rigel 20 Fed Com 8H	Grid North	
Site: Rigel 20 Fed Com 8H	Vertical (TVD) Reference: SITE 3507.0		
Well: Rigel 20 Fed Com 8H	Section (VS) Reference: Well (0:00N, 0:00E, 266.95Az)		
Wellpath:	Survey Calculation Method: Minimum Curvature	Db: Sybase	

Survey

MD ft	Incl deg	Azim deg	TVD ft	N/S ft	E/W ft	VS ft	DLS deg/100ft	MapN ft	MapE ft	Comment
9700.00	91.32	266.95	8124.64	-93.01	-1748.27	1750.74	0.00	596910.59	678308.21	
9800.00	91.32	266.95	8122.34	-98.32	-1848.10	1850.71	0.00	596905.28	678208.38	
9900.00	91.32	266.95	8120.03	-103.63	-1947.93	1950.69	0.00	596899.97	678108.55	
10000.00	91.32	266.95	8117.73	-108.95	-2047.76	2050.66	0.00	596894.65	678008.72	
10100.00	91.32	266.95	8115.43	-114.26	-2147.60	2150.63	0.00	596889.34	677908.88	
10200.00	91.32	266.95	8113.12	-119.57	-2247.43	2250.61	0.00	596884.03	677809.05	
10300.00	91.32	266.95	8110.82	-124.88	-2347.26	2350.58	0.00	596878.72	677709.22	
10400.00	91.32	266.95	8108.52	-130.19	-2447.09	2450.55	0.00	596873.41	677609.39	
10500.00	91.32	266.95	8106.21	-135.50	-2546.92	2550.53	0.00	596868.10	677509.56	
10600.00	91.32	266.95	8103.91	-140.81	-2646.76	2650.50	0.00	596862.79	677409.72	
10700.00	91.32	266.95	8101.61	-146.13	-2746.59	2750.47	0.00	596857.47	677309.89	
10800.00	91.32	266.95	8099.30	-151.44	-2846.42	2850.45	0.00	596852.16	677210.06	
10900.00	91.32	266.95	8097.00	-156.75	-2946.25	2950.42	0.00	596846.85	677110.23	
11000.00	91.32	266.95	8094.69	-162.06	-3046.09	3050.39	0.00	596841.54	677010.39	
11100.00	91.32	266.95	8092.39	-167.37	-3145.92	3150.37	0.00	596836.23	676910.56	
11200.00	91.32	266.95	8090.09	-172.68	-3245.75	3250.34	0.00	596830.92	676810.73	
11300.00	91.32	266.95	8087.78	-177.99	-3345.58	3350.31	0.00	596825.61	676710.90	
11400.00	91.32	266.95	8085.48	-183.30	-3445.42	3450.29	0.00	596820.30	676611.06	
11500.00	91.32	266.95	8083.18	-188.62	-3545.25	3550.26	0.00	596814.98	676511.23	
11600.00	91.32	266.95	8080.87	-193.93	-3645.08	3650.23	0.00	596809.67	676411.40	
11700.00	91.32	266.95	8078.57	-199.24	-3744.91	3750.21	0.00	596804.36	676311.57	
11800.00	91.32	266.95	8076.27	-204.55	-3844.74	3850.18	0.00	596799.05	676211.74	
11900.00	91.32	266.95	8073.96	-209.86	-3944.58	3950.16	0.00	596793.74	676111.90	
12000.00	91.32	266.95	8071.66	-215.17	-4044.41	4050.13	0.00	596788.43	676012.07	
12100.00	91.32	266.95	8069.36	-220.48	-4144.24	4150.10	0.00	596783.12	675912.24	
12200.00	91.32	266.95	8067.05	-225.80	-4244.07	4250.08	0.00	596777.80	675812.41	
12300.00	91.32	266.95	8064.75	-231.11	-4343.91	4350.05	0.00	596772.49	675712.57	
12400.00	91.32	266.95	8062.44	-236.42	-4443.74	4450.02	0.00	596767.18	675612.74	
12500.00	91.32	266.95	8060.14	-241.73	-4543.57	4550.00	0.00	596761.87	675512.91	
12600.00	91.32	266.95	8057.84	-247.04	-4643.40	4649.97	0.00	596756.56	675413.08	
12700.00	91.32	266.95	8055.53	-252.35	-4743.23	4749.94	0.00	596751.25	675313.25	
12800.00	91.32	266.95	8053.23	-257.66	-4843.07	4849.92	0.00	596745.94	675213.41	
12900.00	91.32	266.95	8050.93	-262.97	-4942.90	4949.89	0.00	596740.63	675113.58	
12940.20	91.32	266.95	8050.00	-265.11	-4983.03	4990.08	0.00	596738.49	675073.45	PBHL

Targets

Name	Description	TVD ft	N/S ft	E/W ft	Map Northing ft	Map Easting ft	Latitude Deg Min Sec	Longitude Deg Min Sec
PBHL		8050.00	-265.11	-4983.03	596738.49	675073.45	32 38 23.020 N	103 53 55.943 W
Tgt		8155.00	-22.90	-430.37	596980.70	679626.11	32 38 25.229 N	103 53 2.688 W

Casing Points

MD	TVD	Diameter	Hole Size	Name



Weatherford

Wft Plan Report X Y's.



Company: Devon Energy Date: 7/9/2013 Time: 12:11:23 Page: 3
Field: Eddy Co. NM (NAD 83) Co-ordinate(NE) Reference: Well: Rigel 20 Fed Com 8H Grid North
Site: Rigel 20 Fed Com 8H Vertical (TVD) Reference: SITE: 3507.0
Well: Rigel 20 Fed Com 8H Section (VS) Reference: Well: (0:00N,0.00E,266.95Azi)
Wellpath: 1 Survey Calculation Method: Minimum Curvature Db: Sybase

Formations

MD	TVD	Formations	Lithology	Dip Angle	Dip Direction

Annotation

MD ft	TVD ft	
7676.39	7676.39	KOP
8437.39	8153.73	LP
12940.19	8050.00	PBHL



Weatherford Anticollision Report



Company: Devon Energy Date: 7/9/2013 Time: 12:14:30 Page: 1
 Field: Eddy Co. NM (NAD 83)
 Reference Site: Rigel 20 Fed Com 8H Co-ordinate (NE) Reference Well: Rigel 20 Fed Com 8H Grid North
 Reference Well: Rigel 20 Fed Com 8H Vertical (TVD) Reference: SITE 3507.0
 Reference Wellpath: Db: Sybase

NO GLOBAL SCAN: Using user defined selection & scan criteria Reference: Plan: Plan #1
 Interpolation Method MD + Stations Interval: 100.00 ft Error Model: ISCWSA Ellipse
 Depth Range: 0.00 to 19369.32 ft Scan Method: Closest Approach 3D
 Maximum Radius 40000.00 ft Error Surface: Ellipse

Plan: Plan #1 Date Composed: 6/12/2013
 Principal: Yes Version: 1
 Tied-to: From Surface

Summary

Site	Offset Wellpath Well	Wellpath	Reference MD ft	Offset MD ft	Ctr-Ctr Distance ft	Edge Distance ft	Separation Factor	Warning
Rigel 20 Fed Com #4H		1 V0	12940.20	9590.03	1150.92	1063.00	13.09	
Rigel 20 Fed Com 7H	Rigel 20 Fed Com 7H	1 V0 Plan: Plan #1 V1	7676.39	7673.62	50.05	15.82	1.46	Level 3

Site: Rigel 20 Fed Com #4H
 Well: #4H
 Wellpath: 1 V0
 Inter-Site Error: 0.00 ft

Reference MD ft	TVD ft	Offset MD ft	TVD ft	Semi-Major Axis Ref ft	Offset TFO deg	Offset Location North ft	Offset Location East ft	Ctr-Ctr Distance ft	Edge Distance ft	Separation Factor	Warning
0.00	0.00	0.00	0.00	0.00	0.00	282.23	1084.49	-5003.07	5119.81		No Data
100.00	100.00	31.74	31.74	0.09	0.03	282.23	1084.53	-5003.04	5119.24	5119.12	42277.30
200.00	200.00	245.78	245.76	0.31	0.47	282.25	1085.85	-5000.49	5118.46	5117.67	6502.00
300.00	300.00	439.94	439.76	0.54	0.98	282.29	1087.56	-4992.97	5114.56	5113.04	3365.75
400.00	400.00	513.65	513.40	0.76	1.18	282.30	1088.18	-4989.86	5110.61	5108.68	2637.69
500.00	500.00	587.56	587.26	0.99	1.37	282.31	1088.69	-4987.16	5107.18	5104.82	2166.44
600.00	600.00	669.72	669.37	1.21	1.59	282.33	1089.17	-4984.54	5104.19	5101.39	1823.44
700.00	700.00	753.12	752.74	1.44	1.81	282.34	1089.58	-4982.17	5101.52	5098.28	1572.41
800.00	800.00	848.07	847.66	1.66	2.06	282.35	1089.96	-4979.77	5099.13	5095.41	1370.70
900.00	900.00	958.25	957.80	1.89	2.35	282.36	1090.33	-4976.86	5096.63	5092.39	1203.25
1000.00	1000.00	1093.93	1093.41	2.11	2.71	282.37	1090.79	-4972.75	5093.77	5088.95	1057.02
1100.00	1100.00	1240.33	1239.69	2.34	3.11	282.40	1091.88	-4966.87	5090.00	5084.57	936.95
1200.00	1200.00	1384.68	1383.85	2.56	3.49	282.43	1093.45	-4959.64	5085.34	5079.30	841.78
1300.00	1300.00	1491.93	1490.92	2.79	3.78	282.46	1094.86	-4953.63	5080.14	5073.59	775.39
1400.00	1400.00	1594.61	1593.43	3.01	4.06	282.49	1096.36	-4947.76	5074.88	5067.83	719.82
1500.00	1500.00	1685.30	1683.95	3.24	4.30	282.52	1097.87	-4942.59	5069.68	5062.16	674.45
1600.00	1600.00	1775.44	1773.94	3.46	4.54	282.55	1099.60	-4937.58	5064.66	5056.68	634.54
1700.00	1700.00	1846.41	1844.79	3.69	4.73	282.58	1101.05	-4933.84	5059.98	5051.59	602.74
1800.00	1800.00	1900.00	1898.32	3.91	4.88	282.60	1102.05	-4931.40	5056.01	5047.25	577.03
1900.00	1900.00	1975.36	1973.61	4.14	5.08	282.62	1103.27	-4928.55	5052.71	5043.52	550.04
2000.00	2000.00	2046.53	2044.75	4.36	5.26	282.63	1104.26	-4926.41	5050.08	5040.48	526.16
2100.00	2100.00	2121.87	2120.06	4.59	5.46	282.65	1105.24	-4924.55	5047.95	5037.93	503.79
2200.00	2200.00	2200.00	2198.17	4.81	5.66	282.66	1106.15	-4923.03	5046.30	5035.86	483.00
2300.00	2300.00	2290.41	2288.56	5.03	5.90	282.68	1107.05	-4921.60	5044.97	5034.06	462.51
2400.00	2400.00	2381.85	2379.99	5.26	6.14	282.69	1107.78	-4920.33	5043.79	5032.42	443.54
2500.00	2500.00	2481.41	2479.54	5.48	6.40	282.70	1108.28	-4919.13	5042.72	5030.87	425.25
2600.00	2600.00	2576.74	2574.86	5.71	6.65	282.70	1108.35	-4918.09	5041.68	5029.35	408.95
2700.00	2700.00	2677.01	2675.13	5.93	6.89	282.70	1108.11	-4917.14	5040.70	5027.91	393.93
2800.00	2800.00	2776.41	2774.52	6.16	7.11	282.70	1107.60	-4916.24	5039.71	5026.47	380.63
2900.00	2900.00	2882.84	2880.95	6.38	7.32	282.69	1106.75	-4915.31	5038.68	5025.00	368.30
3000.00	3000.00	2989.08	2987.17	6.61	7.52	282.68	1105.55	-4914.30	5037.50	5023.40	357.09
3100.00	3100.00	3089.50	3087.59	6.83	7.71	282.67	1104.19	-4913.32	5036.26	5021.74	346.93
3200.00	3200.00	3189.29	3187.36	7.06	7.90	282.65	1102.82	-4912.36	5035.02	5020.09	337.30
3300.00	3300.00	3289.36	3287.41	7.28	8.09	282.64	1101.45	-4911.40	5033.78	5018.43	328.06
3400.00	3400.00	3389.27	3387.31	7.51	8.29	282.63	1100.16	-4910.42	5032.54	5016.77	319.15
3500.00	3500.00	3498.50	3496.53	7.73	8.52	282.62	1098.86	-4909.23	5031.22	5014.99	310.08



Weatherford Anticollision Report



Company: Devon Energy	Date: 7/9/2013	Time: 12:14:30	Page: 2
Field: Eddy Co. NM (NAD 83)	Co-ordinate(NE) Reference: Well: Rigel 20 Fed Com 8H; Grid North		
Reference Site: Rigel 20 Fed Com 8H	Vertical (TVD) Reference: SITE 3507.0		
Reference Well: Rigel 20 Fed Com 8H	Db: Sybase		
Reference Wellpath:			

Site: Rigel 20 Fed Com #4H
 Well: #4H
 Wellpath: 1 V0

Inter-Site Error: 0.00 ft

Reference MD	TVD	Offset		Semi-Major Axis			Offset Location		Ctr-Ctr Edge Separation		Warning
		MD	TVD	Ref	Offset	TFO-HS	North	East	Distance	Distance	
ft	ft	ft	ft	ft	ft	deg	ft	ft	ft	ft	
3600.00	3600.00	3610.39	3608.40	7.96	8.78	282.61	1097.66	-4907.76	5029.70	5012.99	301.01
3700.00	3700.00	3756.29	3754.27	8.18	9.13	282.59	1095.90	-4904.99	5027.59	5010.30	290.80
3800.00	3800.00	3869.38	3867.31	8.41	9.41	282.58	1094.31	-4902.12	5024.79	5007.00	282.38
3900.00	3900.00	3968.40	3966.28	8.63	9.66	282.58	1092.96	-4899.56	5021.97	5003.70	274.90
4000.00	4000.00	4070.95	4068.79	8.86	9.92	282.57	1091.64	-4896.88	5019.14	5000.39	267.65
4100.00	4100.00	13807.00	8954.11	9.08	120.43	239.58	-222.69	-379.25	4948.69	4900.42	102.53
4200.00	4200.00	13807.00	8954.11	9.31	120.43	239.58	-222.69	-379.25	4849.10	4800.59	99.97
4300.00	4300.00	13807.00	8954.11	9.53	120.43	239.58	-222.69	-379.25	4749.52	4700.77	97.43
4400.00	4400.00	13807.00	8954.11	9.75	120.43	239.58	-222.69	-379.25	4649.96	4600.97	94.92
4500.00	4500.00	13807.00	8954.11	9.98	120.43	239.58	-222.69	-379.25	4550.41	4501.19	92.44
4600.00	4600.00	13807.00	8954.11	10.20	120.43	239.58	-222.69	-379.25	4450.89	4401.42	89.97
4700.00	4700.00	13807.00	8954.11	10.43	120.43	239.58	-222.69	-379.25	4351.39	4301.68	87.53
4800.00	4800.00	13807.00	8954.11	10.65	120.43	239.58	-222.69	-379.25	4251.92	4201.96	85.11
4900.00	4900.00	13807.00	8954.11	10.88	120.43	239.58	-222.69	-379.25	4152.47	4102.26	82.71
5000.00	5000.00	13807.00	8954.11	11.10	120.43	239.58	-222.69	-379.25	4053.04	4002.59	80.33
5100.00	5100.00	13807.00	8954.11	11.33	120.43	239.58	-222.69	-379.25	3953.65	3902.94	77.97
5200.00	5200.00	13807.00	8954.11	11.55	120.43	239.58	-222.69	-379.25	3854.28	3803.33	75.64
5300.00	5300.00	13807.00	8954.11	11.78	120.43	239.58	-222.69	-379.25	3754.95	3703.74	73.32
5400.00	5400.00	13807.00	8954.11	12.00	120.43	239.58	-222.69	-379.25	3655.66	3604.19	71.03
5500.00	5500.00	13807.00	8954.11	12.23	120.43	239.58	-222.69	-379.25	3556.41	3504.68	68.76
5600.00	5600.00	13807.00	8954.11	12.45	120.43	239.58	-222.69	-379.25	3457.20	3405.21	66.50
5700.00	5700.00	13807.00	8954.11	12.68	120.43	239.58	-222.69	-379.25	3358.03	3305.78	64.27
5800.00	5800.00	13807.00	8954.11	12.90	120.43	239.58	-222.69	-379.25	3258.92	3206.40	62.05
5900.00	5900.00	13807.00	8954.11	13.13	120.43	239.58	-222.69	-379.25	3159.87	3107.07	59.85
6000.00	6000.00	13807.00	8954.11	13.35	120.43	239.58	-222.69	-379.25	3060.87	3007.80	57.68
6100.00	6100.00	13807.00	8954.11	13.58	120.43	239.58	-222.69	-379.25	2961.94	2908.59	55.52
6200.00	6200.00	13807.00	8954.11	13.80	120.43	239.58	-222.69	-379.25	2863.09	2809.45	53.38
6300.00	6300.00	13807.00	8954.11	14.03	120.43	239.58	-222.69	-379.25	2764.32	2710.38	51.25
6400.00	6400.00	13807.00	8954.11	14.25	120.43	239.58	-222.69	-379.25	2665.64	2611.40	49.15
6500.00	6500.00	13807.00	8954.11	14.47	120.43	239.58	-222.69	-379.25	2567.06	2512.51	47.06
6600.00	6600.00	13807.00	8954.11	14.70	120.43	239.58	-222.69	-379.25	2468.60	2413.73	44.99
6700.00	6700.00	13807.00	8954.11	14.92	120.43	239.58	-222.69	-379.25	2370.27	2315.06	42.94
6800.00	6800.00	13807.00	8954.11	15.15	120.43	239.58	-222.69	-379.25	2272.08	2216.53	40.90
6900.00	6900.00	13807.00	8954.11	15.37	120.43	239.58	-222.69	-379.25	2174.06	2118.14	38.88
7000.00	7000.00	13807.00	8954.11	15.60	120.43	239.58	-222.69	-379.25	2076.22	2019.92	36.88
7100.00	7100.00	13807.00	8954.11	15.82	120.43	239.58	-222.69	-379.25	1978.61	1921.90	34.89
7200.00	7200.00	13807.00	8954.11	16.05	120.43	239.58	-222.69	-379.25	1881.24	1824.10	32.92
7300.00	7300.00	13807.00	8954.11	16.27	120.43	239.58	-222.69	-379.25	1784.16	1726.55	30.97
7400.00	7400.00	13807.00	8954.11	16.50	120.43	239.58	-222.69	-379.25	1687.43	1629.30	29.03
7500.00	7500.00	13807.00	8954.11	16.72	120.43	239.58	-222.69	-379.25	1591.10	1532.41	27.11
7600.00	7600.00	13807.00	8954.11	16.95	120.43	239.58	-222.69	-379.25	1495.25	1435.92	25.20
7676.39	7676.39	13807.00	8954.11	17.12	120.43	239.58	-222.69	-379.25	1422.42	1362.55	23.76
7700.00	7699.99	13807.00	8954.11	17.17	120.43	328.01	-222.69	-379.25	1399.83	1339.80	23.32
7725.00	7724.92	13807.00	8954.11	17.23	120.43	321.42	-222.69	-379.25	1375.65	1315.45	22.85
7750.00	7749.71	13807.00	8954.11	17.28	120.43	312.27	-222.69	-379.25	1351.26	1290.89	22.38
7775.00	7774.30	13807.00	8954.11	17.34	120.43	299.62	-222.69	-379.25	1326.70	1266.13	21.90
7800.00	7798.62	13807.00	8954.11	17.40	120.43	283.12	-222.69	-379.25	1302.05	1241.22	21.40
7825.00	7822.61	13807.00	8954.11	17.46	120.43	264.48	-222.69	-379.25	1277.37	1216.29	20.92
7850.00	7846.20	13807.00	8954.11	17.51	120.43	247.23	-222.69	-379.25	1252.71	1191.53	20.48
7875.00	7869.32	13807.00	8954.11	17.57	120.43	233.68	-222.69	-379.25	1228.16	1167.00	20.08
7900.00	7891.92	13807.00	8954.11	17.64	120.43	223.82	-222.69	-379.25	1203.79	1142.72	19.71



Weatherford Anticollision Report



Company: Devon Energy	Date: 7/9/2013	Time: 12:14:30	Page: 3
Field: Eddy Co.: NM (NAD 83)	Co-ordinate(NE) Reference: Well: Rigel 20 Fed.Com 8H Gnd.North		
Reference Site: Rigel 20 Fed.Com 8H	Vertical (TVD) Reference: SITE 3507.0		
Reference Well: Rigel 20 Fed.Com 8H	Db: Sybase		
Reference Wellpath:			

Site: Rigel 20 Fed Com #4H
 Well: #4H
 Wellpath: 1 V0

Inter-Site Error: 0.00 ft

Reference MD	TVD	Offset		Semi-Major Axis			Offset Location		Ctr-Ctr Edge Separation		Warning
		MD	TVD	Ref	Offset	TFO-HS	North	East	Distance	Distance	
ft	ft	ft	ft	ft	ft	deg	ft	ft	ft	ft	
7925.00	7913.92	13807.00	8954.11	17.70	120.43	216.74	-222.69	-379.25	1179.68	1118.73	19.35
7950.00	7935.27	13807.00	8954.11	17.77	120.43	211.58	-222.69	-379.25	1155.92	1095.11	19.01
7975.00	7955.91	13807.00	8954.11	17.85	120.43	207.72	-222.69	-379.25	1132.59	1071.93	18.67
8000.00	7975.79	13807.00	8954.11	17.93	120.43	204.76	-222.69	-379.25	1109.78	1049.29	18.35
8025.00	7994.84	13807.00	8954.11	18.02	120.43	202.45	-222.69	-379.25	1087.60	1027.29	18.03
8050.00	8013.02	13807.00	8954.11	18.12	120.43	200.60	-222.69	-379.25	1066.15	1006.02	17.73
8075.00	8030.28	13807.00	8954.11	18.24	120.43	199.11	-222.69	-379.25	1045.52	985.60	17.45
8100.00	8046.57	13807.00	8954.11	18.36	120.43	197.90	-222.69	-379.25	1025.84	966.12	17.18
8125.00	8061.85	13807.00	8954.11	18.50	120.43	196.89	-222.69	-379.25	1007.20	947.71	16.93
8150.00	8076.07	13807.00	8954.11	18.66	120.43	196.06	-222.69	-379.25	989.73	930.46	16.70
8175.00	8089.19	13807.00	8954.11	18.83	120.43	195.37	-222.69	-379.25	973.53	914.48	16.49
8200.00	8101.18	13807.00	8954.11	19.02	120.43	194.79	-222.69	-379.25	958.71	899.88	16.30
8225.00	8112.01	13807.00	8954.11	19.23	120.43	194.32	-222.69	-379.25	945.39	886.77	16.13
8250.00	8121.64	13807.00	8954.11	19.46	120.43	193.93	-222.69	-379.25	933.65	875.24	15.98
8275.00	8130.05	13807.00	8954.11	19.71	120.43	193.62	-222.69	-379.25	923.60	865.37	15.86
8300.00	8137.22	13814.85	8954.34	19.98	120.64	193.34	-222.41	-371.41	915.28	857.15	15.74
8325.00	8143.13	13790.75	8953.63	20.27	119.99	193.23	-223.27	-395.48	908.72	850.94	15.73
8350.00	8147.76	13766.33	8952.90	20.58	119.33	193.13	-224.14	-419.87	903.41	845.95	15.72
8375.00	8151.09	13741.68	8952.16	20.91	118.65	193.05	-225.02	-444.50	899.34	842.18	15.73
8400.00	8153.13	13716.65	8951.41	21.25	117.95	192.98	-225.92	-469.50	896.54	839.63	15.76
8425.00	8153.85	13691.24	8950.63	21.60	117.20	192.94	-226.88	-494.88	894.99	838.31	15.79
8437.39	8153.73	13678.93	8950.25	21.78	116.85	192.92	-227.35	-507.17	894.70	838.10	15.81
8500.00	8152.29	13617.79	8948.40	22.76	115.22	192.87	-229.69	-568.24	894.05	837.89	15.92
8600.00	8149.98	13519.02	8945.62	24.48	112.63	192.78	-233.30	-666.91	893.19	837.65	16.08
8700.00	8147.68	13421.18	8943.08	26.37	110.03	192.66	-236.61	-764.66	892.48	837.54	16.25
8800.00	8145.37	13323.59	8940.86	28.41	107.43	192.54	-239.76	-862.16	892.04	837.67	16.41
8900.00	8143.07	13226.26	8939.00	30.55	105.00	192.38	-242.54	-959.44	891.90	838.06	16.57
9000.00	8140.77	13124.60	8937.30	32.79	102.41	192.17	-244.75	-1061.06	891.84	838.52	16.72
9100.00	8138.46	13024.38	8935.53	35.09	99.72	191.95	-246.63	-1161.25	891.65	838.82	16.88
9200.00	8136.16	12929.21	8934.07	37.46	97.00	191.74	-248.58	-1256.39	891.73	839.40	17.04
9300.00	8133.86	12831.08	8932.95	39.87	94.52	191.52	-250.52	-1354.49	892.20	840.31	17.19
9400.00	8131.55	12733.36	8932.14	42.33	91.95	191.27	-252.04	-1452.20	892.90	841.46	17.36
9500.00	8129.25	12636.19	8931.63	44.82	89.35	191.01	-253.38	-1549.35	893.89	842.89	17.53
9600.00	8126.95	12539.07	8931.52	47.33	86.82	190.73	-254.50	-1646.47	895.26	844.68	17.70
9700.00	8124.64	12437.26	8931.40	49.87	84.00	190.42	-255.39	-1748.28	896.59	846.40	17.87
9800.00	8122.34	12339.45	8931.18	52.43	80.90	190.22	-257.76	-1846.06	898.11	848.22	18.00
9900.00	8120.03	12234.40	8930.80	55.01	78.67	189.94	-259.33	-1951.09	899.35	849.75	18.13
10000.00	8117.73	12119.12	8929.68	57.60	75.71	189.59	-260.00	-2066.36	899.91	850.59	18.25
10100.00	8115.43	11999.63	8925.63	60.21	72.79	189.19	-259.80	-2185.78	897.90	848.86	18.31
10200.00	8113.12	11901.54	8921.57	62.83	70.43	188.80	-258.59	-2283.78	895.06	846.42	18.40
10300.00	8110.82	11801.20	8917.74	65.46	67.77	188.36	-256.77	-2384.03	892.48	844.25	18.50
10400.00	8108.52	11699.42	8913.69	68.10	65.17	187.90	-254.73	-2485.71	889.78	841.94	18.60
10500.00	8106.21	11600.60	8909.75	70.74	62.73	187.42	-252.11	-2584.42	887.04	839.61	18.70
10600.00	8103.91	11510.00	8906.65	73.39	60.16	186.96	-249.66	-2674.93	884.91	837.86	18.81
10700.00	8101.61	11438.23	8905.64	76.05	58.04	186.62	-248.23	-2746.68	884.94	838.23	18.94
10800.00	8099.30	11346.12	8906.55	78.72	55.59	186.20	-246.90	-2838.76	887.43	840.97	19.10
10900.00	8097.00	11245.74	8907.51	81.39	52.70	185.75	-245.63	-2939.13	889.99	843.75	19.25
11000.00	8094.69	11126.70	8907.30	84.06	49.09	185.35	-245.93	-3058.17	891.65	845.57	19.35
11100.00	8092.39	11026.93	8905.84	86.74	46.67	185.06	-246.79	-3157.92	892.08	846.10	19.40
11200.00	8090.09	10931.80	8904.82	89.43	44.54	184.72	-246.71	-3253.04	892.83	846.96	19.46
11300.00	8087.78	10835.87	8904.37	92.11	42.38	184.33	-245.70	-3348.97	894.16	848.39	19.54



Weatherford Anticollision Report



Company:	Devon Energy	Date:	7/9/2013	Time:	12:14:30	Page:	4
Field:	Eddy Co. NM (NAD:83)	Co-ordinate(NE) Reference:	Well- Rigel 20 Fed.Com 8H, Grid:North				
Reference Site:	Rigel 20 Fed.Com 8H	Vertical (TVD) Reference:	SITE 3507.0				
Reference Well:	Rigel 20 Fed.Com 8H	Db:	Sybase				
Reference Wellpath:							

Site: Rigel 20 Fed Com #4H
Well: #4H
Wellpath: 1 V0

Inter-Site Error: 0.00 ft

Reference MD	TVD	Offset		Semi-Major Axis			Offset Location		Ctr-Ctr Distance	Edge Distance	Separation Distance	Factor	Warning
		MD	TVD	Ref	Offset	TFO-HS	North	East					
11400.00	8085.48	10731.35	8904.01	94.80	40.59	183.72	-241.96	-3453.42	895.49	849.90	19.64		
11500.00	8083.18	10625.02	8903.01	97.50	38.94	182.92	-235.13	-3559.52	896.15	850.77	19.75		
11600.00	8080.87	10507.80	8901.29	100.19	38.04	181.45	-218.32	-3675.47	896.27	851.21	19.89		
11700.00	8078.57	10403.09	8897.41	102.89	36.82	179.65	-195.48	-3777.56	894.45	849.44	19.88		
11800.00	8076.27	10317.79	8894.65	105.59	35.86	177.82	-171.28	-3859.29	894.12	848.66	19.67		
11900.00	8073.96	10230.06	8892.52	108.29	34.67	175.60	-140.88	-3941.54	896.22	849.65	19.24		
12000.00	8071.66	10134.14	8889.57	111.00	33.27	172.86	-102.48	-4029.37	900.12	851.47	18.50		
12100.00	8069.36	10050.90	8885.82	113.70	32.04	170.20	-64.29	-4103.23	905.97	854.35	17.55		
12200.00	8067.05	9983.97	8883.08	116.41	30.97	167.91	-30.72	-4161.06	915.91	860.84	16.63		
12300.00	8064.75	9929.68	8881.83	119.12	30.07	165.99	-1.77	-4206.97	931.21	872.51	15.87		
12400.00	8062.44	9875.50	8881.71	121.83	29.20	164.03	28.60	-4251.83	952.24	889.55	15.19		
12500.00	8060.14	9821.89	8882.27	124.55	28.35	162.06	60.29	-4295.07	978.68	911.70	14.61		
12600.00	8057.84	9761.55	8883.22	127.26	27.40	159.80	97.92	-4342.22	1010.15	938.35	14.07		
12700.00	8055.53	9703.38	8883.57	129.97	26.48	157.57	136.16	-4386.04	1045.95	969.19	13.63		
12800.00	8053.23	9656.01	8883.63	132.69	25.76	155.74	168.80	-4420.37	1086.41	1005.05	13.35		
12900.00	8050.93	9610.99	8883.61	135.41	25.06	153.97	201.07	-4451.76	1131.57	1045.66	13.17		
12940.20	8050.00	9590.03	8883.51	136.50	24.72	153.15	216.44	-4466.00	1150.92	1063.00	13.09		

Site: Rigel 20 Fed Com 7H
Well: Rigel 20 Fed Com 7H
Wellpath: 1 V0 Plan: Plan #1 V1

Inter-Site Error: 0.00 ft

Reference MD	TVD	Offset		Semi-Major Axis			Offset Location		Ctr-Ctr Distance	Edge Distance	Separation Distance	Factor	Warning
		MD	TVD	Ref	Offset	TFO-HS	North	East					
0.00	0.00	2.00	-2.00	0.00	0.00	-0.41	49.99	-0.36	49.99	49.99	27801.85		
100.00	100.00	98.00	98.00	0.09	0.09	-0.41	49.99	-0.36	49.99	49.81	280.83		
200.00	200.00	198.00	198.00	0.31	0.31	-0.41	49.99	-0.36	49.99	49.37	80.01		
300.00	300.00	298.00	298.00	0.54	0.53	-0.41	49.99	-0.36	49.99	48.92	46.53		
400.00	400.00	398.00	398.00	0.76	0.76	-0.41	49.99	-0.36	49.99	48.47	32.80		
500.00	500.00	498.00	498.00	0.99	0.98	-0.41	49.99	-0.36	49.99	48.02	25.33		
600.00	600.00	598.00	598.00	1.21	1.21	-0.41	49.99	-0.36	49.99	47.57	20.63		
700.00	700.00	698.00	698.00	1.44	1.43	-0.41	49.99	-0.36	49.99	47.12	17.40		
800.00	800.00	798.00	798.00	1.66	1.66	-0.41	49.99	-0.36	49.99	46.67	15.05		
900.00	900.00	898.00	898.00	1.89	1.88	-0.41	49.99	-0.36	49.99	46.22	13.25		
1000.00	1000.00	998.00	998.00	2.11	2.11	-0.41	49.99	-0.36	49.99	45.77	11.84		
1100.00	1100.00	1098.00	1098.00	2.34	2.33	-0.41	49.99	-0.36	49.99	45.32	10.70		
1200.00	1200.00	1198.00	1198.00	2.56	2.56	-0.41	49.99	-0.36	49.99	44.87	9.76		
1300.00	1300.00	1298.00	1298.00	2.79	2.78	-0.41	49.99	-0.36	49.99	44.42	8.98		
1400.00	1400.00	1398.00	1398.00	3.01	3.01	-0.41	49.99	-0.36	49.99	43.97	8.31		
1500.00	1500.00	1498.00	1498.00	3.24	3.23	-0.41	49.99	-0.36	49.99	43.52	7.73		
1600.00	1600.00	1598.00	1598.00	3.46	3.46	-0.41	49.99	-0.36	49.99	43.07	7.23		
1700.00	1700.00	1698.00	1698.00	3.69	3.68	-0.41	49.99	-0.36	49.99	42.62	6.79		
1800.00	1800.00	1798.00	1798.00	3.91	3.91	-0.41	49.99	-0.36	49.99	42.17	6.39		
1900.00	1900.00	1898.00	1898.00	4.14	4.13	-0.41	49.99	-0.36	49.99	41.72	6.05		
2000.00	2000.00	1998.00	1998.00	4.36	4.36	-0.41	49.99	-0.36	49.99	41.27	5.74		
2100.00	2100.00	2098.00	2098.00	4.59	4.58	-0.41	49.99	-0.36	49.99	40.83	5.45		
2200.00	2200.00	2198.00	2198.00	4.81	4.81	-0.41	49.99	-0.36	49.99	40.38	5.20		
2300.00	2300.00	2298.00	2298.00	5.03	5.03	-0.41	49.99	-0.36	49.99	39.93	4.97		
2400.00	2400.00	2398.00	2398.00	5.26	5.26	-0.41	49.99	-0.36	49.99	39.48	4.75		
2500.00	2500.00	2498.00	2498.00	5.48	5.48	-0.41	49.99	-0.36	49.99	39.03	4.56		
2600.00	2600.00	2598.00	2598.00	5.71	5.70	-0.41	49.99	-0.36	49.99	38.58	4.38		
2700.00	2700.00	2698.00	2698.00	5.93	5.93	-0.41	49.99	-0.36	49.99	38.13	4.21		



Weatherford Anticollision Report



Company: Devon Energy	Date: 7/9/2013	Time: 12:14:30	Page: 5
Field: Eddy Co. NM (NAD 83)	Co-ordinate(N.E.) Reference: Well: Rigel 20 Fed Com 8H Grid: North		
Reference Site: Rigel 20 Fed Com 8H	Vertical (TVD) Reference: SITE 3507.0		
Reference Well: Rigel 20 Fed Com 8H	Db: Sybase		
Reference Wellpath:			

Site: Rigel 20 Fed Com 7H
 Well: Rigel 20 Fed Com 7H
 Wellpath: 1 V0 Plan: Plan #1 V1

Inter-Site Error: 0.00 ft

Reference MD (ft)	TVD (ft)	Offset		Semi-Major Axis			Offset Location		Ctr-Ctr Edge Separation		Warning	
		MD (ft)	TVD (ft)	Ref	Offset (ft)	TFO=HS (deg)	North (ft)	East (ft)	Distance (ft)	Distance (ft)		Factor
2800.00	2800.00	2798.00	2798.00	6.16	6.15	-0.41	49.99	-0.36	49.99	37.68	4.06	
2900.00	2900.00	2898.00	2898.00	6.38	6.38	-0.41	49.99	-0.36	49.99	37.23	3.92	
3000.00	3000.00	2998.00	2998.00	6.61	6.60	-0.41	49.99	-0.36	49.99	36.78	3.78	
3100.00	3100.00	3098.00	3098.00	6.83	6.83	-0.41	49.99	-0.36	49.99	36.33	3.66	
3200.00	3200.00	3198.00	3198.00	7.06	7.05	-0.41	49.99	-0.36	49.99	35.88	3.54	
3300.00	3300.00	3298.00	3298.00	7.28	7.28	-0.41	49.99	-0.36	49.99	35.43	3.43	
3400.00	3400.00	3398.00	3398.00	7.51	7.50	-0.41	49.99	-0.36	49.99	34.98	3.33	
3500.00	3500.00	3498.00	3498.00	7.73	7.73	-0.41	49.99	-0.36	49.99	34.53	3.23	
3600.00	3600.00	3598.00	3598.00	7.96	7.95	-0.41	49.99	-0.36	49.99	34.08	3.14	
3700.00	3700.00	3698.00	3698.00	8.18	8.18	-0.41	49.99	-0.36	49.99	33.63	3.06	
3800.00	3800.00	3798.00	3798.00	8.41	8.40	-0.41	49.99	-0.36	49.99	33.18	2.97	
3900.00	3900.00	3898.00	3898.00	8.63	8.63	-0.41	49.99	-0.36	49.99	32.73	2.90	
4000.00	4000.00	3998.00	3998.00	8.86	8.85	-0.41	49.99	-0.36	49.99	32.28	2.82	
4100.00	4100.00	4098.00	4098.00	9.08	9.08	-0.41	49.99	-0.36	49.99	31.83	2.75	
4200.00	4200.00	4198.00	4198.00	9.31	9.30	-0.41	49.99	-0.36	49.99	31.39	2.69	
4300.00	4300.00	4298.00	4298.00	9.53	9.53	-0.41	49.99	-0.36	49.99	30.94	2.62	
4400.00	4400.00	4398.00	4398.00	9.75	9.75	-0.41	49.99	-0.36	49.99	30.49	2.56	
4500.00	4500.00	4498.00	4498.00	9.98	9.98	-0.41	49.99	-0.36	49.99	30.04	2.51	
4600.00	4600.00	4598.00	4598.00	10.20	10.20	-0.41	49.99	-0.36	49.99	29.59	2.45	
4700.00	4700.00	4698.00	4698.00	10.43	10.42	-0.41	49.99	-0.36	49.99	29.14	2.40	
4800.00	4800.00	4798.00	4798.00	10.65	10.65	-0.41	49.99	-0.36	49.99	28.69	2.35	
4900.00	4900.00	4898.00	4898.00	10.88	10.87	-0.41	49.99	-0.36	49.99	28.24	2.30	
5000.00	5000.00	4998.00	4998.00	11.10	11.10	-0.41	49.99	-0.36	49.99	27.79	2.25	
5100.00	5100.00	5098.00	5098.00	11.33	11.32	-0.41	49.99	-0.36	49.99	27.34	2.21	
5200.00	5200.00	5198.00	5198.00	11.55	11.55	-0.41	49.99	-0.36	49.99	26.89	2.16	
5300.00	5300.00	5298.00	5298.00	11.78	11.77	-0.41	49.99	-0.36	49.99	26.44	2.12	
5400.00	5400.00	5398.00	5398.00	12.00	12.00	-0.41	49.99	-0.36	49.99	25.99	2.08	
5500.00	5500.00	5498.00	5498.00	12.23	12.22	-0.41	49.99	-0.36	49.99	25.54	2.04	
5600.00	5600.00	5598.00	5598.00	12.45	12.45	-0.41	49.99	-0.36	49.99	25.09	2.01	
5700.00	5700.00	5698.00	5698.00	12.68	12.67	-0.41	49.99	-0.36	49.99	24.64	1.97	
5800.00	5800.00	5798.00	5798.00	12.90	12.90	-0.41	49.99	-0.36	49.99	24.19	1.94	
5900.00	5900.00	5898.00	5898.00	13.13	13.12	-0.41	49.99	-0.36	49.99	23.74	1.90	
6000.00	6000.00	5998.00	5998.00	13.35	13.35	-0.41	49.99	-0.36	49.99	23.29	1.87	
6100.00	6100.00	6098.00	6098.00	13.58	13.57	-0.41	49.99	-0.36	49.99	22.84	1.84	
6200.00	6200.00	6198.00	6198.00	13.80	13.80	-0.41	49.99	-0.36	49.99	22.39	1.81	
6300.00	6300.00	6298.00	6298.00	14.03	14.02	-0.41	49.99	-0.36	49.99	21.94	1.78	
6400.00	6400.00	6398.00	6398.00	14.25	14.25	-0.41	49.99	-0.36	49.99	21.50	1.75	
6500.00	6500.00	6498.00	6498.00	14.47	14.47	-0.41	49.99	-0.36	49.99	21.05	1.73	
6600.00	6600.00	6598.00	6598.00	14.70	14.70	-0.41	49.99	-0.36	49.99	20.60	1.70	
6700.00	6700.00	6698.00	6698.00	14.92	14.92	-0.41	49.99	-0.36	49.99	20.15	1.68	
6800.00	6800.00	6798.00	6798.00	15.15	15.14	-0.41	49.99	-0.36	49.99	19.70	1.65	
6900.00	6900.00	6898.00	6898.00	15.37	15.37	-0.41	49.99	-0.36	49.99	19.25	1.63	
7000.00	7000.00	6998.00	6998.00	15.60	15.59	-0.41	49.99	-0.36	49.99	18.80	1.60	
7100.00	7100.00	7098.00	7098.00	15.82	15.82	-0.41	49.99	-0.36	49.99	18.35	1.58	
7200.00	7200.00	7198.00	7198.00	16.05	16.04	-0.41	49.99	-0.36	49.99	17.90	1.56	
7300.00	7300.00	7298.00	7298.00	16.27	16.27	-0.41	49.99	-0.36	49.99	17.45	1.54	
7400.00	7400.00	7398.00	7398.00	16.50	16.49	-0.41	49.99	-0.36	49.99	17.00	1.52	
7500.00	7500.00	7498.00	7498.00	16.72	16.72	-0.41	49.99	-0.36	49.99	16.55	1.49	Level 3
7600.00	7600.00	7598.00	7598.00	16.95	16.94	-0.41	49.99	-0.36	49.99	16.10	1.48	Level 3
7676.39	7676.39	7673.62	7673.62	17.12	17.11	-0.41	50.05	-0.36	50.05	15.82	1.46	Level 3
7700.00	7699.99	7694.95	7694.94	17.17	17.16	93.21	50.85	-0.28	50.97	16.67	1.49	Level 3



Weatherford Anticollision Report



Company: Devon Energy	Date: 7/9/2013	Time: 12:14:30	Page: 6
Field: Eddy Co. NM (NAD 83)	Co-ordinate(NE) Reference: Well: Rigel 20 Fed Com 8H Grid: North		
Reference Site: Rigel 20 Fed Com 8H	Vertical (TVD) Reference: SITE 3507.0		
Reference Well: Rigel 20 Fed Com 8H	Db: Sybase		
Reference Wellpath:			

Site: Rigel 20 Fed Com 7H
 Well: Rigel 20 Fed Com 7H
 Wellpath: 1 V0 Plan: Plan #1 V1

Inter-Site Error: 0.00 ft

Reference MD	TVD	Offset		Semi-Major Axis			Offset Location		Ctr-Ctr Edge		Separation Factor	Warning
		MD	TVD	Ref	Offset	TFO-HS	North	East	Distance	Distance		
ft	ft	ft	ft	ft	ft	deg	ft	ft	ft	ft		
7725.00	7724.92	7717.34	7717.24	17.23	17.21	94.94	52.71	-0.12	53.20	18.84	1.55	
7750.00	7749.71	7739.33	7739.04	17.28	17.26	97.50	55.55	0.13	56.82	22.43	1.65	
7775.00	7774.30	7760.77	7760.16	17.34	17.30	100.50	59.28	0.45	61.95	27.57	1.80	
7800.00	7798.62	7781.52	7780.41	17.40	17.35	103.54	63.79	0.85	68.71	34.34	2.00	
7825.00	7822.61	7801.46	7799.66	17.46	17.39	106.32	68.94	1.30	77.12	42.79	2.25	
7850.00	7846.20	7820.48	7817.81	17.51	17.43	108.69	74.59	1.79	87.17	52.90	2.54	
7875.00	7869.32	7838.51	7834.79	17.57	17.47	110.55	80.62	2.32	98.78	64.58	2.89	
7900.00	7891.92	7855.49	7850.58	17.64	17.50	111.89	86.87	2.87	111.87	77.72	3.28	
7925.00	7913.92	7871.41	7865.15	17.70	17.54	112.71	93.24	3.42	126.31	92.22	3.70	
7950.00	7935.27	7886.24	7878.54	17.77	17.57	113.04	99.60	3.98	142.00	107.93	4.17	
7975.00	7955.91	7899.99	7890.76	17.85	17.60	112.89	105.87	4.53	158.80	124.74	4.66	
8000.00	7975.79	7912.67	7901.87	17.93	17.63	112.27	111.95	5.06	176.61	142.53	5.18	
8025.00	7994.84	7924.29	7911.91	18.02	17.66	111.20	117.79	5.57	195.31	161.18	5.72	
8050.00	8013.02	7934.90	7920.94	18.12	17.68	109.67	123.33	6.06	214.81	180.57	6.27	
8075.00	8030.28	7944.52	7929.03	18.24	17.70	107.65	128.52	6.51	235.01	200.61	6.83	
8100.00	8046.57	7953.18	7936.22	18.36	17.72	105.14	133.33	6.93	255.81	221.22	7.39	
8125.00	8061.85	7960.93	7942.57	18.50	17.74	102.11	137.75	7.32	277.13	242.30	7.95	
8150.00	8076.07	7967.79	7948.14	18.66	17.76	98.54	141.75	7.67	298.90	263.79	8.51	
8175.00	8089.19	7973.81	7952.97	18.83	17.77	94.43	145.32	7.98	321.04	285.64	9.07	
8200.00	8101.18	7979.01	7957.11	19.02	17.79	89.78	148.45	8.25	343.48	307.81	9.63	
8225.00	8112.01	7983.43	7960.61	19.23	17.80	84.65	151.15	8.49	366.16	330.28	10.21	
8250.00	8121.64	7987.10	7963.49	19.46	17.81	79.11	153.41	8.69	389.00	353.03	10.81	
8275.00	8130.05	7990.04	7965.78	19.71	17.82	73.29	155.24	8.85	411.97	376.03	11.46	
8300.00	8137.22	7992.27	7967.52	19.98	17.82	67.34	156.65	8.97	434.99	399.25	12.17	
8325.00	8143.13	7993.83	7968.72	20.27	17.83	61.43	157.62	9.06	458.02	422.63	12.94	
8350.00	8147.76	7994.71	7969.41	20.58	17.83	55.71	158.18	9.11	481.01	446.10	13.78	
8375.00	8151.09	7994.95	7969.59	20.91	17.83	50.31	158.33	9.12	503.91	469.58	14.68	
8400.00	8153.13	7994.55	7969.28	21.25	17.83	45.31	158.08	9.10	526.68	492.96	15.62	
8425.00	8153.85	7993.51	7968.48	21.60	17.83	40.74	157.43	9.04	549.27	516.16	16.59	
8437.39	8153.73	7992.77	7967.90	21.78	17.82	38.65	156.96	9.00	560.38	527.57	17.08	
8500.00	8152.29	7988.67	7964.71	22.76	17.81	37.74	154.39	8.77	617.02	583.71	18.53	
8600.00	8149.98	7982.25	7959.67	24.48	17.80	36.33	150.42	8.43	709.48	675.38	20.80	
8700.00	8147.68	7975.98	7954.70	26.37	17.78	34.99	146.62	8.09	803.67	768.75	23.02	
8800.00	8145.37	7969.86	7949.81	28.41	17.77	33.70	142.97	7.77	899.04	863.31	25.16	
8900.00	8143.07	7963.90	7944.99	30.55	17.75	32.47	139.47	7.47	995.26	958.71	27.23	
9000.00	8140.77	7958.07	7940.24	32.79	17.74	31.29	136.11	7.17	1092.10	1054.75	29.23	
9100.00	8138.46	9830.97	8112.23	35.09	34.98	88.62	1109.99	-1044.61	1176.05	1105.98	16.79	
9200.00	8136.16	9929.97	8110.30	37.46	37.34	88.65	1118.76	-1143.19	1190.18	1115.39	15.91	
9300.00	8133.86	10028.96	8108.38	39.87	39.75	88.68	1127.53	-1241.78	1204.30	1124.69	15.13	
9400.00	8131.55	10127.96	8106.45	42.33	42.19	88.71	1136.30	-1340.37	1218.43	1133.92	14.42	
9500.00	8129.25	10226.95	8104.52	44.82	44.67	88.74	1145.07	-1438.95	1232.56	1143.08	13.77	
9600.00	8126.95	10325.95	8102.60	47.33	47.18	88.77	1153.84	-1537.54	1246.69	1152.18	13.19	
9700.00	8124.64	10424.94	8100.67	49.87	49.72	88.80	1162.61	-1636.13	1260.82	1161.23	12.66	
9800.00	8122.34	10523.94	8098.74	52.43	52.27	88.83	1171.39	-1734.71	1274.94	1170.25	12.18	
9900.00	8120.03	10622.93	8096.81	55.01	54.85	88.86	1180.16	-1833.30	1289.07	1179.22	11.73	
10000.00	8117.73	10721.93	8094.89	57.60	57.43	88.89	1188.93	-1931.89	1303.20	1188.17	11.33	
10100.00	8115.43	10820.92	8092.96	60.21	60.04	88.91	1197.70	-2030.47	1317.33	1197.09	10.96	
10200.00	8113.12	10919.92	8091.03	62.83	62.65	88.94	1206.47	-2129.06	1331.46	1205.99	10.61	
10300.00	8110.82	11018.91	8089.10	65.46	65.27	88.96	1215.24	-2227.65	1345.59	1214.87	10.29	
10400.00	8108.52	11117.91	8087.18	68.10	67.91	88.99	1224.01	-2326.23	1359.72	1223.73	10.00	
10500.00	8106.21	11216.90	8085.25	70.74	70.55	89.01	1232.78	-2424.82	1373.85	1232.57	9.72	



Weatherford Anticollision Report



Company: Devon Energy	Date: 7/9/2013	Time: 12:14:30	Page: 7
Field: Eddy Co. NM (NAD 83)	Co-ordinate(N/E) Reference: Well: Rigel 20 Fed Com 8H Gnd: North		
Reference Site: Rigel 20 Fed Com 8H	Vertical (TVD) Reference: SITE 3507-0		
Reference Well: Rigel 20 Fed Com 8H	Db: Sybase		
Reference Wellpath:			

Site: Rigel 20 Fed Com 7H
 Well: Rigel 20 Fed Com 7H
 Wellpath: 1 V0 Plan: Plan #1 V1

Inter-Site Error: 0.00 ft

Reference MD	TVD	Offset		Semi-Major Axis			Offset Location		Ctr-Ctr Edge Separation		Warning
		MD	TVD	Ref	Offset	TFO-HS	North	East	Distance	Distance	
ft	ft	ft	ft	ft	ft	deg	ft	ft	ft	ft	
10600.00	8103.91	11315.89	8083.32	73.39	73.19	89.04	1241.55	-2523.41	1387.98	1241.40	9.47
10700.00	8101.61	11414.89	8081.39	76.05	75.85	89.06	1250.32	-2621.99	1402.12	1250.22	9.23
10800.00	8099.30	11513.88	8079.47	78.72	78.51	89.08	1259.10	-2720.58	1416.25	1259.03	9.01
10900.00	8097.00	11612.88	8077.54	81.39	81.17	89.10	1267.87	-2819.17	1430.38	1267.82	8.80
11000.00	8094.69	11711.87	8075.61	84.06	83.84	89.13	1276.64	-2917.75	1444.51	1276.61	8.60
11100.00	8092.39	11810.87	8073.69	86.74	86.52	89.15	1285.41	-3016.34	1458.64	1285.39	8.42
11200.00	8090.09	11909.86	8071.76	89.43	89.20	89.17	1294.18	-3114.93	1472.77	1294.16	8.25
11300.00	8087.78	12008.86	8069.83	92.11	91.88	89.19	1302.95	-3213.51	1486.91	1302.92	8.08
11400.00	8085.48	12107.85	8067.90	94.80	94.56	89.21	1311.72	-3312.10	1501.04	1311.68	7.93
11500.00	8083.18	12206.85	8065.98	97.50	97.25	89.23	1320.49	-3410.69	1515.17	1320.43	7.78
11600.00	8080.87	12305.84	8064.05	100.19	99.94	89.25	1329.26	-3509.28	1529.31	1329.18	7.64
11700.00	8078.57	12404.84	8062.12	102.89	102.64	89.27	1338.03	-3607.86	1543.44	1337.92	7.51
11800.00	8076.27	12503.83	8060.19	105.59	105.33	89.29	1346.81	-3706.45	1557.57	1346.66	7.38
11900.00	8073.96	12602.83	8058.27	108.29	108.03	89.31	1355.58	-3805.04	1571.70	1355.39	7.27
12000.00	8071.66	12701.82	8056.34	111.00	110.73	89.33	1364.35	-3903.62	1585.84	1364.12	7.15
12100.00	8069.36	12800.82	8054.41	113.70	113.43	89.34	1373.12	-4002.21	1599.97	1372.84	7.04
12200.00	8067.05	12899.81	8052.48	116.41	116.13	89.36	1381.89	-4100.80	1614.11	1381.57	6.94
12300.00	8064.75	12998.81	8050.56	119.12	118.84	89.38	1390.66	-4199.38	1628.24	1390.28	6.84
12400.00	8062.44	13097.80	8048.63	121.83	121.55	89.40	1399.43	-4297.97	1642.37	1399.00	6.75
12500.00	8060.14	13196.80	8046.70	124.55	124.25	89.41	1408.20	-4396.56	1656.51	1407.71	6.66
12600.00	8057.84	13295.79	8044.78	127.26	126.96	89.43	1416.97	-4495.14	1670.64	1416.43	6.57
12700.00	8055.53	13394.79	8042.85	129.97	129.67	89.44	1425.74	-4593.73	1684.78	1425.13	6.49
12800.00	8053.23	13493.78	8040.92	132.69	132.38	89.46	1434.52	-4692.32	1698.91	1433.84	6.41
12900.00	8050.93	13592.78	8038.99	135.41	135.10	89.48	1443.29	-4790.90	1713.05	1442.55	6.33
12940.20	8050.00	13632.57	8038.22	136.50	136.19	89.48	1446.81	-4830.53	1718.73	1446.04	6.30



Weatherford

Weatherford Drilling Services

GeoDec v5.03

Report Date: June 12, 2013
 Job Number: _____
 Customer: Devon
 Well Name: Rigel 20 Fed Com 8H
 API Number: _____
 Rig Name: _____
 Location: Eddy Co., NM
 Block: _____
 Engineer: RWJ

US State Plane 1983	Geodetic Latitude / Longitude
System: New Mexico Eastern Zone	System: Latitude / Longitude
Projection: Transverse Mercator/Gauss Kruger	Projection: Geodetic Latitude and Longitude
Datum: North American Datum 1983	Datum: North American Datum 1983
Ellipsoid: GRS 1980	Ellipsoid: GRS 1980
North/South 597003.600 USFT	Latitude 32.6404026 DEG
East/West 680056.480 USFT	Longitude -103.8826770 DEG
Grid Convergence: 24°	
Total Correction: +7.34°	

Geodetic Location WGS84 Elevation = 0.0 Meters
 Latitude = 32.64040° N 32° 38 min 25.449 sec
 Longitude = 103.88268° W 103° 52 min 57.637 sec

Magnetic Declination =	7.58°	[True North Offset]	
Local Gravity =	.9988 g	Checksum =	6636
Local Field Strength =	48595 nT	Magnetic Vector X =	23760 nT
Magnetic Dip =	60.45°	Magnetic Vector Y =	3161 nT
Magnetic Model =	bggm2013	Magnetic Vector Z =	42272 nT
Spud Date =	Nov 30, 2013	Magnetic Vector H =	23969 nT

Signed: _____

Date: _____

Weatherford
Wft Plan Report X Y's.

Company: Devon Energy Date: 7/9/2013 Time: 12:12:16 Page: 1
 Field: Eddy Co., NM (NAD 83) Co-ordinate(N/E) Reference: Well: Rigel 20 Fed Com 8H, Grid North
 Site: Rigel 20 Fed Com 8H Vertical (TVD) Reference: SITE 3507.0
 Well: Rigel 20 Fed Com 8H Section (VS) Reference: Well (0.00N,0.00E,266.95Azi)
 Wellpath: 1 Survey Calculation Method: Minimum Curvature Db: Sybase

Plan: Plan #1 Date Composed: 6/12/2013
 Principal: Yes Version: 1
 Site: Rigel 20 Fed Com 8H Tied-to: From Surface

Site Position: Northing: 597003.60 ft Latitude: 32 38 25.437 N
 From: Map Easting: 680056.48 ft Longitude: 103 52 57.653 W
 Position Uncertainty: 0.00 ft North Reference: Grid
 Ground Level: 3487.00 ft Grid Convergence: 0.24 deg

Well: Rigel 20 Fed Com 8H Slot Name:
 Well Position: +N/-S 0.00 ft Northing: 597003.60 ft Latitude: 32 38 25.437 N
 +E/-W 0.00 ft Easting: 680056.48 ft Longitude: 103 52 57.653 W
 Position Uncertainty: 0.00 ft

Wellpath: 1 Drilled From: Surface
 Current Datum: SITE Height 3507.00 ft Tie-on Depth: 0.00 ft
 Magnetic Data: 11/30/2013 Above System Datum: Mean Sea Level
 Field Strength: 48612 nT Declination: 7.46 deg
 Vertical Section: Depth From (TVD) +N/-S +E/-W Mag Dip Angle: 60.46 deg
 ft ft ft +E/-W Direction
 0.00 0.00 0.00 0.00 266.95

MD	Incl	Azim	TVD	+N/-S	+E/-W	DLS	Build	Turn	TFO	Target
ft	deg	deg	ft	ft	ft	deg/100ft	deg/100ft	deg/100ft	deg	
0.00	0.00	266.95	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
7676.39	0.00	266.95	7676.39	0.00	0.00	0.00	0.00	0.00	0.00	
8437.39	91.32	266.95	8153.73	-25.95	-487.77	12.00	12.00	0.00	266.95	
12940.20	91.32	266.95	8050.00	-265.11	-4983.03	0.00	0.00	0.00	0.00	PBHL

MD	Incl	Azim	TVD	N/S	E/W	VS	DLS	MapN	MapE	Comment
ft	deg	deg	ft	ft	ft	ft	deg/100ft	ft	ft	
7600.00	0.00	266.95	7600.00	0.00	0.00	0.00	0.00	597003.60	680056.48	
7676.39	0.00	266.95	7676.39	0.00	0.00	0.00	0.00	597003.60	680056.48	KOP
7700.00	2.83	266.95	7699.99	-0.03	-0.58	0.58	12.00	597003.57	680055.90	
7800.00	14.83	266.95	7798.62	-0.85	-15.89	15.91	12.00	597002.75	680040.59	
7900.00	26.83	266.95	7891.92	-2.73	-51.34	51.41	12.00	597000.87	680005.14	
8000.00	38.83	266.95	7975.79	-5.61	-105.38	105.53	12.00	596997.99	679951.10	
8100.00	50.83	266.95	8046.57	-9.35	-175.66	175.91	12.00	596994.25	679880.82	
8200.00	62.83	266.95	8101.18	-13.78	-259.10	259.46	12.00	596989.82	679797.38	
8300.00	74.83	266.95	8137.22	-18.73	-352.05	352.55	12.00	596984.87	679704.43	
8400.00	86.83	266.95	8153.13	-23.97	-450.45	451.09	12.00	596979.63	679606.03	
8437.39	91.32	266.95	8153.73	-25.95	-487.77	488.46	12.00	596977.65	679568.71	LP
8500.00	91.32	266.95	8152.29	-29.28	-550.28	551.06	0.00	596974.32	679506.20	
8600.00	91.32	266.95	8149.98	-34.59	-650.11	651.03	0.00	596969.01	679406.37	
8700.00	91.32	266.95	8147.68	-39.90	-749.94	751.00	0.00	596963.70	679306.54	
8800.00	91.32	266.95	8145.37	-45.21	-849.78	850.98	0.00	596958.39	679206.70	
8900.00	91.32	266.95	8143.07	-50.52	-949.61	950.95	0.00	596953.08	679106.87	
9000.00	91.32	266.95	8140.77	-55.83	-1049.44	1050.92	0.00	596947.77	679007.04	
9100.00	91.32	266.95	8138.46	-61.14	-1149.27	1150.90	0.00	596942.46	678907.21	
9200.00	91.32	266.95	8136.16	-66.46	-1249.11	1250.87	0.00	596937.14	678807.37	
9300.00	91.32	266.95	8133.86	-71.77	-1348.94	1350.85	0.00	596931.83	678707.54	
9400.00	91.32	266.95	8131.55	-77.08	-1448.77	1450.82	0.00	596926.52	678607.71	
9500.00	91.32	266.95	8129.25	-82.39	-1548.60	1550.79	0.00	596921.21	678507.89	
9600.00	91.32	266.95	8126.95	-87.70	-1648.43	1650.77	0.00	596915.90	678408.05	
9700.00	91.32	266.95	8124.64	-93.01	-1748.27	1750.74	0.00	596910.59	678308.21	
9800.00	91.32	266.95	8122.34	-98.32	-1848.10	1850.71	0.00	596905.28	678208.38	
9900.00	91.32	266.95	8120.03	-103.63	-1947.93	1950.69	0.00	596899.97	678108.55	
10000.00	91.32	266.95	8117.73	-108.95	-2047.76	2050.66	0.00	596894.65	678008.72	
10100.00	91.32	266.95	8115.43	-114.26	-2147.60	2150.63	0.00	596889.34	677908.88	
10200.00	91.32	266.95	8113.12	-119.57	-2247.43	2250.61	0.00	596884.03	677809.05	
10300.00	91.32	266.95	8110.82	-124.88	-2347.26	2350.58	0.00	596878.72	677709.22	
10400.00	91.32	266.95	8108.52	-130.19	-2447.09	2450.55	0.00	596873.41	677609.39	
10500.00	91.32	266.95	8106.21	-135.50	-2546.92	2550.53	0.00	596868.10	677509.56	
10600.00	91.32	266.95	8103.91	-140.81	-2646.76	2650.50	0.00	596862.79	677409.72	
10700.00	91.32	266.95	8101.61	-146.13	-2746.59	2750.47	0.00	596857.47	677309.89	
10800.00	91.32	266.95	8099.30	-151.44	-2846.42	2850.45	0.00	596852.16	677210.06	

10900.00	91.32	266.95	8097.00	-156.75	-2946.25	2950.42	0.00	596846.85	677110.23
11000.00	91.32	266.95	8094.69	-162.06	-3046.09	3050.39	0.00	596841.54	677010.39
11100.00	91.32	266.95	8092.39	-167.37	-3145.92	3150.37	0.00	596836.23	676910.56
11200.00	91.32	266.95	8090.09	-172.68	-3245.75	3250.34	0.00	596830.92	676810.73
11300.00	91.32	266.95	8087.78	-177.99	-3345.58	3350.31	0.00	596825.61	676710.90
11400.00	91.32	266.95	8085.48	-183.30	-3445.42	3450.29	0.00	596820.30	676611.06
11500.00	91.32	266.95	8083.18	-188.62	-3545.25	3550.26	0.00	596814.98	676511.23
11600.00	91.32	266.95	8080.87	-193.93	-3645.08	3650.23	0.00	596809.67	676411.40
11700.00	91.32	266.95	8078.57	-199.24	-3744.91	3750.21	0.00	596804.36	676311.57
11800.00	91.32	266.95	8076.27	-204.55	-3844.74	3850.18	0.00	596799.05	676211.74
11900.00	91.32	266.95	8073.96	-209.86	-3944.58	3950.16	0.00	596793.74	676111.90
12000.00	91.32	266.95	8071.66	-215.17	-4044.41	4050.13	0.00	596788.43	676012.07
12100.00	91.32	266.95	8069.36	-220.48	-4144.24	4150.10	0.00	596783.12	675912.24
12200.00	91.32	266.95	8067.05	-225.80	-4244.07	4250.08	0.00	596777.80	675812.41
12300.00	91.32	266.95	8064.75	-231.11	-4343.91	4350.05	0.00	596772.49	675712.57
12400.00	91.32	266.95	8062.44	-236.42	-4443.74	4450.02	0.00	596767.18	675612.74
12500.00	91.32	266.95	8060.14	-241.73	-4543.57	4550.00	0.00	596761.87	675512.91
12600.00	91.32	266.95	8057.84	-247.04	-4643.40	4649.97	0.00	596756.56	675413.08
12700.00	91.32	266.95	8055.53	-252.35	-4743.23	4749.94	0.00	596751.25	675313.25
12800.00	91.32	266.95	8053.23	-257.66	-4843.07	4849.92	0.00	596745.94	675213.41
12900.00	91.32	266.95	8050.93	-262.97	-4942.90	4949.89	0.00	596740.63	675113.58
12940.20	91.32	266.95	8050.00	-265.11	-4983.03	4990.08	0.00	596738.49	675073.45 PBHL

Targets

Name	Description	TVD	+N/-S	+E/-W	Map Northing	Map Easting	Latitude	Longitude
	Dip. Dir.	ft	ft	ft	ft	ft	Deg Min Sec	Deg Min Sec
PBHL		8050.00	-265.11	-4983.03	596738.49	675073.45	32 38 23.020 N	103 53 55.943 W
Tgt		8155.00	-22.90	-430.37	596980.70	679626.11	32 38 25.229 N	103 53 2.688 W

Casing Points

MD	TVD	Diameter	Hole Size	Name
----	-----	----------	-----------	------

Weatherford
Wft Plan Report X Y's.

Company: Devon Energy Date: 7/9/2013 Time: 12:12:16 Page: 3
 Field: Eddy Co., NM (NAD 83) Co-ordinate(NE) Reference: Well: Rigel 20 Fed Com 8H, Grid North
 Site: Rigel 20 Fed Com 8H Vertical (TVD) Reference: SITE 3507.0
 Well: Rigel 20 Fed Com 8H Section (VS) Reference: Well (0.00N,0.00E,266.95Azi)
 Wellpath: 1 Survey Calculation Method: Minimum Curvature Db: Sybase


Formations

MD	TVD	Formations	Lithology	Dip Angle	Dip Direction
----	-----	------------	-----------	-----------	---------------

Annotation


MD	TVD	
ft	ft	
7676.39	7676.39	KOP
8437.39	8153.73	LP
12940.19	8050.00	PBHL

20" 2K Annular



***The same choke manifold will be used with all BOP's**

13-5/8" 3M BOPE & Closed Loop Equipment Schematic



NOTES REGARDING BLOWOUT PREVENTERS

Devon Energy Production Company, LP

Rigel 20 Fed Com 8H


Surface Location: 635 FSL & 45 FWL, Unit M, Sec 21 T19S R31E, Eddy, NM

Bottom hole Location: 400 FSL & 340' FWL, Unit M, Sec 20 T19S R31E, Eddy, NM

1. Drilling nipple will be constructed so it can be removed mechanically without the aid of a welder. The minimum internal diameter will equal BOP bore.
2. Wear ring will be properly installed in head.
3. Blowout preventer and all associated fittings will be in operable condition to withstand a minimum 3000 psi working pressure.
4. All fittings will be flanged.
5. A full bore safety valve tested to a minimum 3000 psi WP with proper thread connections will be available on the rotary rig floor at all times.
6. All choke lines will be anchored to prevent movement.
7. All BOP equipment will be equal to or larger in bore than the internal diameter of the last casing string.
8. Will maintain a kelly cock attached to the kelly.
9. Hand wheels and wrenches will be properly installed and tested for safe operation.
10. Hydraulic floor control for blowout preventer will be located as near in proximity to driller's controls as possible.
11. All BOP equipment will meet API standards and include a minimum 40 gallon accumulator having two independent means of power to initiate closing operation.




Hydrostatic Test Certificate

Certificate Number: 4520	PBC No: 10321	Customer Name & Address	
Customer Purchase Order No: RIG 300	Project:	HELMERICH & PAYNE INT'L DRILLING CO 1437 SOUTH BOULDER TULSA, OK 74119	
Test Centre Address		Accepted by ContiTech Beattie Inspection	
ContiTech Beattie Corp. 11535 Brittmoore Park Drive Houston, TX 77041 USA		Signed: Josh Sims 	Accepted by Client Inspection
		Date: 10/27/10	

We certify that the goods detailed hereon have been inspected by our Quality Management System, and to the best of our knowledge are found to conform to relevant industrial standards within the requirements of the purchase order as issued to ContiTech Beattie Corporation.

These goods were made in the United States of America.

Item	Part No.	Description	Qty	Serial Number	As-Built Length (m)	Work Press	Test Press	Test Time (minutes)
1		3" ID 10K Choke & Kill Hose x 35ft OAL End A: 4.1/16" 10Kpsi API Spec 6A Type 6BX Flange End B: 4.1/16" 10Kpsi API Spec 6A Type 6BX Flange Working Pressure: 10,000psi Test Pressure: 15,000psi Serial#: 49106	1	49106		10 kpsi	15 kpsi	60



360 deg = 96 min

CHART NO. MC MP-20000-1

METER RC# 4486

CHART PUT ON
SN/34403

TAKEN OFF

LOCATION IX Recertification wase

REMARKS LTB TK. 10/22/10

Certified by: *[Signature]*
Certified Type: *[Signature]*



Fluid Technology

ContiTech Beattie Corp.

Website: www.contitechbeattie.com

Monday, June 14, 2010

RE: Drilling & Production Hoses
Lifting & Safety Equipment

To Helmerich & Payne,

A Continental ContiTech hose assembly can perform as intended and suitable for the application regardless of whether the hose is secured or unsecured in its configuration. As a manufacturer of High Pressure Hose Assemblies for use in Drilling & Production, we do offer the corresponding lifting and safety equipment, this has the added benefit of easing the lifting and handling of each hose assembly whilst affording hose longevity by ensuring correct handling methods and procedures as well as securing the hose in the unlikely event of a failure; but in no way does the lifting and safety equipment affect the performance of the hoses providing the hoses have been handled and installed correctly. It is good practice to use lifting & safety equipment but not mandatory.


Should you have any questions or require any additional information/clarifications then please do not hesitate to contact us.

ContiTech Beattie is part of the Continental AG Corporation and can offer the full support resources associated with a global organization.

Best regards,


Robin Hodgson
Sales Manager
ContiTech Beattie Corp

ContiTech Beattie Corp,
11535 Brittmoore Park Drive,
Houston, TX 77041
Phone: +1 (832) 327-0141
Fax: +1 (832) 327-0148
www.contitechbeattie.com





Commitment Runs Deep



Design Plan
Operation and Maintenance Plan
Closure Plan

SENM - Closed Loop Systems
June 2008

I. Design Plan

Devon uses MI SWACO closed loop system (CLS). The MI SWACO CLS is designed to maintain drill solids at or below 5%. The equipment is arranged to progressively remove solids from the largest to the smallest size. Drilling fluids can thus be reused and savings is realized on mud and disposal costs. Dewatering may be required with the centrifuges to insure removal of ultra fine solids.

The drilling location is constructed to allow storm water to flow to a central sump normally the cellar. This insures no contamination leaves the drilling pad in the event of a spill. Storm water is reused in the mud system or stored in a reserve fluid tank farm until it can be reused. All lubricants, oils, or chemicals are removed immediately from the ground to prevent the contamination of storm water. An oil trap is normally installed on the sump if an oil spill occurs during a storm.

A tank farm is utilized to store drilling fluids including fresh water and brine fluids. The tank farm is constructed on a 20 ml plastic lined, bermed pad to prevent the contamination of the drilling site during a spill. Fluids from other sites may be stored in these tanks for processing by the solids control equipment and reused in the mud system. At the end of the well the fluids are transported from the tank farm to an adjoining well or to the next well for the rig.

Prior to installing a closed-loop system on site, the topsoil, if present, will be stripped and stockpiled for use as the final cover or fill at the time of closure.

Signs will be posted on the fence surrounding the closed-loop system unless the closed-loop system is located on a site where there is an existing well, that is operated by Devon.


II. Operations and Maintenance Plan

Primary Shakers: The primary shakers make the first removal of drill solids from the drilling mud as it leaves the well bore. The shakers are sized to handle maximum drilling rate at optimal screen size. The shakers normally remove solids down to 74 microns.

Mud Cleaner: The Mud Cleaner cleans the fluid after it leaves the shakers. A set of hydrocyclones are sized to handle 1.25 to 1.5 times the maximum circulating rate. This ensures all the fluid is being processed to an average cut point of 25 microns. The wet discharged is dewatered on a shaker equipped with ultra fine mesh screens and generally cut at 40 microns.



Closed Loop Schematic



Centrifuges: The centrifuges can be one or two in number depending on the well geometry or depth of well. The centrifuges are sized to maintain low gravity solids at 5% or below. They may or may not need a dewatering system to enhance the removal rates. The centrifuges can make a cut point of 8-10 microns depending on bowl speed, feed rate, solids loading and other factors.

The centrifuge system is designed to work on the active system and be flexible to process incoming fluids from other locations. This set-up is also dependant on well factors.

Dewatering System: The dewatering system is a chemical mixing and dosing system designed to enhance the solids removal of the centrifuge. Not commonly used in shallow wells. It may contain pH adjustment, coagulant mixing and dosing, and polymer mixing and dosing. Chemical flocculation binds ultra fine solids into a mass that is within the centrifuge operating design. The

dewatering system improves the centrifuge cut point to infinity or allows for the return of clear water or brine fluid. This ability allows for the ultimate control of low gravity solids.

Cuttings Boxes: Cuttings boxes are utilized to capture drill solids that are discarded from the solids control equipment. These boxes are set upon a rail system that allows for the removal and replacement of a full box of cuttings with an empty one. They are equipped with a cover that insures no product is spilled into the environment during the transportation phase.

Process Tank: (Optional) The process tank allows for the holding and process of fluids that are being transferred into the mud system. Additionally, during times of lost circulation the process tank may hold active fluids that are removed for additional treatment. It can further be used as a mixing tank during well control conditions.

Sump and Sump Pump: The sump is used to collect storm water and the pump is used to transfer this fluid to the active system or to the tank for to hold in reserve. It can also be used to collect fluids that may escape during spills. The location contains drainage ditches that allow the location fluids to drain to the sump.

Reserve Fluids (Tank Farm): A series of frac tanks are used to replace the reserve pit. These are steel tanks that are equipped with a manifold system and a transfer pump. These tanks can contain any number of fluids used during the drilling process. These can include fresh water, cut brine, and saturated salt fluid. The fluid can be from the active well or reclaimed fluid from other locations. A 20 ml liner and berm system is employed to ensure the fluids do not migrate to the environment during a spill.

If a leak develops, the appropriate division district office will be notified within 48 hours of the discovery and the leak will be addressed. Spill prevention is accomplished by maintaining pump packing, hoses, and pipe fittings to insure no leaks are occurring. During an upset condition the source of the spill is isolated and repaired as soon as it is discovered. Free liquid is removed by a diaphragm pump and returned to the mud system. Loose topsoil may be used to stabilize the spill and the contaminated soil is excavated and placed in the cuttings boxes. After the well is finished and the rig has moved, the entire location is scrapped and testing will be performed to determine if a release has occurred.

All trash is kept in a wire mesh enclosure and removed to an approved landfill when full. All spent motor oils are kept in separate containers and they are removed and sent to an approved recycling center. Any spilled lubricants, pipe

dope, or regulated chemicals are removed from soil and sent to landfills approved for these products.


These operations are monitored by Mi Swaco service technicians. Daily logs are maintained to ensure optimal equipment operation and maintenance. Screen and chemical use is logged to maintain inventory control. Fluid properties are monitored and recorded and drilling mud volumes are accounted for in the mud storage farm. This data is kept for end of well review to insure performance goals are met. Lessons learned are logged and used to help with continuous improvement.

A MI SWACO field supervisor manages from 3-5 wells. They are responsible for training personnel, supervising installations, and inspecting sites for compliance of MI SWACO safety and operational policy.

III. Closure Plan

A maximum 340' X 340' caliche pad is built per well. All of the trucks and steel tanks fit on this pad. All fluid cuttings go to the steel tanks to be hauled by various trucking companies to an agency approved disposal.

H&P Flex Rig Location 1 Layout 2 Well Pad





**Devon Energy Center
333 West Sheridan Avenue
Oklahoma City, Oklahoma 73102-5015**

Hydrogen Sulfide (H₂S) Contingency Plan

For



Rigel 20 Fed Com 8H

**Sec-21, T-19S R-31E
635' FSL & 45' FWL,
LAT. = 32.6404026'N (NAD83)
LONG = 103.8826771'W**

Eddy County NM

Rigel 20 Fed Com 8H

This is an open drilling site. H₂S monitoring equipment and emergency response equipment will be used within 500' of zones known to contain H₂S, including warning signs, wind indicators and H₂S monitor.



Assumed 100 ppm @ 3000' (see H₂S @ 3000' table)
100 ppm H₂S concentration shall trigger activation of this plan.

Escape

Crews shall escape upwind of escaping gas in the event of an emergency release of gas. Escape can be facilitated from the location entrance road, West then Northwest on lease road. Crews should then block entrance to the location from the lease road so as not to allow anyone traversing into a hazardous area. The blockade should be at a safe distance outside of the ROE. There are no homes or buildings in or near the ROE.

Assumed 100 ppm ROE = 3000'

100 ppm H₂S concentration shall trigger activation of this plan.

Emergency Procedures

In the event of a release of gas containing H₂S, the first responder(s) must

- **Isolate the area and prevent entry by other persons into the 100 ppm ROE.**
- **Evacuate any public places encompassed by the 100 ppm ROE.**
- **Be equipped with H₂S monitors and air packs in order to control the release.**
- **Use the “buddy system” to ensure no injuries occur during the response**
- **Take precautions to avoid personal injury during this operation.**
- **Contact operator and/or local officials to aid in operation. See list of phone numbers attached.**
- **Have received training in the**
 - **Detection of H₂S, and**
 - **Measures for protection against the gas,**
 - **Equipment used for protection and emergency response.**

Ignition of Gas Source

Should control of the well be considered lost and ignition considered, take care to protect against exposure to Sulfur Dioxide (SO₂). Intentional ignition must be coordinated with the NMOCD and local officials. Additionally the NM State Police may become involved. NM State Police shall be the Incident Command on scene of any major release. Take care to protect downwind whenever there is an ignition of the gas

Characteristics of H₂S and SO₂

Common Name	Chemical Formula	Specific Gravity	Threshold Limit	Hazardous Limit	Lethal Concentration
Hydrogen Sulfide	H₂S	1.189 Air = 1	10 ppm	100 ppm/hr	600 ppm
Sulfur Dioxide	SO₂	2.21 Air = 1	2 ppm	N/A	1000 ppm

Contacting Authorities

Devon Energy Corp. personnel must liaison with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such as type and volume of release, wind direction, location of release, etc. Be prepared with all information available. The following call list of essential and potential responders has been prepared for use during a release. Devon Energy Corp. Company response must be in coordination with the State of New Mexico's 'Hazardous Materials Emergency Response Plan' (HMER)

Hydrogen Sulfide Drilling Operation Plan

I. HYDROGEN SULFIDE (H₂S) TRAINING

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on this well:

1. The hazards and characteristics of hydrogen sulfide (H₂S)
2. The proper use and maintenance of personal protective equipment and life support systems.
3. The proper use of H₂S detectors, alarms, warning systems, briefing areas, evacuation procedures, and prevailing winds.
4. The proper techniques for first aid and rescue procedures.

In addition, supervisory personnel will be trained in the following areas:

1. The effects of H₂S metal components. If high tensile tubular are to be used, personnel will be trained in their special maintenance requirements.
2. Corrective action and shut-in procedures when drilling or reworking a well and blowout prevention and well control procedures.
3. The contents and requirements of the H₂S Drilling Operations Plan and Public Protection Plan.

There will be an initial training session just prior to encountering a known or probable H₂S zone (within 3 days or 500 feet) and weekly H₂S and well control drills for all personnel in each crew. The initial training session shall include a review of the site specific H₂S Drilling Operations Plan and the Public Protection Plan.

II. HYDROGEN SULFIDE TRAINING

Note: All H₂S safety equipment and systems will be installed, tested, and operational when drilling reaches a depth of 500 feet above, or three days prior to penetrating the first zone containing or reasonable expected to contain H₂S.

1. Well Control Equipment

- A. Flare line
- B. Choke-manifold— Remotely Operated Choke
- C. Blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit
- D. Auxiliary equipment may include if applicable: annular preventer and rotating head.
- E. Mud/Gas Separator

2. Protective equipment for essential personnel:

- A. 30-minute SCBA units located in the doghouse and at briefing areas, as indicated on well site diagram. As it may be difficult to communicate audibly while wearing these units, hand signals shall be utilized.

3. H₂S detection and monitoring equipment:

- A. Portable H₂S monitors positioned on location for best coverage and response. These units have warning lights and audible sirens when H₂S levels of 20 PPM are reached. These units are usually capable of detecting SO₂, which is a byproduct of burning H₂S.

4. Visual warning systems:

- B. Caution/ Danger signs shall be posted on roads providing direct access to locations. Signs will be painted a high visibility yellow with black lettering of sufficient size to be reasonable distance from the immediate location. Bilingual signs will be used when appropriate.

5. Mud program:

- A. The mud program has been designed to minimize the volume of H₂S circulated to surface. Proper mud weight, safe drilling practices and the use of H₂S scavengers will minimize hazards when penetrating H₂S bearing zones.

6. Metallurgy:

- A. All drill strings, casings, tubing, wellhead, blowout preventer, drilling spool, kill lines, choke manifold lines, and valves shall be H₂S trim.
- B. All elastomers used for packing and seals shall be H₂S trim.

7. Communication:

- A. Radio communications in company vehicles including cellular telephones and 2-way radio
- B. Land line (telephone) communications at Office

8. Well testing:

- A. Drill stem testing will be performed with a minimum number of personnel in the immediate vicinity, which are necessary to safety and adequately conduct the test. The drill stem testing will be conducted during daylight hours and formation fluids will not be flowed to the surface. All drill-stem-testing operations conducted in an H₂S environment will use the closed chamber method of testing.
- B. There will be no drill stem testing.

Devon Energy Corp. Company Call List

<u>Artesia (575)</u>	<u>Cellular</u>	<u>Office</u>	<u>Home</u>
Foreman – Robert Bell.....	748-7448.....	748-0178.....	746-2991
Asst. Foreman –Tommy Polly.....	748-5290.....	748-0165.....	748-2846
Don Mayberry.....	748-5235.....	748-0164.....	746-4945
Montral Walker.....	390-5182.....	748-0193.....	(936) 414-6246
Engineer – Marcos Ortiz.....	(405) 317-0666.....	(405) 552-8152.....	(405) 381-4350

Agency Call List

<u>Lea County (575)</u>	<u>Hobbs</u>	
	Lea County Communication Authority	393-3981
	State Police	392-5588
	City Police	397-9265
	Sheriff’s Office	393-2515
	Ambulance	911
	Fire Department	397-9308
	LEPC (Local Emergency Planning Committee).....	393-2870
	NMOCD.....	393-6161
	US Bureau of Land Management	393-3612

<u>Eddy County (575)</u>	<u>Carlsbad</u>	
	State Police	885-3137
	City Police	885-2111
	Sheriff’s Office	887-7551
	Ambulance	911
	Fire Department	885-2111
	LEPC (Local Emergency Planning Committee).....	887-3798
	US Bureau of Land Management	887-6544
	NM Emergency Response Commission (Santa Fe)	(505) 476-9600
	24 HR	(505) 827-9126
	National Emergency Response Center (Washington, DC)	(800) 424-8802

Emergency Services

	Boots & Coots IWC	(800)-256-9688 or (281) 931-8884
	Cudd Pressure Control.....	(915) 699-0139 or (915) 563-3356
	Halliburton	(575) 746-2757
	B. J. Services.....	(575) 746-3569
<i>Give</i>	Native Air – Emergency Helicopter – Hobbs.....	(575) 392-6429
<i>GPS</i>	Flight For Life - Lubbock, TX	(806) 743-9911
<i>position:</i>	Aerocare - Lubbock, TX	(806) 747-8923
	Med Flight Air Amb - Albuquerque, NM	(575) 842-4433
	Lifeguard Air Med Svc. Albuquerque, NM	(575) 272-3115

Prepared in conjunction with
Dave Small



Devon Energy - 2 Well Pad Rig Location Layout Safety Equipment Location

Prevailing Wind
Direction S, SW

CAUTION
H₂S Poison Gas
May Be Present

Secondary Egress

Frac Tank & Water Storage

175 ft

Closed Loop
Equip

Mud Logger

Volume Tanks

Process Tanks

Shakers

4" Panic line 150ft from wellbore
Mud/Gas Separator

FLARE
IGNITER

Flare stack with
Electronic Igniter

Pipe Racks

Mud Storage

Diesel Tank

Generator

Generator

Generator

VFD House

Parts House

Mud Pump

Mud Pump

Water Tank

Trip Tank

Choke

(Remotely operated)

Rig

Floor

210 ft

H₂S Sensor Beneath
Rig Floor

Draw works

Spool

BOP Skid

HPU/Accumulator

Driller's Cabin

Parts House

260 ft

NORTH

Location Dimensions
470 ft x 350 ft
Scale: 1 inch = 50 ft

○ Wellhead Location

175 ft

★ Primary Briefing Area

CAUTION
H₂S Poison Gas
May Be Present

Crew Housing

Change House

Rig Manager House

Potable
Water

Co Man Housing

Directional Housing


- | | | | |
|--|--|--|---|
| | Wind Indicators | | Self-Contained Breathing Apparatus (SCBA) |
| | Location Entrance Warning Sign used to control location in event of an emergency | | H ₂ S Sensors Located Around the Rig |
| | Safe Briefing Area | | H ₂ S Monitor Control/ Alarm box |



devon

Proposed Interim Site Reclamation


Devon Energy Production Co.
Rigel 20 FC 8H
635' FSL & 45' FWL
Sec. 21-T19S-R31E
Eddy County, NM



Proposed Reclamation Area



Scale: 1in = 60ft.



SURFACE USE PLAN

Devon Energy Production Company, LP

Rigel 20 Fed Com 8H

Surface Location: 635 FSL & 45 FWL, Unit M, Sec 21 T19S R31E, Eddy, NM

Bottom hole Location: 400 FSL & 340' FWL, Unit M, Sec 20 T19S R31E, Eddy, NM

1. Existing Roads:

- a. The well site and elevation plat for the proposed well are reflected on the "Site Map". The well was staked by Madron Surveyors.
- b. All roads into the location are depicted on the "Vicinity Map". Existing roads will be maintained and kept the same or better condition than before operations began.
- c. Directions to Location: From the intersection of CR 222 (Shugart Rd) and CR 248 (Lusk Plant Rd) go south on CR 222 3.75 miles to caliche lease road on right, go north 0.75 miles to intersection, take right go east along north side of existing pad 0.45 miles, road ends at existing Tandem Energy pad, site lies ~400' NW.

2. New or Reconstructed Access Roads:

- a. The "Site Map" shows the existing County Road and ~ 150' new proposed access road and will be constructed as follows..
- b. The maximum width of the road will be 14'. It will be crowned and made of 6" of rolled and compacted caliche. Water will be deflected, as necessary, to avoid accumulation and prevent surface erosion.
- c. Surface material will be native caliche. This material will be obtained from a BLM approved pit nearest in proximity to the location. The average grade will be approximately 1%.
- d. No cattle guards, grates or fence cuts will be required. No turnouts are planned.

3. Location of Existing Wells:

One Mile Radius Plat shows all existing and proposed wells within a one-mile radius of the proposed location. See attached plat.

4. Location of Existing and/or Proposed Production Facilities:

- a. In the event the well is found productive, the Rigel 20 Fed Com 3H tank battery located in Section 20, T19S R31E will be utilized and the necessary production equipment will be installed at the well site. ~~All flowlines will follow the road and if impossible a sundry notice will be filed with your office depicting whereabouts.~~ *12-20-2013*
- b. If necessary, the well will be operated by means of an electric prime mover. ~~Electric power poles will be set along side of the access road.~~ If said power poles are needed, a plat and a sundry notice will be filed with your office. *12-20-2013*
- c. All flow lines will adhere to API standards.
- d. If the well is productive, rehabilitation plans are as follows:
 - i. The original topsoil from the well site will be returned to the location. The drill site will then be contoured as close as possible to the original state.

5. Location and Types of Water Supply:

This location will be drilled using a combination of water mud systems (outlined in the Drilling Program). The water will be obtained from commercial water stations in the area and hauled to location by transport truck using the existing and proposed roads shown on the "Vicinity Map". On occasion, water will be obtained from a pre-existing water well, running a pump directly to the drill rig. In these cases where a poly pipeline is used to transport water for drilling purposes, proper authorizations will be secured. If a poly pipeline is used, the size, distance, and map showing route will be provided to the BLM via sundry notice.

6. Construction Materials:

Obtaining caliche: One primary way of obtaining caliche to build locations and roads will be by "turning over" the location. This means caliche will be obtained from the actual well site. Actual amounts will vary for each pad. The procedure below has been approved by BLM personnel:

- a. The top 6 inches of topsoil is pushed off and stockpiled along the side of the location.
- b. Subsoil is removed and stockpiled within the surveyed well pad.
- c. When caliche is found, material will be stock piled within the pad site to build the location and road.
- d. Then subsoil is pushed back in the hole and caliche is spread accordingly across entire location and road.
- e. Once well is drilled, the stock piled top soil will be used for interim reclamation and spread along areas where caliche is picked up and the location size is reduced.
- f. Neither caliche, nor subsoil will be stock piled outside of the well pad. Topsoil will be stockpiled along the edge of the pad as depicted in the Well Site Layout or survey plat.

In the event that no caliche is found onsite, caliche will be hauled in from a BLM approved caliche pit or other established mineral pit. A BLM mineral material permit will be acquired prior to obtaining any mineral material from BLM pits or land.

7. Methods of Handling Waste Material:

- a. Drill cuttings will be safely contained in a closed loop system and disposed of properly at a NMOCD approved disposal site.
- b. All trash, junk and other waste material will be contained in trash cages or trash bins to prevent scattering. When the job is completed all contents will be removed and disposed of in an approved sanitary landfill.
- c. The supplier, including broken sacks, will pick up salts remaining after completion of well.
- d. A Porto-john will be provided for the rig crews. This equipment will be properly maintained during the drilling and completion operations and will be removed when all operations are complete.
- e. Remaining drilling fluids will be sent to a closed loop system. Water produced during completion will be put into a closed loop system. Oil and condensate produced will be put into a storage tank and sold.
- f. Disposal of fluids to be transported by the following companies:
 - i. American Production Service Inc, Odessa TX
 - ii. Gandy Corporation, Lovington NM
 - iii. I & W Inc, Loco Hill NM
 - iv. Jims Water Service of Co Inc, Denver CO

8. Ancillary Facilities: No campsite or other facilities will be constructed as a result of this well.

9. Well Site Layout

- a. Plat shows proposed well site layout with dimensions of the pad layout.
- b. This exhibit indicated proposed location of sump pits and living facilities.
- c. Mud pits in the active circulating system will be steel pits.
- d. A closed loop system will be utilized.
- e. If a ~~pit or~~ closed loop system is utilized, Devon will comply and provide a copy of the Design Plan to the BLM. 12-20-2013

10. Plans for Surface Reclamation

- a. After concluding the drilling and/or completion operations, if the well is found non-commercial, the caliche will be removed from the pad and transported to the original caliche pit or used for other drilling locations. The road will be reclaimed as directed by the BLM. The original top soil will again be returned to the pad and contoured, as close as possible, to the original topography. We will use a closed loop system.
- b. The location and road will be rehabilitated as recommended by the BLM.
- c. If the well is deemed commercially productive, caliche from areas of the pad site not required for operations will be reclaimed. The original top soil will be returned to the area of the drill pad not necessary to operate the well. These unused areas of the drill pad will be contoured, as close as possible, to match the original topography.
- d. All disturbed areas not needed for active support of production operations will undergo interim reclamation. The portions of the cleared well site not needed for operational and safety purposes will be recontoured to a final or intermediate contour that blends with the surrounding topography as much as possible. Topsoil will be respread over areas not needed for all-weather operations.

10. Surface Ownership

- a. The surface is owned by the US Government and is administered by the Bureau of Land Management. The surface is multiple use with the primary uses of the region for the grazing of livestock and the production of oil and gas.
- b. The proposed road routes and the surface location will be restored as directed by the BLM.

11. Other Information:

- a. The area surrounding the well site is grassland. The topsoil is very sandy in nature. The vegetation is moderately sparse with native prairie grass, sage bush, yucca and miscellaneous weeds. No wildlife was observed but it is likely that deer, rabbits, coyotes, and rodents traverse the area.
- b. There is no permanent or live water in the general proximity of the location.
- c. There are no dwellings within 2 miles of location.
- d. A Cultural Resources Examination will be completed by the Permian Basin Cultural Resource Fund in lieu of being required to conduct a Class III Survey for cultural resources associated with their project within the BLM office in Carlsbad, New Mexico.

13. Bond Coverage:

Bond Coverage is Nationwide, Bond # is CO-1104; NMB-000801

Operators Representative:

The Devon Energy Production Company, L.P. representatives responsible for ensuring compliance of the surface use plan are listed below.

Justin Lazzari
Operations Engineer Advisor
Devon Energy Production Company, L.P.
333 W. Sheridan
Oklahoma City, OK 73102-8260

(405) 228-8466 (Office)
(405) 464-9261 (Cellular)

Jerry Mathews
Superintendent
Devon Energy Production Company, L.P.
6488 Seven Rivers Hwy
Artesia, NM 88211-0250

(505) 748-0161 (Office)
(505) 748-5234 (Cellular)

PECOS DISTRICT CONDITIONS OF APPROVAL

OPERATOR'S NAME:	Devon Energy Production Company, LP
LEASE NO.:	NMLC-063642A
WELL NAME & NO.:	Rigel 20 Fed Com 8H
SURFACE HOLE FOOTAGE:	0635' FSL & 0045' FWL
BOTTOM HOLE FOOTAGE:	0400' FSL & 0340' FWL Sec. 20, T. 19 S., R 31 E.
LOCATION:	Section 21, T. 19 S., R 31 E., NMPM
COUNTY:	Eddy County, New Mexico

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- General Provisions**
- Permit Expiration**
- Archaeology, Paleontology, and Historical Sites**
- Noxious Weeds**
- Special Requirements**
 - Hackberry Lake Special Recreation Management Area (OHV)
 - Lesser Prairie-Chicken Timing Stipulations
 - Ground-level Abandoned Well Marker
 - Communitization Agreement
- Construction**
 - Notification
 - Topsoil
 - Closed Loop System
 - Federal Mineral Material Pits
 - Well Pads
 - Roads
- Road Section Diagram**
- Drilling**
 - Cement Requirements
 - H2S Requirements
 - Capitan Reef
 - Logging Requirements
 - Waste Material and Fluids
- Production (Post Drilling)**
 - Well Structures & Facilities
 - Pipelines
 - Electric Lines
- Interim Reclamation**
- Final Abandonment & Reclamation**

I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

V. SPECIAL REQUIREMENT(S)

Hackberry Lake Special Recreation Management Area (OHV)

This project falls within 100 yards of an existing or proposed trail. All pipelines (including surface lines) shall be buried a minimum of 24 inches under all roads, "two-tracks," and trails. Burial of the pipe will continue for 20 feet on each side of each crossing. Power poles and associated ground structures (poles, guy wires) will not be placed within 20 feet of recreation trails. Guy wires must be equipped with a sleeve, tape or other industry approved apparatus that is highly visible during the day and reflective at night. Appropriate safety signage will be in place during all phases of the project. Upon completion of construction, the road shall be returned to pre-construction condition with no bumps or dips. All vehicle and equipment operators will observe speed limits and practice responsible defensive driving habits.

Timing Limitation Stipulation / Condition of Approval for lesser prairie-chicken:

Oil and gas activities including 3-D geophysical exploration, and drilling will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Additionally, no new drilling will be allowed within up to 200 meters of leks known at the time of permitting. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 feet from the source of the noise.

Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well. For more installation details, contact the Carlsbad Field Office at 575-234-5972.

Communitization Agreement

A Communitization Agreement covering the acreage dedicated to this well must be filed for approval with the BLM. The effective date of the agreement shall be prior to any sales. In addition, the well sign shall include the surface and bottom hole lease numbers. If the Communitization Agreement number is known, it shall also be on the sign. If not, it shall be placed on the sign when the sign is replaced.

VI. CONSTRUCTION

A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. TOPSOIL

The operator shall stockpile the topsoil in a low profile manner in order to prevent wind/water erosion of the topsoil. The topsoil to be stripped is approximately 6 inches in depth. The topsoil will be used for interim and final reclamation.

C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation.

The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

F. EXCLOSURE FENCING (CELLARS & PITS)

Exclosure Fencing

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For

examples of enclosure fencing design, refer to BLM's Oil and Gas Gold Book, Enclosure Fence Illustrations, Figure 1, Page 18.)

G. ON LEASE ACCESS ROADS

Road Width

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning


Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

Ditching

Ditching shall be required on both sides of the road.

Turnouts

Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall be constructed on all blind curves. Turnouts shall conform to the following diagram:




Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill out sloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

Culvert Installations

Appropriately sized culvert(s) shall be installed at the deep waterway channel flow crossing.

Cattleguards

An appropriately sized cattleguard(s) sufficient to carry out the project shall be installed and maintained at fence crossing(s).

Any existing cattleguard(s) on the access road shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattleguard(s) that are in place and are utilized during lease operations.

A gate shall be constructed and fastened securely to H-braces.

Fence Requirement


Where entry is required across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting.

The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fence(s).

Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Figure 1 – Cross Sections and Plans For Typical Road Sections



VII. DRILLING

A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

Eddy County

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,
(575) 361-2822

1. A Hydrogen Sulfide (H₂S) Drilling Plan shall be activated 500 feet prior to drilling into the Yates formation. **As a result, the Hydrogen Sulfide area must meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM. Operator has stated that they will have monitoring equipment in place prior to drilling out of the surface shoe.**
2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. **If the drilling rig is removed without approval – an Incident of Non-Compliance will be written and will be a “Major” violation.**
3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works is located, this does not include the dog house or stairway area.
4. **The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.**

B. CASING

Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need

prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.).

Centralizers required on surface casing per Onshore Order 2.III.B.1.f.

Wait on cement (WOC) time prior to drilling out for a primary cement job will be a minimum 18 hours for a water basin, 24 hours in the potash area, or 500 pounds compressive strength, whichever is greater for all casing strings. DURING THIS WOC TIME, NO DRILL PIPE, ETC. SHALL BE RUN IN THE HOLE. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. IF OPERATOR DOES NOT HAVE THE WELL SPECIFIC CEMENT DETAILS ONSITE PRIOR TO PUMPING THE CEMENT FOR EACH CASING STRING, THE WOC WILL BE 30 HOURS. See individual casing strings for details regarding lead cement slurry requirements.

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

Capitan Reef

Possibility of water flows in the Artesia Group, Salado, and Delaware.

Possibility of lost circulation in the Artesia Group, Capitan Reef, and Delaware.

1. The **20** inch surface casing shall be set at approximately **440** feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface. **If salt is encountered, set casing at least 25 feet above the salt.**
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.**
 - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
 - d. If cement falls back, remedial cementing will be done prior to drilling out that string.
2. The minimum required fill of cement behind the **13-3/8** inch 1st intermediate casing is:

Cement to surface. If cement does not circulate see B.1.a, c-d above.

3. The minimum required fill of cement behind the **9-5/8** inch 2nd intermediate casing is:

Operator has proposed DV tool at depth of 2445'. Operator is to submit sundry if DV tool depth varies by more than 100' from approved depth.

a. First stage to DV tool:

Cement to circulate. If cement does not circulate, contact the appropriate BLM office before proceeding with second stage cement job. Operator should have plans as to how they will achieve circulation on the next stage.

b. Second stage above DV tool:

Cement to surface. If cement does not circulate see B.1.a, c-d above. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to Capitan Reef. Excess calculates to 3% - Additional cement may be required.**

Centralizers required on horizontal leg, must be type for horizontal service and a minimum of one every other joint.

4. The minimum required fill of cement behind the **5-1/2** inch production casing is:

Operator has proposed DV tool at depth of 5000'. Operator is to submit sundry if DV tool depth varies by more than 100' from approved depth.

a. First stage to DV tool:

Cement to circulate. If cement does not circulate, contact the appropriate BLM office before proceeding with second stage cement job. Operator should have plans as to how they will achieve approved top of cement on the next stage.

b. Second stage above DV tool:

Cement should tie-back at least **50 feet above the Capitan Reef**. Operator shall provide method of verification.

4. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

C. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. Variance approved to use flex line from BOP to choke manifold. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. **Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.** If the BLM inspector questions the straightness of the hose, a BLM engineer will be contacted and will review in the field or via picture supplied by inspector to determine if changes are required (operator shall expect delays if this occurs).
3. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **2000 (2M)** psi.
 - a. **For surface casing only:** If the BOP/BOPE is to be tested against casing, the wait on cement (WOC) time for that casing is to be met (see WOC statement at start of casing section). Independent service company required.
4. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the **13-3/8** 1st intermediate casing shoe shall be **3000 (3M)** psi.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
 - b. The tests shall be done by an independent service company utilizing a test plug **not a cup or J-packer**. The operator also has the option of utilizing an

independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (18 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).

- c. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- d. The results of the test shall be reported to the appropriate BLM office.
- e. All tests are required to be recorded on a calibrated test chart. **A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.**
- f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.

D. DRILL STEM TEST

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

E. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

JAM 020714

VIII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Exclosure Netting (Open-top Tanks)

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

Chemical and Fuel Secondary Containment and Exclosure Screening

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

Open-Vent Exhaust Stack Exclosures

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

Containment Structures

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the

largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

Painting Requirement

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

B. PIPELINES (Not applied for in the APD a sundry will be required prior to constructing any pipeline)

C. ELECTRIC LINES (Not applied for in the APD)

IX. INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

X. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well.

Seed Mixture 2, for Sandy Sites

The holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed will be done in accordance with State law (s) and within nine (9) months prior to purchase. Commercial seed will be either certified or registered seed. The seed container will be tagged in accordance with State law(s) and available for inspection by the authorized officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). The holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. The seeding will be repeated until a satisfactory stand is established as determined by the authorized officer. Evaluation of growth will not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed* per acre:

<u>Species</u>	<u>lb/acre</u>
Sand dropseed (<i>Sporobolus cryptandrus</i>)	1.0
Sand love grass (<i>Eragrostis trichodes</i>)	1.0
Plains bristlegrass (<i>Setaria macrostachya</i>)	2.0

*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed