

OCD Artesia  
**NM OIL CONSERVATION**  
ARTESIA DISTRICT

FORM APPROVED  
OMB No. 1004-0137  
Expires October 31, 2014

**UNORTHODOX  
LOCATION**

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

JUN 06 2014

**APPLICATION FOR PERMIT TO DRILL OR REENTER**

RECEIVED

5. Lease Serial No. **TES 66-19**  
NMNM100342  
6. If Indian, Allottee or Tribe Name

1a. Type of Work: ☒ DRILL ☐ REENTER

7. If Unit or CA Agreement, Name and No.

1b. Type of Well: ☒ Oil Well ☐ Gas Well ☐ Other ☒ Single Zone ☐ Multiple Zone

8. Lease Name and Well No. **<38871>**  
Airbus 12 Federal #3H

2. Name of Operator

COG Operating LLC.

**<229137>**

9. API Well No.

**30-015-42412**

3a. Address

2208 West Main Street  
Artesia, NM 88210

3b. Phone No. (include area code)

575-748-6940

10. Field and Pool, or Exploratory **<29290>**  
Greenwood; Bone Spring

4. Location of Well (Report location clearly and in accordance with any State requirements.)\*

At surface 190' FSL & 1980' FWL Unit Letter C [NENW] SHL

At proposed prod. Zone 330' FNL & 1980' FWL Unit Letter N [SESW] BHL

11. Sec., T.R.M. or Blk and Survey or Area

Sec. 12 - T19S - R31E

14. Distance in miles and direction from nearest town or post office\*

Approximately 10 miles from Loco Hills

12. County or Parish

Eddy County

13. State

NM

15. Distance from proposed\*  
location to nearest  
property or lease line, ft.  
(Also to nearest drig. Unit line, if any)

190'

16. No. of acres in lease

320

17. Spacing Unit dedicated to this well

160

18. Distance from location\*  
to nearest well, drilling, completed,  
applied for, on this lease, ft.

SHL: 1620' BHL: 1264'

Closest to the wellbore: 160'

19. Proposed Depth

TVD: 9,000' MD: 13,701'

20. BLM/BIA Bond No. on file

NMB000740 & NMB000215

21. Elevations (Show whether DF, KDB, RT, GL, etc.)

3600.7' GL

22. Approximate date work will start\*

7/1/2013

23. Estimated duration

30 days

**24. Attachments**

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, shall be attached to this form:

1. Well plat certified by a registered surveyor.

2. A Drilling Plan

3. A Surface Use Plan (If the location is on National Forest System Lands, the  
SUPO shall be filed with the appropriate Forest Service Office).

4. Bond to cover the operations unless covered by an existing bond on file (see  
Item 20 above).

5. Operator certification

6. Such other site specific information and/or plans as may be required by the  
authorized officer.

25. Signature

*Mayte Reyes*

Name (Printed/Typed)

Mayte Reyes

Date

3/15/2013

Title

Regulatory Analyst

Approved by (Signature)

**Steve Caffey**

Name (Printed/Typed)

Date

**MAY 30 2014**

Title

FIELD MANAGER

Office

CARLSBAD FIELD OFFICE

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to  
conduct operations thereon.

Conditions of approval, if any, are attached.

**APPROVAL FOR TWO YEARS**

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United  
States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

\*(Instructions on page 2)

Capitan Controlled Water Basin

Approval Subject to General Requirements  
& Special Stipulations Attached


SEE ATTACHED FOR  
CONDITIONS OF APPROVAL

*Surface Use Plan*  
*COG Operating, LLC*  
*Airbus 12 Federal #3H*  
*SL: 190' FSL & 1980' FWL      UL N*  
*Section 12, T19S, R31E*  
*BHL: 330' FNL & 1980' FWL      UL C*  
*Section 12, T19S, R31E*  
*Eddy County, New Mexico*

---

### **OPERATOR CERTIFICATION**

I hereby certify that I, or persons under my direct supervision, have inspected the drill site and access road proposed herein; that I am familiar with the conditions that presently exist; that I have full knowledge of State and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or COG Operating, LLC, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements. Executed this 15th day of May, 2013.

Signed: 

Printed Name: Melanie J. Parker

Position: Regulatory Coordinator

Address: 2208 W. Main Street, Artesia, NM 88210

Telephone: (575) 748-6940

Field Representative (if not above signatory): Rand French

E-mail: [mparker@concho.com](mailto:mparker@concho.com)

Surface Use Plan  
COG Operating, LLC  
Airbus 12 Federal #3H  
SL: 190' FSL & 1980' FWL      UL N  
Section 12, T19S, R31E  
BHL: 330' FNL & 1980' FWL      UL C  
Section 12, T19S, R31E  
Eddy County, New Mexico

---

STATEMENT ACCEPTING RESPONSIBILITY FOR OPERATIONS

The undersigned accepts all applicable terms, conditions, stipulations, and restrictions concerning operations conducted on the leased land or portion thereof, as described below:

Date: May 15, 2013

Lease #: NMNM100342  
Airbus 12 Federal #3H


Legal Description: Sec. 12 – T19S – R31E  
Eddy County, New Mexico

Formation(s): Bone Spring

Bond Coverage: Statewide

BLM Bond File #: NMB000740 & NMB000215

COG OPERATING LLC



Mayte Reyes  
Regulatory Analyst

DISTRICT I  
1625 N. FRANCIS DR., HOHES, NM 87440  
Phone: (505) 892-0161 Fax: (505) 283-0780

DISTRICT II  
1561 W. GRAND AVENUE, ARTERIA, NM 86210  
Phone: (505) 746-1883 Fax: (505) 746-0720

DISTRICT III  
1000 RIO BRAZOS RD., AZTEC, NM 87410  
Phone: (505) 334-0175 Fax: (505) 334-0170

DISTRICT IV  
11685 S. ST. FRANCIS DR., SANTA FE, NM 87505  
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico  
Energy, Minerals & Natural Resources Department  
**OIL CONSERVATION DIVISION**  
11885 SOUTH ST. FRANCIS DR.  
Santa Fe, New Mexico 87505

Form C-102

Revised August 1, 2011

Submit one copy to appropriate

☐ AMENDED REPORT

**WELL LOCATION AND ACREAGE DEDICATION PLAT**

|                                    |  |                                     |
|------------------------------------|--|-------------------------------------|
| API Number<br>30-015- <b>42412</b> | Pool Code<br>29290                         | Pool Name<br>Greenwood; Bone Spring |
| Property Code<br><b>38871</b>      | Property Name<br><b>AIRBUS 12 FEDERAL</b>  | Well Number<br>3H                   |
| OGRID No.<br>229137                | Operator Name<br><b>COG OPERATING, LLC</b> | Elevation<br>3600.7                 |


**Surface Location**

| UL or lot No. | Section | Township | Range | Lot Idn | Feet from the | North/South line | Feet from the | East/West line | County |
|---------------|---------|----------|-------|---------|---------------|------------------|---------------|----------------|--------|
| N             | 12      | 19-S     | 31-E  |         | 190           | SOUTH            | 1980          | WEST           | EDDY   |

**Bottom Hole Location If Different From Surface**

| UL or lot No.          | Section         | Township           | Range     | Lot Idn       | Feet from the | North/South line | Feet from the | East/West line | County |
|------------------------|-----------------|--------------------|-----------|---------------|---------------|------------------|---------------|----------------|--------|
| C                      | 12              | 19-S               | 31-E      |               | 330           | NORTH            | 1980          | WEST           | EDDY   |
| Dedicated Acres<br>160 | Joint or Infill | Consolidation Code | Order No. | S-30<br>13701 |               |                  |               |                |        |

NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED  
OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION




## NEW MEXICO



**FILE: 13-176**

# EXHIBIT 2


## LOCATION VERIFICATION MAP



SEC. 12, TWP. 19S, RGE. 31E  
 SURVEY: N.M.P.M.  
 COUNTY: EDDY STATE: NEW MEXICO  
 DESCRIPTION: AIRBUS 12 FED #3H  
 190' FSL & 1980' FWL

ELEVATION: 3600.7'  
 OPERATOR: COG OPERATING  
 LEASE: AIRBUS 12 FED

W.O. # 13-176




- WELL
- WELL PAD
- PROPOSED ROAD
- EXISTING ROAD

HARCROW SURVEYING, LLC.  
 1107 WATSON, ARTESIA N.M. 88210  
 PH: (575) 513-2570 FAX: (575) 746-2158  
 chad\_harcrow77@yahoo.com



MAP DATE: 4/10/2013

# VICINITY MAP



SEC. 12, TWP. 19S, RGE. 31E  
 SURVEY: N.M.P.M.  
 COUNTY: EDDY STATE: NEW MEXICO  
 DESCRIPTION: AIRBUS 12 FED #3H  
 190' FSL & 1980' FWL

ELEVATION: 3600.7'  
 OPERATOR: COG OPERATING  
 LEASE: AIRBUS 12 FED

W.O. # 13-176



1 IN = 6,000 FT

0 0.5 1 1.5 MILES

● WELL

— Existing Road

□ TOWNSHIP

□ SECTION

HARCROW SURVEYING, LLC  
 1107 WATSON, ARTESIA N.M. 88210  
 PH: (575) 513-2570 FAX: (575) 746-2158  
 chad\_harcrow77@yahoo.com



MAP DATE: 4/10/2013





**COG Operating LLC**  
**DRILLING AND OPERATIONS PROGRAM**  
**Airbus 12 Federal 3H**  
**SHL: 190' FNL & 1980' FWL**  
**BHL: 330' FSL & 1980' FWL**  
**Section 12 T19S R31E**  
**Eddy County, New Mexico**

In conjunction with Form 3160-3, Application for Permit to Drill subject well, COG Operating LLC submits the following eleven items of pertinent information in accordance with BLM requirements.

1. Geological surface formation: Permian
2. The estimated tops of geologic markers & estimated depths at which anticipated water, oil or gas formations are expected to be encountered are as follows:

|              |         |     |
|--------------|---------|-----|
| Fresh Water  | 130'    |     |
| Rustler      | 746'    |     |
| Top of Salt  | 829'    |     |
| Base of Salt | 2,401'  |     |
| Yates        | 2,660'  |     |
| Seven Rivers | 2,844'  |     |
| Grayburg     | 3,929'  |     |
| Delaware     | 4,734'  | Oil |
| Bone Spring  | 6,773'  | Oil |
| Wolfcamp     | 9,958'  |     |
| TD TVD       | 9,185'  |     |
| TD MD        | 13,563' |     |

No other formations are expected to give up oil, gas or fresh water in measurable quantities. The surface fresh water sands will be protected by setting 13-3/8" casing at 865' ~~771'~~ and circulating cement back to surface. All intervals will be isolated by setting 5 1/2" casing to total depth and tying back cement to a minimum of 500' into 9-5/8" csg.

**3. Proposed Casing Program: All casing is new and API approved**

See COA

| Hole Size | Depths                    | Section                    | OD Casing | New/Used | Wt    | Collar | Grade | Collapse Design Factor | Burst Design Factor | Tension Design Factor |
|-----------|---------------------------|----------------------------|-----------|----------|-------|--------|-------|------------------------|---------------------|-----------------------|
| 17 1/2"   | 0' - <del>771'</del> 865' | Surface                    | 13 3/8"   | New      | 54.5# | STC    | J-55  | 1.125                  | 1.125               | 1.6                   |
| 12 1/4"   | 0' - 2,860'               | Intrmd                     | 9 5/8"    | New      | 36#   | LTC    | J-55  | 1.125                  | 1.125               | 1.6                   |
| 7 7/8"    | 0' - 13,563'              | Production Curve & Lateral | 5 1/2"    | New      | 17#   | LTC    | P-110 | 1.125                  | 1.125               | 1.6                   |

- While running all casing strings, the pipe will be kept a minimum of 1/3 full at all times to avoid approaching the collapse pressure of casing.

#### 4. Proposed Cement Program

- a. 13-3/8" Surface
- Lead: 300 sx Class C + 4% Gel + 2% CaCl<sub>2</sub>  
(13.5 ppg / 1.75 cuft/sx)
- Tail: 250 sx Class C + 2% CaCl<sub>2</sub>  
(14.8 ppg / 1.34 cuft/sx)
- \*\*Calculated w/50% excess on OH volumes
- b. 9 5/8" Intermediate:
- Lead: 500 sx Class C + 4% Gel + 2% CaCl<sub>2</sub>  
(13.5 ppg / 1.75 cuft/sx)
- Tail: 250 sx Class C + 2% CaCl<sub>2</sub>  
(14.8 ppg / 1.34 cuft/sx)
- \*\*Calculated w/35% excess on OH volumes
- d. 5 1/2" Production
- Lead: 600 sx 50:50:10 H + Salt+Gilsonite+CFR-3+ HR601  
(11.9 ppg / 2.51 cuft/sx)
- Tail: 950 sx 50:50:2 H +Salt+GasStop +HR601 +CFR-3  
(14.4 ppg / 1.25 cuft/sx)
- \*\*Calculated w/35% excess on OH volumes

- The above cement volumes could be revised pending the caliper measurement.
- The 9-5/8" intermediate string is designed to circulate to surface.
- The production string will tie back a minimum of 500' into 9-5/8" shoe

## 5. Control:

Nipple up on 13 3/8 with annular preventer tested to 50% of rated working pressure by independent tester and the rest of the 2M system tested to 2000 psi.

Nipple up on 9 5/8 with 3M system tested to 3000 psi by independent tester.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. A 2" kill line and a minimum 3" choke line will be included in the drilling spool located below the ram-type BOP. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold with 3000 psi WP rating. A remotely operated choke will be installed before drilling out intermediate shoe.

## 6. Estimated BHP & BHT:

Lateral TD = 4203 psi

Lateral TD= 148°F

**7. Mud Program:** The applicable depths and properties of this system are as follows:

| Depth                      | Type System | Mud Weight | Viscosity (sec) | Waterloss (cc) |
|----------------------------|-------------|------------|-----------------|----------------|
| 0' - 771'                  | Fresh Water | 8.4        | 29              | N.C.           |
| 771' - 2,860'              | Brine       | 10         | 29              | N.C.           |
| 2,860' - 13,563' (Lateral) | Cut Brine   | 8.8 - 9.2  | 29              | N.C.           |

See  
COTA

- The necessary mud products for weight addition and fluid loss control will be on location at all times.
- A visual and electronic mud monitoring system will be rigged up prior to spud to detect changes in the volume of mud system. The electronic system consists of a pit volume total, stroke counter and flow sensor at flow line.
- If weight and/or viscosity are introduced to the mud system a daily mud check will be performed by mud contractor, along with tourly check by rig personnel.
- After setting intermediate casing, a third party gas unit detection system will be installed at the flow line.

#### **8. Auxiliary Well Control and Monitoring Equipment:**

- a. A Kelly cock will be in the drill string at all times.
  - b. A full opening drill pipe stabbing valve having the appropriate connections will be on the rig floor at all times.
  - c. Hydrogen Sulfide detection equipment will be in operation after drilling out the 13 3/8" casing shoe until the 5 1/2" casing is cemented. Breathing equipment will be on location upon drilling the 13 3/8" shoe until total depth is reached.
- See COA*

#### **9. Testing, Logging and Coring Program:**

- a. Drill stem tests will be based on geological sample shows.
- b. If open hole electrical logging is performed, the program will be:
  - i. Total Depth to Intermediate Casing: Dual Laterolog-Micro Laterolog and Gamma Ray. Compensated Neutron – Z Density log with Gamma Ray and Caliper.
  - ii. Total Depth to Surface: Compensated Neutron with Gamma Ray
  - iii. No coring program is planned
  - iv. Additional testing will be initiated subsequent to setting the 5 1/2" production casing. Specific intervals will be targeted based on log evaluation, geological sample shows and drill stem tests.

#### **10. Potential Hazards:**

- a. No abnormal pressures or temperatures are expected. There is no known presence of H2S in this area. If H2S is encountered the operator will comply with the provisions of Onshore Oil and Gas Order No. 6. All personnel will be familiar with all aspects of safe operation of equipment being used to drill this well. No H2S is anticipated to be encountered.
- See COA*

#### **11. Anticipated starting date and Duration of Operations:**

- a. Road and location construction will begin after the BLM has approved the APD. Anticipated spud date will be as soon as possible after BLM approval and as soon as a rig will be available. Move in operations and drilling is expected to take 30 days.



# COG Airbus 12 Fed 3H Rev0 mcs 12Mar13 Proposal Geodetic Report

(Def Plan)



Report Date: March 12, 2013 - 04:28 PM  
Client: COG Operating, Inc.  
Field: NM Eddy County (NAD 27)  
Structure / Slot: COG Airbus 12 Fed 3H / COG Airbus 12 Fed 3H  
Well: COG Airbus 12 Fed 3H  
Borehole: Original Borehole  
UWI / API#: Patriot 6 / Unknown  
Survey Name: COG Airbus 12 Fed 3H Rev0 mcs 12Mar13  
Survey Date: March 12, 2013  
Tort / AHD / DDI / ERD Ratio: 87.540 \* / 4763.652 ft / 5.789 / 0.519  
Coordinate Reference System: NAD27 New Mexico State Plane, Eastern Zone, US Feet  
Location Lat / Long: N 32° 40' 53.91767", W 103° 49' 28.37282"  
Location Grid N/E Y/X: N 612068.400 ftUS, E 656543.700 ftUS  
CRS Grid Convergence Angle: 0.2747 \*  
Grid Scale Factor: 0.99993715

Survey / DLS Computation: Minimum Curvature / Lubinski  
Vertical Section Azimuth: 179.556 \* (Grid North)  
Vertical Section Origin: 0.000 ft, 0.000 ft  
TVD Reference Datum: RKB  
TVD Reference Elevation: 3640.500 ft above MSL  
Seabed / Ground Elevation: 3622.500 ft above MSL  
Magnetic Declination: 7.632 \*  
Total Gravity Field Strength: 998.5039mgm (9.80665 Based)  
Total Magnetic Field Strength: 48665.734 nT  
Magnetic Dip Angle: 60.486 \*  
Declination Date: March 12, 2013  
Magnetic Declination Model: BGGM 2012  
North Reference: Grid North  
Grid Convergence Used: 0.2747 \*  
Total Corr Mag North->Grid North: 7.3568 \*

Local Coord Referenced To: Structure Reference Point

| Comments                   | MD<br>(ft) | Incl<br>(°) | Azim Grid<br>(°) | TVD<br>(ft) | VSEC<br>(ft) | NS<br>(ft) | EW<br>(ft) | DLS<br>("/100ft) | Northing<br>(ftUS) | Easting<br>(ftUS) | Latitude<br>(N/S ° ' ") | Longitude<br>(E/W ° ' ") |
|----------------------------|------------|-------------|------------------|-------------|--------------|------------|------------|------------------|--------------------|-------------------|-------------------------|--------------------------|
| COG Airbus 12 Fed 3H - SHL | 0.00       | 0.00        | 179.56           | 0.00        | 0.00         | 0.00       | 0.00       | N/A              | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 100.00     | 0.00        | 179.56           | 100.00      | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 200.00     | 0.00        | 179.56           | 200.00      | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 300.00     | 0.00        | 179.56           | 300.00      | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 400.00     | 0.00        | 179.56           | 400.00      | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 500.00     | 0.00        | 179.56           | 500.00      | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 600.00     | 0.00        | 179.56           | 600.00      | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 700.00     | 0.00        | 179.56           | 700.00      | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 800.00     | 0.00        | 179.56           | 800.00      | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 900.00     | 0.00        | 179.56           | 900.00      | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 1000.00    | 0.00        | 179.56           | 1000.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 1100.00    | 0.00        | 179.56           | 1100.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 1200.00    | 0.00        | 179.56           | 1200.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 1300.00    | 0.00        | 179.56           | 1300.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 1400.00    | 0.00        | 179.56           | 1400.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 1500.00    | 0.00        | 179.56           | 1500.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 1600.00    | 0.00        | 179.56           | 1600.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 1700.00    | 0.00        | 179.56           | 1700.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 1800.00    | 0.00        | 179.56           | 1800.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 1900.00    | 0.00        | 179.56           | 1900.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 2000.00    | 0.00        | 179.56           | 2000.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 2100.00    | 0.00        | 179.56           | 2100.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 2200.00    | 0.00        | 179.56           | 2200.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 2300.00    | 0.00        | 179.56           | 2300.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 2400.00    | 0.00        | 179.56           | 2400.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 2500.00    | 0.00        | 179.56           | 2500.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 2600.00    | 0.00        | 179.56           | 2600.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 2700.00    | 0.00        | 179.56           | 2700.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 2800.00    | 0.00        | 179.56           | 2800.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 2900.00    | 0.00        | 179.56           | 2900.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 3000.00    | 0.00        | 179.56           | 3000.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 3100.00    | 0.00        | 179.56           | 3100.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 3200.00    | 0.00        | 179.56           | 3200.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 3300.00    | 0.00        | 179.56           | 3300.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 3400.00    | 0.00        | 179.56           | 3400.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 3500.00    | 0.00        | 179.56           | 3500.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 3600.00    | 0.00        | 179.56           | 3600.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 3700.00    | 0.00        | 179.56           | 3700.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 3800.00    | 0.00        | 179.56           | 3800.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 3900.00    | 0.00        | 179.56           | 3900.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 4000.00    | 0.00        | 179.56           | 4000.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 4100.00    | 0.00        | 179.56           | 4100.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 4200.00    | 0.00        | 179.56           | 4200.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 4300.00    | 0.00        | 179.56           | 4300.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 4400.00    | 0.00        | 179.56           | 4400.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 4500.00    | 0.00        | 179.56           | 4500.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 4600.00    | 0.00        | 179.56           | 4600.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 4700.00    | 0.00        | 179.56           | 4700.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 4800.00    | 0.00        | 179.56           | 4800.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 4900.00    | 0.00        | 179.56           | 4900.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 5000.00    | 0.00        | 179.56           | 5000.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 5100.00    | 0.00        | 179.56           | 5100.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 5200.00    | 0.00        | 179.56           | 5200.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 5300.00    | 0.00        | 179.56           | 5300.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 5400.00    | 0.00        | 179.56           | 5400.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 5500.00    | 0.00        | 179.56           | 5500.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 5600.00    | 0.00        | 179.56           | 5600.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 5700.00    | 0.00        | 179.56           | 5700.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 5800.00    | 0.00        | 179.56           | 5800.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 5900.00    | 0.00        | 179.56           | 5900.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 6000.00    | 0.00        | 179.56           | 6000.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 6100.00    | 0.00        | 179.56           | 6100.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 6200.00    | 0.00        | 179.56           | 6200.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 6300.00    | 0.00        | 179.56           | 6300.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 6400.00    | 0.00        | 179.56           | 6400.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 6500.00    | 0.00        | 179.56           | 6500.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 6600.00    | 0.00        | 179.56           | 6600.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 6700.00    | 0.00        | 179.56           | 6700.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 6800.00    | 0.00        | 179.56           | 6800.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 6900.00    | 0.00        | 179.56           | 6900.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 7000.00    | 0.00        | 179.56           | 7000.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |
|                            | 7100.00    | 0.00        | 179.56           | 7100.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | N 32 40 53.92           | W 103 49 28.37           |

| Comments                    | MD<br>(ft) | Incl<br>(°) | Azim Grid<br>(°) | TVD<br>(ft) | VSEC<br>(ft) | NS<br>(ft) | EW<br>(ft) | DLS<br>(°/100ft) | Northing<br>(ftUS) | Easting<br>(ftUS) | Latitude<br>(N/S ° ' '') | Longitude<br>(E/W ° ' '') |
|-----------------------------|------------|-------------|------------------|-------------|--------------|------------|------------|------------------|--------------------|-------------------|--------------------------|---------------------------|
|                             | 7200.00    | 0.00        | 179.56           | 7200.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | 32 40 53.92              | W 103 49 28.37            |
|                             | 7300.00    | 0.00        | 179.56           | 7300.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | 32 40 53.92              | W 103 49 28.37            |
|                             | 7400.00    | 0.00        | 179.56           | 7400.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | 32 40 53.92              | W 103 49 28.37            |
|                             | 7500.00    | 0.00        | 179.56           | 7500.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | 32 40 53.92              | W 103 49 28.37            |
|                             | 7600.00    | 0.00        | 179.56           | 7600.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | 32 40 53.92              | W 103 49 28.37            |
|                             | 7700.00    | 0.00        | 179.56           | 7700.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | 32 40 53.92              | W 103 49 28.37            |
|                             | 7800.00    | 0.00        | 179.56           | 7800.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | 32 40 53.92              | W 103 49 28.37            |
|                             | 7900.00    | 0.00        | 179.56           | 7900.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | 32 40 53.92              | W 103 49 28.37            |
|                             | 8000.00    | 0.00        | 179.56           | 8000.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | 32 40 53.92              | W 103 49 28.37            |
|                             | 8100.00    | 0.00        | 179.56           | 8100.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | 32 40 53.92              | W 103 49 28.37            |
|                             | 8200.00    | 0.00        | 179.56           | 8200.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | 32 40 53.92              | W 103 49 28.37            |
|                             | 8300.00    | 0.00        | 179.56           | 8300.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | 32 40 53.92              | W 103 49 28.37            |
|                             | 8400.00    | 0.00        | 179.56           | 8400.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | 32 40 53.92              | W 103 49 28.37            |
| KOP Build 12"/100ft DLS     | 8500.00    | 0.00        | 179.56           | 8500.00     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | 32 40 53.92              | W 103 49 28.37            |
|                             | 8522.98    | 0.00        | 179.56           | 8522.98     | 0.00         | 0.00       | 0.00       | 0.00             | 612068.40          | 656543.70         | 32 40 53.92              | W 103 49 28.37            |
|                             | 8600.00    | 9.24        | 179.56           | 8599.67     | 6.20         | -6.20      | 0.05       | 12.00            | 612062.20          | 656543.75         | 32 40 53.86              | W 103 49 28.37            |
|                             | 8700.00    | 21.24       | 179.56           | 8695.97     | 32.44        | -32.44     | 0.25       | 12.00            | 612035.96          | 656543.95         | 32 40 53.92              | W 103 49 28.37            |
|                             | 8800.00    | 33.24       | 179.56           | 8784.72     | 78.13        | -78.13     | 0.61       | 12.00            | 611990.27          | 656544.31         | 32 40 53.14              | W 103 49 28.37            |
|                             | 8900.00    | 45.24       | 179.56           | 8862.02     | 141.28       | -141.27    | 1.09       | 12.00            | 611927.14          | 656544.79         | 32 40 52.52              | W 103 49 28.37            |
|                             | 9000.00    | 57.24       | 179.56           | 8924.51     | 219.12       | -219.11    | 1.70       | 12.00            | 611849.31          | 656545.40         | 32 40 51.75              | W 103 49 28.37            |
|                             | 9100.00    | 69.24       | 179.56           | 8969.45     | 308.24       | -308.23    | 2.39       | 12.00            | 611760.19          | 656546.09         | 32 40 50.87              | W 103 49 28.36            |
| Landina Point               | 9200.00    | 81.24       | 179.56           | 8994.88     | 404.77       | -404.76    | 3.14       | 12.00            | 611663.67          | 656546.84         | 32 40 49.61              | W 103 49 28.36            |
|                             | 9252.48    | 87.54       | 179.56           | 9000.00     | 456.97       | -456.96    | 3.54       | 12.00            | 611611.47          | 656547.24         | 32 40 48.40              | W 103 49 28.36            |
|                             | 9300.00    | 87.54       | 179.56           | 9002.04     | 504.45       | -504.43    | 3.91       | 0.00             | 611564.00          | 656547.61         | 32 40 48.93              | W 103 49 28.36            |
|                             | 9400.00    | 87.54       | 179.56           | 9006.34     | 604.36       | -604.34    | 4.68       | 0.00             | 611464.10          | 656548.38         | 32 40 47.92              | W 103 49 28.35            |
|                             | 9500.00    | 87.54       | 179.56           | 9010.63     | 704.26       | -704.24    | 5.46       | 0.00             | 611364.20          | 656549.16         | 32 40 46.95              | W 103 49 28.35            |
|                             | 9600.00    | 87.54       | 179.56           | 9014.92     | 804.17       | -804.15    | 6.23       | 0.00             | 611264.31          | 656549.93         | 32 40 45.96              | W 103 49 28.34            |
|                             | 9700.00    | 87.54       | 179.56           | 9019.21     | 904.08       | -904.05    | 7.00       | 0.00             | 611164.41          | 656550.70         | 32 40 44.97              | W 103 49 28.34            |
|                             | 9800.00    | 87.54       | 179.56           | 9023.50     | 1003.99      | -1003.96   | 7.78       | 0.00             | 611064.51          | 656551.48         | 32 40 43.98              | W 103 49 28.34            |
|                             | 9900.00    | 87.54       | 179.56           | 9027.79     | 1103.89      | -1103.86   | 8.55       | 0.00             | 610964.61          | 656552.25         | 32 40 42.99              | W 103 49 28.33            |
|                             | 10000.00   | 87.54       | 179.56           | 9032.09     | 1203.80      | -1203.77   | 9.33       | 0.00             | 610864.71          | 656553.02         | 32 40 42.01              | W 103 49 28.33            |
|                             | 10100.00   | 87.54       | 179.56           | 9036.38     | 1303.71      | -1303.67   | 10.10      | 0.00             | 610764.81          | 656553.80         | 32 40 41.02              | W 103 49 28.33            |
|                             | 10200.00   | 87.54       | 179.56           | 9040.67     | 1403.62      | -1403.58   | 10.87      | 0.00             | 610664.91          | 656554.57         | 32 40 40.03              | W 103 49 28.32            |
|                             | 10300.00   | 87.54       | 179.56           | 9044.96     | 1503.53      | -1503.48   | 11.65      | 0.00             | 610565.02          | 656555.35         | 32 40 39.04              | W 103 49 28.32            |
|                             | 10400.00   | 87.54       | 179.56           | 9049.25     | 1603.43      | -1603.39   | 12.42      | 0.00             | 610465.12          | 656556.12         | 32 40 38.05              | W 103 49 28.32            |
|                             | 10500.00   | 87.54       | 179.56           | 9053.54     | 1703.34      | -1703.29   | 13.20      | 0.00             | 610365.22          | 656556.89         | 32 40 37.06              | W 103 49 28.31            |
|                             | 10600.00   | 87.54       | 179.56           | 9057.83     | 1803.25      | -1803.20   | 13.97      | 0.00             | 610265.32          | 656557.67         | 32 40 36.08              | W 103 49 28.31            |
|                             | 10700.00   | 87.54       | 179.56           | 9062.13     | 1903.16      | -1903.10   | 14.74      | 0.00             | 610165.42          | 656558.44         | 32 40 35.09              | W 103 49 28.31            |
|                             | 10800.00   | 87.54       | 179.56           | 9066.42     | 2003.07      | -2003.01   | 15.52      | 0.00             | 610065.52          | 656559.22         | 32 40 34.10              | W 103 49 28.30            |
|                             | 10900.00   | 87.54       | 179.56           | 9070.71     | 2102.97      | -2102.92   | 16.29      | 0.00             | 609965.63          | 656559.99         | 32 40 33.11              | W 103 49 28.30            |
|                             | 11000.00   | 87.54       | 179.56           | 9075.00     | 2202.88      | -2202.82   | 17.06      | 0.00             | 609865.73          | 656560.76         | 32 40 32.12              | W 103 49 28.30            |
|                             | 11100.00   | 87.54       | 179.56           | 9079.29     | 2302.79      | -2302.72   | 17.84      | 0.00             | 609765.83          | 656561.54         | 32 40 31.13              | W 103 49 28.29            |
|                             | 11200.00   | 87.54       | 179.56           | 9083.58     | 2402.70      | -2402.62   | 18.61      | 0.00             | 609665.93          | 656562.31         | 32 40 30.14              | W 103 49 28.29            |
|                             | 11300.00   | 87.54       | 179.56           | 9087.88     | 2502.60      | -2502.53   | 19.39      | 0.00             | 609566.03          | 656563.09         | 32 40 29.16              | W 103 49 28.29            |
|                             | 11400.00   | 87.54       | 179.56           | 9092.17     | 2602.51      | -2602.43   | 20.16      | 0.00             | 609466.13          | 656563.86         | 32 40 28.17              | W 103 49 28.28            |
|                             | 11500.00   | 87.54       | 179.56           | 9096.46     | 2702.42      | -2702.34   | 20.93      | 0.00             | 609366.24          | 656564.63         | 32 40 27.18              | W 103 49 28.28            |
|                             | 11600.00   | 87.54       | 179.56           | 9100.75     | 2802.33      | -2802.24   | 21.71      | 0.00             | 609266.34          | 656565.41         | 32 40 26.19              | W 103 49 28.28            |
|                             | 11700.00   | 87.54       | 179.56           | 9105.04     | 2902.24      | -2902.15   | 22.48      | 0.00             | 609166.44          | 656566.18         | 32 40 25.20              | W 103 49 28.27            |
|                             | 11800.00   | 87.54       | 179.56           | 9109.33     | 3002.14      | -3002.05   | 23.26      | 0.00             | 609066.54          | 656566.96         | 32 40 24.21              | W 103 49 28.27            |
|                             | 11900.00   | 87.54       | 179.56           | 9113.63     | 3102.05      | -3101.96   | 24.03      | 0.00             | 608966.64          | 656567.73         | 32 40 23.22              | W 103 49 28.27            |
|                             | 12000.00   | 87.54       | 179.56           | 9117.92     | 3201.96      | -3201.86   | 24.80      | 0.00             | 608866.74          | 656568.50         | 32 40 22.24              | W 103 49 28.26            |
|                             | 12100.00   | 87.54       | 179.56           | 9122.21     | 3301.87      | -3301.77   | 25.58      | 0.00             | 608766.85          | 656569.28         | 32 40 21.25              | W 103 49 28.26            |
|                             | 12200.00   | 87.54       | 179.56           | 9126.50     | 3401.78      | -3401.67   | 26.35      | 0.00             | 608666.95          | 656570.05         | 32 40 20.26              | W 103 49 28.26            |
|                             | 12300.00   | 87.54       | 179.56           | 9130.79     | 3501.68      | -3501.58   | 27.13      | 0.00             | 608567.05          | 656570.82         | 32 40 19.27              | W 103 49 28.25            |
|                             | 12400.00   | 87.54       | 179.56           | 9135.08     | 3601.59      | -3601.48   | 27.90      | 0.00             | 608467.15          | 656571.60         | 32 40 18.28              | W 103 49 28.25            |
|                             | 12500.00   | 87.54       | 179.56           | 9139.37     | 3701.50      | -3701.39   | 28.67      | 0.00             | 608367.25          | 656572.37         | 32 40 17.29              | W 103 49 28.24            |
|                             | 12600.00   | 87.54       | 179.56           | 9143.67     | 3801.41      | -3801.29   | 29.45      | 0.00             | 608267.35          | 656573.15         | 32 40 16.30              | W 103 49 28.24            |
|                             | 12700.00   | 87.54       | 179.56           | 9147.96     | 3901.31      | -3901.20   | 30.22      | 0.00             | 608167.46          | 656573.92         | 32 40 15.32              | W 103 49 28.24            |
|                             | 12800.00   | 87.54       | 179.56           | 9152.25     | 4001.22      | -4001.10   | 31.00      | 0.00             | 608067.56          | 656574.69         | 32 40 14.33              | W 103 49 28.23            |
|                             | 12900.00   | 87.54       | 179.56           | 9156.54     | 4101.13      | -4101.01   | 31.77      | 0.00             | 607967.66          | 656575.47         | 32 40 13.34              | W 103 49 28.23            |
|                             | 13000.00   | 87.54       | 179.56           | 9160.83     | 4201.04      | -4200.91   | 32.54      | 0.00             | 607867.76          | 656576.24         | 32 40 12.35              | W 103 49 28.23            |
|                             | 13100.00   | 87.54       | 179.56           | 9165.12     | 4300.95      | -4300.82   | 33.32      | 0.00             | 607767.86          | 656577.02         | 32 40 11.36              | W 103 49 28.22            |
|                             | 13200.00   | 87.54       | 179.56           | 9169.42     | 4400.85      | -4400.72   | 34.09      | 0.00             | 607667.96          | 656577.79         | 32 40 10.37              | W 103 49 28.22            |
|                             | 13300.00   | 87.54       | 179.56           | 9173.71     | 4500.76      | -4500.63   | 34.87      | 0.00             | 607568.06          | 656578.56         | 32 40 9.38               | W 103 49 28.22            |
|                             | 13400.00   | 87.54       | 179.56           | 9178.00     | 4600.67      | -4600.53   | 35.64      | 0.00             | 607468.17          | 656579.34         | 32 40 8.40               | W 103 49 28.21            |
|                             | 13500.00   | 87.54       | 179.56           | 9182.29     | 4700.58      | -4700.44   | 36.41      | 0.00             | 607368.27          | 656580.11         | 32 40 7.41               | W 103 49 28.21            |
| COG Airbus 12 Fed 3H - PBHL | 13563.13   | 87.54       | 179.56           | 9185.00     | 4763.65      | -4763.51   | 36.90      | 0.00             | 607305.20          | 656580.60         | 32 40 6.78               | W 103 49 28.21            |

Survey Type:

Def Plan

Survey Error Model:

ISWISA Rev 0 \*\*\* 3-D 95.000% Confidence 2.7955 sigma

Survey Program:


| Description | MD From<br>(ft) | MD To<br>(ft) | EOU Freq<br>(ft) | Hole Size<br>(in) | Casing Diameter<br>(in) | Survey Tool Type       | Borehole / Survey  |
|-------------|-----------------|---------------|------------------|-------------------|-------------------------|------------------------|--|
|             | 0.000           | 18.000        | 1/100.000        | 30.000            | 30.000                  | SLB_MWD-STD-Depth Only | Original Borehole / COG Airbus<br>12 Fed 3H Rev0 mcs 12Mar13 |
|             | 18.000          | 13563.132     | 1/100.000        | 30.000            | 30.000                  | SLB_MWD-STD            | Original Borehole / COG Airbus<br>12 Fed 3H Rev0 mcs 12Mar13 |

|                     |  |                |  |                          |  |                     |  |                        |  |                        |  |                       |  |                                |  |
|---------------------|--|----------------|--|--------------------------|--|---------------------|--|------------------------|--|------------------------|--|-----------------------|--|--------------------------------|--|
| WELL                |  |                |  | FIELD                    |  |                     |  | STRUCTURE              |  |                        |  |                       |  |                                |  |
| Airbus 12 Fed 3H    |  |                |  | Eddy County, NM (NAD 27) |  |                     |  | Patriot 6              |  |                        |  |                       |  |                                |  |
| Magnetic Parameters |  |                |  |                          |  |                     |  | Surface Location       |  |                        |  | Miscellaneous         |  |                                |  |
| Model: UDOM 2012    |  | Dip 69.486°    |  | Date March 12, 2013      |  | Lat N 32 40 53.918  |  | North: 612068.40 RJL   |  | Grid Conv. 0.375°      |  | Slot Airbus 12 Fed 3H |  | TVD Ref RJL(3443.58 above MSL) |  |
|                     |  | Mag Dec 7.632° |  | FS 48665.707             |  | Lon W 103 49 28.373 |  | Easting: 656543.70 RJL |  | Scale Fact. 0.99992713 |  | Rev Rev0 mcs 12Mar13  |  | Entry Date March 12, 2013      |  |


Legend

|                         |                   |
|-------------------------|-------------------|
| SHL                     | 0.00' 179.56° az  |
| KOP Build 12"/100ft DLS | 8523 MD 8523 TVD  |
| Landing Point           | 9252 MD 9000 TVD  |
| PBHL                    | 13563 MD 9185 TVD |

Grid North  
Tot Corr (M→G 7.3568°)  
Mag Dec (7.632°)  
Grid Conv (0.275°)



| Comments                | Survey | MD       | Inc   | Azim   | TVD     | SSTVD    | VS      | NS       | EW    | Longitude       | Latitude       | Easting   | Northing  | DLS   | Tool Face |
|-------------------------|--------|----------|-------|--------|---------|----------|---------|----------|-------|-----------------|----------------|-----------|-----------|-------|-----------|
| SHL                     |        | 0.00     | 0.00  | 179.56 | 0.00    | -3640.50 | 0.00    | 0.00     | 0.00  | W 103 49 28.373 | N 32 40 53.918 | 656543.70 | 612068.40 |       | 179.56    |
| KOP Build 12"/100ft DLS |        | 8522.98  | 0.00  | 179.56 | 8522.98 | 4882.48  | 0.00    | 0.00     | 0.00  | W 103 49 28.373 | N 32 40 53.918 | 656543.70 | 612068.40 | 0.00  | 179.56    |
| Landing Point           |        | 9252.48  | 87.54 | 179.56 | 9000.00 | 5359.50  | 456.97  | -456.96  | 3.54  | W 103 49 28.357 | N 32 40 49.396 | 656547.24 | 611611.47 | 12.00 | 0.00      |
| PBHL                    |        | 13563.13 | 87.54 | 179.56 | 9185.00 | 5544.50  | 4763.65 | -4763.51 | 36.90 | W 103 49 28.208 | N 32 40 6.783  | 656580.60 | 607305.20 | 0.00  |           |



Drawn By: MShaffer  
Date Created: March 12, 2013 04:32:37 PM  
Checked By: \_\_\_\_\_  
Approved By: \_\_\_\_\_  
Approval Date: \_\_\_\_\_



---

*New Mexico Office of the State Engineer*  
**Water Column/Average Depth to Water**

---

No records found.

**PLSS Search:**

**Section(s):** 12

**Township:** 19S

**Range:** 31E

---

The data is furnished by the NMOSE/ISC and is accepted by the recipient with the expressed understanding that the OSE/ISC make no warranties, expressed or implied, concerning the accuracy, completeness, reliability, usability, or suitability for any particular purpose of the data.

---



# New Mexico Office of the State Engineer Water Column/Average Depth to Water

(A CLW##### in the  
POD suffix indicates the  
POD has been replaced  
& no longer serves a  
water right file.)

(R=POD has  
been replaced,  
O=orphaned,  
C=the file is  
closed)

(quarters are 1=NW 2=NE 3=SW 4=SE)

(quarters are smallest to largest) (NAD83 UTM in meters) (In feet)

| POD Number    | POD Code | Subbasin | County | Q 64 | Q 16 | Q 4 | Sec | Tws | Rng    | X        | Y   | Depth Well | Depth Water | Water Column |
|---------------|----------|----------|--------|------|------|-----|-----|-----|--------|----------|-----|------------|-------------|--------------|
| CP 00641 EXPL |          |          | ED     | 4    | 1    | 36  | 19S | 31E | 610247 | 3609634* | 300 | 130        | 170         |              |
| CP 00642 EXPL |          |          | ED     | 2    | 2    | 25  | 19S | 31E | 611025 | 3611657* | 250 |            |             |              |
| CP 00829      |          |          | LE     | 2    | 4    | 16  | 19S | 31E | 606165 | 3614009* | 120 |            |             |              |

Average Depth to Water: 130 feet

Minimum Depth: 130 feet

Maximum Depth: 130 feet

**Record Count: 3**

**PLSS Search:**

Township: 19S


Range: 31E

\*UTM location was derived from PLSS - see Help


The data is furnished by the NMOSE/ISC and is accepted by the recipient with the expressed understanding that the OSE/ISC make no warranties, expressed or implied, concerning the accuracy, completeness, reliability, usability, or suitability for any particular purpose of the data.




# 2,000 psi BOP Schematic




# 3,000 psi BOP Schematic



# 2M Choke Manifold Equipment



# 3M Choke Manifold Equipment



COG Operating LLC

Rig Plat & Closed Loop Equipment Diagram

Well pad will be 340' X 340'  
with cellar in center of pad




Exhibit 1

District I  
1625 N. French Dr., Hobbs, NM 88240  
District II  
1301 W. Grand Avenue, Artesia, NM 88210  
District III  
1000 Rio Brazos Road, Aztec, NM 87410  
District IV  
1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico  
Energy Minerals and Natural Resources  
Department  
Oil Conservation Division  
1220 South St. Francis Dr.  
Santa Fe, NM 87505

Form C-144 CLEZ  
July 21, 2008

For closed-loop systems that only use above ground steel tanks or haul-off bins and propose to implement waste removal for closure, submit to the appropriate NMOCD District Office.

**Closed-Loop System Permit or Closure Plan Application**

*(that only use above ground steel tanks or haul-off bins and propose to implement waste removal for closure)*

Type of action: ☒ Permit ☐ Closure

**Instructions:** Please submit one application (Form C-144 CLEZ) per individual closed-loop system request. For any application request other than for a closed-loop system that only use above ground steel tanks or haul-off bins and propose to implement waste removal for closure, please submit a Form C-144.

Please be advised that approval of this request does not relieve the operator of liability should operations result in pollution of surface water, ground water or the environment. Nor does approval relieve the operator of its responsibility to comply with any other applicable governmental authority's rules, regulations or ordinances.

1.  
Operator: COG Operating LLC OGRID #: 229137  
Address: 2208 West Main Street, Artesia, NM 88211-0227  
Facility or well name: Airbus 12 Federal #3H  
API Number: \_\_\_\_\_ OCD Permit Number: \_\_\_\_\_  
U/L or Qtr/Qtr Unit C, NENW Section 12 Township 19S Range 31E County: Eddy  
Center of Proposed Design: Latitude \_\_\_\_\_ Longitude \_\_\_\_\_ NAD: ☐ 1927 ☐ 1983  
Surface Owner: ☒ Federal ☐ State ☐ Private ☐ Tribal Trust or Indian Allotment

2.  
☒ **Closed-loop System:** Subsection H of 19.15.17.11 NMAC  
Operation: ☒ Drilling a new well ☐ Workover or Drilling (Applies to activities which require prior approval of a permit or notice of intent) ☐ P&A  
☐ Above Ground Steel Tanks or ☒ Haul-off Bins

3.  
**Signs:** Subsection C of 19.15.17.11 NMAC  
☐ 12"x 24", 2" lettering, providing Operator's name, site location, and emergency telephone numbers  
☒ Signed in compliance with 19.15.3.103 NMAC

4.  
**Closed-loop Systems Permit Application Attachment Checklist:** Subsection B of 19.15.17.9 NMAC  
**Instructions:** Each of the following items must be attached to the application. Please indicate, by a check mark in the box, that the documents are attached.  
☒ Design Plan - based upon the appropriate requirements of 19.15.17.11 NMAC  
☒ Operating and Maintenance Plan - based upon the appropriate requirements of 19.15.17.12 NMAC  
☒ Closure Plan (Please complete Box 5) - based upon the appropriate requirements of Subsection C of 19.15.17.9 NMAC and 19.15.17.13 NMAC  
☐ Previously Approved Design (attach copy of design) API Number: \_\_\_\_\_  
☐ Previously Approved Operating and Maintenance Plan API Number: \_\_\_\_\_

5.  
**Waste Removal Closure For Closed-loop Systems That Utilize Above Ground Steel Tanks or Haul-off Bins Only:** (19.15.17.13.D NMAC)  
**Instructions:** Please identify the facility or facilities for the disposal of liquids, drilling fluids and drill cuttings. Use attachment if more than two facilities are required.  
Disposal Facility Name: Controlled Recovery, Inc. Disposal Facility Permit Number: R-9166  
Disposal Facility Name: \_\_\_\_\_ Disposal Facility Permit Number: \_\_\_\_\_  
Will any of the proposed closed-loop system operations and associated activities occur on or in areas that will not be used for future service and operations?  
☐ Yes (If yes, please provide the information below) ☒ No  
Required for impacted areas which will not be used for future service and operations:  
☐ Soil Backfill and Cover Design Specifications - based upon the appropriate requirements of Subsection H of 19.15.17.13 NMAC  
☐ Re-vegetation Plan - based upon the appropriate requirements of Subsection I of 19.15.17.13 NMAC  
☐ Site Reclamation Plan - based upon the appropriate requirements of Subsection G of 19.15.17.13 NMAC

6.  
**Operator Application Certification:**  
I hereby certify that the information submitted with this application is true, accurate and complete to the best of my knowledge and belief.  
Name (Print): Mayte Reyes Title: Regulatory Analyst  
Signature: Mayte Reyes Date: 3/15/2013  
e-mail address: mreyes1@conchoresource.com Telephone: 575-748-6945

7.  
**OCD Approval:** ☐ Permit Application (including closure plan) ☐ Closure Plan (only)

**OCD Representative Signature:** \_\_\_\_\_ **Approval Date:** \_\_\_\_\_

**Title:** \_\_\_\_\_ **OCD Permit Number:** \_\_\_\_\_

8.  
**Closure Report (required within 60 days of closure completion):** Subsection K of 19.15.17.13 NMAC

*Instructions: Operators are required to obtain an approved closure plan prior to implementing any closure activities and submitting the closure report. The closure report is required to be submitted to the division within 60 days of the completion of the closure activities. Please do not complete this section of the form until an approved closure plan has been obtained and the closure activities have been completed.*

☐ **Closure Completion Date:** \_\_\_\_\_

9.  
**Closure Report Regarding Waste Removal Closure For Closed-loop Systems That Utilize Above Ground Steel Tanks or Haul-off Bins Only:**

*Instructions: Please indentify the facility or facilities for where the liquids, drilling fluids and drill cuttings were disposed. Use attachment if more than two facilities were utilized.*

Disposal Facility Name: \_\_\_\_\_ Disposal Facility Permit Number: \_\_\_\_\_

Disposal Facility Name: \_\_\_\_\_ Disposal Facility Permit Number: \_\_\_\_\_

Were the closed-loop system operations and associated activities performed on or in areas that *will not* be used for future service and operations?

☐ Yes (If yes, please demonstrate compliance to the items below) ☐ No

*Required for impacted areas which will not be used for future service and operations:*

☐ Site Reclamation (Photo Documentation)

☐ Soil Backfilling and Cover Installation

☐ Re-vegetation Application Rates and Seeding Technique

10.  
**Operator Closure Certification:**

I hereby certify that the information and attachments submitted with this closure report is true, accurate and complete to the best of my knowledge and belief. I also certify that the closure complies with all applicable closure requirements and conditions specified in the approved closure plan.

Name (Print): \_\_\_\_\_ Title: \_\_\_\_\_

Signature: \_\_\_\_\_ Date: \_\_\_\_\_

e-mail address: \_\_\_\_\_ Telephone: \_\_\_\_\_

**Design Plan  
Operating and Maintenance Plan  
Closure Plan  
Airbus 12 Federal 3H  
SHL: 190' FNL & 1980' FWL  
BHL: 330' FSL & 1980' FWL  
Section 12 T19S R31E  
Eddy County, New Mexico**

COG Operating LLC will be using all above ground steel pits for fluid and cuttings while drilling. If any tank develops a leak we will have immediate visual discovery, we would then transfer the fluid to another tank then remove any contaminated soil and dispose of it in the cuttings bins for transportation. All leaks should be kept to less than 5 barrels. Rig crews will monitor the tanks at all times.

Equipment List:

- 2- Mongoose Shale Shakers
- 1- 414 Centrifuge
- 1- 518 Centrifuge
- 2- Roll Off Bins w/ Tracks
- 2- 500 BBL Frac Tanks

During drilling operations all liquids, drilling fluids and cuttings will be hauled off via CRI (Controlled Recovery Inc.) Permit R-9166 or any other approved facility.






COG Operating LLC  
2208 West Main  
Artesia, NM 88210

## Production Facility Layout

Airbus 12 Federal #3H  
Section 12-T19S-R31E



North



Scale

■ = 5' x 5'

Legend

- = 500 BBL Steel Oil Tank
- ⊙ = 500 BBL Steel Water Tank
- ⊙ = 6' x 20' Heater

Exhibit 3

**COG OPERATING LLC**  
**HYDROGEN SULFIDE DRILLING OPERATIONS PLAN**

**1. HYDROGEN SULFIDE TRAINING**

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on this well:

- a. The hazards and characteristics of hydrogen sulfide (H<sub>2</sub>S).
- b. The proper use and maintenance of personal protective equipment and life support systems.
- c. The proper use of H<sub>2</sub>S detectors, alarms, warning systems, briefing areas, evacuation procedures, and prevailing winds.
- d. The proper techniques for first aid and rescue procedures.

In addition, supervisory personnel will be trained in the following areas:

- a. The effects of H<sub>2</sub>S on metal components. If high tensile tubulars are to be used, personnel will be trained in their special maintenance requirements.
- b. Corrective action and shut-in procedures when drilling or reworking a well and blowout prevention and well control procedures.
- c. The contents and requirements of the H<sub>2</sub>S Drilling Operations Plan and the Public Protection Plan.

There will be an initial training session just prior to encountering a known or probable H<sub>2</sub>S zone (within 3 days or 500 feet) and weekly H<sub>2</sub>S and well control drills for all personnel in each crew. The initial training session shall include a review of the site specific H<sub>2</sub>S Drilling Operations Plan and the Public Protection Plan. This plan shall be available at the well site. All personnel will be required to carry documentation that they have received the proper training.

**2. H<sub>2</sub>S SAFETY EQUIPMENT AND SYSTEMS**

Note: All H<sub>2</sub>S safety equipment and systems will be installed, tested, and operational when drilling reaches a depth of 500 feet above, or three days prior to penetrating the first zone containing or reasonably expected to contain H<sub>2</sub>S.

- a. Well Control Equipment:
  - Flare line.
  - Choke manifold. *with remotely operated choke.*
  - Blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit.
  - Auxiliary equipment to include: annular preventer, mud-gas separator, rotating head.

- b. Protective equipment for essential personnel:  
Mark II Surviveair 30-minute units located in the dog house and at briefing areas.
- c. H2S detection and monitoring equipment:  
2 - portable H2S monitor positioned on location for best coverage and response. These units have warning lights and audible sirens when H2S levels of 20 ppm are reached.
- d. Visual warning systems:  
Caution/Danger signs shall be posted on roads providing direct access to location. Signs will be painted a high visibility yellow with black lettering of sufficient size to be readable at a reasonable distance from the immediate location. Bilingual signs will be used, when appropriate. See example attached.
- e. Mud Program:  
The mud program has been designed to minimize the volume of H2S circulated to the surface.
- f. Metallurgy:  
All drill strings, casings, tubing, wellhead, blowout preventers, drilling spool, kill lines, choke manifold and lines, and valves shall be suitable for H2S service.
- g. Communication:  
Company vehicles equipped with cellular telephone.

COG OPERATING LLC has conducted a review to determine if an H2S contingency plan is required for the above referenced well. We were able to conclude that any potential hazardous volume would be minimal. H2S concentrations of wells in this area from surface to TD are low enough; therefore, we do not believe that an H2S contingency plan is necessary.

# **W A R N I N G**

**YOU ARE ENTERING AN H<sub>2</sub>S AREA  
AUTHORIZED PERSONNEL ONLY**

- 1. BEARDS OR CONTACT LENSES NOT ALLOWED***
- 2. HARD HATS REQUIRED***
- 3. SMOKING IN DESIGNATED AREAS ONLY***
- 4. BE WIND CONSCIOUS AT ALL TIMES***
- 5. CK WITH COG OPERATING LLC FOREMAN AT MAIN OFFICE***

**COG OPERATING LLC**

**1-575-748-6940**

## **EMERGENCY CALL LIST**

|                          | <b><u>OFFICE</u></b> | <b><u>MOBILE</u></b> |
|--------------------------|----------------------|----------------------|
| COG OPERATING LLC OFFICE | 575-748-6940         |                      |
| SHERYL BAKER             | 575-748-6940         | 432-934-1873         |
| KENT GREENWAY            | 575-746-2010         | 432-557-1694         |
| SETH WILD                | 575-748-6940         | 432-528-3633         |
| WALTER ROYE              | 575-748-6940         | 432-934-1886         |


## **EMERGENCY RESPONSE NUMBERS**

|  | <b><u>OFFICE</u></b> |
|--|----------------------|
| STATE POLICE                                     | 575-748-9718         |
| EDDY COUNTY SHERIFF                              | 575-746-2701         |
| EMERGENCY MEDICAL SERVICES (AMBULANCE)           | 911 or 575-746-2701  |
| EDDY COUNTY EMERGENCY MANAGEMENT (HARRY BURGESS) | 575-887-9511         |
| STATE EMERGENCY RESPONSE CENTER (SERC)           | 575-476-9620         |
| CARLSBAD POLICE DEPARTMENT                       | 575-885-2111         |
| CARLSBAD FIRE DEPARTMENT                         | 575-885-3125         |
| NEW MEXICO OIL CONSERVATION DIVISION             | 575-748-1283         |
| INDIAN FIRE & SAFETY                             | 800-530-8693         |
| HALLIBURTON SERVICES                             | 800-844-8451         |

COG Operating LLC  
H<sub>2</sub>S Equipment Schematic  
Terrain: Shinnery sand hills.

Secondary egress.

Well pad will be 340' X 340'  
with cellar in center of pad



*Surface Use Plan  
COG Operating, LLC  
Airbus 12 Federal #3H  
SL: 190' FSL & 1980' FWL      UL N  
Section 12, T19S, R31E  
BHL: 330' FNL & 1980' FWL      UL C  
Section 12, T19S, R31E  
Eddy County, New Mexico*

---

# **Surface Use & Operating Plan**

## **Airbus 12 Federal #3H**

- Surface Tenant: Richardson Cattle Co.; P O Box 487, Carlsbad, NM 88221.
- New Road: approximately 368'
- Flow Line: on well pad
- Facilities: will be constructed on well pad – see Exhibit 3

### **Well Site Information**

V Door: East

Topsoil: East

Interim Reclamation: North & East

### **Notes**

**Onsite:** On-site was done by Tanner Nygren (BLM); Rand French and Gerald Herrera (COG) on March 21, 2013.

## **SURFACE USE AND OPERATING PLAN**

### **1. Existing & Proposed Access Roads**

- A. The well site survey and elevation plat for the proposed well is attached with this application. It was staked by Harcrow Surveying, Artesia, NM.
- B. All roads to the location are shown in the Location Verification Map – Exhibit 2. The existing lease roads are illustrated and are adequate for travel during drilling and production operations. Upgrading existing roads prior to drilling the well will be done where necessary. The road route to the well site is depicted in Exhibit #2. The road shown in Exhibit #2 will be used to access the well.
- C. Directions to location: See 600 x 600 plat
- D. Routine grading and maintenance of existing roads will be conducted as necessary to maintain their condition as long as any operations continue on this lease. Roads will be maintained according to specifications in section 2A of this Surface Use and Operating Plan.

### **2. Proposed Access Road:**

The Elevation Plat shows that 41' of new access road from the proposed Liberator Federal Com #3H will be required for this location. There is 327' of new access road proposed from existing lease road to the Liberator Federal Com #3H. If any road is required it will be constructed as follows:

- A. The maximum width of the running surface will be 14'. The road will be crowned, ditched and constructed of 6" rolled and compacted caliche. Ditches will be at 3:1 slope and 4 feet wide. Water will be diverted where necessary to avoid ponding, prevent erosion, maintain good drainage, and to be consistent with local drainage patterns.
- B. The average grade will be less than 1%.
- C. No turnouts are planned.
- D. No culverts, cattle guard, gates, low water crossings or fence cuts are necessary.
- E. Surfacing material will consist of native caliche. Caliche will be obtained from the actual well site if available. If not available onsite, caliche will be hauled from the nearest BLM approved caliche pit.



**3. Location of Existing Well:**

The One-Mile Radius Map shows existing wells within a one-mile radius of surface hole location and the bottom hole location.

According to records found in OCD online, there is one well producing from the Atoka formation, there is three wells producing from the Strawn formation, there is two wells producing from the Delaware formation, there is two wells producing from the Yates-Seven Rivers formation, there is one well producing from the Upper Penn formation, there are numerous wells producing from the Morrow formation, there are numerous wells producing from the Grayburg formation, and numerous wells producing from the Bone Spring formation within the one-mile radius area.

**4. Location of Existing and/or Proposed Facilities:**

- A. COG Operating LLC does not operate a production facility on this lease.
- B. If the well is productive, contemplated facilities will be as follows:
  - 1) A tank battery and facilities will be constructed as shown on Exhibit 3.
  - 2) The tank battery and facilities including all flow lines and piping will be installed according to API specifications.
  - 3) Any additional caliche will be obtained from the actual well site. If caliche does not exist or is not plentiful from the well site, the caliche will be hauled from a BLM approved caliche pit. Any additional construction materials will be purchased from contractors.
  - 4) It will be necessary to run electric power if this well is productive. Power will be provided by Xcel Energy and they will submit a separate plan and ROW for service to the well location.
  - 5) If the well is productive, rehabilitation plans will include the following:
    - The original topsoil from the well site will be returned to the location, and the site will be re-contoured as close as possible to the original site.

**5. Location and Type of Water Supply:**

The well will be drilled with combination brine and fresh water mud system as outlined in the drilling program. The water will be obtained from commercial water stations in the area and hauled to location by transport truck over the existing and proposed access roads shown in Exhibit #1. If a

commercial fresh water source is nearby, fast line may be laid along existing road ROW's and fresh water pumped to the well. No water well will be drilled on the location.

**6. Source of Construction Materials and Location "Turn-Over" Procedure:**

Obtaining caliche: The primary way of obtaining caliche to build locations and roads will be by "turning over" the location. This means, caliche will be obtained from the actual well sight. A caliche permit will be obtained from BLM prior to pushing up any caliche. 2400 cu. Yards is max amount of caliche needed for pad and roads. Amount will vary for each pad. The procedure below has been approved by BLM personnel:

- A. The top 6 inches of topsoil is pushed off and stockpiled along the side of the location.
- B. An approximate 160' X 160' area is used within the proposed well site to remove caliche.
- C. Subsoil is removed and stockpiled along the entire length of one side of a 340' x 340' pad.
- D. When caliche is found, material will be stock piled within the pad site to build the location and road.
- E. Then subsoil is pushed back in the hole and caliche is spread accordingly across entire location and road.
- F. Once well is drilled, the stock piled top soil will be used for interim reclamation and spread along areas where caliche is picked up and the location size is reduced. Neither caliche nor subsoil will be stock piled outside of the well pad. Topsoil will be stockpiled along the edge of the pad as depicted in attached plat.

In the event that no caliche is found onsite, caliche will be hauled in from a BLM approved caliche pit or other source.

**7. Methods of Handling Water Disposal:**

- A. The well will be drilled utilizing a closed loop mud system. Drill cuttings will be held in roll-off style mud boxes and taken to an NMOCD approved disposal site.
- B. Drilling fluids will be contained in steel mud pits.
- C. Water produced from the well during completion will be held temporarily in steel tanks and then taken to an NMOCD approved commercial disposal facility.

- D. Garbage and trash produced during drilling or completion operations will be collected in a trash bin and hauled to an approved landfill. No toxic waste or hazardous chemicals will be produced by this operation.
- E. Human waste and grey water will need to be properly contained and disposed of. Proper disposal and elimination of waste and grey water may include but are not limited to portable septic systems and/or portable waste gathering systems (i.e. portable toilets).
- F. After the rig is moved out and the well is either completed or abandoned, all waste materials will be cleaned up within 30 days. In the event of a dry hole only a dry hole marker will remain.

**8. Ancillary Facilities:**

No airstrip, campsite or other facilities will be built as a result of the operation on this well.

**9. Well Site Layout:**

- A. The drill pad layout, with elevations staked by Harcrow Surveying, is shown in the Elevation Plat. Dimensions of the pad and pits are shown on the Rig Layout. V door direction is East. Topsoil, if available, will be stockpiled per BLM specifications. Because the pad is almost level no major cuts will be required.
- B. The Rig Layout Closed-Loop exhibit shows the proposed orientation of closed loop system and access road. No permanent living facilities are planned, but a temporary foreman/toolpusher's trailer will be on location during the drilling operations.

**10. Plans for Restoration of the Surface:**

- A. Interim Reclamation will take place after the well has been completed. The pad will be downsized by reclaiming the areas not needed for production operations. The portions of the pad that are not needed for production operations will be re-contoured to its original state as much as possible. The caliche that is removed will be reused to either build another pad site or for road repairs within the lease. The stockpiled topsoil will then be spread out reclaimed area and reseeded with a BLM approved seed mixture. In the event that the well must be worked over or maintained, it may be necessary to drive, park, and/or operate machinery on reclaimed land. This area will be repaired or reclaimed after work is complete.

*Surface Use Plan*  
*COG Operating, LLC*  
*Airbus 12 Federal #3H*  
**SL: 190' FSL & 1980' FWL      UL N**  
*Section 12, T19S, R31E*  
**BHL: 330' FNL & 1980' FWL      UL C**  
*Section 12, T19S, R31E*  
*Eddy County, New Mexico*

---

- B. Final Reclamation: Upon plugging and abandoning the well all caliche for well pad and lease road will be removed and surface will be recountoured to reflect its surroundings as much as possible. Caliche will be recycled for road repair or reused for another well pad within the lease. If any topsoil remains, it will be spread out and the area will be re-seeded with a BLM approved mixture and re-vegetated as per BLM orders.

**11.Surface Ownership:**

- A. The surface is owned by the U.S. Government and is administered by the Bureau of Land Management. The surface is multiple uses with the primary uses of the region for grazing of livestock and the production of oil and gas.
- B. The surface tenant is Richardson Cattle Co., P O Box 487, Carlsbad, NM 88221.
- C. The proposed road routes and surface location will be restored as directed by the BLM

**12.Other Information:**

- A. The area around the well site is grassland and the topsoil is sandy. The vegetation is moderately sparse with native prairie grasses, some mesquite and shinnery oak. No wildlife was observed but it is likely that mule deer, rabbits, coyotes and rodents traverse the area.
- B. There is no permanent or live water in the immediate area.
- C. There are no dwellings within 2 miles of this location.
- D. If needed, a Cultural Resources Examination is being prepared by Southern New Mexico Archaeological Services, Inc. P.O. Box 1, Bent New Mexico, 88314, phone # 505-671-4797 and the results will be forwarded to your office in the near future. Otherwise, COG will be participating in the Permian Basin MOA Program.

**13. Bond Coverage:**

Bond Coverage is Statewide Bonds # NMB000215 and NMB000740

**Surface Use Plan**  
**COG Operating, LLC**  
**Airbus 12 Federal #3H**  
**SL: 190' FSL & 1980' FWL      UL N**  
**Section 12, T19S, R31E**  
**BHL: 330' FNL & 1980' FWL      UL C**  
**Section 12, T19S, R31E**  
**Eddy County, New Mexico**

---

**14. Lessee's and Operator's Representative:**

The COG Operating LLC representative responsible for assuring compliance with the surface use plan is as follows:

Sheryl Baker  
Drilling Superintendent  
COG Operating LLC  
2208 West Main Street  
Artesia, NM 88210  
Phone (575) 748-6940 (office)  
(432) 934-1873 (cell)

Ray Peterson  
Drilling Manager  
COG Operating LLC  
One Concho Center  
600 W Illinois Ave  
Midland, TX 79701  
Phone (432) 685-4304 (office)  
(432) 818-2254 (business)

# PECOS DISTRICT CONDITIONS OF APPROVAL

|                              |  |
|------------------------------|--|
| <b>OPERATOR'S NAME:</b>      | <b>COG Operating LLC</b>                   |
| <b>LEASE NO.:</b>            | <b>NMNM-100342</b>                         |
| <b>WELL NAME &amp; NO.:</b>  | <b>Airbus 12 Federal 3H</b>                |
| <b>SURFACE HOLE FOOTAGE:</b> | <b>0190' FSL &amp; 1980' FWL</b>           |
| <b>BOTTOM HOLE FOOTAGE:</b>  | <b>0330' FNL &amp; 1980' FWL</b>           |
| <b>LOCATION:</b>             | <b>Section 12, T. 19 S., R 31 E., NMPM</b> |
| <b>COUNTY:</b>               | <b>Eddy County, New Mexico</b>             |

## TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- ☐ **General Provisions**
- ☐ **Permit Expiration**
- ☐ **Archaeology, Paleontology, and Historical Sites**
- ☐ **Noxious Weeds**
- ☒ **Special Requirements**
  - Lesser Prairie-Chicken Timing Stipulations
  - Ground-level Abandoned Well Marker
- ☐ **Construction**
  - Notification
  - Topsoil
  - Closed Loop System
  - Federal Mineral Material Pits
  - Well Pads
  - Roads
- ☐ **Road Section Diagram**
- ☒ **Drilling**
  - Cement Requirements
  - H2S Requirements
  - Capitan Reef
  - Logging Requirements
  - Waste Material and Fluids
- ☒ **Production (Post Drilling)**
  - Well Structures & Facilities
- ☐ **Interim Reclamation**
- ☒ **Final Abandonment & Reclamation**

## **I. GENERAL PROVISIONS**

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

## **II. PERMIT EXPIRATION**

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

## **III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES**

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

## **IV. NOXIOUS WEEDS**

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

## **V. SPECIAL REQUIREMENT(S)**

### **Timing Limitation Stipulation/Condition of Approval for Lesser Prairie-Chicken:**

Oil and gas activities including 3-D geophysical exploration, and drilling will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, geophysical exploration other than 3-D operations, and pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Additionally, no new drilling will be allowed within up to 200 meters of leks known at the time of permitting. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 ft. from the source of the noise.

### **Ground-level Abandoned Well Marker to avoid raptor perching:**

Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well. For more installation details, contact the Carlsbad Field Office at 575-234-5972.



## **VI. CONSTRUCTION**

### **A. NOTIFICATION**

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

### **B. TOPSOIL**

The operator shall stockpile the topsoil in a low profile manner in order to prevent wind/water erosion of the topsoil. The topsoil to be stripped is approximately 6 inches in depth. The topsoil will be used for interim and final reclamation.

### **C. CLOSED LOOP SYSTEM**

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

### **D. FEDERAL MINERAL MATERIALS PIT**

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

### **E. WELL PAD SURFACING**

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation.

The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

### **F. ON LEASE ACCESS ROADS**

#### **Road Width**

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of

surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

### **Surfacing**

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

### **Crowning**


Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

### **Ditching**

Ditching shall be required on both sides of the road.

### **Turnouts**

Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall be constructed on all blind curves. Turnouts shall conform to the following diagram:




### **Drainage**

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outsliping and insliping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

#### **Cross Section of a Typical Lead-off Ditch**



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

#### **Formula for Spacing Interval of Lead-off Ditches**

Example - On a 4% road slope that is 400-feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$


#### **Culvert Installations**

Appropriately sized culvert(s) shall be installed at the deep waterway channel flow crossing.

#### **Public Access**

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

**Figure 1 = Cross Sections and Plans For Typical Road Sections**



## VII. DRILLING

### A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ **Eddy County**

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,  
(575) 361-2822

1. **A Hydrogen Sulfide (H<sub>2</sub>S) Drilling Plan shall be activated prior to drilling out the surface shoe. As a result, the Hydrogen Sulfide area must meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM.**
2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. **If the drilling rig is removed without approval – an Incident of Non-Compliance will be written and will be a “Major” violation.**
3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works is located, this does not include the dog house or stairway area.
4. **The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.**

## **B. CASING**

Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.).

**Centralizers required on surface casing per Onshore Order 2.III.B.1.f.**

**Wait on cement (WOC) time prior to drilling out for a primary cement job will be a minimum 18 hours for a water basin, 24 hours in the potash area, or 500 pounds compressive strength, whichever is greater for all casing strings. DURING THIS WOC TIME, NO DRILL PIPE, ETC. SHALL BE RUN IN THE HOLE. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. IF OPERATOR DOES NOT HAVE THE WELL SPECIFIC CEMENT DETAILS ONSITE PRIOR TO PUMPING THE CEMENT FOR EACH CASING STRING, THE WOC WILL BE 30 HOURS. See individual casing strings for details regarding lead cement slurry requirements.**

**No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.**

### **Capitan Reef**

**Possibility of water and brine flows in the Artesia and Salado Groups.**

**Possibility of lost circulation in the Rustler, Artesia Group, Capitan Reef, and Delaware Sands.**

1. **The 13-3/8 inch surface casing shall be set at approximately 865 feet (in a competent bed below the Magenta Dolomite, which is a Member of the Rustler, and if salt is encountered, set casing at least 25 feet above the salt) and cemented to the surface.**
  - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
  - b. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.**
  - c. **Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.**

- d. If cement falls back, remedial cementing will be done prior to drilling out that string.
2. The minimum required fill of cement behind the **9-5/8** inch intermediate casing is:
  - ☒ Cement to surface. If cement does not circulate see B.1.a, c-d above. **Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to Capitan Reef.**

**Centralizers required on horizontal leg, must be type for horizontal service and a minimum of one every other joint.**

3. The minimum required fill of cement behind the **5-1/2** inch production casing is:
  - ☒ Cement should tie-back at least 500 feet into previous casing string. Operator shall provide method of verification.
4. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

#### **C. PRESSURE CONTROL**

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **2000 (2M)** psi.
  - a. **For surface casing only:** If the BOP/BOPE is to be tested against casing, the wait on cement (WOC) time for that casing is to be met (see WOC statement at start of casing section). Independent service company required.
3. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the **9-5/8** intermediate casing shoe shall be **3000 (3M)** psi.

4. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
- a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
  - b. The tests shall be done by an independent service company utilizing a test plug **not a cup or J-packer**. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (18 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
  - c. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock.
  - d. The results of the test shall be reported to the appropriate BLM office.
  - e. All tests are required to be recorded on a calibrated test chart. **A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.**
  - f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.

#### **D. DRILL STEM TEST**

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.



## **E. WASTE MATERIAL AND FLUIDS**

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

**JAM 071513**

## **VIII. PRODUCTION (POST DRILLING)**

### **A. WELL STRUCTURES & FACILITIES**

#### **Placement of Production Facilities**

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

#### **Containment Structures**

The containment structure shall be constructed to hold the capacity of the entire contents of the largest tank, plus 24 hour production, unless more stringent protective requirements are deemed necessary by the Authorized Officer.

#### **Painting Requirement**

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, Shale Green from the BLM Standard Environmental Color Chart (CC-001: June 2008).

## **IX. INTERIM RECLAMATION**

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

## **X. FINAL ABANDONMENT & RECLAMATION**

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well.

## Seed Mixture for LPC Sand/Shinnery Sites

The holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)\* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed will be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed will be either certified or registered seed. The seed container will be tagged in accordance with State law(s) and available for inspection by the authorized officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). The holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. The seeding will be repeated until a satisfactory stand is established as determined by the authorized officer. Evaluation of growth will not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed\* per acre:

| <u>Species</u>      | <u>lb/acre</u> |
|---------------------|----------------|
| Plains Bristlegrass | 5lbs/A         |
| Sand Bluestem       | 5lbs/A         |
| Little Bluestem     | 3lbs/A         |
| Big Bluestem        | 6lbs/A         |
| Plains Coreopsis    | 2lbs/A         |
| Sand Dropseed       | 1lbs/A         |

\*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed