

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT


APPLICATION FOR PERMIT TO DRILL OR REENTER

NM OIL CONSERVATION 15-914
ARTESIA DISTRICT
DEC 09 2015
RECEIVED
FORM APPROVED
No. 1004-0137
Expires October 31, 2014

1a. Type of work: ☒ DRILL ☐ REENTER		5. Lease Serial No. BHL:NMLC 00057055 0005705	
1b. Type of Well: ☒ Oil Well ☐ Gas Well ☐ Other ☒ Single Zone ☐ Multiple Zone		6. If Indian, Allottee or Tribe Name	
2. Name of Operator BOPCO, L.P.		7. If Unit or CA Agreement, Name and No. Poker Lake Unit NMNM 71016X	
3a. Address P.O. Box 2760 Midland, TX 79702		8. Lease Name and Well No. Poker Lake Unit #482H	
3b. Phone No. (include area code) 432-683-2277		9. API Well No. 30-015-43511	
4. Location of Well (Report location clearly and in accordance with any State requirements.) At surface NENW ULC, 382' FNL & 2057' FWL, Lat:N32.136496,Long:W103.887711 At proposed prod. zone 660' FNL,2590'FEL, Sec18,T25S-R30E,Lat:N32.1355,Long:W103.9199		10. Field and Pool, or Exploratory Corral Canyon NE (Delaware)	
11. Sec., T. R. M. or Blk and Survey or Area Sec 16, T25S-R30E		12. County or Parish Eddy County	
13. State NM		14. Distance in miles and direction from nearest town or post office* 12 miles southeast of Malaga, NM	
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 382'		16. No. of acres in lease 1,441.4	
17. Spacing Unit dedicated to this well 320 acres		18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 40'	
19. Proposed Depth 17,144 MD / 7,287 TVD		20. BLM/BIA Bond No. on file COB 000050	
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3,242 GL.		22. Approximate date work will start* 12/01/2015	
23. Estimated duration 25 days		24. Attachments	

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, must be attached to this form:

- Well plat certified by a registered surveyor.
- A Drilling Plan.
- A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office).
- Bond to cover the operations unless covered by an existing bond on file (see Item 20 above).
- Operator certification
- Such other site specific information and/or plans as may be required by the BLM.

25. Signature 	Name (Printed/Typed) Whitney McKee	Date 7/21/15
Title Engineering Assistant		
Approved by (Signature) 	Name (Printed/Typed) STEPHEN J. CAFFEY	Date DEC 01 2015
Title FOR FIELD MANAGER		
Office BLM-CARLSBAD FIELD OFFICE		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

APPROVAL FOR TWO YEARS

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

Witness Surface Casing

*(Instructions on page 2)

Carlsbad Controlled Water Basin

SEE ATTACHED FOR
CONDITIONS OF APPROVAL

APPROVAL SUBJECT TO NM OIL CONSERVATION
GENERAL REQUIREMENTS AND
SPECIAL STIPULATIONS
ATTACHED

RECEIVED

DISTRICT I
1625 N. French Dr., Hobbs, NM 88240
Phone (575) 393-8161 Fax: (575) 393-0720

DISTRICT II
811 S. First St., Artesia, NM 88210
Phone (575) 748-1283 Fax: (575) 748-0720

DISTRICT III
1000 Rio Brazos Rd., Aztec, NM 87410
Phone (505) 334-8178 Fax: (505) 334-8170

DISTRICT IV
1225 S. St. Francis Dr., Santa Fe, NM 87505
Phone (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals and Natural Resources Department

Form C-102
Revised August 1, 2011

Submit one copy to appropriate
District Office

OIL CONSERVATION DIVISION
1225 South St. Francis Dr.
Santa Fe, New Mexico 87505

WELL LOCATION AND ACREAGE DEDICATION PLAT

☐ AMENDED REPORT

API Number 30-015-43511		Pool Code 96209	Pool Name CORRAL CANYON NE (DELAWARE)
Property Code 306402	Property Name POKER LAKE UNIT		Well Number 482H
OGRID No. 260737	Operator Name BOPCO, L.P.		Elevation 3242

Surface Location

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
C	16	25 S	30 E		382	NORTH	2057	WEST	EDDY

Bottom Hole Location If Different From Surface

UL or lot No.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
B	18	25 S	30 E		660	NORTH	2590	EAST	EDDY

Dedicated Acres	Joint or Infill	Consolidation Code	Order No.
320			


NO ALLOWABLE WILL BE ASSIGNED TO THIS COMPLETION UNTIL ALL INTERESTS HAVE BEEN CONSOLIDATED
OR A NON-STANDARD UNIT HAS BEEN APPROVED BY THE DIVISION

BOTTOM HOLE LOCATION
Lat - N 32°08'07.85"
Long - W 103°55'11.90"
NMSPCE- N 413267.0
E 627951.1
(NAD-27)


SURFACE LOCATION
Lat - N 32°08'11.29"
Long - W 103°53'15.76"
NMSPCE- N 413655.2
E 637936.1
(NAD-27)

OPERATOR CERTIFICATION
I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division.

Signature Date
Whitney McKee
Printed Name
wbmckee@basspet.com
Email Address

SURVEYOR CERTIFICATION
I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief.
Date Surveyed
Signature & Seal of Professional Surveyor

Certificate No. 7977
Scale: 1" = 2000'
WO Num.: 31732

SECTION 16, TOWNSHIP 25 SOUTH, RANGE 30 EAST, N.M.P.M.,
EDDY COUNTY, NEW MEXICO.




BOPCO, L.P.
POKER LAKE UNIT 482H
ELEV. - 3242'

Lat - N 32°08'11.29"
Long - W 103°53'15.76"
NMSPCE- N 413655.2
E 637936.1
(NAD-27)

Directions to Location:

FROM TWIN WELLS AND BUCK JACKSON GO NORTHWEST 467'
AND TURN SOUTHWEST 3.27 MILES TO PROPOSED LEASE
ROAD DUE SOUTH.

LOVING, NM IS ± 20 MILES TO THE NORTHWEST OF LOCATION.



BOPCO, L.P. 


REF: POKER LAKE UNIT 482H / WELL PAD TOPO

THE POKER LAKE UNIT 482H LOCATED 382' FROM
THE NORTH LINE AND 2057' FROM THE WEST LINE OF
SECTION 16, TOWNSHIP 25 SOUTH, RANGE 30 EAST,
N.M.P.M., EDDY COUNTY, NEW MEXICO.

basin surveys

P.O. Box 1786 (575) 393-7316 - Office
1120 N. West County Rd. (575) 392-2206 - Fax
Hobbs, New Mexico 88241 basinsurveys.com

SECTION 16, TOWNSHIP 25 SOUTH, RANGE 30 EAST, N.M.P.M.,
EDDY COUNTY, NEW MEXICO.



BOPCO, L.P.

REF: POKER LAKE UNIT 482H / WELL PAD TOPO


THE POKER LAKE UNIT 482H LOCATED 382' FROM
THE NORTH LINE AND 2057' FROM THE WEST LINE OF
SECTION 16, TOWNSHIP 25 SOUTH, RANGE 30 EAST,
N.M.P.M., EDDY COUNTY, NEW MEXICO.

**basin
surveys**

focused on excellence
in the oilfield

P.O. Box 1786
1120 N. West County Rd.
Hobbs, New Mexico 88241

(575) 393-7316 - Office
(575) 392-2206 - Fax
basinsurveys.com



POKER LAKE UNIT 482H

Located 382' FNL and 2057' FWL

Section 16, Township 25 South, Range 30 East,
N.M.P.M., Eddy County, New Mexico.

basin
surveys
focused on excellence

P.O. Box 1786
1120 N. West County Rd.
Hobbs, New Mexico 88241
(575) 393-7316 - Office
(575) 392-2206 - Fax
basinsurveys.com

0' 1000' 2000' 3000' 4000'

SCALE: 1" = 2000'


W.O. Number: KAN 31732

Survey Date: 06-10-2015

YELLOW TINT - USA LAND
BLUE TINT - STATE LAND

BOPCO, L.P.

BOPCO, L.P.



POKER LAKE UNIT 482H

Located 382' FNL and 2057' FWL


Section 16, Township 25 South, Range 30 East,
N.M.P.M., Eddy County, New Mexico.

basin
surveys
focused on excellence

P.O. Box 1786
1120 N. West County Rd.
Hobbs, New Mexico 88241
(575) 393-7316 - Office
(575) 392-2208 - Fax
basinsurveys.com

0 1 MI 2 MI 3 MI 4 MI
SCALE: 1" = 2 MILES
W.O. Number: KAN 31732
Survey Date: 06-10-2015
YELLOW TINT - USA LAND
BLUE TINT - STATE LAND


BOPCO, L.P.



POKER LAKE UNIT 482H BOTTOM

Located 660' FNL and 2590' FEL

Section 18, Township 25 South, Range 30 East,
N.M.P.M., Eddy County, New Mexico.



P.O. Box 1786
1120 N. West County Rd.
Hobbs, New Mexico 88241
(575) 393-7316 - Office
(575) 392-2206 - Fax
basinsurveys.com

0' 1000' 2000' 3000' 4000'
SCALE: 1" = 2000'


W.O. Number: KAN 31732

Survey Date: 06-10-2015

YELLOW TINT - USA LAND
BLUE TINT - STATE LAND

BOPCO, L.P.


EXHIBIT "D"
RIG LAYOUT SCHEMATIC
INCLUSIVE OF CLOSED-LOOP DESIGN PLAN



Flowline Route Diagram 4



Access Road Diagram



BOPCO, L.P., Poker Lake Unit #482H

1. Geologic Formations

TVD of target	7472	Pilot hole depth	NA
MD at TD:	17144	Deepest expected fresh water:	400

The Poker Lake Unit #482H has a nonstandard surface hole location.

Basin

Formation	Depth (TVD) from KB	Water/Mineral Bearing/ Target Zone?	Hazards
Quaternary Fill	Surface	Water	
Rustler	1122	Water	
Top of Salado	1282	Salt	
Base of Salt	3557	Barren	
T/ Delaware Mtn Group	3782	Oil/Gas	
Top Cherry Canyon	4702	Oil/Gas	
T/ Brushy Canyon	5927	Oil/Gas	
T/Lower Brushy Canyon	7322	Target Zone	
Bone Spring 1 Lime	7587	Oil/Gas	

*H₂S, water flows, loss of circulation, abnormal pressures, etc

2. Casing Program

See COA

Hole Size	Casing Interval		Csg Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
	From	To							
17.5"	0	1175 1050	13.375"	54.5	J55	STC	1.97	1.76	15.50
12.25"	0	3700	9.625"	40	J55	LTC	1.20	1.91	5.04
8.75"	0	7708	7"	26	N80	LTC	1.30	1.75	3.12
6.125"	7658	17144	4.5"	11.6	HCP110	LTC	2.16	2.56	3.73
BLM Minimum Safety Factor							1.125	1	1.6 Dry 1.8 Wet

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

An open hole completion system is being used on the Poker Lake Unit #482H

Must have table for contingency casing

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Is casing API approved? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	N

BOPCO, L.P., Poker Lake Unit #482H

Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	N
Is well within the designated 4 string boundary.	N
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 rd string cement tied back 500' into previous casing?	N
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	N
Is 2 nd string set 100' to 600' below the base of salt?	N
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	N
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	N
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	N

2. Cementing Program

Casing	# Sk.	Wt. lb/ gal	Yld ft ³ / sack	H ₂ O gal/sk	500# Comp Strength (hours)	Slurry Description
Surf.	700	13.5	1.75	8.69	14	Lead: Class C +2% CACL + 4% Bentonite + 0.25 LB/SK Cello Flake + 3 lb/sk LCM-1
	340	14.8	1.35	6.35	8	Tail: Class C + 2% CACL + 0.25 LB/Sk CF + 3 LB/Sk LCM-1
Inter.	720	12.9	1.85	9.32	14	Lead: EconoCEM HLC + 5% CaCl + 5#/sk Gilsonite
	200	14.8	1.33	6.34	6	Tail: Class C neat
Prod.	100	11	2.64	14.87	11	1 st Lead: Tuned Light + 0.125 pps Poly – E- Flake
	220	12	2.03	11.41	14	1 st Tail: Class H + 0.5% Halad-344 + 0.25% CFR-3 + 0.5% Econolite
	170	11	2.35	11.7	11	DV Tool 5000' 2 nd stage Primary: Tuned Light + 0.125 pps Poly – E- Flake

DV tool depth(s) will be adjusted based on hole conditions and cement volumes will be adjusted proportionally. DV tool will be set a minimum of 50 feet below previous casing and a minimum of 200 feet above current shoe.

Casing String	TOC	% Excess
Surface	0'	100%
Intermediate	0'	30%
Production	3200'	50%

BOPCO, L.P., Poker Lake Unit #482H

Include Pilot Hole Cementing specs:

Pilot hole depth NA

KOP 6808

4. Pressure Control Equipment

NO	A variance is requested for the use of a diverter on the surface casing. See attached for schematic.
-----------	--

BOP installed and tested before drilling which hole?	Size?	System Rated WP	Type	✓	Tested to:
12-1/4"	13-5/8"	3M	Annular	x	50% of working pressure
			Blind Ram	x	3000
			Pipe Ram	x	
			Double Ram		
			Other*		
			Annular		
			Blind Ram		
			Pipe Ram		
			Double Ram		
			Other*		
			Annular		
			Blind Ram		
			Pipe Ram		
			Double Ram		
			Other*		

*Specify if additional ram is utilized.

BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other

BOPCO, L.P., Poker Lake Unit #482H

accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

	Formation integrity test will be performed per Onshore Order #2. On Exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.i.
X	A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.
N	Are anchors required by manufacturer?
X	A multibowl wellhead is being used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested. After running the 13-3/8" surface casing, a 13-5/8" BOP/BOPE system with a minimum rating of 3M will be installed on the Cameron Multi-Bowl System wellhead. The BOP/BOPE will be pressure tested to 250 psi low and 3,000 psi high after installation on the surface casing which will cover testing requirements for the duration of the well as per Onshore Order #2. The 9-5/8" intermediate casing and 7" production casing will be run with a mandrel hanger through the 13-5/8" BOP/BOPE system without breaking any connections on the BOP/BOPE system and thus not requiring a pressure test. Please find attached wellhead schematic. The field reports from the Cameron representative and the BOP test information will be on location. See attached schematic.

5. Mud Program

Depth		Type	Weight (ppg)	Viscosity	Water Loss
From	To				
0	Surf. shoe	FW Gel	8-9.2	38-70	N/C
Surf csg	Int shoe	Saturated Brine	9.8-10.2	28-30	N/C
Int. shoe	Prod. casing shoe	FW/Gel	8.7-9.0	28-36	N/C
Prod. casing shoe	TD	FW/Gel/Starch	8.7-9.0	28-36	<100

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	PVT/Pason/Visual Monitoring
---	-----------------------------

BOPCO, L.P., Poker Lake Unit #482H

6. Logging and Testing Procedures

Logging, Coring and Testing	
	Will run GR/CNL from TD to surface (horizontal well – vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
X	No Logs are planned based on well control or offset log information.
	Drill stem test? If yes, explain
	Coring? If yes, explain

Additional logs planned	Interval
Resistivity	Int. shoe to KOP
Density	Int. shoe to KOP
CBL	Production casing
Mud log	Intermediate shoe to TD
PEX	

7. Drilling Conditions

Condition	Specify what type and where?
BH Pressure at deepest TVD	3497 psi
Abnormal Temperature	No

Mitigation measure for abnormal conditions. Describe. Standard LCM will be on location to use when needed.

Hydrogen Sulfide (H2S) monitors will be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.	
	H2S is present
X	H2S Plan attached

8. Other facets of operation

Is this a walking operation? If yes, describe. No
 Will be pre-setting casing? If yes, describe. No

Attachments

☒ Directional Plan
☐ Other, describe




WTD - West Texas Division

Location: Eddy County, NM
Field: Poker Lake Unit
Facility: PLU Pad (482.483)


BOPCO, L.P.

Scale 1 inch = 1200 ft

Easting (ft)



Northing (ft)




IGRF (1900.0 to 2020.0)
Magnetic North is 7.30 degrees East of True North (at 7/9/2015)
Grid North is 0.24 degrees East of True North
To correct azimuth from True to Grid subtract 0.24 degrees
To correct azimuth from Magnetic to Grid add 7.06 degrees

Well Profile Data

Design Comment	MD (ft)	Az (°)	Inc (°)	TVD (ft)	Local N (ft)	Local E (ft)	DLS (°/100ft)	VS (ft)
Tie On	20.00	267.774	0.000	20.00	0.00	0.00	0.00	0.00
Est KOP	6808.00	267.774	0.000	6808.00	0.00	0.00	0.00	0.00
70° Curve	7508.00	267.774	70.000	7346.40	-14.84	-376.71	10.00	376.99
200' Tangent	7708.00	267.774	70.000	7414.81	-21.94	-564.51	0.00	564.93
EOC	8039.03	267.774	70.000	7472.00	-34.54	-889.61	6.04	889.28
TL	8097.43	267.774	70.000	7471.40	-36.81	-946.96	2.00	947.67
No. 482H PBHL	17144.89	267.774	70.000	7287.00	-388.23	-9985.71	0.00	9993.25

Plot reference weights as B-1	Grid System: NAD27 / TM New Mexico SP, Eastern Zone (3001), US feet
True vertical depths are referenced to Rig on PLU No. 482H (KB)	North Reference: Grid north
Measured depths are referenced to Rig on PLU No. 482H (KB)	Scale: True distance
Rig on PLU No. 482H (KB) to Mean Sea Level: 3262 feet	Diagrams are in feet
Mean Sea Level to Mud line (At Site: PLU No. 482H): 0 feet	Coordinates are in feet referenced to Sea
Coordinates are in feet referenced to Sea	Created by: BWGentry on 7/9/2015

Scale 1 inch = 1200 ft



No. 482H PBHL: 91.17° Inc, 17144.89ft MD, 7287.00ft TVD, 9993.25ft VS

Vertical Section (ft)
Azimuth 267.77° with reference 0.00 N, 0.00 E

Scale 1 inch = 1200 ft



Planned Wellpath Report

B-1

Page 1 of 6

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION

Operator	WTD - West Texas Division	Slot	PLU No.482H
Area	Eddy County, NM	Well	No.482H
Field	Poker Lake Unit	Wellbore	No.482H PWB
Facility	PLU Pad (482,483)		

REPORT SETUP INFORMATION

Projection System	NAD27 / TM New Mexico SP, Eastern Zone (3001), US feet	Software System	WellArchitect® 4.1.1
North Reference	Grid	User	BWGentry
Scale	0.999931	Report Generated	7/9/2015 at 2:14:57 PM
Convergence at slot	0.24° East	Database/Source file	WellArchitectDB/No.482H_PWB.xml

WELLPATH LOCATION

	Local coordinates		Grid coordinates		Geographic coordinates	
	North[ft]	East[ft]	Easting[US ft]	Northing[US ft]	Latitude	Longitude
Slot Location	-0.60	-20.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W
Facility Reference Pt			637956.10	413655.80	32°08'11.298"N	103°53'15.528"W
Field Reference Pt			675156.40	424489.10	32°09'56.776"N	103°46'02.231"W

WELLPATH DATUM

Calculation method	Minimum curvature	Rig on PLU No.482H (KB) to Facility Vertical Datum	3262.00ft
Horizontal Reference Pt	Slot	Rig on PLU No.482H (KB) to Mean Sea Level	3262.00ft
Vertical Reference Pt	Rig on PLU No.482H (KB)	Rig on PLU No.482H (KB) to Mud Line at Slot (PLU No.482H)	3262.00ft
MD Reference Pt	Rig on PLU No.482H (KB)	Section Origin	N 0.00, E 0.00 ft
Field Vertical Reference	Mean Sea Level	Section Azimuth	267.77°



Planned Wellpath Report

B-1

Page 2 of 6

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION

Operator	WTD - West Texas Division	Slot	PLU No.482H
Area	Eddy County, NM	Well	No.482H
Field	Poker Lake Unit	Wellbore	No.482H PWB
Facility	PLU Pad (482,483)		

WELLPATH DATA (188 stations) † = interpolated/extrapolated station

MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	Grid East [US ft]	Grid North [US ft]	Latitude	Longitude	DLS °/100ft	Comments
0.00†	0.000	267.774	0.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
20.00	0.000	267.774	20.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	Tie On
120.00†	0.000	267.774	120.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
220.00†	0.000	267.774	220.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
320.00†	0.000	267.774	320.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
420.00†	0.000	267.774	420.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
520.00†	0.000	267.774	520.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
620.00†	0.000	267.774	620.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
720.00†	0.000	267.774	720.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
820.00†	0.000	267.774	820.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
920.00†	0.000	267.774	920.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
1020.00†	0.000	267.774	1020.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
1120.00†	0.000	267.774	1120.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
1122.00†	0.000	267.774	1122.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	Rustler
1220.00†	0.000	267.774	1220.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
1282.00†	0.000	267.774	1282.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	Top of Salado
1320.00†	0.000	267.774	1320.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
1420.00†	0.000	267.774	1420.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
1520.00†	0.000	267.774	1520.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
1620.00†	0.000	267.774	1620.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
1720.00†	0.000	267.774	1720.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
1820.00†	0.000	267.774	1820.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
1920.00†	0.000	267.774	1920.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
2020.00†	0.000	267.774	2020.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
2120.00†	0.000	267.774	2120.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
2220.00†	0.000	267.774	2220.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
2320.00†	0.000	267.774	2320.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
2420.00†	0.000	267.774	2420.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
2520.00†	0.000	267.774	2520.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
2620.00†	0.000	267.774	2620.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
2720.00†	0.000	267.774	2720.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
2820.00†	0.000	267.774	2820.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
2920.00†	0.000	267.774	2920.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
3020.00†	0.000	267.774	3020.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
3120.00†	0.000	267.774	3120.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
3220.00†	0.000	267.774	3220.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
3320.00†	0.000	267.774	3320.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
3420.00†	0.000	267.774	3420.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
3520.00†	0.000	267.774	3520.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
3557.00†	0.000	267.774	3557.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	Base of Salt
3620.00†	0.000	267.774	3620.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
3720.00†	0.000	267.774	3720.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
3782.00†	0.000	267.774	3782.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	T/ Delaware Mtn Group
3820.00†	0.000	267.774	3820.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
3920.00†	0.000	267.774	3920.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	



Planned Wellpath Report

B-1

Page 3 of 6

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION

Operator	WTD - West Texas Division	Slot	PLU No.482H
Area	Eddy County, NM	Well	No.482H
Field	Poker Lake Unit	Wellbore	No.482H PWB
Facility	PLU Pad (482,483)		

WELLPATH DATA (188 stations) † = interpolated/extrapolated station

MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	Grid East [US ft]	Grid North [US ft]	Latitude	Longitude	DLS [°/100ft]	Comments
4020.00†	0.000	267.774	4020.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
4120.00†	0.000	267.774	4120.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
4220.00†	0.000	267.774	4220.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
4320.00†	0.000	267.774	4320.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
4420.00†	0.000	267.774	4420.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
4520.00†	0.000	267.774	4520.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
4620.00†	0.000	267.774	4620.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
4702.00†	0.000	267.774	4702.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	Top Cherry Car
4720.00†	0.000	267.774	4720.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
4820.00†	0.000	267.774	4820.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
4920.00†	0.000	267.774	4920.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
5020.00†	0.000	267.774	5020.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
5120.00†	0.000	267.774	5120.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
5220.00†	0.000	267.774	5220.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
5320.00†	0.000	267.774	5320.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
5420.00†	0.000	267.774	5420.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
5520.00†	0.000	267.774	5520.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
5620.00†	0.000	267.774	5620.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
5720.00†	0.000	267.774	5720.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
5820.00†	0.000	267.774	5820.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
5920.00†	0.000	267.774	5920.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
5927.00†	0.000	267.774	5927.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	T/Brushy Canyon
6020.00†	0.000	267.774	6020.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
6120.00†	0.000	267.774	6120.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
6220.00†	0.000	267.774	6220.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
6320.00†	0.000	267.774	6320.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
6420.00†	0.000	267.774	6420.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
6520.00†	0.000	267.774	6520.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
6620.00†	0.000	267.774	6620.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
6720.00†	0.000	267.774	6720.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	
6808.00	0.000	267.774	6808.00	0.00	0.00	0.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W	0.00	Est KOP
6820.00†	1.200	267.774	6820.00	0.13	0.00	-0.13	637935.97	413655.20	32°08'11.293"N	103°53'15.762"W	10.00	
6920.00†	11.200	267.774	6919.29	10.91	-0.42	-10.90	637925.20	413654.78	32°08'11.290"N	103°53'15.887"W	10.00	
7020.00†	21.200	267.774	7015.20	38.78	-1.51	-38.75	637897.36	413653.69	32°08'11.280"N	103°53'16.211"W	10.00	
7120.00†	31.200	267.774	7104.81	82.87	-3.22	-82.81	637853.30	413651.98	32°08'11.265"N	103°53'16.724"W	10.00	
7220.00†	41.200	267.774	7185.40	141.86	-5.51	-141.75	637794.36	413649.69	32°08'11.245"N	103°53'17.409"W	10.00	
7320.00†	51.200	267.774	7254.53	213.94	-8.31	-213.78	637722.34	413646.89	32°08'11.220"N	103°53'18.247"W	10.00	
7420.00†	61.200	267.774	7310.09	296.93	-11.53	-296.71	637639.41	413643.67	32°08'11.191"N	103°53'19.211"W	10.00	
7445.79†	63.779	267.774	7322.00	319.81	-12.42	-319.57	637616.56	413642.78	32°08'11.183"N	103°53'19.477"W	10.00	T/Lower Brushy
7508.00	70.000	267.774	7346.40	376.99	-14.64	-376.71	637559.42	413640.56	32°08'11.164"N	103°53'20.142"W	10.00	70° Curve
7520.00†	70.000	267.774	7350.51	388.27	-15.08	-387.98	637548.15	413640.12	32°08'11.160"N	103°53'20.273"W	0.00	
7620.00†	70.000	267.774	7384.71	482.24	-18.73	-481.88	637454.26	413636.47	32°08'11.128"N	103°53'21.365"W	0.00	
7708.00	70.000	267.774	7414.81	564.93	-21.94	-564.51	637371.63	413633.26	32°08'11.099"N	103°53'22.326"W	0.00	200' Tangent
7720.00†	70.725	267.774	7418.84	576.24	-22.38	-575.80	637360.34	413632.82	32°08'11.095"N	103°53'22.458"W	6.04	
7808.00†	76.042	267.774	7444.00	660.53	-25.66	-660.03	637276.12	413629.55	32°08'11.066"N	103°53'23.437"W	6.04	ETP



Planned Wellpath Report

B-1

Page 4 of 6

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION

Operator	WTD - West Texas Division	Slot	PLU No.482H
Area	Eddy County, NM	Well	No.482H
Field	Poker Lake Unit	Wellbore	No.482H PWB
Facility	PLU Pad (482,483)		

WELLPATH DATA (188 stations) † = interpolated/extrapolated station

MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	Grid East [US ft]	Grid North [US ft]	Latitude	Longitude	DLS [°/100ft]	Comments
7820.00†	76.767	267.774	7446.82	672.19	-26.11	-671.69	637264.46	413629.09	32°08'11.062"N	103°53'23.573"W	6.04	
7920.00†	82.808	267.774	7464.54	770.56	-29.93	-769.98	637166.17	413625.27	32°08'11.029"N	103°53'24.716"W	6.04	
8020.00†	88.850	267.774	7471.81	870.25	-33.80	-869.60	637066.57	413621.40	32°08'10.994"N	103°53'25.875"W	6.04	
8039.03	90.000	267.774	7472.00	889.28	-34.54	-888.61	637047.55	413620.66	32°08'10.988"N	103°53'26.096"W	6.04	EOC
8097.43†	91.168	267.774	7471.40	947.67	-36.81	-946.96	636989.21	413618.39	32°08'10.968"N	103°53'26.775"W	2.00	TL
8120.00†	91.168	267.774	7470.94	970.24	-37.69	-969.51	636966.66	413617.52	32°08'10.960"N	103°53'27.037"W	0.00	
8220.00†	91.168	267.774	7468.91	1070.22	-41.57	-1069.41	636866.76	413613.63	32°08'10.926"N	103°53'28.199"W	0.00	
8320.00†	91.168	267.774	7466.87	1170.20	-45.45	-1169.32	636766.87	413609.75	32°08'10.891"N	103°53'29.361"W	0.00	
8420.00†	91.168	267.774	7464.83	1270.18	-49.34	-1269.22	636666.97	413605.87	32°08'10.857"N	103°53'30.523"W	0.00	
8520.00†	91.168	267.774	7462.79	1370.16	-53.22	-1369.13	636567.07	413601.98	32°08'10.822"N	103°53'31.685"W	0.00	
8620.00†	91.168	267.774	7460.75	1470.14	-57.11	-1469.03	636467.18	413598.10	32°08'10.788"N	103°53'32.847"W	0.00	
8720.00†	91.168	267.774	7458.72	1570.12	-60.99	-1568.93	636367.28	413594.21	32°08'10.754"N	103°53'34.009"W	0.00	
8820.00†	91.168	267.774	7456.68	1670.10	-64.88	-1668.84	636267.38	413590.33	32°08'10.719"N	103°53'35.171"W	0.00	
8920.00†	91.168	267.774	7454.64	1770.08	-68.76	-1768.74	636167.49	413586.45	32°08'10.685"N	103°53'36.333"W	0.00	
9020.00†	91.168	267.774	7452.60	1870.06	-72.64	-1868.64	636067.59	413582.56	32°08'10.650"N	103°53'37.495"W	0.00	
9120.00†	91.168	267.774	7450.56	1970.04	-76.53	-1968.55	635967.69	413578.68	32°08'10.616"N	103°53'38.657"W	0.00	
9220.00†	91.168	267.774	7448.52	2070.01	-80.41	-2068.45	635867.80	413574.79	32°08'10.582"N	103°53'39.819"W	0.00	
9320.00†	91.168	267.774	7446.49	2169.99	-84.30	-2168.36	635767.90	413570.91	32°08'10.547"N	103°53'40.981"W	0.00	
9420.00†	91.168	267.774	7444.45	2269.97	-88.18	-2268.26	635668.00	413567.03	32°08'10.513"N	103°53'42.143"W	0.00	
9520.00†	91.168	267.774	7442.41	2369.95	-92.06	-2368.16	635568.11	413563.14	32°08'10.478"N	103°53'43.305"W	0.00	
9620.00†	91.168	267.774	7440.37	2469.93	-95.95	-2468.07	635468.21	413559.26	32°08'10.444"N	103°53'44.467"W	0.00	
9720.00†	91.168	267.774	7438.33	2569.91	-99.83	-2567.97	635368.31	413555.37	32°08'10.410"N	103°53'45.629"W	0.00	
9820.00†	91.168	267.774	7436.30	2669.89	-103.72	-2667.87	635268.42	413551.49	32°08'10.375"N	103°53'46.791"W	0.00	
9920.00†	91.168	267.774	7434.26	2769.87	-107.60	-2767.78	635168.52	413547.61	32°08'10.341"N	103°53'47.953"W	0.00	
10020.00†	91.168	267.774	7432.22	2869.85	-111.49	-2867.68	635068.62	413543.72	32°08'10.306"N	103°53'49.114"W	0.00	
10120.00†	91.168	267.774	7430.18	2969.83	-115.37	-2967.59	634968.73	413539.84	32°08'10.272"N	103°53'50.276"W	0.00	
10220.00†	91.168	267.774	7428.14	3069.81	-119.25	-3067.49	634868.83	413535.96	32°08'10.237"N	103°53'51.438"W	0.00	
10320.00†	91.168	267.774	7426.10	3169.79	-123.14	-3167.39	634768.93	413532.07	32°08'10.203"N	103°53'52.600"W	0.00	
10420.00†	91.168	267.774	7424.07	3269.76	-127.02	-3267.30	634669.04	413528.19	32°08'10.169"N	103°53'53.762"W	0.00	
10520.00†	91.168	267.774	7422.03	3369.74	-130.91	-3367.20	634569.14	413524.30	32°08'10.134"N	103°53'54.924"W	0.00	
10620.00†	91.168	267.774	7419.99	3469.72	-134.79	-3467.10	634469.24	413520.42	32°08'10.100"N	103°53'56.086"W	0.00	
10720.00†	91.168	267.774	7417.95	3569.70	-138.67	-3567.01	634369.35	413516.54	32°08'10.065"N	103°53'57.248"W	0.00	
10820.00†	91.168	267.774	7415.91	3669.68	-142.56	-3666.91	634269.45	413512.65	32°08'10.031"N	103°53'58.410"W	0.00	
10920.00†	91.168	267.774	7413.88	3769.66	-146.44	-3766.82	634169.55	413508.77	32°08'09.996"N	103°53'59.572"W	0.00	
11020.00†	91.168	267.774	7411.84	3869.64	-150.33	-3866.72	634069.66	413504.88	32°08'09.962"N	103°54'00.734"W	0.00	
11120.00†	91.168	267.774	7409.80	3969.62	-154.21	-3966.62	633969.76	413501.00	32°08'09.927"N	103°54'01.896"W	0.00	
11220.00†	91.168	267.774	7407.76	4069.60	-158.10	-4066.53	633869.86	413497.12	32°08'09.893"N	103°54'03.058"W	0.00	
11320.00†	91.168	267.774	7405.72	4169.58	-161.98	-4166.43	633769.97	413493.23	32°08'09.858"N	103°54'04.220"W	0.00	
11420.00†	91.168	267.774	7403.68	4269.56	-165.86	-4266.33	633670.07	413489.35	32°08'09.824"N	103°54'05.382"W	0.00	
11520.00†	91.168	267.774	7401.65	4369.54	-169.75	-4366.24	633570.17	413485.46	32°08'09.790"N	103°54'06.544"W	0.00	
11620.00†	91.168	267.774	7399.61	4469.52	-173.63	-4466.14	633470.28	413481.58	32°08'09.755"N	103°54'07.706"W	0.00	
11720.00†	91.168	267.774	7397.57	4569.49	-177.52	-4566.05	633370.38	413477.70	32°08'09.721"N	103°54'08.868"W	0.00	
11820.00†	91.168	267.774	7395.53	4669.47	-181.40	-4665.95	633270.48	413473.81	32°08'09.686"N	103°54'10.030"W	0.00	
11920.00†	91.168	267.774	7393.49	4769.45	-185.28	-4765.85	633170.59	413469.93	32°08'09.652"N	103°54'11.192"W	0.00	
12020.00†	91.168	267.774	7391.46	4869.43	-189.17	-4865.76	633070.69	413466.05	32°08'09.617"N	103°54'12.354"W	0.00	



Planned Wellpath Report

B-1

Page 5 of 6

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION			
Operator	WTD - West Texas Division	Slot	PLU No.482H
Area	Eddy County, NM	Well	No.482H
Field	Poker Lake Unit	Wellbore	No.482H PWB
Facility	PLU Pad (482,483)		

WELLPATH DATA (188 stations) † = interpolated/extrapolated station												
MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	Grid East [US ft]	Grid North [US ft]	Latitude	Longitude	DLS [°/100ft]	Comments
12120.00†	91.168	267.774	7389.42	4969.41	-193.05	-4965.66	632970.79	413462.16	32°08'09.583"N	103°54'13.516"W	0.00	
12220.00†	91.168	267.774	7387.38	5069.39	-196.94	-5065.56	632870.90	413458.28	32°08'09.548"N	103°54'14.678"W	0.00	
12320.00†	91.168	267.774	7385.34	5169.37	-200.82	-5165.47	632771.00	413454.39	32°08'09.514"N	103°54'15.840"W	0.00	
12420.00†	91.168	267.774	7383.30	5269.35	-204.71	-5265.37	632671.10	413450.51	32°08'09.479"N	103°54'17.002"W	0.00	
12520.00†	91.168	267.774	7381.26	5369.33	-208.59	-5365.28	632571.21	413446.63	32°08'09.445"N	103°54'18.164"W	0.00	
12620.00†	91.168	267.774	7379.23	5469.31	-212.47	-5465.18	632471.31	413442.74	32°08'09.410"N	103°54'19.326"W	0.00	
12720.00†	91.168	267.774	7377.19	5569.29	-216.36	-5565.08	632371.41	413438.86	32°08'09.376"N	103°54'20.488"W	0.00	
12820.00†	91.168	267.774	7375.15	5669.27	-220.24	-5664.99	632271.52	413434.97	32°08'09.341"N	103°54'21.650"W	0.00	
12920.00†	91.168	267.774	7373.11	5769.25	-224.13	-5764.89	632171.62	413431.09	32°08'09.307"N	103°54'22.812"W	0.00	
13020.00†	91.168	267.774	7371.07	5869.22	-228.01	-5864.79	632071.72	413427.21	32°08'09.272"N	103°54'23.974"W	0.00	
13120.00†	91.168	267.774	7369.04	5969.20	-231.89	-5964.70	631971.83	413423.32	32°08'09.238"N	103°54'25.136"W	0.00	
13220.00†	91.168	267.774	7367.00	6069.18	-235.78	-6064.60	631871.93	413419.44	32°08'09.203"N	103°54'26.298"W	0.00	
13320.00†	91.168	267.774	7364.96	6169.16	-239.66	-6164.51	631772.03	413415.55	32°08'09.168"N	103°54'27.460"W	0.00	
13420.00†	91.168	267.774	7362.92	6269.14	-243.55	-6264.41	631672.14	413411.67	32°08'09.134"N	103°54'28.622"W	0.00	
13520.00†	91.168	267.774	7360.88	6369.12	-247.43	-6364.31	631572.24	413407.79	32°08'09.099"N	103°54'29.784"W	0.00	
13620.00†	91.168	267.774	7358.84	6469.10	-251.32	-6464.22	631472.34	413403.90	32°08'09.065"N	103°54'30.946"W	0.00	
13720.00†	91.168	267.774	7356.81	6569.08	-255.20	-6564.12	631372.45	413400.02	32°08'09.030"N	103°54'32.108"W	0.00	
13820.00†	91.168	267.774	7354.77	6669.06	-259.08	-6664.02	631272.55	413396.13	32°08'08.996"N	103°54'33.270"W	0.00	
13920.00†	91.168	267.774	7352.73	6769.04	-262.97	-6763.93	631172.65	413392.25	32°08'08.961"N	103°54'34.432"W	0.00	
14020.00†	91.168	267.774	7350.69	6869.02	-266.85	-6863.83	631072.76	413388.37	32°08'08.927"N	103°54'35.594"W	0.00	
14120.00†	91.168	267.774	7348.65	6969.00	-270.74	-6963.74	630972.86	413384.48	32°08'08.892"N	103°54'36.755"W	0.00	
14220.00†	91.168	267.774	7346.61	7068.98	-274.62	-7063.64	630872.96	413380.60	32°08'08.858"N	103°54'37.917"W	0.00	
14320.00†	91.168	267.774	7344.58	7168.95	-278.50	-7163.54	630773.07	413376.72	32°08'08.823"N	103°54'39.079"W	0.00	
14420.00†	91.168	267.774	7342.54	7268.93	-282.39	-7263.45	630673.17	413372.83	32°08'08.789"N	103°54'40.241"W	0.00	
14520.00†	91.168	267.774	7340.50	7368.91	-286.27	-7363.35	630573.27	413368.95	32°08'08.754"N	103°54'41.403"W	0.00	
14620.00†	91.168	267.774	7338.46	7468.89	-290.16	-7463.25	630473.38	413365.06	32°08'08.719"N	103°54'42.565"W	0.00	
14720.00†	91.168	267.774	7336.42	7568.87	-294.04	-7563.16	630373.48	413361.18	32°08'08.685"N	103°54'43.727"W	0.00	
14820.00†	91.168	267.774	7334.39	7668.85	-297.93	-7663.06	630273.58	413357.30	32°08'08.650"N	103°54'44.889"W	0.00	
14920.00†	91.168	267.774	7332.35	7768.83	-301.81	-7762.97	630173.69	413353.41	32°08'08.616"N	103°54'46.051"W	0.00	
15020.00†	91.168	267.774	7330.31	7868.81	-305.69	-7862.87	630073.79	413349.53	32°08'08.581"N	103°54'47.213"W	0.00	
15120.00†	91.168	267.774	7328.27	7968.79	-309.58	-7962.77	629973.89	413345.64	32°08'08.546"N	103°54'48.375"W	0.00	
15220.00†	91.168	267.774	7326.23	8068.77	-313.46	-8062.68	629874.00	413341.76	32°08'08.512"N	103°54'49.537"W	0.00	
15320.00†	91.168	267.774	7324.19	8168.75	-317.35	-8162.58	629774.10	413337.88	32°08'08.477"N	103°54'50.699"W	0.00	
15420.00†	91.168	267.774	7322.16	8268.73	-321.23	-8262.48	629674.20	413333.99	32°08'08.443"N	103°54'51.861"W	0.00	
15427.68†	91.168	267.774	7322.00	8276.41	-321.53	-8270.16	629666.53	413333.69	32°08'08.440"N	103°54'51.950"W	0.00	T/Lower B
15520.00†	91.168	267.774	7320.12	8368.71	-325.11	-8362.39	629574.31	413330.11	32°08'08.408"N	103°54'53.023"W	0.00	
15620.00†	91.168	267.774	7318.08	8468.68	-329.00	-8462.29	629474.41	413326.22	32°08'08.374"N	103°54'54.185"W	0.00	
15720.00†	91.168	267.774	7316.04	8568.66	-332.88	-8562.20	629374.51	413322.34	32°08'08.339"N	103°54'55.347"W	0.00	
15820.00†	91.168	267.774	7314.00	8668.64	-336.77	-8662.10	629274.62	413318.46	32°08'08.304"N	103°54'56.509"W	0.00	
15920.00†	91.168	267.774	7311.97	8768.62	-340.65	-8762.00	629174.72	413314.57	32°08'08.270"N	103°54'57.671"W	0.00	
16020.00†	91.168	267.774	7309.93	8868.60	-344.54	-8861.91	629074.82	413310.69	32°08'08.235"N	103°54'58.833"W	0.00	
16120.00†	91.168	267.774	7307.89	8968.58	-348.42	-8961.81	628974.93	413306.81	32°08'08.201"N	103°54'59.995"W	0.00	
16220.00†	91.168	267.774	7305.85	9068.56	-352.30	-9061.71	628875.03	413302.92	32°08'08.166"N	103°55'01.157"W	0.00	
16320.00†	91.168	267.774	7303.81	9168.54	-356.19	-9161.62	628775.13	413299.04	32°08'08.131"N	103°55'02.319"W	0.00	
16420.00†	91.168	267.774	7301.77	9268.52	-360.07	-9261.52	628675.24	413295.15	32°08'08.097"N	103°55'03.481"W	0.00	



Planned Wellpath Report

B-1

Page 6 of 6

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION			
Operator	WTD - West Texas Division	Slot	PLU No.482H
Area	Eddy County, NM	Well	No.482H
Field	Poker Lake Unit	Wellbore	No.482H PWB
Facility	PLU Pad (482,483)		

WELLPATH DATA (188 stations) † = interpolated/extrapolated station

MD [ft]	Inclination [°]	Azimuth [°]	TVD [ft]	Vert Sect [ft]	North [ft]	East [ft]	Grid East [US ft]	Grid North [US ft]	Latitude	Longitude	DLS [°/100ft]	Comments
16520.00†	91.168	267.774	7299.74	9368.50	-363.96	-9361.43	628575.34	413291.27	32°08'08.062"N	103°55'04.643"W	0.00	
16620.00†	91.168	267.774	7297.70	9468.48	-367.84	-9461.33	628475.44	413287.39	32°08'08.027"N	103°55'05.805"W	0.00	
16720.00†	91.168	267.774	7295.66	9568.46	-371.72	-9561.23	628375.55	413283.50	32°08'07.993"N	103°55'06.967"W	0.00	
16820.00†	91.168	267.774	7293.62	9668.44	-375.61	-9661.14	628275.65	413279.62	32°08'07.958"N	103°55'08.129"W	0.00	
16920.00†	91.168	267.774	7291.58	9768.41	-379.49	-9761.04	628175.75	413275.73	32°08'07.924"N	103°55'09.291"W	0.00	
17020.00†	91.168	267.774	7289.55	9868.39	-383.38	-9860.94	628075.86	413271.85	32°08'07.889"N	103°55'10.453"W	0.00	
17120.00†	91.168	267.774	7287.51	9968.37	-387.26	-9960.85	627975.96	413267.97	32°08'07.854"N	103°55'11.615"W	0.00	
17144.89	91.168	267.774	7287.00	9993.25	-388.23	-9985.71	627951.10	413267.00	32°08'07.846"N	103°55'11.904"W	0.00	No.482H PWB

TARGETS

Name	MD [ft]	TVD [ft]	North [ft]	East [ft]	Grid East [US ft]	Grid North [US ft]	Latitude	Longitude	Shape
1) PLU No.482H PBHL	17144.89	7287.00	-388.23	-9985.71	627951.10	413267.00	32°08'07.846"N	103°55'11.904"W	point

SURVEY PROGRAM - Ref Wellbore: No.482H PWB Ref Wellpath: B-1

Start MD [ft]	End MD [ft]	Positional Uncertainty Model	Log Name/Comment	Wellbore
20.00	500.00	Generic gyro - northseeking (Standard)		No.482H PWB
500.00	17144.89	ISCWSA MWD, Rev. 3 (Standard)		No.482H PWB



Clearance Report

B-1
Closest Approach
Page 1 of 27

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION			
Operator	WTD - West Texas Division	Slot	No.482H SHL
Area	Eddy County, NM	Well	No.482H
Field	Poker Lake Unit	Wellbore	No.482H PWB
Facility	PLU Pad (482,483)		

REPORT SETUP INFORMATION			
Projection System	NAD27 / TM New Mexico SP, Eastern Zone (3001), US feet	Software System	WellArchitect® 4.1.1
North Reference	Grid	User	BWGentry
Scale	0.999931	Report Generated	8/28/2015 at 10:33:36 AM
Convergence at slot	0.24° East	Database/Source file	WellArchitectDB/No.482H_PWB_CR.xml

WELLPATH LOCATION						
	Local coordinates		Grid coordinates		Geographic coordinates	
	North[ft]	East[ft]	Easting[US ft]	Northing[US ft]	Latitude	Longitude
Slot Location	-0.60	-20.00	637936.10	413655.20	32°08'11.293"N	103°53'15.760"W
Facility Reference Pt			637956.10	413655.80	32°08'11.298"N	103°53'15.528"W
Field Reference Pt			675156.40	424489.10	32°09'56.776"N	103°46'02.231"W

WELLPATH DATUM			
Calculation method	Minimum Curvature	Rig on PLU No.482H (KB) to Facility Vertical Datum	3262.00ft
Horizontal Reference Pt	Slot	Rig on PLU No.482H (KB) to Mean Sea Level	3262.00ft
Vertical Reference Pt	Rig on PLU No.482H (KB)	Rig on PLU No.482H (KB) to Mud Line at Slot (No.482H SHL)	3262.00ft
MD Reference Pt	Rig on PLU No.482H (KB)		
Field Vertical Reference	Mean Sea Level		

POSITIONAL UNCERTAINTY CALCULATION SETTINGS					
Ellipse Confidence Limit	3.00 Std Dev	Ellipse Start MD	20.00ft	Surface Position Uncertainty	Included
Declination	7.30° East of TN	Dip Angle	59.95°	Mag Field Strength	48053 nT
Slot Surface Uncertainty @1SD		Horizontal	0.100ft	Vertical	0.100ft
Facility Surface Uncertainty @1SD		Horizontal	1.000ft	Vertical	1.000ft
Positional Uncertainty values in the WELLPATH DATA table are the projection of the ellipsoid of uncertainty onto the vertical and horizontal planes					

ANTI-COLLISION RULE			
Rule Name	Separation Factor : R-type Closest Approach w/Hole&Csg Limit:1.0 StdDev:3.00 w/Surface Uncert R=(D-H&C)/PU	Rule Based On	Ratio
Plane of Rule	Closest Approach	Threshold Value	1.00
Subtract Casing & Hole Size	yes	Apply Cone of Safety	no

SURVEY PROGRAM - Ref Wellbore: No.482H PWB Ref Wellpath: B-1				
Start MD [ft]	End MD [ft]	Positional Uncertainty Model	Log Name/Comment	Wellbore
20.00	500.00	Generic gyro - northseeking (Standard)		No.482H PWB
500.00	17144.89	ISWWSA MWD, Rev. 3 (Standard)		No.482H PWB



Clearance Report

B-1
Closest Approach
Page 2 of 27

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION			
Operator	WTD - West Texas Division	Slot	No.482H SHL
Area	Eddy County, NM	Well	No.482H
Field	Poker Lake Unit	Wellbore	No.482H PWB
Facility	PLU Pad (482,483)		

CALCULATION RANGE & CUTOFF		
From: 20.00ft MD	To: 17144.89ft MD	C-C Cutoff: (none)

OFFSET WELL CLEARANCE SUMMARY (5 Offset Wellpaths selected) Ratios are calculated in Closest Approach plane											
Offset Facility	Offset Slot	Offset Well	Offset Wellbore	Offset Wellpath	C-C Clearance Distance			ACR Separation Ratio			
					Ref MD [ft]	Min C-C Clear Dist [ft]	Diverging from MD [ft]	Ref MD of Min Ratio [ft]	Min Ratio	Min Ratio Dvrg from [ft]	ACR Status
PLU Pad (482,483)	No.483H SHL	No.483H	No.483H PWB	B-1	20.00	39.90	6808.00	6811.59	1.00	6811.59	PASS
PLU CVX JV PC No.001H	No.001H SHL	No.001H	No.001H AWB	No.001H AWP	9560.00	793.38	9560.00	10048.31	8.44	10048.31	PASS
Giant / R&B Federal No.1X	No.1X	No.1X	No.1X AWB	No.1X AWP	14007.50	3592.02	14007.50	16620.00	21.75	16620.00	PASS
PLU No.064	No.64 SHL	No.64	No.64 AWB	No.64 AWP	12985.00	3532.33	12985.00	15665.22	21.88	15665.22	PASS
PLU CVX JV PC No.21H	No.21H SHL	No.21H	No.21H AWB	No.21H AWP	9770.00	2709.77	9770.00	11610.67	24.81	11610.67	PASS



Clearance Report

B-1

Closest Approach

Page 3 of 27

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION

Operator	WTD - West Texas Division	Slot	No.482H SHL
Area	Eddy County, NM	Well	No.482H
Field	Poker Lake Unit	Wellbore	No.482H PWB
Facility	PLU Pad (482,483)		

CLEARANCE DATA - Offset Wellbore: No.483H PWB Offset Wellpath: B-1

Facility: PLU Pad (482,483)				Slot: No.483H SHL		Well: No.483H		Threshold Value=1.00		† = Interpolated/extrapolated s		
Ref MD [ft]	Ref TVD [ft]	Ref North [ft]	Ref East [ft]	Offset MD [ft]	Offset TVD [ft]	Offset North [ft]	Offset East [ft]	Horiz Bearing [°]	C-C Clear Dist [ft]	ACR MASD [ft]	Sep Ratio	
20.00	20.00	0.00	0.00	20.00	20.00	0.40	39.90	89.43	39.90	0.60	66.51	
120.00†	120.00	0.00	0.00	120.00	120.00	0.40	39.90	89.43	39.90	1.00	39.74	
220.00†	220.00	0.00	0.00	220.00	220.00	0.40	39.90	89.43	39.90	1.72	23.22	
320.00†	320.00	0.00	0.00	320.00	320.00	0.40	39.90	89.43	39.90	2.49	16.03	
420.00†	420.00	0.00	0.00	420.00	420.00	0.40	39.90	89.43	39.90	3.28	12.18	
520.00†	520.00	0.00	0.00	520.00	520.00	0.40	39.90	89.43	39.90	3.67	10.86	
620.00†	620.00	0.00	0.00	620.00	620.00	0.40	39.90	89.43	39.90	3.75	10.65	
720.00†	720.00	0.00	0.00	720.00	720.00	0.40	39.90	89.43	39.90	3.92	10.18	
820.00†	820.00	0.00	0.00	820.00	820.00	0.40	39.90	89.43	39.90	4.18	9.55	
920.00†	920.00	0.00	0.00	920.00	920.00	0.40	39.90	89.43	39.90	4.51	8.84	
1020.00†	1020.00	0.00	0.00	1020.00	1020.00	0.40	39.90	89.43	39.90	4.91	8.13	
1120.00†	1120.00	0.00	0.00	1120.00	1120.00	0.40	39.90	89.43	39.90	5.34	7.47	
1220.00†	1220.00	0.00	0.00	1220.00	1220.00	0.40	39.90	89.43	39.90	5.82	6.86	
1320.00†	1320.00	0.00	0.00	1320.00	1320.00	0.40	39.90	89.43	39.90	6.32	6.32	
1420.00†	1420.00	0.00	0.00	1420.00	1420.00	0.40	39.90	89.43	39.90	6.84	5.84	
1520.00†	1520.00	0.00	0.00	1520.00	1520.00	0.40	39.90	89.43	39.90	7.37	5.41	
1620.00†	1620.00	0.00	0.00	1620.00	1620.00	0.40	39.90	89.43	39.90	7.92	5.04	
1720.00†	1720.00	0.00	0.00	1720.00	1720.00	0.40	39.90	89.43	39.90	8.49	4.70	
1820.00†	1820.00	0.00	0.00	1820.00	1820.00	0.40	39.90	89.43	39.90	9.06	4.41	
1920.00†	1920.00	0.00	0.00	1920.00	1920.00	0.40	39.90	89.43	39.90	9.63	4.14	
2020.00†	2020.00	0.00	0.00	2020.00	2020.00	0.40	39.90	89.43	39.90	10.22	3.91	
2120.00†	2120.00	0.00	0.00	2120.00	2120.00	0.40	39.90	89.43	39.90	10.81	3.69	
2220.00†	2220.00	0.00	0.00	2220.00	2220.00	0.40	39.90	89.43	39.90	11.40	3.50	
2320.00†	2320.00	0.00	0.00	2320.00	2320.00	0.40	39.90	89.43	39.90	12.00	3.33	
2420.00†	2420.00	0.00	0.00	2420.00	2420.00	0.40	39.90	89.43	39.90	12.60	3.17	
2520.00†	2520.00	0.00	0.00	2520.00	2520.00	0.40	39.90	89.43	39.90	13.20	3.02	
2620.00†	2620.00	0.00	0.00	2620.00	2620.00	0.40	39.90	89.43	39.90	13.80	2.89	
2720.00†	2720.00	0.00	0.00	2720.00	2720.00	0.40	39.90	89.43	39.90	14.41	2.77	
2820.00†	2820.00	0.00	0.00	2820.00	2820.00	0.40	39.90	89.43	39.90	15.02	2.66	
2920.00†	2920.00	0.00	0.00	2920.00	2920.00	0.40	39.90	89.43	39.90	15.63	2.55	
3020.00†	3020.00	0.00	0.00	3020.00	3020.00	0.40	39.90	89.43	39.90	16.24	2.46	
3120.00†	3120.00	0.00	0.00	3120.00	3120.00	0.40	39.90	89.43	39.90	16.85	2.37	
3220.00†	3220.00	0.00	0.00	3220.00	3220.00	0.40	39.90	89.43	39.90	17.47	2.29	
3320.00†	3320.00	0.00	0.00	3320.00	3320.00	0.40	39.90	89.43	39.90	18.08	2.21	
3420.00†	3420.00	0.00	0.00	3420.00	3420.00	0.40	39.90	89.43	39.90	18.70	2.13	
3520.00†	3520.00	0.00	0.00	3520.00	3520.00	0.40	39.90	89.43	39.90	19.31	2.07	
3620.00†	3620.00	0.00	0.00	3620.00	3620.00	0.40	39.90	89.43	39.90	19.93	2.00	
3720.00†	3720.00	0.00	0.00	3720.00	3720.00	0.40	39.90	89.43	39.90	20.55	1.94	
3820.00†	3820.00	0.00	0.00	3820.00	3820.00	0.40	39.90	89.43	39.90	21.17	1.89	
3920.00†	3920.00	0.00	0.00	3920.00	3920.00	0.40	39.90	89.43	39.90	21.79	1.83	
4020.00†	4020.00	0.00	0.00	4020.00	4020.00	0.40	39.90	89.43	39.90	22.40	1.78	
4120.00†	4120.00	0.00	0.00	4120.00	4120.00	0.40	39.90	89.43	39.90	23.02	1.73	
4220.00†	4220.00	0.00	0.00	4220.00	4220.00	0.40	39.90	89.43	39.90	23.65	1.69	
4320.00†	4320.00	0.00	0.00	4320.00	4320.00	0.40	39.90	89.43	39.90	24.27	1.64	
4420.00†	4420.00	0.00	0.00	4420.00	4420.00	0.40	39.90	89.43	39.90	24.89	1.60	



Clearance Report

B-1

Closest Approach

Page 4 of 27

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION

Operator	WTD - West Texas Division	Slot	No.482H SHL
Area	Eddy County, NM	Well	No.482H
Field	Poker Lake Unit	Wellbore	No.482H PWB
Facility	PLU Pad (482,483)		

CLEARANCE DATA - Offset Wellbore: No.483H PWB Offset Wellpath: B-1

Facility: PLU Pad (482,483)				Slot: No.483H SHL		Well: No.483H		Threshold Value=1.00 † = Interpolated/extrapolated s			
Ref MD [ft]	Ref TVD [ft]	Ref North [ft]	Ref East [ft]	Offset MD [ft]	Offset TVD [ft]	Offset North [ft]	Offset East [ft]	Horiz Bearing [°]	C-C Clear Dist [ft]	ACR MASD [ft]	Sep Ratio
4520.00†	4520.00	0.00	0.00	4520.00	4520.00	0.40	39.90	89.43	39.90	25.51	1.56
4620.00†	4620.00	0.00	0.00	4620.00	4620.00	0.40	39.90	89.43	39.90	26.13	1.53
4720.00†	4720.00	0.00	0.00	4720.00	4720.00	0.40	39.90	89.43	39.90	26.75	1.49
4820.00†	4820.00	0.00	0.00	4820.00	4820.00	0.40	39.90	89.43	39.90	27.38	1.46
4920.00†	4920.00	0.00	0.00	4920.00	4920.00	0.40	39.90	89.43	39.90	28.00	1.43
5020.00†	5020.00	0.00	0.00	5020.00	5020.00	0.40	39.90	89.43	39.90	28.62	1.39
5120.00†	5120.00	0.00	0.00	5120.00	5120.00	0.40	39.90	89.43	39.90	29.24	1.36
5220.00†	5220.00	0.00	0.00	5220.00	5220.00	0.40	39.90	89.43	39.90	29.87	1.34
5320.00†	5320.00	0.00	0.00	5320.00	5320.00	0.40	39.90	89.43	39.90	30.49	1.31
5420.00†	5420.00	0.00	0.00	5420.00	5420.00	0.40	39.90	89.43	39.90	31.12	1.28
5520.00†	5520.00	0.00	0.00	5520.00	5520.00	0.40	39.90	89.43	39.90	31.74	1.26
5620.00†	5620.00	0.00	0.00	5620.00	5620.00	0.40	39.90	89.43	39.90	32.36	1.23
5720.00†	5720.00	0.00	0.00	5720.00	5720.00	0.40	39.90	89.43	39.90	32.99	1.21
5820.00†	5820.00	0.00	0.00	5820.00	5820.00	0.40	39.90	89.43	39.90	33.61	1.19
5920.00†	5920.00	0.00	0.00	5920.00	5920.00	0.40	39.90	89.43	39.90	34.24	1.17
6020.00†	6020.00	0.00	0.00	6020.00	6020.00	0.40	39.90	89.43	39.90	34.86	1.14
6120.00†	6120.00	0.00	0.00	6120.00	6120.00	0.40	39.90	89.43	39.90	35.49	1.12
6220.00†	6220.00	0.00	0.00	6220.00	6220.00	0.40	39.90	89.43	39.90	36.11	1.11
6320.00†	6320.00	0.00	0.00	6320.00	6320.00	0.40	39.90	89.43	39.90	36.74	1.09
6420.00†	6420.00	0.00	0.00	6420.00	6420.00	0.40	39.90	89.43	39.90	37.36	1.07
6520.00†	6520.00	0.00	0.00	6520.00	6520.00	0.40	39.90	89.43	39.90	37.99	1.05
6620.00†	6620.00	0.00	0.00	6620.00	6620.00	0.40	39.90	89.43	39.90	38.61	1.03
6720.00†	6720.00	0.00	0.00	6720.00	6720.00	0.40	39.90	89.43	39.90	39.24	1.02
6808.00	6808.00	0.00	0.00	6808.00	6808.00	0.40	39.90	89.43	39.90	39.79	1.00
6811.59†	6811.59	0.00	-0.01	6811.60	6811.60	0.40	39.90	89.43	39.92	39.81	1.00
6820.00†	6820.00	0.00	-0.13	6820.00	6820.00	0.40	39.90	89.42	40.03	39.86	1.00
6920.00†	6919.29	-0.42	-10.90	6911.26	6910.97	0.28	45.94	89.29	57.45	40.32	1.43
7020.00†	7015.20	-1.51	-38.75	6988.30	6986.22	-0.05	62.18	89.17	105.01	40.49	2.59
7120.00†	7104.81	-3.22	-82.81	7045.00	7039.85	-0.42	80.50	89.02	175.77	40.55	4.34
7220.00†	7185.40	-5.51	-141.75	7081.48	7073.29	-0.71	95.05	88.84	262.04	40.58	6.46
7320.00†	7254.53	-8.31	-213.78	7100.99	7090.78	-0.89	103.70	88.66	357.30	40.65	8.79
7420.00†	7310.09	-11.53	-296.71	7107.32	7096.39	-0.95	106.64	88.50	456.58	40.76	11.20
7508.00	7346.40	-14.64	-376.71	7104.58	7093.96	-0.92	105.36	88.37	544.34	40.89	13.31
7520.00†	7350.51	-15.08	-387.98	7103.77	7093.25	-0.92	104.98	88.35	556.23	40.91	13.60
7620.00†	7384.71	-18.73	-481.88	7097.65	7087.81	-0.86	102.18	88.25	655.43	41.06	15.96
7708.00	7414.81	-21.94	-564.51	7093.03	7083.68	-0.82	100.10	88.18	742.83	41.19	18.03
7720.00†	7418.84	-22.38	-575.80	7092.42	7083.13	-0.81	99.83	88.17	754.75	41.21	18.31
7820.00†	7446.82	-26.11	-671.69	7085.34	7076.77	-0.75	96.72	88.11	853.24	41.36	20.63
7920.00†	7464.54	-29.93	-769.98	7075.29	7067.69	-0.66	92.44	88.06	949.80	41.51	22.88
8020.00†	7471.81	-33.80	-869.60	7062.87	7056.35	-0.56	87.36	88.01	1043.78	41.67	25.05
8039.03	7472.00	-34.54	-888.61	7060.28	7053.97	-0.54	86.33	88.00	1061.33	41.69	25.46
8097.43	7471.40	-36.81	-946.96	7052.28	7046.60	-0.48	83.23	87.98	1114.93	41.78	26.68
8120.00†	7470.94	-37.69	-969.51	7049.25	7043.79	-0.45	82.08	87.97	1135.65	41.82	27.16
8220.00†	7468.91	-41.57	-1069.41	7036.68	7032.10	-0.36	77.48	87.94	1227.95	41.96	29.27
8320.00†	7466.87	-45.45	-1169.32	7025.34	7021.46	-0.28	73.54	87.92	1321.04	42.09	31.39



Clearance Report

B-1

Closest Approach

Page 5 of 27

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION			
Operator	WTD - West Texas Division	Slot	No.482H SHL
Area	Eddy County, NM	Well	No.482H
Field	Poker Lake Unit	Wellbore	No.482H PWB
Facility	PLU Pad (482,483)		

CLEARANCE DATA - Offset Wellbore: No.483H PWB Offset Wellpath: B-1											
Facility: PLU Pad (482,483)			Slot: No.483H SHL		Well: No.483H		Threshold Value=1.00		† = Interpolated/extrapolated s		
Ref MD [ft]	Ref TVD [ft]	Ref North [ft]	Ref East [ft]	Offset MD [ft]	Offset TVD [ft]	Offset North [ft]	Offset East [ft]	Horiz Bearing [°]	C-C Clear Dist [ft]	ACR MASD [ft]	Sep Ratio
8420.00†	7464.83	-49.34	-1269.22	7015.06	7011.75	-0.21	70.16	87.90	1414.79	42.21	33.52
8520.00†	7462.79	-53.22	-1369.13	7005.71	7002.87	-0.15	67.24	87.88	1509.13	42.32	35.66
8620.00†	7460.75	-57.11	-1469.03	6997.17	6994.72	-0.10	64.69	87.87	1603.97	42.43	37.80
8720.00†	7458.72	-60.99	-1568.93	6989.35	6987.22	-0.06	62.47	87.86	1699.26	42.53	39.95
8820.00†	7456.68	-64.88	-1668.84	6982.15	6980.30	-0.02	60.51	87.85	1794.93	42.63	42.11
8920.00†	7454.64	-68.76	-1768.74	6975.52	6973.89	0.02	58.78	87.85	1890.95	42.72	44.26
9020.00†	7452.60	-72.64	-1868.64	6969.38	6967.95	0.05	57.25	87.84	1987.27	42.81	46.42
9120.00†	7450.56	-76.53	-1968.55	6963.69	6962.43	0.08	55.89	87.83	2083.87	42.90	48.57
9220.00†	7448.52	-80.41	-2068.45	6958.40	6957.28	0.10	54.67	87.83	2180.70	42.99	50.73
9320.00†	7446.49	-84.30	-2168.36	6953.47	6952.47	0.12	53.58	87.82	2277.76	43.07	52.88
9420.00†	7444.45	-88.18	-2268.26	6948.86	6947.97	0.14	52.60	87.82	2375.01	43.16	55.03
9520.00†	7442.41	-92.06	-2368.16	6944.55	6943.75	0.16	51.71	87.82	2472.44	43.24	57.18
9620.00†	7440.37	-95.95	-2468.07	6940.50	6939.78	0.18	50.91	87.82	2570.03	43.33	59.32
9720.00†	7438.33	-99.83	-2567.97	6936.70	6936.05	0.19	50.18	87.81	2667.77	43.41	61.45
9820.00†	7436.30	-103.72	-2667.87	6933.12	6932.53	0.21	49.52	87.81	2765.65	43.50	63.58
9920.00†	7434.26	-107.60	-2767.78	6929.75	6929.22	0.22	48.91	87.81	2863.64	43.58	65.71
10020.00†	7432.22	-111.49	-2867.68	6926.56	6926.08	0.23	48.36	87.81	2961.75	43.67	67.83
10120.00†	7430.18	-115.37	-2967.59	6923.55	6923.11	0.24	47.85	87.80	3059.96	43.75	69.94
10220.00†	7428.14	-119.25	-3067.49	6920.69	6920.29	0.25	47.38	87.80	3158.26	43.84	72.04
10320.00†	7426.10	-123.14	-3167.39	6917.98	6917.61	0.26	46.95	87.80	3256.66	43.93	74.14
10420.00†	7424.07	-127.02	-3267.30	6915.41	6915.07	0.27	46.56	87.80	3355.13	44.02	76.23
10520.00†	7422.03	-130.91	-3367.20	6912.96	6912.65	0.27	46.19	87.80	3453.68	44.11	78.30
10620.00†	7419.99	-134.79	-3467.10	6910.63	6910.34	0.28	45.85	87.80	3552.30	44.20	80.37
10720.00†	7417.95	-138.67	-3567.01	6908.40	6908.14	0.29	45.53	87.80	3650.98	44.29	82.43
10820.00†	7415.91	-142.56	-3666.91	6906.28	6906.04	0.29	45.24	87.80	3749.73	44.38	84.49
10920.00†	7413.88	-146.44	-3766.82	6904.26	6904.03	0.30	44.97	87.80	3848.53	44.48	86.53
11020.00†	7411.84	-150.33	-3866.72	6902.32	6902.11	0.30	44.72	87.80	3947.38	44.57	88.56
11120.00†	7409.80	-154.21	-3966.62	6900.46	6900.27	0.31	44.48	87.79	4046.29	44.67	90.58
11220.00†	7407.76	-158.10	-4066.53	6898.69	6898.51	0.31	44.26	87.79	4145.24	44.77	92.59
11320.00†	7405.72	-161.98	-4166.43	6896.98	6896.82	0.32	44.05	87.79	4244.23	44.87	94.59
11420.00†	7403.68	-165.86	-4266.33	6895.35	6895.19	0.32	43.86	87.79	4343.26	44.97	96.58
11520.00†	7401.65	-169.75	-4366.24	6893.78	6893.63	0.32	43.67	87.79	4442.33	45.08	98.55
11620.00†	7399.61	-173.63	-4466.14	6892.27	6892.13	0.33	43.50	87.79	4541.44	45.18	100.52
11720.00†	7397.57	-177.52	-4566.05	6890.81	6890.69	0.33	43.34	87.79	4640.58	45.29	102.47
11820.00†	7395.53	-181.40	-4665.95	6889.42	6889.30	0.33	43.19	87.79	4739.76	45.39	104.42
11920.00†	7393.49	-185.28	-4765.85	6888.07	6887.96	0.34	43.05	87.79	4838.96	45.50	106.35
12020.00†	7391.46	-189.17	-4865.76	6886.77	6886.67	0.34	42.91	87.79	4938.20	45.61	108.27
12120.00†	7389.42	-193.05	-4965.66	6885.52	6885.42	0.34	42.79	87.79	5037.46	45.72	110.17
12220.00†	7387.38	-196.94	-5065.56	6884.31	6884.22	0.34	42.67	87.79	5136.74	45.84	112.07
12320.00†	7385.34	-200.82	-5165.47	6883.14	6883.06	0.35	42.55	87.79	5236.05	45.95	113.95
12420.00†	7383.30	-204.71	-5265.37	6882.01	6881.93	0.35	42.45	87.79	5335.39	46.07	115.82
12520.00†	7381.26	-208.59	-5365.28	6880.92	6880.85	0.35	42.34	87.79	5434.74	46.18	117.68
12620.00†	7379.23	-212.47	-5465.18	6879.87	6879.79	0.35	42.25	87.79	5534.12	46.30	119.53
12720.00†	7377.19	-216.36	-5565.08	6878.85	6878.78	0.35	42.16	87.79	5633.52	46.42	121.36
12820.00†	7375.15	-220.24	-5664.99	6877.85	6877.79	0.36	42.07	87.79	5732.93	46.54	123.18



Clearance Report

B-1

Closest Approach

Page 6 of 27

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION			
Operator	WTD - West Texas Division	Slot	No.482H SHL
Area	Eddy County, NM	Well	No.482H
Field	Poker Lake Unit	Wellbore	No.482H PWB
Facility	PLU Pad (482,483)		

CLEARANCE DATA - Offset Wellbore: No.483H PWB Offset Wellpath: B-1

Facility: PLU Pad (482,483) Slot: No.483H SHL Well: No.483H Threshold Value=1.00 ↑ = Interpolated/extrapolated s											
Ref MD [ft]	Ref TVD [ft]	Ref North [ft]	Ref East [ft]	Offset MD [ft]	Offset TVD [ft]	Offset North [ft]	Offset East [ft]	Horiz Bearing [°]	C-C Clear Dist [ft]	ACR MASD [ft]	Sep Ratio
12920.00†	7373.11	-224.13	-5764.89	6876.90	6876.84	0.36	41.99	87.79	5832.37	46.66	124.99
13020.00†	7371.07	-228.01	-5864.79	6875.97	6875.91	0.36	41.91	87.79	5931.82	46.79	126.78
13120.00†	7369.04	-231.89	-5964.70	6875.07	6875.01	0.36	41.83	87.79	6031.29	46.91	128.57
13220.00†	7367.00	-235.78	-6064.60	6874.19	6874.14	0.36	41.76	87.79	6130.77	47.04	130.34
13320.00†	7364.96	-239.66	-6164.51	6873.34	6873.29	0.36	41.70	87.79	6230.27	47.17	132.09
13420.00†	7362.92	-243.55	-6264.41	6872.52	6872.47	0.37	41.63	87.79	6329.78	47.29	133.84
13520.00†	7360.88	-247.43	-6364.31	6871.71	6871.67	0.37	41.57	87.79	6429.31	47.42	135.57
13620.00†	7358.84	-251.32	-6464.22	6870.93	6870.89	0.37	41.51	87.79	6528.85	47.56	137.29
13720.00†	7356.81	-255.20	-6564.12	6870.18	6870.14	0.37	41.45	87.78	6628.41	47.69	139.00
13820.00†	7354.77	-259.08	-6664.02	6869.44	6869.40	0.37	41.40	87.78	6727.97	47.82	140.69
13920.00†	7352.73	-262.97	-6763.93	6868.72	6868.69	0.37	41.35	87.78	6827.55	47.96	142.37
14020.00†	7350.69	-266.85	-6863.83	6868.03	6867.99	0.37	41.30	87.78	6927.14	48.09	144.04
14120.00†	7348.65	-270.74	-6963.74	6867.35	6867.32	0.37	41.25	87.78	7026.74	48.23	145.69
14220.00†	7346.61	-274.62	-7063.64	6866.69	6866.66	0.37	41.21	87.78	7126.35	48.37	147.34
14320.00†	7344.58	-278.50	-7163.54	6866.04	6866.01	0.37	41.16	87.78	7225.97	48.51	148.97
14420.00†	7342.54	-282.39	-7263.45	6865.41	6865.39	0.38	41.12	87.78	7325.60	48.65	150.58
14520.00†	7340.50	-286.27	-7363.35	6864.80	6864.77	0.38	41.08	87.78	7425.24	48.79	152.19
14620.00†	7338.46	-290.16	-7463.25	6864.20	6864.18	0.38	41.05	87.78	7524.88	48.93	153.78
14720.00†	7336.42	-294.04	-7563.16	6863.61	6863.59	0.38	41.01	87.78	7624.54	49.08	155.36
14820.00†	7334.39	-297.93	-7663.06	6863.05	6863.02	0.38	40.97	87.78	7724.20	49.22	156.93
14920.00†	7332.35	-301.81	-7762.97	6862.49	6862.47	0.38	40.94	87.78	7823.88	49.37	158.49
15020.00†	7330.31	-305.69	-7862.87	6861.95	6861.93	0.38	40.91	87.78	7923.56	49.51	160.03
15120.00†	7328.27	-309.58	-7962.77	6861.42	6861.40	0.38	40.88	87.78	8023.24	49.66	161.56
15220.00†	7326.23	-313.46	-8062.68	6860.90	6860.88	0.38	40.85	87.78	8122.94	49.81	163.08
15320.00†	7324.19	-317.35	-8162.58	6860.39	6860.37	0.38	40.82	87.78	8222.64	49.96	164.59
15420.00†	7322.16	-321.23	-8262.48	6859.90	6859.88	0.38	40.79	87.78	8322.35	50.11	166.08
15520.00†	7320.12	-325.11	-8362.39	6859.41	6859.40	0.38	40.76	87.78	8422.06	50.26	167.56
15620.00†	7318.08	-329.00	-8462.29	6858.94	6858.93	0.38	40.74	87.78	8521.79	50.41	169.03
15720.00†	7316.04	-332.88	-8562.20	6858.48	6858.46	0.38	40.71	87.78	8621.51	50.57	170.49
15820.00†	7314.00	-336.77	-8662.10	6858.02	6858.01	0.38	40.69	87.78	8721.25	50.72	171.94
15920.00†	7311.97	-340.65	-8762.00	6857.58	6857.57	0.38	40.67	87.78	8820.98	50.88	173.37
16020.00†	7309.93	-344.54	-8861.91	6857.15	6857.13	0.39	40.64	87.78	8920.73	51.03	174.80
16120.00†	7307.89	-348.42	-8961.81	6856.72	6856.71	0.39	40.62	87.78	9020.48	51.19	176.21
16220.00†	7305.85	-352.30	-9061.71	6856.30	6856.29	0.39	40.60	87.78	9120.23	51.35	177.61
16320.00†	7303.81	-356.19	-9161.62	6855.89	6855.88	0.39	40.58	87.78	9219.99	51.51	179.00
16420.00†	7301.77	-360.07	-9261.52	6855.50	6855.49	0.39	40.56	87.78	9319.76	51.67	180.38
16520.00†	7299.74	-363.96	-9361.43	6855.10	6855.09	0.39	40.54	87.78	9419.53	51.83	181.74
16620.00†	7297.70	-367.84	-9461.33	6854.72	6854.71	0.39	40.53	87.78	9519.30	51.99	183.10
16720.00†	7295.66	-371.72	-9561.23	6854.34	6854.33	0.39	40.51	87.78	9619.08	52.15	184.44
16820.00†	7293.62	-375.61	-9661.14	6853.97	6853.96	0.39	40.49	87.78	9718.86	52.31	185.78
16920.00†	7291.58	-379.49	-9761.04	6853.61	6853.60	0.39	40.48	87.78	9818.65	52.48	187.10
17020.00†	7289.55	-383.38	-9860.94	6853.26	6853.25	0.39	40.46	87.78	9918.44	52.64	188.41
17120.00†	7287.51	-387.26	-9960.85	6852.91	6852.90	0.39	40.44	87.78	10018.23	52.81	189.71
17144.89	7287.00	-388.23	-9985.71	6852.82	6852.81	0.39	40.44	87.78	10043.07	52.85	190.03



Clearance Report

B-1

Closest Approach

Page 7 of 27

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION

Operator	WTD - West Texas Division	Slot	No.482H SHL
Area	Eddy County, NM	Well	No.482H
Field	Poker Lake Unit	Wellbore	No.482H PWB
Facility	PLU Pad (482,483)		

POSITIONAL UNCERTAINTY - Offset Wellbore: No.483H PWB Offset Wellpath: B-1

Slot Surface Uncertainty @1SD	Horizontal	0.100ft	Vertical	0.100ft
Facility Surface Uncertainty @1SD	Horizontal	1.000ft	Vertical	1.000ft

SURVEY PROGRAM - Offset Wellbore: No.483H PWB Offset Wellpath: B-1

Start MD [ft]	End MD [ft]	Positional Uncertainty Model	Log Name/Comment	Wellbore
20.00	500.00	Generic gyro - northseeking (Standard)		No.483H PWB
500.00	15656.35	ISCWSA MWD, Rev. 3 (Standard)		No.483H PWB

OFFSET WELLPATH MD REFERENCE - Offset Wellbore: No.483H PWB Offset Wellpath: B-1

MD Reference: Rig on No.483H SHL (KB)	Offset TVD & local coordinates use Reference Wellpath settings (See WELLPATH DATUM on page 1 of this report)
Ellipse Start MD	20.00ft



Clearance Report

B-1

Closest Approach

Page 8 of 27

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION

Operator	WTD - West Texas Division	Slot	No.482H SHL
Area	Eddy County, NM	Well	No.482H
Field	Poker Lake Unit	Wellbore	No.482H PWB
Facility	PLU Pad (482,483)		

CLEARANCE DATA - Offset Wellbore: No.001H AWB Offset Wellpath: No.001H AWP

Facility: PLU CVX JV PC No.001H				Slot: No.001H SHL		Well: No.001H		Threshold Value=1.00		† = Interpolated/extrapol		
Ref MD [ft]	Ref TVD [ft]	Ref North [ft]	Ref East [ft]	Offset MD [ft]	Offset TVD [ft]	Offset North [ft]	Offset East [ft]	Horiz Bearing [°]	C-C Clear Dist [ft]	ACR MASD [ft]	Se Rat	
20.00	20.00	0.00	0.00	13.73	20.73	-4615.63	-2379.97	207.28	5193.10	3.01	17	
120.00†	120.00	0.00	0.00	119.36	126.36	-4615.50	-2380.06	207.28	5193.03	8.41	6	
220.00†	220.00	0.00	0.00	219.42	226.42	-4615.21	-2380.27	207.28	5192.87	12.09	4	
320.00†	320.00	0.00	0.00	301.48	308.48	-4615.07	-2380.62	207.29	5192.91	12.18	4	
420.00†	420.00	0.00	0.00	383.54	390.54	-4615.16	-2381.16	207.29	5193.31	12.30	4	
520.00†	520.00	0.00	0.00	454.22	461.21	-4615.44	-2381.87	207.30	5194.14	12.41	4	
620.00†	620.00	0.00	0.00	522.03	529.01	-4615.96	-2383.00	207.31	5195.58	12.50	4	
720.00†	720.00	0.00	0.00	589.82	596.78	-4616.72	-2384.57	207.32	5197.64	12.59	4	
820.00†	820.00	0.00	0.00	664.10	671.02	-4617.78	-2386.77	207.33	5200.27	12.78	4	
920.00†	920.00	0.00	0.00	739.49	746.35	-4619.02	-2389.47	207.35	5203.37	13.00	4	
1020.00†	1020.00	0.00	0.00	816.81	823.58	-4620.44	-2392.72	207.38	5206.94	13.22	3	
1120.00†	1120.00	0.00	0.00	902.09	908.76	-4622.23	-2396.52	207.41	5210.85	13.48	3	
1220.00†	1220.00	0.00	0.00	987.35	993.92	-4624.26	-2400.38	207.43	5215.05	13.74	3	
1320.00†	1320.00	0.00	0.00	1092.92	1099.35	-4626.93	-2405.10	207.47	5219.36	14.05	3	
1420.00†	1420.00	0.00	0.00	1202.62	1208.91	-4629.61	-2409.77	207.50	5223.50	14.38	3	
1520.00†	1520.00	0.00	0.00	1341.71	1347.87	-4632.66	-2414.96	207.53	5227.16	14.80	3	
1620.00†	1620.00	0.00	0.00	1466.07	1472.15	-4634.91	-2418.75	207.56	5230.16	15.23	3	
1720.00†	1720.00	0.00	0.00	1579.76	1585.79	-4636.70	-2421.94	207.58	5232.86	15.67	3	
1820.00†	1820.00	0.00	0.00	1681.04	1687.01	-4638.11	-2424.77	207.60	5235.39	16.09	3	
1920.00†	1920.00	0.00	0.00	1779.61	1785.53	-4639.37	-2427.81	207.62	5237.94	16.51	3	
2020.00†	2020.00	0.00	0.00	1878.78	1884.63	-4640.51	-2431.14	207.65	5240.52	16.94	3	
2120.00†	2120.00	0.00	0.00	1978.09	1983.87	-4641.52	-2434.74	207.68	5243.11	17.38	3	
2220.00†	2220.00	0.00	0.00	2072.74	2078.45	-4642.42	-2438.40	207.71	5245.75	17.83	2	
2320.00†	2320.00	0.00	0.00	2166.06	2171.69	-4643.33	-2442.20	207.74	5248.51	18.27	2	
2420.00†	2420.00	0.00	0.00	2263.77	2269.31	-4644.38	-2446.21	207.78	5251.37	18.75	2	
2520.00†	2520.00	0.00	0.00	2364.01	2369.47	-4645.73	-2449.81	207.80	5254.24	19.24	2	
2620.00†	2620.00	0.00	0.00	2435.17	2440.59	-4646.91	-2452.15	207.82	5257.28	19.69	2	
2720.00†	2720.00	0.00	0.00	2490.00	2495.36	-4648.13	-2454.34	207.84	5261.12	20.13	2	
2820.00†	2820.00	0.00	0.00	2544.78	2550.05	-4649.66	-2456.96	207.85	5265.82	20.57	2	
2920.00†	2920.00	0.00	0.00	2599.49	2604.65	-4651.48	-2460.00	207.87	5271.37	21.02	2	
3020.00†	3020.00	0.00	0.00	2652.28	2657.30	-4653.53	-2463.38	207.90	5277.80	21.53	2	
3120.00†	3120.00	0.00	0.00	2704.97	2709.79	-4655.86	-2467.22	207.92	5285.12	22.05	2	
3220.00†	3220.00	0.00	0.00	2757.56	2762.14	-4658.46	-2471.51	207.95	5293.32	22.57	2	
3320.00†	3320.00	0.00	0.00	2827.26	2831.45	-4662.29	-2477.83	207.99	5302.39	23.17	2	
3420.00†	3420.00	0.00	0.00	2969.80	2973.24	-4669.85	-2490.32	208.07	5311.20	24.06	2	
3520.00†	3520.00	0.00	0.00	12740.00	8233.60	-33.62	-2430.63	269.21	5303.50	83.01		
3620.00†	3620.00	0.00	0.00	12740.00	8233.60	-33.62	-2430.63	269.21	5214.82	83.83		
3720.00†	3720.00	0.00	0.00	12740.00	8233.60	-33.62	-2430.63	269.21	5126.56	84.69		
3820.00†	3820.00	0.00	0.00	12740.00	8233.60	-33.62	-2430.63	269.21	5038.74	85.57		
3920.00†	3920.00	0.00	0.00	12740.00	8233.60	-33.62	-2430.63	269.21	4951.38	86.48		
4020.00†	4020.00	0.00	0.00	12740.00	8233.60	-33.62	-2430.63	269.21	4864.51	87.43		
4120.00†	4120.00	0.00	0.00	12740.00	8233.60	-33.62	-2430.63	269.21	4778.15	88.41		
4220.00†	4220.00	0.00	0.00	12740.00	8233.60	-33.62	-2430.63	269.21	4692.34	89.42		
4320.00†	4320.00	0.00	0.00	12740.00	8233.60	-33.62	-2430.63	269.21	4607.09	90.47		
4420.00†	4420.00	0.00	0.00	12740.00	8233.60	-33.62	-2430.63	269.21	4522.46	91.56		



Clearance Report

B-1

Closest Approach

Page 9 of 27

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION

Operator	WTD - West Texas Division	Slot	No.482H SHL
Area	Eddy County, NM	Well	No.482H
Field	Poker Lake Unit	Wellbore	No.482H PWB
Facility	PLU Pad (482,483)		

CLEARANCE DATA - Offset Wellbore: No.001H AWB Offset Wellpath: No.001H AWP

Facility: PLU CVX JV PC No.001H				Slot: No.001H SHL		Well: No.001H		Threshold Value=1.00		† = Interpolated/extrapol		
Ref MD [ft]	Ref TVD [ft]	Ref North [ft]	Ref East [ft]	Offset MD [ft]	Offset TVD [ft]	Offset North [ft]	Offset East [ft]	Horiz Bearing [°]	C-C Clear Dist [ft]	ACR MASD [ft]	S	R
4520.00†	4520.00	0.00	0.00	12740.00	8233.60	-33.62	-2430.63	269.21	4438.45	92.68		
4620.00†	4620.00	0.00	0.00	12740.00	8233.60	-33.62	-2430.63	269.21	4355.13	93.85		
4720.00†	4720.00	0.00	0.00	12740.00	8233.60	-33.62	-2430.63	269.21	4272.52	95.05		
4820.00†	4820.00	0.00	0.00	12740.00	8233.60	-33.62	-2430.63	269.21	4190.67	96.30		
4920.00†	4920.00	0.00	0.00	12740.00	8233.60	-33.62	-2430.63	269.21	4109.62	97.58		
5020.00†	5020.00	0.00	0.00	12740.00	8233.60	-33.62	-2430.63	269.21	4029.43	98.91		
5120.00†	5120.00	0.00	0.00	12740.00	8233.60	-33.62	-2430.63	269.21	3950.13	100.29		
5220.00†	5220.00	0.00	0.00	12740.00	8233.60	-33.62	-2430.63	269.21	3871.80	101.71		
5320.00†	5320.00	0.00	0.00	12740.00	8233.60	-33.62	-2430.63	269.21	3794.49	103.17		
5420.00†	5420.00	0.00	0.00	12740.00	8233.60	-33.62	-2430.63	269.21	3718.25	104.68		
5520.00†	5520.00	0.00	0.00	12740.00	8233.60	-33.62	-2430.63	269.21	3643.17	106.23		
5620.00†	5620.00	0.00	0.00	12740.00	8233.60	-33.62	-2430.63	269.21	3569.31	107.84		
5720.00†	5720.00	0.00	0.00	12740.00	8233.60	-33.62	-2430.63	269.21	3496.75	109.48		
5820.00†	5820.00	0.00	0.00	12740.00	8233.60	-33.62	-2430.63	269.21	3425.57	111.17		
5920.00†	5920.00	0.00	0.00	12740.00	8233.60	-33.62	-2430.63	269.21	3355.86	112.90		
6020.00†	6020.00	0.00	0.00	12740.00	8233.60	-33.62	-2430.63	269.21	3287.72	114.67		
6120.00†	6120.00	0.00	0.00	12740.00	8233.60	-33.62	-2430.63	269.21	3221.24	116.48		
6220.00†	6220.00	0.00	0.00	12740.00	8233.60	-33.62	-2430.63	269.21	3156.52	118.32		
6320.00†	6320.00	0.00	0.00	12740.00	8233.60	-33.62	-2430.63	269.21	3093.69	120.19		
6420.00†	6420.00	0.00	0.00	12740.00	8233.60	-33.62	-2430.63	269.21	3032.86	122.09		
6520.00†	6520.00	0.00	0.00	12740.00	8233.60	-33.62	-2430.63	269.21	2974.14	124.00		
6620.00†	6620.00	0.00	0.00	12740.00	8233.60	-33.62	-2430.63	269.21	2917.67	125.92		
6720.00†	6720.00	0.00	0.00	12740.00	8233.60	-33.62	-2430.63	269.21	2863.57	127.85		
6808.00	6808.00	0.00	0.00	12740.00	8233.60	-33.62	-2430.63	269.21	2818.05	129.54		
6820.00†	6820.00	0.00	-0.13	12740.00	8233.60	-33.62	-2430.63	269.21	2811.89	129.77		
6920.00†	6919.29	-0.42	-10.90	12740.00	8233.60	-33.62	-2430.63	269.21	2753.83	131.58		
7020.00†	7015.20	-1.51	-38.75	12740.00	8233.60	-33.62	-2430.63	269.23	2684.52	133.21		
7120.00†	7104.81	-3.22	-82.81	12740.00	8233.60	-33.62	-2430.63	269.26	2605.25	134.58		
7220.00†	7185.40	-5.51	-141.75	12740.00	8233.60	-33.62	-2430.63	269.30	2517.63	135.69		
7320.00†	7254.53	-8.31	-213.78	12740.00	8233.60	-33.62	-2430.63	269.35	2423.56	136.50		
7420.00†	7310.09	-11.53	-296.71	12740.00	8233.60	-33.62	-2430.63	269.41	2325.29	136.99		
7508.00	7346.40	-14.64	-376.71	12738.13	8233.64	-35.49	-2430.59	269.42	2237.42	137.08		
7520.00†	7350.51	-15.08	-387.98	12737.82	8233.64	-35.80	-2430.58	269.42	2225.44	137.07		
7620.00†	7384.71	-18.73	-481.88	12735.26	8233.70	-38.36	-2430.54	269.42	2125.66	136.99		
7708.00	7414.81	-21.94	-564.51	12733.01	8233.74	-40.61	-2430.49	269.43	2037.87	136.91		
7720.00†	7418.84	-22.38	-575.80	12732.70	8233.75	-40.92	-2430.49	269.43	2025.90	136.89		
7820.00†	7446.82	-26.11	-671.69	12730.23	8233.80	-43.39	-2430.44	269.44	1926.88	136.63		
7920.00†	7464.54	-29.93	-769.98	12727.93	8233.85	-45.69	-2430.39	269.46	1830.04	136.07		
8020.00†	7471.81	-33.80	-869.60	12725.81	8233.89	-47.80	-2430.35	269.49	1736.93	135.16		
8039.03	7472.00	-34.54	-888.61	12725.44	8233.90	-48.18	-2430.35	269.49	1719.77	134.93		
8097.43	7471.40	-36.81	-946.96	12724.30	8233.93	-49.32	-2430.32	269.52	1667.92	134.19		
8120.00†	7470.94	-37.69	-969.51	12723.87	8233.94	-49.75	-2430.32	269.53	1648.11	133.87		
8220.00†	7468.91	-41.57	-1069.41	12721.95	8233.98	-51.67	-2430.28	269.58	1561.21	132.28		
8320.00†	7466.87	-45.45	-1169.32	12720.02	8234.02	-53.59	-2430.24	269.63	1475.98	130.10		
8420.00†	7464.83	-49.34	-1269.22	12718.10	8234.06	-55.51	-2430.21	269.70	1392.71	126.67		



Clearance Report

B-1

Closest Approach

Page 10 of 27

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION			
Operator	WTD - West Texas Division	Slot	No.482H SHL
Area	Eddy County, NM	Well	No.482H
Field	Poker Lake Unit	Wellbore	No.482H PWB
Facility	PLU Pad (482,483)		

CLEARANCE DATA - Offset Wellbore: No.001H AWP Offset Wellpath: No.001H AWP											
Facility: PLU CVX JV PC No.001H				Slot: No.001H SHL		Well: No.001H		Threshold Value=1.00		+ = Interpolated/extrapol	
Ref MD [ft]	Ref TVD [ft]	Ref North [ft]	Ref East [ft]	Offset MD [ft]	Offset TVD [ft]	Offset North [ft]	Offset East [ft]	Horiz Bearing [°]	C-C Clear Dist [ft]	ACR MASD [ft]	R
8520.00†	7462.79	-53.22	-1369.13	12716.18	8234.10	-57.44	-2430.17	269.77	1311.77	124.80	
8620.00†	7460.75	-57.11	-1469.03	12714.26	8234.14	-59.36	-2430.13	269.87	1233.63	123.41	
8720.00†	7458.72	-60.99	-1568.93	12712.33	8234.18	-61.28	-2430.10	269.98	1158.85	120.86	
8820.00†	7456.68	-64.86	-1668.84	12710.41	8234.22	-63.20	-2430.06	270.13	1088.13	117.53	
8920.00†	7454.64	-68.76	-1768.74	12708.49	8234.26	-65.12	-2430.02	270.32	1022.31	113.51	
9020.00†	7452.60	-72.64	-1868.64	12706.57	8234.30	-67.04	-2429.98	270.57	962.38	108.82	
9120.00†	7450.56	-76.53	-1968.55	12704.64	8234.34	-68.97	-2429.95	270.94	909.53	103.52	
9220.00†	7448.52	-80.41	-2068.45	12702.72	8234.38	-70.89	-2429.91	271.51	865.05	97.82	
9320.00†	7446.49	-84.30	-2168.36	12700.80	8234.42	-72.81	-2429.87	272.52	830.28	92.21	
9420.00†	7444.45	-88.18	-2268.26	12698.88	8234.46	-74.73	-2429.84	274.76	806.48	87.54	
9520.00†	7442.41	-92.06	-2368.16	12696.95	8234.50	-76.65	-2429.80	284.04	794.63	85.00	
9560.00†	7441.59	-93.62	-2408.12	12697.25	8234.49	-76.36	-2429.81	308.53	793.38	84.84	
9620.00†	7440.37	-95.95	-2468.07	12695.03	8234.54	-78.57	-2429.76	65.60	795.28	85.56	
9720.00†	7438.33	-99.83	-2567.97	12693.29	8234.58	-80.32	-2429.73	81.97	808.39	89.24	
9820.00†	7436.30	-103.72	-2667.87	12691.43	8234.62	-82.17	-2429.70	84.83	833.37	95.05	
9920.00†	7434.26	-107.60	-2767.78	12689.45	8234.66	-84.15	-2429.66	86.03	869.20	101.72	
10020.00†	7432.22	-111.49	-2867.68	12687.33	8234.71	-86.28	-2429.63	86.71	914.61	108.31	
10048.31†	7431.64	-112.58	-2895.96	12686.70	8234.72	-86.91	-2429.62	86.85	929.02	110.08	
10120.00†	7430.18	-115.37	-2967.59	12685.04	8234.76	-88.56	-2429.59	87.15	968.25	114.31	
10220.00†	7428.14	-119.25	-3067.49	12682.59	8234.81	-91.01	-2429.55	87.47	1028.83	119.52	
10320.00†	7426.10	-123.14	-3167.39	12679.93	8234.88	-93.67	-2429.51	87.71	1095.19	123.93	
10420.00†	7424.07	-127.02	-3267.30	12677.06	8234.95	-96.54	-2429.48	87.92	1166.36	127.62	
10520.00†	7422.03	-130.91	-3367.20	12673.94	8235.02	-99.66	-2429.44	88.09	1241.51	130.67	
10620.00†	7419.99	-134.79	-3467.10	12670.53	8235.11	-103.06	-2429.40	88.25	1319.95	133.20	
10720.00†	7417.95	-138.67	-3567.01	12666.80	8235.21	-106.79	-2429.36	88.40	1401.13	135.30	
10820.00†	7415.91	-142.56	-3666.91	12662.70	8235.32	-110.89	-2429.33	88.53	1484.60	137.03	
10920.00†	7413.88	-146.44	-3766.82	12658.17	8235.44	-115.42	-2429.30	88.67	1569.99	138.48	
11020.00†	7411.84	-150.33	-3866.72	12653.14	8235.59	-120.45	-2429.27	88.81	1657.02	139.69	
11120.00†	7409.80	-154.21	-3966.62	12647.52	8235.75	-126.07	-2429.26	88.95	1745.42	140.71	
11220.00†	7407.76	-158.10	-4066.53	12641.19	8235.95	-132.39	-2429.25	89.10	1835.00	141.56	
11320.00†	7405.72	-161.98	-4166.43	12634.03	8236.18	-139.55	-2429.26	89.26	1925.59	142.29	
11420.00†	7403.68	-165.86	-4266.33	12627.41	8236.40	-146.16	-2429.29	89.39	2017.06	142.92	
11520.00†	7401.65	-169.75	-4366.24	12620.86	8236.62	-152.71	-2429.32	89.50	2109.29	143.46	
11620.00†	7399.61	-173.63	-4466.14	12613.88	8236.85	-159.69	-2429.37	89.61	2202.19	143.94	
11720.00†	7397.57	-177.52	-4566.05	12606.43	8237.11	-167.13	-2429.42	89.72	2295.67	144.35	
11820.00†	7395.53	-181.40	-4665.95	12598.46	8237.39	-175.10	-2429.50	89.84	2389.66	144.71	
11920.00†	7393.49	-185.28	-4765.85	12589.91	8237.69	-183.65	-2429.60	89.96	2484.10	145.04	
12020.00†	7391.46	-189.17	-4865.76	12580.71	8238.03	-192.83	-2429.72	90.09	2578.95	145.32	
12120.00†	7389.42	-193.05	-4965.66	12570.80	8238.39	-202.74	-2429.87	90.22	2674.15	145.58	
12220.00†	7387.38	-196.94	-5065.56	12560.07	8238.79	-213.46	-2430.06	90.36	2769.67	145.82	
12320.00†	7385.34	-200.82	-5165.47	12548.44	8239.23	-225.08	-2430.28	90.51	2865.48	146.04	
12420.00†	7383.30	-204.71	-5265.37	12542.18	8239.47	-231.33	-2430.41	90.54	2961.54	146.25	
12520.00†	7381.26	-208.59	-5365.28	12536.18	8239.69	-237.33	-2430.54	90.56	3057.84	146.46	
12620.00†	7379.23	-212.47	-5465.18	12530.23	8239.90	-243.27	-2430.66	90.58	3154.37	146.64	
12720.00†	7377.19	-216.36	-5565.08	12524.33	8240.11	-249.17	-2430.78	90.60	3251.09	146.82	



Clearance Report

B-1

Closest Approach

Page 11 of 27

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION

Operator	WTD - West Texas Division	Slot	No.482H SHL
Area	Eddy County, NM	Well	No.482H
Field	Poker Lake Unit	Wellbore	No.482H PWB
Facility	PLU Pad (482,483)		

CLEARANCE DATA - Offset Wellbore: No.001H AWB Offset Wellpath: No.001H AWP

Facility: PLU CVX JV PC No.001H				Slot: No.001H SHL		Well: No.001H		Threshold Value=1.00		+ = Interpolated/extrapol	
Ref MD [ft]	Ref TVD [ft]	Ref North [ft]	Ref East [ft]	Offset MD [ft]	Offset TVD [ft]	Offset North [ft]	Offset East [ft]	Horiz Bearing [°]	C-C Clear Dist [ft]	ACR MASD [ft]	R
12820.00†	7375.15	-220.24	-5664.99	12518.47	8240.31	-255.03	-2430.89	90.62	3348.00	146.99	
12920.00†	7373.11	-224.13	-5764.89	12512.65	8240.50	-260.84	-2431.01	90.63	3445.07	147.15	
13020.00†	7371.07	-228.01	-5864.79	12506.88	8240.69	-266.60	-2431.12	90.64	3542.29	147.30	
13120.00†	7369.04	-231.89	-5964.70	12501.15	8240.86	-272.33	-2431.23	90.66	3639.66	147.44	
13220.00†	7367.00	-235.78	-6064.60	12495.47	8241.04	-278.01	-2431.34	90.67	3737.16	147.58	
13320.00†	7364.96	-239.66	-6164.51	12489.83	8241.20	-283.65	-2431.44	90.68	3834.78	147.72	
13420.00†	7362.92	-243.55	-6264.41	12484.23	8241.36	-289.24	-2431.54	90.68	3932.51	147.85	
13520.00†	7360.88	-247.43	-6364.31	12478.67	8241.51	-294.80	-2431.64	90.69	4030.34	147.98	
13620.00†	7358.84	-251.32	-6464.22	12473.15	8241.66	-300.31	-2431.74	90.70	4128.27	148.10	
13720.00†	7356.81	-255.20	-6564.12	12467.68	8241.80	-305.79	-2431.84	90.70	4226.29	148.23	
13820.00†	7354.77	-259.08	-6664.02	12460.38	8241.97	-313.07	-2431.97	90.73	4324.39	148.35	
13920.00†	7352.73	-262.97	-6763.93	12448.99	8242.24	-324.46	-2432.18	90.81	4422.56	148.47	
14020.00†	7350.69	-266.85	-6863.83	12437.19	8242.48	-336.26	-2432.40	90.90	4520.80	148.60	
14120.00†	7348.65	-270.74	-6963.74	12424.96	8242.71	-348.49	-2432.65	90.98	4619.11	148.74	
14220.00†	7346.61	-274.62	-7063.64	12412.27	8242.93	-361.17	-2432.92	91.07	4717.46	148.87	
14320.00†	7344.58	-278.50	-7163.54	12399.10	8243.12	-374.33	-2433.21	91.16	4815.87	149.02	
14420.00†	7342.54	-282.39	-7263.45	12385.43	8243.29	-388.00	-2433.53	91.25	4914.32	149.17	
14520.00†	7340.50	-286.27	-7363.35	12375.40	8243.40	-398.03	-2433.78	91.30	5012.83	149.31	
14620.00†	7338.46	-290.16	-7463.25	12367.86	8243.48	-405.57	-2433.96	91.32	5111.37	149.43	
14720.00†	7336.42	-294.04	-7563.16	12360.27	8243.55	-413.15	-2434.15	91.33	5209.97	149.56	
14820.00†	7334.39	-297.93	-7663.06	12352.65	8243.62	-420.77	-2434.34	91.35	5308.61	149.69	
14920.00†	7332.35	-301.81	-7762.97	12344.99	8243.68	-428.43	-2434.53	91.36	5407.29	149.81	
15020.00†	7330.31	-305.69	-7862.87	12337.29	8243.74	-436.13	-2434.73	91.38	5506.01	149.94	
15120.00†	7328.27	-309.58	-7962.77	12329.54	8243.80	-443.87	-2434.92	91.39	5604.76	150.07	
15220.00†	7326.23	-313.46	-8062.68	12321.75	8243.86	-451.65	-2435.12	91.41	5703.55	150.20	
15320.00†	7324.19	-317.35	-8162.58	12313.92	8243.91	-459.48	-2435.32	91.42	5802.37	150.33	
15420.00†	7322.16	-321.23	-8262.48	12306.05	8243.96	-467.35	-2435.53	91.44	5901.23	150.46	
15520.00†	7320.12	-325.11	-8362.39	12298.14	8244.00	-475.26	-2435.73	91.45	6000.11	150.59	
15620.00†	7318.08	-329.00	-8462.29	12291.28	8244.03	-482.12	-2435.91	91.46	6099.02	150.72	
15720.00†	7316.04	-332.88	-8562.20	12284.62	8244.06	-488.77	-2436.09	91.46	6197.96	150.84	
15820.00†	7314.00	-336.77	-8662.10	12277.99	8244.07	-495.40	-2436.26	91.46	6296.93	150.97	
15920.00†	7311.97	-340.65	-8762.00	12271.38	8244.08	-502.01	-2436.43	91.46	6395.92	151.10	
16020.00†	7309.93	-344.54	-8861.91	12264.79	8244.09	-508.60	-2436.60	91.46	6494.94	151.22	
16120.00†	7307.89	-348.42	-8961.81	12258.23	8244.08	-515.16	-2436.76	91.46	6593.97	151.35	
16220.00†	7305.85	-352.30	-9061.71	12251.69	8244.07	-521.69	-2436.93	91.47	6693.04	151.48	
16320.00†	7303.81	-356.19	-9161.62	12245.17	8244.05	-528.21	-2437.09	91.47	6792.12	151.60	
16420.00†	7301.77	-360.07	-9261.52	12238.68	8244.03	-534.70	-2437.26	91.47	6891.22	151.73	
16520.00†	7299.74	-363.96	-9361.43	12232.21	8244.00	-541.17	-2437.42	91.47	6990.35	151.86	
16620.00†	7297.70	-367.84	-9461.33	12225.76	8243.96	-547.61	-2437.58	91.47	7089.49	151.99	
16720.00†	7295.66	-371.72	-9561.23	12219.34	8243.91	-554.04	-2437.73	91.47	7188.65	152.12	
16820.00†	7293.62	-375.61	-9661.14	12212.95	8243.86	-560.42	-2437.89	91.47	7287.82	152.25	
16920.00†	7291.58	-379.49	-9761.04	12208.41	8243.82	-566.95	-2438.00	91.45	7387.02	152.37	
17020.00†	7289.55	-383.38	-9860.94	12203.92	8243.78	-569.45	-2438.11	91.44	7486.23	152.49	
17120.00†	7287.51	-387.26	-9960.85	12199.46	8243.73	-573.91	-2438.21	91.42	7585.46	152.60	
17144.89	7287.00	-388.23	-9985.71	12198.35	8243.72	-575.01	-2438.24	91.42	7610.16	152.63	



Clearance Report

B-1

Closest Approach

Page 12 of 27

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION

Operator	WTD - West Texas Division	Slot	No.482H SHL
Area	Eddy County, NM	Well	No.482H
Field	Poker Lake Unit	Wellbore	No.482H PWB
Facility	PLU Pad (482,483)		

POSITIONAL UNCERTAINTY - Offset Wellbore: No.001H AWB Offset Wellpath: No.001H AWP

Slot Surface Uncertainty @1SD	Horizontal	0.100ft	Vertical	0.100ft
Facility Surface Uncertainty @1SD	Horizontal	3.000ft	Vertical	1.000ft

WELLPATH COMPOSITION - Offset Wellbore: No.001H AWB Offset Wellpath: No.001H AWP

Start MD [ft]	End MD [ft]	Positional Uncertainty Model	Log Name/Comment	Wellbore
0.00	7400.00	Generic gyro - northseeking (Standard)	Gyro <200-7400>	No.001H AWB
7400.00	12695.00	ISCWSA MWD, Rev. 3 (Standard)	Ryan MWD <7545-	No.001H AWB
12695.00	12740.00	Blind Drilling (std)	Projection to bit	No.001H AWB

OFFSET WELLPATH MD REFERENCE - Offset Wellbore: No.001H AWB Offset Wellpath: No.001H AWP

MD Reference: Rig on No.001H SHL (KB)	Offset TVD & local coordinates use Reference Wellpath settings (See WELLPATH DATUM on page 1 of this report)
Ellipse Start MD	22.00ft



Clearance Report

B-1

Closest Approach

Page 13 of 27

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION

Operator	WTD - West Texas Division	Slot	No.482H SHL
Area	Eddy County, NM	Well	No.482H
Field	Poker Lake Unit	Wellbore	No.482H PWB
Facility	PLU Pad (482,483)		

CLEARANCE DATA - Offset Wellbore: No.1X AWB Offset Wellpath: No.1X AWP

Facility: Giant / R&B Federal No.1X				Slot: No.1X		Well: No.1X		Threshold Value=1.00		† = Interpolated/extrapolated sta		
Ref MD [ft]	Ref TVD [ft]	Ref North [ft]	Ref East [ft]	Offset MD [ft]	Offset TVD [ft]	Offset North [ft]	Offset East [ft]	Horiz Bearing [°]	C-C Clear Dist [ft]	ACR MASD [ft]	Sep Ratio	A St
20.00	20.00	0.00	0.00	-20.00	32.00	-304.02	-6771.78	267.43	6778.61	3.01	2248.32	P
120.00†	120.00	0.00	0.00	68.00	120.00	-304.02	-6771.78	267.43	6778.60	15.46	438.36	P
220.00†	220.00	0.00	0.00	168.00	220.00	-304.02	-6771.78	267.43	6778.60	20.57	329.58	P
320.00†	320.00	0.00	0.00	268.00	320.00	-304.02	-6771.78	267.43	6778.60	25.72	263.56	P
420.00†	420.00	0.00	0.00	368.00	420.00	-304.02	-6771.78	267.43	6778.60	30.91	219.27	P
520.00†	520.00	0.00	0.00	468.00	520.00	-304.02	-6771.78	267.43	6778.60	36.04	188.09	P
620.00†	620.00	0.00	0.00	568.00	620.00	-304.02	-6771.78	267.43	6778.60	41.08	165.00	P
720.00†	720.00	0.00	0.00	668.00	720.00	-304.02	-6771.78	267.43	6778.60	46.15	146.87	P
820.00†	820.00	0.00	0.00	768.00	820.00	-304.02	-6771.78	267.43	6778.60	51.25	132.26	P
920.00†	920.00	0.00	0.00	868.00	920.00	-304.02	-6771.78	267.43	6778.60	56.38	120.24	P
1020.00†	1020.00	0.00	0.00	968.00	1020.00	-304.02	-6771.78	267.43	6778.60	61.52	110.18	P
1120.00†	1120.00	0.00	0.00	1068.00	1120.00	-304.02	-6771.78	267.43	6778.60	66.69	101.65	P
1220.00†	1220.00	0.00	0.00	1168.00	1220.00	-304.02	-6771.78	267.43	6778.60	71.87	94.31	P
1320.00†	1320.00	0.00	0.00	1268.00	1320.00	-304.02	-6771.78	267.43	6778.60	77.08	87.95	P
1420.00†	1420.00	0.00	0.00	1368.00	1420.00	-304.02	-6771.78	267.43	6778.60	82.29	82.37	P
1520.00†	1520.00	0.00	0.00	1468.00	1520.00	-304.02	-6771.78	267.43	6778.60	87.52	77.45	P
1620.00†	1620.00	0.00	0.00	1568.00	1620.00	-304.02	-6771.78	267.43	6778.60	92.76	73.07	P
1720.00†	1720.00	0.00	0.00	1668.00	1720.00	-304.02	-6771.78	267.43	6778.60	98.02	69.16	P
1820.00†	1820.00	0.00	0.00	1768.00	1820.00	-304.02	-6771.78	267.43	6778.60	103.28	65.64	P
1920.00†	1920.00	0.00	0.00	1868.00	1920.00	-304.02	-6771.78	267.43	6778.60	108.54	62.45	P
2020.00†	2020.00	0.00	0.00	1968.00	2020.00	-304.02	-6771.78	267.43	6778.60	113.82	59.56	P
2120.00†	2120.00	0.00	0.00	2068.00	2120.00	-304.02	-6771.78	267.43	6778.60	119.10	56.92	P
2220.00†	2220.00	0.00	0.00	2168.00	2220.00	-304.02	-6771.78	267.43	6778.60	124.39	54.50	P
2320.00†	2320.00	0.00	0.00	2268.00	2320.00	-304.02	-6771.78	267.43	6778.60	129.68	52.27	P
2420.00†	2420.00	0.00	0.00	2368.00	2420.00	-304.02	-6771.78	267.43	6778.60	134.97	50.22	P
2520.00†	2520.00	0.00	0.00	2468.00	2520.00	-304.02	-6771.78	267.43	6778.60	140.27	48.33	P
2620.00†	2620.00	0.00	0.00	2568.00	2620.00	-304.02	-6771.78	267.43	6778.60	145.57	46.57	P
2720.00†	2720.00	0.00	0.00	2668.00	2720.00	-304.02	-6771.78	267.43	6778.60	150.87	44.93	P
2820.00†	2820.00	0.00	0.00	2768.00	2820.00	-304.02	-6771.78	267.43	6778.60	156.18	43.40	P
2920.00†	2920.00	0.00	0.00	2868.00	2920.00	-304.02	-6771.78	267.43	6778.60	161.49	41.98	P
3020.00†	3020.00	0.00	0.00	2968.00	3020.00	-304.02	-6771.78	267.43	6778.60	166.80	40.64	P
3120.00†	3120.00	0.00	0.00	3068.00	3120.00	-304.02	-6771.78	267.43	6778.60	172.11	39.38	P
3220.00†	3220.00	0.00	0.00	3168.00	3220.00	-304.02	-6771.78	267.43	6778.60	177.43	38.21	P
3320.00†	3320.00	0.00	0.00	3268.00	3320.00	-304.02	-6771.78	267.43	6778.60	182.74	37.09	P
3420.00†	3420.00	0.00	0.00	3368.00	3420.00	-304.02	-6771.78	267.43	6778.60	188.06	36.04	P
3520.00†	3520.00	0.00	0.00	3468.00	3520.00	-304.02	-6771.78	267.43	6778.60	193.38	35.05	P
3620.00†	3620.00	0.00	0.00	3568.00	3620.00	-304.02	-6771.78	267.43	6778.60	198.70	34.12	P
3720.00†	3720.00	0.00	0.00	3668.00	3720.00	-304.02	-6771.78	267.43	6778.60	204.02	33.23	P
3820.00†	3820.00	0.00	0.00	3708.00	3760.00	-304.02	-6771.78	267.43	6778.87	206.32	32.86	P
3920.00†	3920.00	0.00	0.00	3708.00	3760.00	-304.02	-6771.78	267.43	6780.49	206.57	32.82	P
4020.00†	4020.00	0.00	0.00	3708.00	3760.00	-304.02	-6771.78	267.43	6783.59	206.78	32.81	P
4120.00†	4120.00	0.00	0.00	3708.00	3760.00	-304.02	-6771.78	267.43	6788.16	206.94	32.80	P
4220.00†	4220.00	0.00	0.00	3708.00	3760.00	-304.02	-6771.78	267.43	6794.19	207.07	32.81	P
4320.00†	4320.00	0.00	0.00	3708.00	3760.00	-304.02	-6771.78	267.43	6801.69	207.15	32.84	P
4420.00†	4420.00	0.00	0.00	3708.00	3760.00	-304.02	-6771.78	267.43	6810.66	207.18	32.87	P



Clearance Report

B-1

Closest Approach

Page 14 of 27

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION

Operator	WTD - West Texas Division	Slot	No.482H SHL
Area	Eddy County, NM	Well	No.482H
Field	Poker Lake Unit	Wellbore	No.482H PWB
Facility	PLU Pad (482,483)		

CLEARANCE DATA - Offset Wellbore: No.1X AWB Offset Wellpath: No.1X AWP

Facility: Giant / R&B Federal No.1X				Slot: No.1X		Well: No.1X		Threshold Value=1.00		† = Interpolated/extrapolated sta			
Ref MD [ft]	Ref TVD [ft]	Ref North [ft]	Ref East [ft]	Offset MD [ft]	Offset TVD [ft]	Offset North [ft]	Offset East [ft]	Horiz Bearing [°]	C-C Clear Dist [ft]	ACR MASD [ft]	Sep Ratio	A SI	
4520.00†	4520.00	0.00	0.00	3708.00	3760.00	-304.02	-6771.78	267.43	6821.07	207.18	32.92	P	
4620.00†	4620.00	0.00	0.00	3708.00	3760.00	-304.02	-6771.78	267.43	6832.94	207.14	32.99	P	
4720.00†	4720.00	0.00	0.00	3708.00	3760.00	-304.02	-6771.78	267.43	6846.24	207.05	33.07	P	
4820.00†	4820.00	0.00	0.00	3708.00	3760.00	-304.02	-6771.78	267.43	6860.98	206.93	33.16	P	
4920.00†	4920.00	0.00	0.00	3708.00	3760.00	-304.02	-6771.78	267.43	6877.14	206.77	33.26	P	
5020.00†	5020.00	0.00	0.00	3708.00	3760.00	-304.02	-6771.78	267.43	6894.71	206.56	33.38	P	
5120.00†	5120.00	0.00	0.00	3708.00	3760.00	-304.02	-6771.78	267.43	6913.69	206.32	33.51	P	
5220.00†	5220.00	0.00	0.00	3708.00	3760.00	-304.02	-6771.78	267.43	6934.05	206.05	33.65	P	
5320.00†	5320.00	0.00	0.00	3708.00	3760.00	-304.02	-6771.78	267.43	6955.79	205.74	33.81	P	
5420.00†	5420.00	0.00	0.00	3708.00	3760.00	-304.02	-6771.78	267.43	6978.90	205.39	33.98	P	
5520.00†	5520.00	0.00	0.00	3708.00	3760.00	-304.02	-6771.78	267.43	7003.36	205.01	34.16	P	
5620.00†	5620.00	0.00	0.00	3708.00	3760.00	-304.02	-6771.78	267.43	7029.16	204.60	34.36	P	
5720.00†	5720.00	0.00	0.00	3708.00	3760.00	-304.02	-6771.78	267.43	7056.28	204.16	34.56	P	
5820.00†	5820.00	0.00	0.00	3708.00	3760.00	-304.02	-6771.78	267.43	7084.71	203.69	34.78	P	
5920.00†	5920.00	0.00	0.00	3708.00	3760.00	-304.02	-6771.78	267.43	7114.43	203.19	35.01	P	
6020.00†	6020.00	0.00	0.00	3708.00	3760.00	-304.02	-6771.78	267.43	7145.42	202.66	35.26	P	
6120.00†	6120.00	0.00	0.00	3708.00	3760.00	-304.02	-6771.78	267.43	7177.68	202.11	35.51	P	
6220.00†	6220.00	0.00	0.00	3708.00	3760.00	-304.02	-6771.78	267.43	7211.18	201.53	35.78	P	
6320.00†	6320.00	0.00	0.00	3708.00	3760.00	-304.02	-6771.78	267.43	7245.90	200.93	36.06	P	
6420.00†	6420.00	0.00	0.00	3708.00	3760.00	-304.02	-6771.78	267.43	7281.83	200.30	36.35	P	
6520.00†	6520.00	0.00	0.00	3708.00	3760.00	-304.02	-6771.78	267.43	7318.95	199.66	36.66	P	
6620.00†	6620.00	0.00	0.00	3708.00	3760.00	-304.02	-6771.78	267.43	7357.25	199.00	36.97	P	
6720.00†	6720.00	0.00	0.00	3708.00	3760.00	-304.02	-6771.78	267.43	7396.69	198.31	37.30	P	
6808.00	6808.00	0.00	0.00	3708.00	3760.00	-304.02	-6771.78	267.43	7432.35	197.70	37.59	P	
6820.00†	6820.00	0.00	-0.13	3708.00	3760.00	-304.02	-6771.78	267.43	7437.16	197.61	37.63	P	
6920.00†	6919.29	-0.42	-10.90	3708.00	3760.00	-304.02	-6771.78	267.43	7468.78	196.83	37.94	P	
7020.00†	7015.20	-1.51	-38.75	3708.00	3760.00	-304.02	-6771.78	267.43	7484.76	195.97	38.19	P	
7120.00†	7104.81	-3.22	-82.81	3708.00	3760.00	-304.02	-6771.78	267.43	7484.69	195.06	38.37	P	
7220.00†	7185.40	-5.51	-141.75	3708.00	3760.00	-304.02	-6771.78	267.42	7468.59	194.12	38.47	P	
7320.00†	7254.53	-8.31	-213.78	3708.00	3760.00	-304.02	-6771.78	267.42	7436.84	193.18	38.50	P	
7420.00†	7310.09	-11.53	-296.71	3708.00	3760.00	-304.02	-6771.78	267.41	7390.21	192.27	38.44	P	
7508.00	7346.40	-14.64	-376.71	3708.00	3760.00	-304.02	-6771.78	267.41	7337.78	191.53	38.31	P	
7520.00†	7350.51	-15.08	-387.98	3708.00	3760.00	-304.02	-6771.78	267.41	7329.95	191.45	38.29	P	
7620.00†	7384.71	-18.73	-481.88	3708.00	3760.00	-304.02	-6771.78	267.40	7265.18	190.58	38.12	P	
7708.00	7414.81	-21.94	-564.51	3708.00	3760.00	-304.02	-6771.78	267.40	7208.85	189.81	37.98	P	
7720.00†	7418.84	-22.38	-575.80	3708.00	3760.00	-304.02	-6771.78	267.40	7201.15	189.71	37.96	P	
7820.00†	7446.82	-26.11	-671.69	3708.00	3760.00	-304.02	-6771.78	267.39	7133.09	188.88	37.76	P	
7920.00†	7464.54	-29.93	-769.98	3708.00	3760.00	-304.02	-6771.78	267.39	7058.35	188.13	37.52	P	
8020.00†	7471.81	-33.80	-869.60	3708.00	3760.00	-304.02	-6771.78	267.38	6977.56	187.44	37.23	P	
8039.03	7472.00	-34.54	-888.61	3708.00	3760.00	-304.02	-6771.78	267.38	6961.55	187.32	37.16	P	
8097.43	7471.40	-36.81	-946.96	3708.00	3760.00	-304.02	-6771.78	267.37	6911.91	186.94	36.97	P	
8120.00†	7470.94	-37.69	-969.51	3708.00	3760.00	-304.02	-6771.78	267.37	6892.63	186.80	36.90	P	
8220.00†	7468.91	-41.57	-1069.41	3708.00	3760.00	-304.02	-6771.78	267.37	6807.49	186.14	36.57	P	
8320.00†	7466.87	-45.45	-1169.32	3708.00	3760.00	-304.02	-6771.78	267.36	6722.75	185.48	36.25	P	
8420.00†	7464.83	-49.34	-1269.22	3708.00	3760.00	-304.02	-6771.78	267.35	6638.43	184.81	35.92	P	



Clearance Report

B-1

Closest Approach

Page 15 of 27

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION

Operator	WTD - West Texas Division	Slot	No.482H SHL
Area	Eddy County, NM	Well	No.482H
Field	Poker Lake Unit	Wellbore	No.482H PWB
Facility	PLU Pad (482,483)		

CLEARANCE DATA - Offset Wellbore: No.1X AWB Offset Wellpath: No.1X AWP

Facility: Giant / R&B Federal No.1X Slot: No.1X Well: No.1X Threshold Value=1.00 † = Interpolated/extrapolated sta												
Ref MD [ft]	Ref TVD [ft]	Ref North [ft]	Ref East [ft]	Offset MD [ft]	Offset TVD [ft]	Offset North [ft]	Offset East [ft]	Horiz Bearing [°]	C-C Clear Dist [ft]	ACR MASD [ft]	Sep Ratio	/ St
8520.00†	7462.79	-53.22	-1369.13	3708.00	3760.00	-304.02	-6771.78	267.34	6554.56	184.12	35.60	P
8620.00†	7460.75	-57.11	-1469.03	3708.00	3760.00	-304.02	-6771.78	267.33	6471.15	183.43	35.28	P
8720.00†	7458.72	-60.99	-1568.93	3708.00	3760.00	-304.02	-6771.78	267.33	6388.21	182.73	34.96	P
8820.00†	7456.68	-64.88	-1668.84	3708.00	3760.00	-304.02	-6771.78	267.32	6305.76	182.01	34.64	P
8920.00†	7454.64	-68.76	-1768.74	3708.00	3760.00	-304.02	-6771.78	267.31	6223.84	181.29	34.33	P
9020.00†	7452.60	-72.64	-1868.64	3708.00	3760.00	-304.02	-6771.78	267.30	6142.44	180.55	34.02	P
9120.00†	7450.56	-76.53	-1968.55	3708.00	3760.00	-304.02	-6771.78	267.29	6061.61	179.79	33.71	P
9220.00†	7448.52	-80.41	-2068.45	3708.00	3760.00	-304.02	-6771.78	267.28	5981.35	179.02	33.41	P
9320.00†	7446.49	-84.30	-2168.36	3708.00	3760.00	-304.02	-6771.78	267.27	5901.69	178.23	33.11	P
9420.00†	7444.45	-88.18	-2268.26	3708.00	3760.00	-304.02	-6771.78	267.26	5822.67	177.42	32.82	P
9520.00†	7442.41	-92.06	-2368.16	3708.00	3760.00	-304.02	-6771.78	267.24	5744.30	176.59	32.53	P
9620.00†	7440.37	-95.95	-2468.07	3708.00	3760.00	-304.02	-6771.78	267.23	5666.60	175.74	32.24	P
9720.00†	7438.33	-99.83	-2567.97	3708.00	3760.00	-304.02	-6771.78	267.22	5589.62	174.86	31.97	P
9820.00†	7436.30	-103.72	-2667.87	3708.00	3760.00	-304.02	-6771.78	267.21	5513.38	173.96	31.69	P
9920.00†	7434.26	-107.60	-2767.78	3708.00	3760.00	-304.02	-6771.78	267.19	5437.90	173.03	31.43	P
10020.00†	7432.22	-111.49	-2867.68	3708.00	3760.00	-304.02	-6771.78	267.18	5363.23	172.06	31.17	P
10120.00†	7430.18	-115.37	-2967.59	3708.00	3760.00	-304.02	-6771.78	267.16	5289.40	171.07	30.92	P
10220.00†	7428.14	-119.25	-3067.49	3708.00	3760.00	-304.02	-6771.78	267.14	5216.43	170.03	30.68	P
10320.00†	7426.10	-123.14	-3167.39	3708.00	3760.00	-304.02	-6771.78	267.13	5144.38	168.96	30.45	P
10420.00†	7424.07	-127.02	-3267.30	3708.00	3760.00	-304.02	-6771.78	267.11	5073.28	167.84	30.23	P
10520.00†	7422.03	-130.91	-3367.20	3708.00	3760.00	-304.02	-6771.78	267.09	5003.16	166.68	30.02	P
10620.00†	7419.99	-134.79	-3467.10	3708.00	3760.00	-304.02	-6771.78	267.07	4934.07	165.46	29.82	P
10720.00†	7417.95	-138.67	-3567.01	3708.00	3760.00	-304.02	-6771.78	267.05	4866.06	164.20	29.64	P
10820.00†	7415.91	-142.56	-3666.91	3708.00	3760.00	-304.02	-6771.78	267.02	4799.17	162.88	29.46	P
10920.00†	7413.88	-146.44	-3766.82	3708.00	3760.00	-304.02	-6771.78	267.00	4733.44	161.50	29.31	P
11020.00†	7411.84	-150.33	-3866.72	3708.00	3760.00	-304.02	-6771.78	266.97	4668.93	160.05	29.17	P
11120.00†	7409.80	-154.21	-3966.62	3708.00	3760.00	-304.02	-6771.78	266.94	4605.69	158.54	29.05	P
11220.00†	7407.76	-158.10	-4066.53	3708.00	3760.00	-304.02	-6771.78	266.91	4543.77	156.95	28.95	P
11320.00†	7405.72	-161.98	-4166.43	3708.00	3760.00	-304.02	-6771.78	266.88	4483.23	155.30	28.87	P
11420.00†	7403.68	-165.86	-4266.33	3708.00	3760.00	-304.02	-6771.78	266.84	4424.11	153.56	28.81	P
11520.00†	7401.65	-169.75	-4366.24	3708.00	3760.00	-304.02	-6771.78	266.81	4366.49	151.73	28.78	P
11620.00†	7399.61	-173.63	-4466.14	3708.00	3760.00	-304.02	-6771.78	266.76	4310.42	149.82	28.77	P
11720.00†	7397.57	-177.52	-4566.05	3708.00	3760.00	-304.02	-6771.78	266.72	4255.96	147.82	28.79	P
11820.00†	7395.53	-181.40	-4665.95	3708.00	3760.00	-304.02	-6771.78	266.67	4203.17	145.73	28.84	P
11920.00†	7393.49	-185.28	-4765.85	3708.00	3760.00	-304.02	-6771.78	266.61	4152.12	143.53	28.93	P
12020.00†	7391.46	-189.17	-4865.76	3708.00	3760.00	-304.02	-6771.78	266.55	4102.88	141.23	29.05	P
12120.00†	7389.42	-193.05	-4965.66	3708.00	3760.00	-304.02	-6771.78	266.48	4055.50	138.83	29.21	P
12220.00†	7387.38	-196.94	-5065.56	3708.00	3760.00	-304.02	-6771.78	266.41	4010.05	136.32	29.42	P
12320.00†	7385.34	-200.82	-5165.47	3708.00	3760.00	-304.02	-6771.78	266.32	3966.61	133.70	29.67	P
12420.00†	7383.30	-204.71	-5265.37	3708.00	3760.00	-304.02	-6771.78	266.23	3925.23	130.97	29.97	P
12520.00†	7381.26	-208.59	-5365.28	3708.00	3760.00	-304.02	-6771.78	266.12	3885.99	128.12	30.33	P
12620.00†	7379.23	-212.47	-5465.18	3708.00	3760.00	-304.02	-6771.78	265.99	3848.95	125.16	30.75	P
12720.00†	7377.19	-216.36	-5565.08	3708.00	3760.00	-304.02	-6771.78	265.85	3814.16	122.09	31.24	P
12820.00†	7375.15	-220.24	-5664.99	3708.00	3760.00	-304.02	-6771.78	265.67	3781.71	118.90	31.81	P
12920.00†	7373.11	-224.13	-5764.89	3708.00	3760.00	-304.02	-6771.78	265.46	3751.64	115.61	32.45	P



Clearance Report

B-1

Closest Approach

Page 16 of 27

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION

Operator	WTD - West Texas Division	Slot	No.482H SHL
Area	Eddy County, NM	Well	No.482H
Field	Poker Lake Unit	Wellbore	No.482H PWB
Facility	PLU Pad (482,483)		

CLEARANCE DATA - Offset Wellbore: No.1X AWB Offset Wellpath: No.1X AWP

Facility: Giant / R&B Federal No.1X				Slot: No.1X		Well: No.1X		Threshold Value=1.00 † = Interpolated/extrapolated sta				
Ref MD [ft]	Ref TVD [ft]	Ref North [ft]	Ref East [ft]	Offset MD [ft]	Offset TVD [ft]	Offset North [ft]	Offset East [ft]	Horiz Bearing [°]	C-C Clear Dist [ft]	ACR MASD [ft]	Sep Ratio	/ St
13020.00†	7371.07	-228.01	-5864.79	3708.00	3760.00	-304.02	-6771.78	265.21	3724.01	112.21	33.19	P
13120.00†	7369.04	-231.89	-5964.70	3708.00	3760.00	-304.02	-6771.78	264.89	3698.88	108.71	34.02	P
13220.00†	7367.00	-235.78	-6064.60	3708.00	3760.00	-304.02	-6771.78	264.49	3676.30	105.13	34.97	P
13320.00†	7364.96	-239.66	-6164.51	3708.00	3760.00	-304.02	-6771.78	263.95	3656.32	101.48	36.03	P
13420.00†	7362.92	-243.55	-6264.41	3708.00	3760.00	-304.02	-6771.78	263.20	3638.97	97.78	37.21	P
13520.00†	7360.88	-247.43	-6364.31	3708.00	3760.00	-304.02	-6771.78	262.09	3624.30	94.08	38.52	P
13620.00†	7358.84	-251.32	-6464.22	3708.00	3760.00	-304.02	-6771.78	260.28	3612.35	90.46	39.93	P
13720.00†	7356.81	-255.20	-6564.12	3708.00	3760.00	-304.02	-6771.78	256.77	3603.13	87.10	41.37	P
13820.00†	7354.77	-259.08	-6664.02	3708.00	3760.00	-304.02	-6771.78	247.36	3596.66	84.49	42.57	P
13920.00†	7352.73	-262.97	-6763.93	3708.00	3760.00	-304.02	-6771.78	190.83	3592.97	83.78	42.89	P
14007.50†	7350.95	-266.37	-6851.34	3708.00	3760.00	-304.02	-6771.78	115.33	3592.02	85.68	41.92	P
14020.00†	7350.69	-266.85	-6863.83	3708.00	3760.00	-304.02	-6771.78	111.99	3592.06	86.13	41.71	P
14120.00†	7348.65	-270.74	-6963.74	3708.00	3760.00	-304.02	-6771.78	99.84	3593.94	90.68	39.63	P
14220.00†	7346.61	-274.62	-7063.64	3708.00	3760.00	-304.02	-6771.78	95.75	3598.59	96.14	37.43	P
14320.00†	7344.58	-278.50	-7163.54	3708.00	3760.00	-304.02	-6771.78	93.73	3606.01	101.91	35.39	P
14420.00†	7342.54	-282.39	-7263.45	3708.00	3760.00	-304.02	-6771.78	92.52	3616.18	107.77	33.55	P
14520.00†	7340.50	-286.27	-7363.35	3708.00	3760.00	-304.02	-6771.78	91.72	3629.08	113.63	31.94	P
14620.00†	7338.46	-290.16	-7463.25	3708.00	3760.00	-304.02	-6771.78	91.15	3644.68	119.42	30.52	P
14720.00†	7336.42	-294.04	-7563.16	3708.00	3760.00	-304.02	-6771.78	90.72	3662.95	125.13	29.27	P
14820.00†	7334.39	-297.93	-7663.06	3708.00	3760.00	-304.02	-6771.78	90.39	3683.84	130.71	28.18	P
14920.00†	7332.35	-301.81	-7762.97	3708.00	3760.00	-304.02	-6771.78	90.13	3707.31	136.17	27.23	P
15020.00†	7330.31	-305.69	-7862.87	3708.00	3760.00	-304.02	-6771.78	89.91	3733.31	141.48	26.39	P
15120.00†	7328.27	-309.58	-7962.77	3708.00	3760.00	-304.02	-6771.78	89.73	3761.79	146.63	25.65	P
15220.00†	7326.23	-313.46	-8062.68	3708.00	3760.00	-304.02	-6771.78	89.58	3792.69	151.63	25.01	P
15320.00†	7324.19	-317.35	-8162.58	3708.00	3760.00	-304.02	-6771.78	89.45	3825.96	156.46	24.45	P
15420.00†	7322.16	-321.23	-8262.48	3708.00	3760.00	-304.02	-6771.78	89.34	3861.53	161.13	23.97	P
15520.00†	7320.12	-325.11	-8362.39	3708.00	3760.00	-304.02	-6771.78	89.24	3899.35	165.62	23.54	P
15620.00†	7318.08	-329.00	-8462.29	3708.00	3760.00	-304.02	-6771.78	89.15	3939.34	169.95	23.18	P
15720.00†	7316.04	-332.88	-8562.20	3708.00	3760.00	-304.02	-6771.78	89.08	3981.44	174.10	22.87	P
15820.00†	7314.00	-336.77	-8662.10	3708.00	3760.00	-304.02	-6771.78	89.01	4025.58	178.09	22.60	P
15920.00†	7311.97	-340.65	-8762.00	3708.00	3760.00	-304.02	-6771.78	88.95	4071.71	181.91	22.38	P
16020.00†	7309.93	-344.54	-8861.91	3708.00	3760.00	-304.02	-6771.78	88.89	4119.74	185.57	22.20	P
16120.00†	7307.89	-348.42	-8961.81	3708.00	3760.00	-304.02	-6771.78	88.84	4169.62	189.07	22.05	P
16220.00†	7305.85	-352.30	-9061.71	3708.00	3760.00	-304.02	-6771.78	88.79	4221.28	192.41	21.94	P
16320.00†	7303.81	-356.19	-9161.62	3708.00	3760.00	-304.02	-6771.78	88.75	4274.65	195.60	21.85	P
16420.00†	7301.77	-360.07	-9261.52	3708.00	3760.00	-304.02	-6771.78	88.71	4329.68	198.64	21.80	P
16520.00†	7299.74	-363.96	-9361.43	3708.00	3760.00	-304.02	-6771.78	88.67	4386.29	201.54	21.76	P
16620.00†	7297.70	-367.84	-9461.33	3708.00	3760.00	-304.02	-6771.78	88.64	4444.44	204.30	21.75	P
16720.00†	7295.66	-371.72	-9561.23	3708.00	3760.00	-304.02	-6771.78	88.61	4504.06	206.93	21.77	P
16820.00†	7293.62	-375.61	-9661.14	3708.00	3760.00	-304.02	-6771.78	88.58	4565.08	209.43	21.80	P
16920.00†	7291.58	-379.49	-9761.04	3708.00	3760.00	-304.02	-6771.78	88.55	4627.47	211.81	21.85	P
17020.00†	7289.55	-383.38	-9860.94	3708.00	3760.00	-304.02	-6771.78	88.53	4691.15	214.07	21.91	P
17120.00†	7287.51	-387.26	-9960.85	3708.00	3760.00	-304.02	-6771.78	88.51	4756.09	216.23	22.00	P
17144.89	7287.00	-388.23	-9985.71	3708.00	3760.00	-304.02	-6771.78	88.50	4772.44	216.75	22.02	P



Clearance Report

B-1

Closest Approach

Page 17 of 27

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION

Operator	WTD - West Texas Division	Slot	No.482H SHL
Area	Eddy County, NM	Well	No.482H
Field	Poker Lake Unit	Wellbore	No.482H PWB
Facility	PLU Pad (482,483)		

POSITIONAL UNCERTAINTY - Offset Wellbore: No.1X AWB Offset Wellpath: No.1X AWP

Slot Surface Uncertainty @1SD	Horizontal	0.100ft	Vertical	0.100ft
Facility Surface Uncertainty @1SD	Horizontal	3.000ft	Vertical	1.000ft

WELLPATH COMPOSITION - Offset Wellbore: No.1X AWB Offset Wellpath: No.1X AWP

Start MD [ft]	End MD [ft]	Positional Uncertainty Model	Log Name/Comment	Wellbore
0.00	3708.00	Unknown Tool (Standard)	Unknown <3708>	No.1X AWB

OFFSET WELLPATH MD REFERENCE - Offset Wellbore: No.1X AWB Offset Wellpath: No.1X AWP

MD Reference: Rig on No.1X (RT)	Offset TVD & local coordinates use Reference Wellpath settings (See WELLPATH DATUM on page 1 of this report)
Ellipse Start MD	0.00ft



Clearance Report

B-1

Closest Approach

Page 18 of 27

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION

Operator	WTD - West Texas Division	Slot	No.482H SHL
Area	Eddy County, NM	Well	No.482H
Field	Poker Lake Unit	Wellbore	No.482H PWB
Facility	PLU Pad (482,483)		

CLEARANCE DATA - Offset Wellbore: No.64 AWB Offset Wellpath: No.64 AWP

Facility: PLU No.064 Slot: No.64 SHL Well: No.64 Threshold Value=1.00 † = Interpolated/extrapolated station												
Ref MD [ft]	Ref TVD [ft]	Ref North [ft]	Ref East [ft]	Offset MD [ft]	Offset TVD [ft]	Offset North [ft]	Offset East [ft]	Horiz Bearing [°]	C-C Clear Dist [ft]	ACR MASD [ft]	Sep Ratio	ACR Status
20.00	20.00	0.00	0.00	-20.00	25.00	-38.10	-5769.81	269.62	5769.94	3.01	1913.77	PASS
120.00†	120.00	0.00	0.00	75.00	120.00	-38.10	-5769.81	269.62	5769.94	16.70	345.46	PASS
220.00†	220.00	0.00	0.00	175.00	220.00	-38.10	-5769.81	269.62	5769.94	21.79	264.81	PASS
320.00†	320.00	0.00	0.00	275.00	320.00	-38.10	-5769.81	269.62	5769.94	26.92	214.30	PASS
420.00†	420.00	0.00	0.00	375.00	420.00	-38.10	-5769.81	269.62	5769.94	32.10	179.74	PASS
520.00†	520.00	0.00	0.00	475.00	520.00	-38.10	-5769.81	269.62	5769.94	37.21	155.06	PASS
620.00†	620.00	0.00	0.00	575.00	620.00	-38.10	-5769.81	269.62	5769.94	42.24	136.61	PASS
720.00†	720.00	0.00	0.00	675.00	720.00	-38.10	-5769.81	269.62	5769.94	47.29	122.01	PASS
820.00†	820.00	0.00	0.00	775.00	820.00	-38.10	-5769.81	269.62	5769.94	52.37	110.17	PASS
920.00†	920.00	0.00	0.00	875.00	920.00	-38.10	-5769.81	269.62	5769.94	57.48	100.39	PASS
1020.00†	1020.00	0.00	0.00	975.00	1020.00	-38.10	-5769.81	269.62	5769.94	62.61	92.16	PASS
1120.00†	1120.00	0.00	0.00	1075.00	1120.00	-38.10	-5769.81	269.62	5769.94	67.76	85.16	PASS
1220.00†	1220.00	0.00	0.00	1175.00	1220.00	-38.10	-5769.81	269.62	5769.94	72.93	79.12	PASS
1320.00†	1320.00	0.00	0.00	1275.00	1320.00	-38.10	-5769.81	269.62	5769.94	78.11	73.87	PASS
1420.00†	1420.00	0.00	0.00	1375.00	1420.00	-38.10	-5769.81	269.62	5769.94	83.31	69.26	PASS
1520.00†	1520.00	0.00	0.00	1475.00	1520.00	-38.10	-5769.81	269.62	5769.94	88.52	65.18	PASS
1620.00†	1620.00	0.00	0.00	1575.00	1620.00	-38.10	-5769.81	269.62	5769.94	93.75	61.55	PASS
1720.00†	1720.00	0.00	0.00	1675.00	1720.00	-38.10	-5769.81	269.62	5769.94	98.98	58.29	PASS
1820.00†	1820.00	0.00	0.00	1775.00	1820.00	-38.10	-5769.81	269.62	5769.94	104.23	55.36	PASS
1920.00†	1920.00	0.00	0.00	1875.00	1920.00	-38.10	-5769.81	269.62	5769.94	109.48	52.70	PASS
2020.00†	2020.00	0.00	0.00	1975.00	2020.00	-38.10	-5769.81	269.62	5769.94	114.74	50.29	PASS
2120.00†	2120.00	0.00	0.00	2075.00	2120.00	-38.10	-5769.81	269.62	5769.94	120.00	48.08	PASS
2220.00†	2220.00	0.00	0.00	2175.00	2220.00	-38.10	-5769.81	269.62	5769.94	125.27	46.06	PASS
2320.00†	2320.00	0.00	0.00	2275.00	2320.00	-38.10	-5769.81	269.62	5769.94	130.54	44.20	PASS
2420.00†	2420.00	0.00	0.00	2375.00	2420.00	-38.10	-5769.81	269.62	5769.94	135.82	42.48	PASS
2520.00†	2520.00	0.00	0.00	2475.00	2520.00	-38.10	-5769.81	269.62	5769.94	141.10	40.89	PASS
2620.00†	2620.00	0.00	0.00	2575.00	2620.00	-38.10	-5769.81	269.62	5769.94	146.38	39.42	PASS
2720.00†	2720.00	0.00	0.00	2675.00	2720.00	-38.10	-5769.81	269.62	5769.94	151.67	38.04	PASS
2820.00†	2820.00	0.00	0.00	2775.00	2820.00	-38.10	-5769.81	269.62	5769.94	156.96	36.76	PASS
2920.00†	2920.00	0.00	0.00	2875.00	2920.00	-38.10	-5769.81	269.62	5769.94	162.25	35.56	PASS
3020.00†	3020.00	0.00	0.00	2975.00	3020.00	-38.10	-5769.81	269.62	5769.94	167.55	34.44	PASS
3120.00†	3120.00	0.00	0.00	3075.00	3120.00	-38.10	-5769.81	269.62	5769.94	172.84	33.38	PASS
3220.00†	3220.00	0.00	0.00	3175.00	3220.00	-38.10	-5769.81	269.62	5769.94	178.14	32.39	PASS
3320.00†	3320.00	0.00	0.00	3275.00	3320.00	-38.10	-5769.81	269.62	5769.94	183.44	31.45	PASS
3420.00†	3420.00	0.00	0.00	3375.00	3420.00	-38.10	-5769.81	269.62	5769.94	188.74	30.57	PASS
3520.00†	3520.00	0.00	0.00	3475.00	3520.00	-38.10	-5769.81	269.62	5769.94	194.04	29.74	PASS
3620.00†	3620.00	0.00	0.00	3575.00	3620.00	-38.10	-5769.81	269.62	5769.94	199.34	28.94	PASS
3720.00†	3720.00	0.00	0.00	3675.00	3720.00	-38.10	-5769.81	269.62	5769.94	204.65	28.19	PASS
3820.00†	3820.00	0.00	0.00	3775.00	3820.00	-38.10	-5769.81	269.62	5769.94	209.95	27.48	PASS
3920.00†	3920.00	0.00	0.00	3800.00	3845.00	-38.10	-5769.81	269.62	5770.42	211.49	27.29	PASS
4020.00†	4020.00	0.00	0.00	3800.00	3845.00	-38.10	-5769.81	269.62	5772.59	211.71	27.27	PASS
4120.00†	4120.00	0.00	0.00	3800.00	3845.00	-38.10	-5769.81	269.62	5776.49	211.87	27.26	PASS
4220.00†	4220.00	0.00	0.00	3800.00	3845.00	-38.10	-5769.81	269.62	5782.11	211.97	27.28	PASS
4320.00†	4320.00	0.00	0.00	3800.00	3845.00	-38.10	-5769.81	269.62	5789.45	212.01	27.31	PASS
4420.00†	4420.00	0.00	0.00	3800.00	3845.00	-38.10	-5769.81	269.62	5798.52	211.99	27.35	PASS



Clearance Report

B-1

Closest Approach

Page 19 of 27

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION

Operator	WTD - West Texas Division	Slot	No.482H SHL
Area	Eddy County, NM	Well	No.482H
Field	Poker Lake Unit	Wellbore	No.482H PWB
Facility	PLU Pad (482,483)		

CLEARANCE DATA - Offset Wellbore: No.64 AWB Offset Wellpath: No.64 AWP

Facility: PLU No.064 Slot: No.64 SHL Well: No.64 Threshold Value=1.00 † = Interpolated/extrapolated station												
Ref MD [ft]	Ref TVD [ft]	Ref North [ft]	Ref East [ft]	Offset MD [ft]	Offset TVD [ft]	Offset North [ft]	Offset East [ft]	Horiz Bearing [°]	C-C Clear Dist [ft]	ACR MASD [ft]	Sep Ratio	ACR Status
4520.00†	4520.00	0.00	0.00	3800.00	3845.00	-38.10	-5769.81	269.62	5809.28	211.92	27.41	PASS
4620.00†	4620.00	0.00	0.00	3800.00	3845.00	-38.10	-5769.81	269.62	5821.75	211.78	27.49	PASS
4720.00†	4720.00	0.00	0.00	3800.00	3845.00	-38.10	-5769.81	269.62	5835.91	211.59	27.58	PASS
4820.00†	4820.00	0.00	0.00	3800.00	3845.00	-38.10	-5769.81	269.62	5851.73	211.34	27.69	PASS
4920.00†	4920.00	0.00	0.00	3800.00	3845.00	-38.10	-5769.81	269.62	5869.22	211.04	27.81	PASS
5020.00†	5020.00	0.00	0.00	3800.00	3845.00	-38.10	-5769.81	269.62	5888.36	210.69	27.95	PASS
5120.00†	5120.00	0.00	0.00	3800.00	3845.00	-38.10	-5769.81	269.62	5909.13	210.28	28.10	PASS
5220.00†	5220.00	0.00	0.00	3800.00	3845.00	-38.10	-5769.81	269.62	5931.51	209.82	28.27	PASS
5320.00†	5320.00	0.00	0.00	3800.00	3845.00	-38.10	-5769.81	269.62	5955.48	209.32	28.45	PASS
5420.00†	5420.00	0.00	0.00	3800.00	3845.00	-38.10	-5769.81	269.62	5981.04	208.77	28.65	PASS
5520.00†	5520.00	0.00	0.00	3800.00	3845.00	-38.10	-5769.81	269.62	6008.14	208.18	28.86	PASS
5620.00†	5620.00	0.00	0.00	3800.00	3845.00	-38.10	-5769.81	269.62	6036.79	207.54	29.09	PASS
5720.00†	5720.00	0.00	0.00	3800.00	3845.00	-38.10	-5769.81	269.62	6066.94	206.87	29.33	PASS
5820.00†	5820.00	0.00	0.00	3800.00	3845.00	-38.10	-5769.81	269.62	6098.59	206.15	29.58	PASS
5920.00†	5920.00	0.00	0.00	3800.00	3845.00	-38.10	-5769.81	269.62	6131.70	205.40	29.85	PASS
6020.00†	6020.00	0.00	0.00	3800.00	3845.00	-38.10	-5769.81	269.62	6166.26	204.62	30.14	PASS
6120.00†	6120.00	0.00	0.00	3800.00	3845.00	-38.10	-5769.81	269.62	6202.24	203.80	30.43	PASS
6220.00†	6220.00	0.00	0.00	3800.00	3845.00	-38.10	-5769.81	269.62	6239.61	202.96	30.74	PASS
6320.00†	6320.00	0.00	0.00	3800.00	3845.00	-38.10	-5769.81	269.62	6278.36	202.09	31.07	PASS
6420.00†	6420.00	0.00	0.00	3800.00	3845.00	-38.10	-5769.81	269.62	6318.45	201.19	31.41	PASS
6520.00†	6520.00	0.00	0.00	3800.00	3845.00	-38.10	-5769.81	269.62	6359.86	200.27	31.76	PASS
6620.00†	6620.00	0.00	0.00	3800.00	3845.00	-38.10	-5769.81	269.62	6402.56	199.33	32.12	PASS
6720.00†	6720.00	0.00	0.00	3800.00	3845.00	-38.10	-5769.81	269.62	6446.53	198.37	32.50	PASS
6808.00	6808.00	0.00	0.00	3800.00	3845.00	-38.10	-5769.81	269.62	6486.26	197.51	32.84	PASS
6820.00†	6820.00	0.00	-0.13	3800.00	3845.00	-38.10	-5769.81	269.62	6491.64	197.39	32.89	PASS
6920.00†	6919.29	-0.42	-10.90	3800.00	3845.00	-38.10	-5769.81	269.63	6528.22	196.31	33.25	PASS
7020.00†	7015.20	-1.51	-38.75	3800.00	3845.00	-38.10	-5769.81	269.63	6549.55	195.12	33.57	PASS
7120.00†	7104.81	-3.22	-82.81	3800.00	3845.00	-38.10	-5769.81	269.65	6555.12	193.84	33.82	PASS
7220.00†	7185.40	-5.51	-141.75	3800.00	3845.00	-38.10	-5769.81	269.67	6544.80	192.53	33.99	PASS
7320.00†	7254.53	-8.31	-213.78	3800.00	3845.00	-38.10	-5769.81	269.69	6518.84	191.20	34.09	PASS
7420.00†	7310.09	-11.53	-296.71	3800.00	3845.00	-38.10	-5769.81	269.72	6477.84	189.91	34.11	PASS
7508.00	7346.40	-14.64	-376.71	3800.00	3845.00	-38.10	-5769.81	269.75	6430.08	188.84	34.05	PASS
7520.00†	7350.51	-15.08	-387.98	3800.00	3845.00	-38.10	-5769.81	269.76	6422.87	188.72	34.03	PASS
7620.00†	7384.71	-18.73	-481.88	3800.00	3845.00	-38.10	-5769.81	269.79	6363.35	187.48	33.94	PASS
7708.00	7414.81	-21.94	-564.51	3800.00	3845.00	-38.10	-5769.81	269.82	6311.81	186.37	33.87	PASS
7720.00†	7418.84	-22.38	-575.80	3800.00	3845.00	-38.10	-5769.81	269.83	6304.79	186.22	33.86	PASS
7820.00†	7446.82	-26.11	-671.69	3800.00	3845.00	-38.10	-5769.81	269.87	6242.12	185.01	33.74	PASS
7920.00†	7464.54	-29.93	-769.98	3800.00	3845.00	-38.10	-5769.81	269.91	6172.47	183.89	33.57	PASS
8020.00†	7471.81	-33.80	-869.60	3800.00	3845.00	-38.10	-5769.81	269.95	6096.38	182.84	33.34	PASS
8039.03	7472.00	-34.54	-888.61	3800.00	3845.00	-38.10	-5769.81	269.96	6081.22	182.67	33.29	PASS
8097.43	7471.40	-36.81	-946.96	3800.00	3845.00	-38.10	-5769.81	269.99	6034.13	182.09	33.14	PASS
8120.00†	7470.94	-37.69	-969.51	3800.00	3845.00	-38.10	-5769.81	270.00	6015.84	181.86	33.08	PASS
8220.00†	7468.91	-41.57	-1069.41	3800.00	3845.00	-38.10	-5769.81	270.04	5935.19	180.86	32.82	PASS
8320.00†	7466.87	-45.45	-1169.32	3800.00	3845.00	-38.10	-5769.81	270.09	5855.13	179.83	32.56	PASS
8420.00†	7464.83	-49.34	-1269.22	3800.00	3845.00	-38.10	-5769.81	270.14	5775.65	178.78	32.31	PASS



Clearance Report

B-1

Closest Approach

Page 20 of 27

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION

Operator	WTD - West Texas Division	Slot	No.482H SHL
Area	Eddy County, NM	Well	No.482H
Field	Poker Lake Unit	Wellbore	No.482H PWB
Facility	PLU Pad (482,483)		

CLEARANCE DATA - Offset Wellbore: No.64 AWB Offset Wellpath: No.64 AWP

Facility: PLU No.064 Slot: No.64 SHL Well: No.64 Threshold Value=1.00 † = Interpolated/extrapolated station												
Ref MD [ft]	Ref TVD [ft]	Ref North [ft]	Ref East [ft]	Offset MD [ft]	Offset TVD [ft]	Offset North [ft]	Offset East [ft]	Horiz Bearing [°]	C-C Clear Dist [ft]	ACR MASD [ft]	Sep Ratio	ACR Status
8520.00†	7462.79	-53.22	-1369.13	3800.00	3845.00	-38.10	-5769.81	270.20	5696.90	177.71	32.06	PASS
8620.00†	7460.75	-57.11	-1469.03	3800.00	3845.00	-38.10	-5769.81	270.25	5618.79	176.62	31.81	PASS
8720.00†	7458.72	-60.99	-1568.93	3800.00	3845.00	-38.10	-5769.81	270.31	5541.37	175.50	31.58	PASS
8820.00†	7456.68	-64.88	-1668.84	3800.00	3845.00	-38.10	-5769.81	270.37	5464.70	174.35	31.34	PASS
8920.00†	7454.64	-68.76	-1768.74	3800.00	3845.00	-38.10	-5769.81	270.44	5388.78	173.18	31.12	PASS
9020.00†	7452.60	-72.64	-1868.64	3800.00	3845.00	-38.10	-5769.81	270.51	5313.67	171.97	30.90	PASS
9120.00†	7450.56	-76.53	-1968.55	3800.00	3845.00	-38.10	-5769.81	270.58	5239.38	170.73	30.69	PASS
9220.00†	7448.52	-80.41	-2068.45	3800.00	3845.00	-38.10	-5769.81	270.66	5165.97	169.45	30.49	PASS
9320.00†	7446.49	-84.30	-2168.36	3800.00	3845.00	-38.10	-5769.81	270.74	5093.46	168.14	30.29	PASS
9420.00†	7444.45	-88.18	-2268.26	3800.00	3845.00	-38.10	-5769.81	270.82	5021.89	166.78	30.11	PASS
9520.00†	7442.41	-92.06	-2368.16	3800.00	3845.00	-38.10	-5769.81	270.91	4951.31	165.38	29.94	PASS
9620.00†	7440.37	-95.95	-2468.07	3800.00	3845.00	-38.10	-5769.81	271.00	4881.76	163.93	29.78	PASS
9720.00†	7438.33	-99.83	-2567.97	3800.00	3845.00	-38.10	-5769.81	271.10	4813.28	162.43	29.63	PASS
9820.00†	7436.30	-103.72	-2667.87	3800.00	3845.00	-38.10	-5769.81	271.21	4745.92	160.87	29.50	PASS
9920.00†	7434.26	-107.60	-2767.78	3800.00	3845.00	-38.10	-5769.81	271.33	4679.72	159.26	29.38	PASS
10020.00†	7432.22	-111.49	-2867.68	3800.00	3845.00	-38.10	-5769.81	271.45	4614.75	157.58	29.29	PASS
10120.00†	7430.18	-115.37	-2967.59	3800.00	3845.00	-38.10	-5769.81	271.58	4551.04	155.83	29.20	PASS
10220.00†	7428.14	-119.25	-3067.49	3800.00	3845.00	-38.10	-5769.81	271.72	4488.66	154.02	29.14	PASS
10320.00†	7426.10	-123.14	-3167.39	3800.00	3845.00	-38.10	-5769.81	271.87	4427.65	152.13	29.11	PASS
10420.00†	7424.07	-127.02	-3267.30	3800.00	3845.00	-38.10	-5769.81	272.04	4368.09	150.16	29.09	PASS
10520.00†	7422.03	-130.91	-3367.20	3800.00	3845.00	-38.10	-5769.81	272.21	4310.02	148.10	29.10	PASS
10620.00†	7419.99	-134.79	-3467.10	3800.00	3845.00	-38.10	-5769.81	272.40	4253.51	145.96	29.14	PASS
10720.00†	7417.95	-138.67	-3567.01	3800.00	3845.00	-38.10	-5769.81	272.61	4198.62	143.73	29.21	PASS
10820.00†	7415.91	-142.56	-3666.91	3800.00	3845.00	-38.10	-5769.81	272.84	4145.42	141.41	29.32	PASS
10920.00†	7413.88	-146.44	-3766.82	3800.00	3845.00	-38.10	-5769.81	273.10	4093.97	138.98	29.46	PASS
11020.00†	7411.84	-150.33	-3866.72	3800.00	3845.00	-38.10	-5769.81	273.38	4044.34	136.46	29.64	PASS
11120.00†	7409.80	-154.21	-3966.62	3800.00	3845.00	-38.10	-5769.81	273.68	3996.59	133.82	29.86	PASS
11220.00†	7407.76	-158.10	-4066.53	3800.00	3845.00	-38.10	-5769.81	274.03	3950.80	131.09	30.14	PASS
11320.00†	7405.72	-161.98	-4166.43	3800.00	3845.00	-38.10	-5769.81	274.42	3907.03	128.24	30.47	PASS
11420.00†	7403.68	-165.86	-4266.33	3800.00	3845.00	-38.10	-5769.81	274.86	3865.36	125.29	30.85	PASS
11520.00†	7401.65	-169.75	-4366.24	3800.00	3845.00	-38.10	-5769.81	275.36	3825.84	122.22	31.30	PASS
11620.00†	7399.61	-173.63	-4466.14	3800.00	3845.00	-38.10	-5769.81	275.94	3788.56	119.05	31.82	PASS
11720.00†	7397.57	-177.52	-4566.05	3800.00	3845.00	-38.10	-5769.81	276.61	3753.56	115.77	32.42	PASS
11820.00†	7395.53	-181.40	-4665.95	3800.00	3845.00	-38.10	-5769.81	277.40	3720.93	112.39	33.11	PASS
11920.00†	7393.49	-185.28	-4765.85	3800.00	3845.00	-38.10	-5769.81	278.34	3690.72	108.91	33.89	PASS
12020.00†	7391.46	-189.17	-4865.76	3800.00	3845.00	-38.10	-5769.81	279.49	3662.99	105.35	34.77	PASS
12120.00†	7389.42	-193.05	-4965.66	3800.00	3845.00	-38.10	-5769.81	280.91	3637.80	101.71	35.77	PASS
12220.00†	7387.38	-196.94	-5065.56	3800.00	3845.00	-38.10	-5769.81	282.71	3615.20	98.02	36.88	PASS
12320.00†	7385.34	-200.82	-5165.47	3800.00	3845.00	-38.10	-5769.81	285.07	3595.24	94.31	38.12	PASS
12420.00†	7383.30	-204.71	-5265.37	3800.00	3845.00	-38.10	-5769.81	288.28	3577.96	90.62	39.48	PASS
12520.00†	7381.26	-208.59	-5365.28	3800.00	3845.00	-38.10	-5769.81	292.85	3563.41	87.04	40.94	PASS
12620.00†	7379.23	-212.47	-5465.18	3800.00	3845.00	-38.10	-5769.81	299.79	3551.61	83.71	42.43	PASS
12720.00†	7377.19	-216.36	-5565.08	3800.00	3845.00	-38.10	-5769.81	311.05	3542.60	80.90	43.79	PASS
12820.00†	7375.15	-220.24	-5664.99	3800.00	3845.00	-38.10	-5769.81	330.08	3536.40	79.14	44.69	PASS
12920.00†	7373.11	-224.13	-5764.89	3800.00	3845.00	-38.10	-5769.81	358.49	3533.02	79.17	44.63	PASS



Clearance Report

B-1

Closest Approach

Page 21 of 27

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION

Operator	WTD - West Texas Division	Slot	No.482H SHL
Area	Eddy County, NM	Well	No.482H
Field	Poker Lake Unit	Wellbore	No.482H PWB
Facility	PLU Pad (482,483)		

CLEARANCE DATA - Offset Wellbore: No.64 AWB Offset Wellpath: No.64 AWP

Facility: PLU No.064 Slot: No.64 SHL Well: No.64 Threshold Value=1.00 † = Interpolated/extrapolated station												
Ref MD [ft]	Ref TVD [ft]	Ref North [ft]	Ref East [ft]	Offset MD [ft]	Offset TVD [ft]	Offset North [ft]	Offset East [ft]	Horiz Bearing [°]	C-C Clear Dist [ft]	ACR MASD [ft]	Sep Ratio	ACR Status
12985.00†	7371.79	-226.65	-5829.83	3800.00	3845.00	-38.10	-5769.81	17.66	3532.33	80.40	43.94	PASS
13020.00†	7371.07	-228.01	-5864.79	3800.00	3845.00	-38.10	-5769.81	26.57	3532.46	81.43	43.38	PASS
13120.00†	7369.04	-231.89	-5964.70	3800.00	3845.00	-38.10	-5769.81	45.16	3534.74	85.45	41.37	PASS
13220.00†	7367.00	-235.78	-6064.60	3800.00	3845.00	-38.10	-5769.81	56.16	3539.84	90.48	39.12	PASS
13320.00†	7364.96	-239.66	-6164.51	3800.00	3845.00	-38.10	-5769.81	62.95	3547.75	96.02	36.95	PASS
13420.00†	7362.92	-243.55	-6264.41	3800.00	3845.00	-38.10	-5769.81	67.44	3558.45	101.78	34.96	PASS
13520.00†	7360.88	-247.43	-6364.31	3800.00	3845.00	-38.10	-5769.81	70.60	3571.93	107.63	33.19	PASS
13620.00†	7358.84	-251.32	-6464.22	3800.00	3845.00	-38.10	-5769.81	72.93	3588.14	113.48	31.62	PASS
13720.00†	7356.81	-255.20	-6564.12	3800.00	3845.00	-38.10	-5769.81	74.71	3607.05	119.27	30.24	PASS
13820.00†	7354.77	-259.08	-6664.02	3800.00	3845.00	-38.10	-5769.81	76.12	3628.63	124.97	29.04	PASS
13920.00†	7352.73	-262.97	-6763.93	3800.00	3845.00	-38.10	-5769.81	77.25	3652.81	130.56	27.98	PASS
14020.00†	7350.69	-266.85	-6863.83	3800.00	3845.00	-38.10	-5769.81	78.19	3679.55	136.01	27.05	PASS
14120.00†	7348.65	-270.74	-6963.74	3800.00	3845.00	-38.10	-5769.81	78.97	3708.80	141.33	26.24	PASS
14220.00†	7346.61	-274.62	-7063.64	3800.00	3845.00	-38.10	-5769.81	79.64	3740.49	146.48	25.54	PASS
14320.00†	7344.58	-278.50	-7163.54	3800.00	3845.00	-38.10	-5769.81	80.21	3774.56	151.48	24.92	PASS
14420.00†	7342.54	-282.39	-7263.45	3800.00	3845.00	-38.10	-5769.81	80.71	3810.96	156.31	24.38	PASS
14520.00†	7340.50	-286.27	-7363.35	3800.00	3845.00	-38.10	-5769.81	81.15	3849.61	160.96	23.92	PASS
14620.00†	7338.46	-290.16	-7463.25	3800.00	3845.00	-38.10	-5769.81	81.53	3890.44	165.45	23.51	PASS
14720.00†	7336.42	-294.04	-7563.16	3800.00	3845.00	-38.10	-5769.81	81.88	3933.40	169.77	23.17	PASS
14820.00†	7334.39	-297.93	-7663.06	3800.00	3845.00	-38.10	-5769.81	82.19	3978.41	173.91	22.88	PASS
14920.00†	7332.35	-301.81	-7762.97	3800.00	3845.00	-38.10	-5769.81	82.46	4025.39	177.88	22.63	PASS
15020.00†	7330.31	-305.69	-7862.87	3800.00	3845.00	-38.10	-5769.81	82.71	4074.30	181.69	22.42	PASS
15120.00†	7328.27	-309.58	-7962.77	3800.00	3845.00	-38.10	-5769.81	82.94	4125.04	185.33	22.26	PASS
15220.00†	7326.23	-313.46	-8062.68	3800.00	3845.00	-38.10	-5769.81	83.15	4177.56	188.82	22.12	PASS
15320.00†	7324.19	-317.35	-8162.58	3800.00	3845.00	-38.10	-5769.81	83.34	4231.80	192.14	22.02	PASS
15420.00†	7322.16	-321.23	-8262.48	3800.00	3845.00	-38.10	-5769.81	83.52	4287.68	195.32	21.95	PASS
15520.00†	7320.12	-325.11	-8362.39	3800.00	3845.00	-38.10	-5769.81	83.68	4345.14	198.35	21.91	PASS
15620.00†	7318.08	-329.00	-8462.29	3800.00	3845.00	-38.10	-5769.81	83.83	4404.13	201.24	21.88	PASS
15665.22†	7317.16	-330.75	-8507.47	3800.00	3845.00	-38.10	-5769.81	83.90	4431.29	202.50	21.88	PASS
15720.00†	7316.04	-332.88	-8562.20	3800.00	3845.00	-38.10	-5769.81	83.97	4464.58	203.99	21.89	PASS
15820.00†	7314.00	-336.77	-8662.10	3800.00	3845.00	-38.10	-5769.81	84.10	4526.42	206.62	21.91	PASS
15920.00†	7311.97	-340.65	-8762.00	3800.00	3845.00	-38.10	-5769.81	84.23	4589.62	209.11	21.95	PASS
16020.00†	7309.93	-344.54	-8861.91	3800.00	3845.00	-38.10	-5769.81	84.34	4654.10	211.49	22.01	PASS
16120.00†	7307.89	-348.42	-8961.81	3800.00	3845.00	-38.10	-5769.81	84.45	4719.83	213.75	22.08	PASS
16220.00†	7305.85	-352.30	-9061.71	3800.00	3845.00	-38.10	-5769.81	84.55	4786.74	215.91	22.17	PASS
16320.00†	7303.81	-356.19	-9161.62	3800.00	3845.00	-38.10	-5769.81	84.64	4854.78	217.96	22.27	PASS
16420.00†	7301.77	-360.07	-9261.52	3800.00	3845.00	-38.10	-5769.81	84.73	4923.92	219.91	22.39	PASS
16520.00†	7299.74	-363.96	-9361.43	3800.00	3845.00	-38.10	-5769.81	84.82	4994.10	221.76	22.52	PASS
16620.00†	7297.70	-367.84	-9461.33	3800.00	3845.00	-38.10	-5769.81	84.90	5065.29	223.53	22.66	PASS
16720.00†	7295.66	-371.72	-9561.23	3800.00	3845.00	-38.10	-5769.81	84.97	5137.44	225.21	22.81	PASS
16820.00†	7293.62	-375.61	-9661.14	3800.00	3845.00	-38.10	-5769.81	85.04	5210.50	226.81	22.97	PASS
16920.00†	7291.58	-379.49	-9761.04	3800.00	3845.00	-38.10	-5769.81	85.11	5284.45	228.33	23.14	PASS
17020.00†	7289.55	-383.38	-9860.94	3800.00	3845.00	-38.10	-5769.81	85.18	5359.24	229.78	23.32	PASS
17120.00†	7287.51	-387.26	-9960.85	3800.00	3845.00	-38.10	-5769.81	85.24	5434.85	231.16	23.51	PASS
17144.89	7287.00	-388.23	-9985.71	3800.00	3845.00	-38.10	-5769.81	85.25	5453.78	231.49	23.56	PASS



Clearance Report

B-1

Closest Approach

Page 22 of 27

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION

Operator	WTD - West Texas Division	Slot	No.482H SHL
Area	Eddy County, NM	Well	No.482H
Field	Poker Lake Unit	Wellbore	No.482H PWB
Facility	PLU Pad (482,483)		

POSITIONAL UNCERTAINTY - Offset Wellbore: No.64 AWB Offset Wellpath: No.64 AWP

Slot Surface Uncertainty @1SD	Horizontal	0.100ft	Vertical	0.100ft
Facility Surface Uncertainty @1SD	Horizontal	3.300ft	Vertical	1.000ft

WELLPATH COMPOSITION - Offset Wellbore: No.64 AWB Offset Wellpath: No.64 AWP

Start MD [ft]	End MD [ft]	Positional Uncertainty Model	Log Name/Comment	Wellbore
0.00	3800.00	Unknown Tool (Standard)	Unknoww <3800>	No.64 AWB

OFFSET WELLPATH MD REFERENCE - Offset Wellbore: No.64 AWB Offset Wellpath: No.64 AWP

MD Reference: Rig on No.64 SHL (RT)	Offset TVD & local coordinates use Reference Wellpath settings (See WELLPATH DATUM on page 1 of this report)
Ellipse Start MD	0.00ft



Clearance Report

B-1

Closest Approach

Page 23 of 27

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION

Operator	WTD - West Texas Division	Slot	No.482H SHL
Area	Eddy County, NM	Well	No.482H
Field	Poker Lake Unit	Wellbore	No.482H PWB
Facility	PLU Pad (482,483)		

CLEARANCE DATA - Offset Wellbore: No.21H AWB Offset Wellpath: No.21H AWP

Facility: PLU CVX JV PC No.21H				Slot: No.21H SHL		Well: No.21H		Threshold Value=1.00 † = Interpolated/extrapolated			
Ref MD [ft]	Ref TVD [ft]	Ref North [ft]	Ref East [ft]	Offset MD [ft]	Offset TVD [ft]	Offset North [ft]	Offset East [ft]	Horiz Bearing [°]	C-C Clear Dist [ft]	ACR MASD [ft]	Sep Ratio
20.00	20.00	0.00	0.00	11.00	20.00	-4638.83	-2693.79	210.14	5364.26	3.01	1779.2
120.00†	120.00	0.00	0.00	116.36	125.36	-4638.65	-2693.99	210.15	5364.21	12.04	445.5
220.00†	220.00	0.00	0.00	226.48	235.48	-4638.23	-2694.40	210.15	5364.06	12.10	443.2
320.00†	320.00	0.00	0.00	352.29	361.29	-4637.21	-2694.71	210.16	5363.48	12.21	439.1
420.00†	420.00	0.00	0.00	456.88	465.88	-4636.14	-2694.79	210.17	5362.63	12.36	433.7
520.00†	520.00	0.00	0.00	550.97	559.96	-4635.24	-2694.81	210.17	5361.82	12.48	429.5
620.00†	620.00	0.00	0.00	641.54	650.52	-4634.59	-2694.74	210.18	5361.16	12.57	426.5
720.00†	720.00	0.00	0.00	736.61	745.59	-4634.17	-2694.53	210.18	5360.66	12.71	421.9
820.00†	820.00	0.00	0.00	843.83	852.81	-4633.71	-2694.19	210.18	5360.14	12.90	415.5
920.00†	920.00	0.00	0.00	949.61	958.58	-4633.13	-2693.73	210.17	5359.44	13.13	408.0
1020.00†	1020.00	0.00	0.00	1048.19	1057.16	-4632.71	-2693.07	210.17	5358.73	13.37	400.7
1120.00†	1120.00	0.00	0.00	1144.06	1153.03	-4632.23	-2692.59	210.17	5358.05	13.57	394.8
1220.00†	1220.00	0.00	0.00	1228.97	1237.93	-4631.98	-2692.21	210.17	5357.57	13.75	389.5
1320.00†	1320.00	0.00	0.00	1319.74	1328.71	-4631.97	-2691.83	210.16	5357.35	13.96	383.7
1420.00†	1420.00	0.00	0.00	1428.90	1437.86	-4631.65	-2691.96	210.17	5357.16	14.20	377.3
1520.00†	1520.00	0.00	0.00	1556.12	1565.07	-4630.20	-2692.95	210.18	5356.56	14.46	370.3
1620.00†	1620.00	0.00	0.00	1629.57	1638.51	-4629.19	-2693.82	210.20	5355.97	14.73	363.6
1720.00†	1720.00	0.00	0.00	1720.66	1729.58	-4628.07	-2695.34	210.22	5355.75	15.02	356.5
1820.00†	1820.00	0.00	0.00	1789.35	1798.25	-4627.15	-2696.97	210.24	5355.80	15.31	349.7
1920.00†	1920.00	0.00	0.00	1862.03	1870.90	-4626.68	-2698.91	210.26	5356.55	15.62	342.9
2020.00†	2020.00	0.00	0.00	1976.76	1985.59	-4626.04	-2701.76	210.29	5357.32	15.98	335.2
2120.00†	2120.00	0.00	0.00	2076.90	2085.72	-4625.80	-2703.34	210.30	5357.91	16.34	327.9
2220.00†	2220.00	0.00	0.00	2167.51	2176.32	-4625.63	-2704.93	210.32	5358.64	16.70	320.9
2320.00†	2320.00	0.00	0.00	2256.06	2264.84	-4625.40	-2706.92	210.34	5359.55	17.07	314.0
2420.00†	2420.00	0.00	0.00	2341.41	2350.16	-4625.19	-2709.26	210.36	5360.72	17.44	307.3
2520.00†	2520.00	0.00	0.00	2436.05	2444.78	-4625.72	-2711.00	210.37	5362.14	17.84	300.5
2620.00†	2620.00	0.00	0.00	2552.76	2561.49	-4626.66	-2712.20	210.38	5363.34	18.28	293.4
2720.00†	2720.00	0.00	0.00	2730.73	2739.45	-4627.66	-2712.06	210.37	5363.85	18.83	284.9
2820.00†	2820.00	0.00	0.00	2845.12	2853.82	-4627.90	-2710.35	210.36	5363.26	19.30	277.9
2920.00†	2920.00	0.00	0.00	2938.13	2946.81	-4628.27	-2708.63	210.34	5362.68	19.73	271.8
3020.00†	3020.00	0.00	0.00	3027.91	3036.57	-4628.90	-2706.84	210.32	5362.27	20.16	265.9
3120.00†	3120.00	0.00	0.00	3161.76	3170.34	-4630.68	-2702.56	210.27	5361.86	20.68	259.2
3220.00†	3220.00	0.00	0.00	3250.53	3259.04	-4631.75	-2699.20	210.23	5361.00	21.14	253.6
3320.00†	3320.00	0.00	0.00	3319.30	3327.76	-4632.78	-2696.78	210.20	5360.54	21.56	248.6
3420.00†	3420.00	0.00	0.00	3392.21	3400.60	-4634.45	-2694.15	210.17	5360.68	21.99	243.7
3520.00†	3520.00	0.00	0.00	3471.61	3479.93	-4636.53	-2691.39	210.13	5361.21	22.45	238.8
3620.00†	3620.00	0.00	0.00	3541.40	3549.65	-4638.67	-2689.14	210.10	5362.24	22.88	234.3
3720.00†	3720.00	0.00	0.00	3628.53	3636.70	-4641.47	-2686.81	210.07	5363.69	23.35	229.6
3820.00†	3820.00	0.00	0.00	3770.44	3778.55	-4644.72	-2684.33	210.03	5364.77	23.95	224.0
3920.00†	3920.00	0.00	0.00	3902.65	3910.74	-4646.64	-2682.71	210.00	5365.47	24.53	218.7
4020.00†	4020.00	0.00	0.00	4038.00	4046.09	-4646.31	-2682.63	210.00	5365.20	25.13	213.5
4120.00†	4120.00	0.00	0.00	4139.52	4147.60	-4645.62	-2682.78	210.01	5364.68	25.65	209.1
4220.00†	4220.00	0.00	0.00	4233.36	4241.44	-4645.08	-2682.86	210.01	5364.23	26.16	205.0
4320.00†	4320.00	0.00	0.00	4326.67	4334.75	-4644.70	-2682.88	210.01	5363.88	26.68	201.0
4420.00†	4420.00	0.00	0.00	4417.68	4425.76	-4644.38	-2683.10	210.02	5363.70	27.19	197.2



Clearance Report

B-1

Closest Approach

Page 24 of 27

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION			
Operator	WTD - West Texas Division	Slot	No.482H SHL
Area	Eddy County, NM	Well	No.482H
Field	Poker Lake Unit	Wellbore	No.482H PWB
Facility	PLU Pad (482,483)		

CLEARANCE DATA - Offset Wellbore: No.21H AWP Offset Wellpath: No.21H AWP											
Facility: PLU CVX JV PC No.21H				Slot: No.21H SHL		Well: No.21H		Threshold Value=1.00 † = Interpolated/extrapolated			
Ref MD [ft]	Ref TVD [ft]	Ref North [ft]	Ref East [ft]	Offset MD [ft]	Offset TVD [ft]	Offset North [ft]	Offset East [ft]	Horiz Bearing [°]	C-C Clear Dist [ft]	ACR MASD [ft]	Sep Ratio
4520.00†	4520.00	0.00	0.00	4515.11	4523.19	-4644.16	-2683.31	210.02	5363.62	27.72	193.5
4620.00†	4620.00	0.00	0.00	4620.81	4628.89	-4643.94	-2683.52	210.02	5363.53	28.27	189.7
4720.00†	4720.00	0.00	0.00	4726.02	4734.10	-4643.47	-2683.68	210.03	5363.22	28.82	186.0
4820.00†	4820.00	0.00	0.00	4809.42	4817.50	-4643.11	-2684.19	210.03	5363.14	29.33	182.8
4920.00†	4920.00	0.00	0.00	4905.15	4913.22	-4642.64	-2685.14	210.04	5363.22	29.87	179.5
5020.00†	5020.00	0.00	0.00	4998.04	5006.10	-4642.27	-2686.18	210.06	5363.43	30.40	176.4
5120.00†	5120.00	0.00	0.00	5100.45	5108.51	-4642.53	-2686.15	210.05	5363.64	30.97	173.1
5220.00†	5220.00	0.00	0.00	5199.95	5208.01	-4643.33	-2685.32	210.04	5363.92	31.54	170.0
5320.00†	5320.00	0.00	0.00	5304.59	5312.64	-4643.60	-2685.04	210.04	5364.00	32.11	167.0
5420.00†	5420.00	0.00	0.00	5392.58	5400.63	-4643.61	-2685.52	210.04	5364.28	32.64	164.3
5520.00†	5520.00	0.00	0.00	14541.63	10145.45	11.77	-2675.17	270.25	5343.36	100.81	53.0
5620.00†	5620.00	0.00	0.00	14541.47	10145.45	11.61	-2675.17	270.25	5257.03	101.92	51.5
5720.00†	5720.00	0.00	0.00	14541.32	10145.45	11.46	-2675.17	270.25	5171.20	103.06	50.1
5820.00†	5820.00	0.00	0.00	14541.16	10145.45	11.30	-2675.17	270.24	5085.88	104.24	48.7
5920.00†	5920.00	0.00	0.00	14541.00	10145.45	11.14	-2675.17	270.24	5001.11	105.45	47.4
6020.00†	6020.00	0.00	0.00	14540.84	10145.45	10.98	-2675.17	270.24	4916.91	106.70	46.0
6120.00†	6120.00	0.00	0.00	14540.68	10145.45	10.82	-2675.17	270.23	4833.31	107.99	44.7
6220.00†	6220.00	0.00	0.00	14540.52	10145.45	10.66	-2675.17	270.23	4750.35	109.31	43.4
6320.00†	6320.00	0.00	0.00	14540.35	10145.45	10.49	-2675.17	270.23	4668.05	110.67	42.1
6420.00†	6420.00	0.00	0.00	14540.18	10145.45	10.32	-2675.17	270.22	4586.46	112.07	40.9
6520.00†	6520.00	0.00	0.00	14540.01	10145.45	10.15	-2675.17	270.22	4505.61	113.51	39.6
6620.00†	6620.00	0.00	0.00	14539.84	10145.45	9.98	-2675.17	270.21	4425.55	114.99	38.4
6720.00†	6720.00	0.00	0.00	14539.67	10145.45	9.81	-2675.17	270.21	4346.31	116.51	37.3
6808.00	6808.00	0.00	0.00	14539.51	10145.46	9.65	-2675.17	270.21	4277.29	117.88	36.2
6820.00†	6820.00	0.00	-0.13	14539.48	10145.46	9.63	-2675.17	270.21	4267.86	118.07	36.1
6920.00†	6919.29	-0.42	-10.90	14539.16	10145.46	9.30	-2675.17	270.21	4184.08	119.51	35.0
7020.00†	7015.20	-1.51	-38.75	14538.59	10145.46	8.73	-2675.17	270.22	4092.60	120.67	33.9
7120.00†	7104.81	-3.22	-82.81	14537.77	10145.46	7.91	-2675.17	270.25	3995.75	121.47	32.8
7220.00†	7185.40	-5.51	-141.75	14536.73	10145.47	6.87	-2675.16	270.28	3896.20	121.87	31.9
7320.00†	7254.53	-8.31	-213.78	14535.47	10145.48	5.61	-2675.16	270.32	3796.87	121.82	31.1
7420.00†	7310.09	-11.53	-296.71	14534.03	10145.48	4.17	-2675.16	270.38	3700.91	121.32	30.5
7508.00	7346.40	-14.64	-376.71	14532.62	10145.49	2.76	-2675.16	270.43	3621.89	120.49	30.0
7520.00†	7350.51	-15.08	-387.98	14532.43	10145.49	2.56	-2675.16	270.44	3611.57	120.34	30.0
7620.00†	7384.71	-18.73	-481.88	14530.73	10145.50	0.87	-2675.17	270.51	3526.03	119.22	29.5
7708.00	7414.81	-21.94	-564.51	14529.19	10145.51	-0.67	-2675.17	270.58	3451.39	118.20	29.2
7720.00†	7418.84	-22.38	-575.80	14528.98	10145.51	-0.88	-2675.17	270.59	3441.30	118.06	29.1
7820.00†	7446.82	-26.11	-671.69	14527.13	10145.52	-2.73	-2675.18	270.67	3361.18	116.69	28.8
7920.00†	7464.54	-29.93	-769.98	14525.19	10145.54	-4.67	-2675.18	270.76	3289.10	115.06	28.5
8020.00†	7471.81	-33.80	-869.60	14523.18	10145.55	-6.68	-2675.19	270.86	3226.42	113.22	28.5
8039.03	7472.00	-34.54	-888.61	14522.80	10145.55	-7.06	-2675.19	270.88	3215.67	112.83	28.5
8097.43	7471.40	-36.81	-946.96	14521.59	10145.56	-8.27	-2675.20	270.95	3184.14	111.68	28.5
8120.00†	7470.94	-37.69	-969.51	14521.12	10145.56	-8.74	-2675.20	270.97	3172.35	111.22	28.5
8220.00†	7468.91	-41.57	-1069.41	14518.97	10145.58	-10.89	-2675.21	271.10	3121.56	109.22	28.5
8320.00†	7466.87	-45.45	-1169.32	14516.73	10145.60	-13.13	-2675.23	271.23	3073.17	107.23	28.6
8420.00†	7464.83	-49.34	-1269.22	14514.40	10145.62	-15.46	-2675.25	271.38	3027.32	105.24	28.7



Clearance Report

B-1

Closest Approach

Page 25 of 27

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION			
Operator	WTD - West Texas Division	Slot	No.482H SHL
Area	Eddy County, NM	Well	No.482H
Field	Poker Lake Unit	Wellbore	No.482H PWB
Facility	PLU Pad (482,483)		

CLEARANCE DATA - Offset Wellbore: No.21H AWP Offset Wellpath: No.21H AWP											
Facility: PLU CVX JV PC No.21H				Slot: No.21H SHL		Well: No.21H		Threshold Value=1.00 † = Interpolated/extrapolated			
Ref MD [ft]	Ref TVD [ft]	Ref North [ft]	Ref East [ft]	Offset MD [ft]	Offset TVD [ft]	Offset North [ft]	Offset East [ft]	Horiz Bearing [°]	C-C Clear Dist [ft]	ACR MASD [ft]	Sep Ratio
8520.00†	7462.79	-53.22	-1369.13	14511.97	10145.64	-17.89	-2675.27	271.55	2984.11	103.27	28.9
8620.00†	7460.75	-57.11	-1469.03	14509.43	10145.66	-20.43	-2675.29	271.74	2943.66	101.33	29.0
8720.00†	7458.72	-60.99	-1568.93	14506.78	10145.68	-23.08	-2675.32	271.96	2906.09	99.46	29.2
8820.00†	7456.68	-64.88	-1668.84	14504.01	10145.71	-25.85	-2675.36	272.22	2871.50	97.66	29.4
8920.00†	7454.64	-68.76	-1768.74	14501.11	10145.74	-28.75	-2675.40	272.53	2840.01	95.95	29.6
9020.00†	7452.60	-72.64	-1868.64	14498.07	10145.77	-31.79	-2675.44	272.90	2811.72	94.38	29.7
9120.00†	7450.56	-76.53	-1968.55	14494.88	10145.80	-34.97	-2675.49	273.36	2786.72	92.97	29.9
9220.00†	7448.52	-80.41	-2068.45	14491.54	10145.84	-38.32	-2675.55	273.97	2765.12	91.75	30.1
9320.00†	7446.49	-84.30	-2168.36	14488.01	10145.88	-41.84	-2675.62	274.78	2746.97	90.77	30.2
9420.00†	7444.45	-88.18	-2268.26	14484.30	10145.93	-45.55	-2675.69	275.97	2732.37	90.06	30.3
9520.00†	7442.41	-92.06	-2368.16	14480.39	10145.98	-49.46	-2675.78	277.89	2721.35	89.66	30.3
9620.00†	7440.37	-95.95	-2468.07	14476.26	10146.04	-53.59	-2675.87	281.52	2713.96	89.59	30.2
9720.00†	7438.33	-99.83	-2567.97	14471.89	10146.10	-57.96	-2675.98	291.19	2710.24	89.88	30.1
9770.00†	7437.31	-101.77	-2617.92	14475.00	10146.05	-54.85	-2675.90	308.98	2709.77	90.24	30.0
9820.00†	7436.30	-103.72	-2667.87	14467.27	10146.17	-62.58	-2676.11	348.68	2710.20	90.55	29.9
9920.00†	7434.26	-107.60	-2767.78	14462.36	10146.24	-67.48	-2676.25	66.33	2713.83	91.58	29.8
10020.00†	7432.22	-111.49	-2867.68	14457.14	10146.33	-72.70	-2676.41	78.54	2721.11	92.98	29.2
10120.00†	7430.18	-115.37	-2967.59	14451.59	10146.42	-78.25	-2676.60	82.73	2732.03	94.69	28.8
10220.00†	7428.14	-119.25	-3067.49	14441.24	10146.60	-88.59	-2676.98	85.51	2746.53	96.65	28.4
10320.00†	7426.10	-123.14	-3167.39	14429.25	10146.79	-100.57	-2677.46	87.36	2764.54	98.84	27.9
10420.00†	7424.07	-127.02	-3267.30	14415.87	10147.00	-113.93	-2678.06	88.73	2785.99	101.21	27.5
10520.00†	7422.03	-130.91	-3367.20	14400.84	10147.22	-128.94	-2678.81	89.84	2810.79	103.71	27.1
10620.00†	7419.99	-134.79	-3467.10	14383.87	10147.45	-145.89	-2679.75	90.81	2838.85	106.31	26.7
10720.00†	7417.95	-138.67	-3567.01	14364.52	10147.68	-165.19	-2680.94	91.71	2870.06	108.95	26.3
10820.00†	7415.91	-142.56	-3666.91	14342.27	10147.92	-187.39	-2682.48	92.61	2904.30	111.59	26.0
10920.00†	7413.88	-146.44	-3766.82	14321.83	10148.10	-207.77	-2684.03	93.24	2941.46	114.26	25.7
11020.00†	7411.84	-150.33	-3866.72	14310.08	10148.20	-219.49	-2684.95	93.35	2981.45	116.99	25.4
11120.00†	7409.80	-154.21	-3966.62	14298.41	10148.30	-231.12	-2685.86	93.44	3024.18	119.68	25.2
11220.00†	7407.76	-158.10	-4066.53	14286.82	10148.39	-242.68	-2686.75	93.51	3069.53	122.31	25.1
11320.00†	7405.72	-161.98	-4166.43	14275.31	10148.49	-254.15	-2687.64	93.57	3117.38	124.86	24.9
11420.00†	7403.68	-165.86	-4266.33	14263.89	10148.57	-265.54	-2688.51	93.62	3167.63	127.33	24.8
11520.00†	7401.65	-169.75	-4366.24	14252.55	10148.66	-276.84	-2689.37	93.65	3220.16	129.71	24.8
11610.67†	7399.80	-173.27	-4456.82	14242.34	10148.73	-287.03	-2690.14	93.68	3269.67	131.78	24.8
11620.00†	7399.61	-173.63	-4466.14	14129.79	10148.21	-399.12	-2700.07	97.28	3274.85	131.39	24.9
11720.00†	7397.57	-177.52	-4566.05	14122.34	10148.09	-406.53	-2700.81	97.00	3331.20	133.61	24.9
11820.00†	7395.53	-181.40	-4665.95	14115.15	10147.97	-413.70	-2701.51	96.74	3389.53	135.73	24.9
11920.00†	7393.49	-185.28	-4765.85	14108.20	10147.87	-420.61	-2702.17	96.51	3449.75	137.76	25.0
12020.00†	7391.46	-189.17	-4865.76	14101.48	10147.77	-427.30	-2702.79	96.28	3511.75	139.68	25.1
12120.00†	7389.42	-193.05	-4965.66	14094.98	10147.68	-433.77	-2703.38	96.07	3575.45	141.51	25.2
12220.00†	7387.38	-196.94	-5065.56	14088.70	10147.59	-440.03	-2703.93	95.88	3640.77	143.25	25.4
12320.00†	7385.34	-200.82	-5165.47	14082.61	10147.51	-446.10	-2704.46	95.69	3707.61	144.89	25.5
12420.00†	7383.30	-204.71	-5265.37	14076.72	10147.44	-451.97	-2704.95	95.52	3775.89	146.45	25.7
12520.00†	7381.26	-208.59	-5365.28	14071.00	10147.38	-457.66	-2705.42	95.35	3845.55	147.92	26.0
12620.00†	7379.23	-212.47	-5465.18	14065.46	10147.31	-463.18	-2705.87	95.19	3916.50	149.31	26.2
12720.00†	7377.19	-216.36	-5565.08	14060.09	10147.26	-468.54	-2706.29	95.04	3988.68	150.63	26.4



Clearance Report

B-1
Closest Approach
Page 26 of 27

BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION

Operator	WTD - West Texas Division	Slot	No.482H SHL
Area	Eddy County, NM	Well	No.482H
Field	Poker Lake Unit	Wellbore	No.482H PWB
Facility	PLU Pad (482,483)		

CLEARANCE DATA - Offset Wellbore: No.21H AWP Offset Wellpath: No.21H AWP

Facility: PLU CVX JV PC No.21H				Slot: No.21H SHL		Well: No.21H		Threshold Value=1.00		† = Interpolated/extrapolated		
Ref MD [ft]	Ref TVD [ft]	Ref North [ft]	Ref East [ft]	Offset MD [ft]	Offset TVD [ft]	Offset North [ft]	Offset East [ft]	Horiz Bearing [°]	C-C Clear Dist [ft]	ACR MASD [ft]	Sep Ratio	
12820.00†	7375.15	-220.24	-5664.99	14054.87	10147.20	-473.74	-2706.69	94.90	4062.02	151.88	26.7	
12920.00†	7373.11	-224.13	-5764.89	14049.81	10147.15	-478.79	-2707.07	94.76	4136.47	153.05	27.0	
13020.00†	7371.07	-228.01	-5864.79	14044.89	10147.11	-483.70	-2707.44	94.63	4211.96	154.17	27.3	
13120.00†	7369.04	-231.89	-5964.70	14024.12	10146.88	-504.41	-2708.93	94.79	4288.44	155.20	27.6	
13220.00†	7367.00	-235.78	-6064.60	13944.67	10144.87	-583.63	-2714.69	95.93	4365.72	156.25	27.9	
13320.00†	7364.96	-239.66	-6164.51	13935.42	10144.53	-592.85	-2715.36	95.85	4443.80	157.20	28.2	
13420.00†	7362.92	-243.55	-6264.41	13926.20	10144.20	-602.03	-2716.04	95.77	4522.72	158.11	28.6	
13520.00†	7360.88	-247.43	-6364.31	13917.01	10143.88	-611.20	-2716.70	95.70	4602.44	158.96	28.9	
13620.00†	7358.84	-251.32	-6464.22	13907.85	10143.56	-620.33	-2717.37	95.63	4682.91	159.77	29.3	
13720.00†	7356.81	-255.20	-6564.12	13898.71	10143.25	-629.43	-2718.03	95.56	4764.11	160.54	29.6	
13820.00†	7354.77	-259.08	-6664.02	13889.61	10142.94	-638.51	-2718.69	95.49	4845.98	161.27	30.0	
13920.00†	7352.73	-262.97	-6763.93	13880.53	10142.64	-647.55	-2719.34	95.43	4928.50	161.97	30.4	
14020.00†	7350.69	-266.85	-6863.83	13871.48	10142.34	-656.57	-2719.99	95.37	5011.64	162.63	30.8	
14120.00†	7348.65	-270.74	-6963.74	13862.46	10142.05	-665.57	-2720.64	95.32	5095.37	163.26	31.2	
14220.00†	7346.61	-274.62	-7063.64	13853.47	10141.76	-674.53	-2721.28	95.26	5179.65	163.85	31.6	
14320.00†	7344.58	-278.50	-7163.54	13839.58	10141.32	-688.38	-2722.28	95.27	5264.47	164.44	32.0	
14420.00†	7342.54	-282.39	-7263.45	13823.61	10140.82	-704.30	-2723.44	95.31	5349.77	165.01	32.4	
14520.00†	7340.50	-286.27	-7363.35	13807.39	10140.30	-720.47	-2724.63	95.35	5435.54	165.57	32.8	
14620.00†	7338.46	-290.16	-7463.25	13790.90	10139.76	-736.90	-2725.85	95.39	5521.76	166.10	33.2	
14720.00†	7336.42	-294.04	-7563.16	13774.15	10139.22	-753.60	-2727.11	95.43	5608.40	166.61	33.6	
14820.00†	7334.39	-297.93	-7663.06	13757.13	10138.65	-770.56	-2728.41	95.47	5695.44	167.11	34.0	
14920.00†	7332.35	-301.81	-7762.97	13751.81	10138.48	-775.86	-2728.82	95.38	5782.88	167.53	34.5	
15020.00†	7330.31	-305.69	-7862.87	13747.40	10138.34	-780.25	-2729.15	95.28	5870.72	167.93	34.9	
15120.00†	7328.27	-309.58	-7962.77	13743.06	10138.21	-784.58	-2729.47	95.19	5958.93	168.31	35.4	
15220.00†	7326.23	-313.46	-8062.68	13738.78	10138.08	-788.85	-2729.79	95.09	6047.49	168.67	35.8	
15320.00†	7324.19	-317.35	-8162.58	13734.57	10137.95	-793.05	-2730.09	95.00	6136.40	169.01	36.3	
15420.00†	7322.16	-321.23	-8262.48	13730.42	10137.84	-797.18	-2730.39	94.92	6225.64	169.35	36.7	
15520.00†	7320.12	-325.11	-8362.39	13726.34	10137.72	-801.25	-2730.68	94.83	6315.20	169.67	37.2	
15620.00†	7318.08	-329.00	-8462.29	13722.31	10137.62	-805.27	-2730.97	94.75	6405.05	169.97	37.6	
15720.00†	7316.04	-332.88	-8562.20	13718.35	10137.51	-809.22	-2731.24	94.67	6495.20	170.27	38.1	
15820.00†	7314.00	-336.77	-8662.10	13714.44	10137.41	-813.11	-2731.51	94.59	6585.62	170.55	38.6	
15920.00†	7311.97	-340.65	-8762.00	13710.59	10137.32	-816.95	-2731.77	94.52	6676.32	170.82	39.0	
16020.00†	7309.93	-344.54	-8861.91	13706.80	10137.23	-820.74	-2732.03	94.44	6767.26	171.09	39.5	
16120.00†	7307.89	-348.42	-8961.81	13703.06	10137.15	-824.46	-2732.27	94.37	6858.46	171.34	40.0	
16220.00†	7305.85	-352.30	-9061.71	13699.38	10137.06	-828.14	-2732.52	94.30	6949.89	171.59	40.5	
16320.00†	7303.81	-356.19	-9161.62	13695.75	10136.99	-831.76	-2732.75	94.23	7041.55	171.82	40.9	
16420.00†	7301.77	-360.07	-9261.52	13692.17	10136.91	-835.33	-2732.98	94.16	7133.42	172.05	41.4	
16520.00†	7299.74	-363.96	-9361.43	13688.64	10136.84	-838.86	-2733.21	94.10	7225.51	172.28	41.9	
16620.00†	7297.70	-367.84	-9461.33	13685.16	10136.78	-842.33	-2733.42	94.03	7317.80	172.49	42.4	
16720.00†	7295.66	-371.72	-9561.23	13681.72	10136.71	-845.76	-2733.64	93.97	7410.29	172.70	42.9	
16820.00†	7293.62	-375.61	-9661.14	13678.34	10136.65	-849.14	-2733.85	93.91	7502.96	172.90	43.3	
16920.00†	7291.58	-379.49	-9761.04	13675.00	10136.59	-852.47	-2734.05	93.85	7595.82	173.10	43.8	
17020.00†	7289.55	-383.38	-9860.94	13671.70	10136.54	-855.76	-2734.25	93.79	7688.85	173.29	44.3	
17120.00†	7287.51	-387.26	-9960.85	13668.45	10136.49	-859.00	-2734.44	93.74	7782.04	173.48	44.8	
17144.89	7287.00	-388.23	-9985.71	13667.65	10136.48	-859.80	-2734.49	93.72	7805.26	173.53	44.9	



Clearance Report

B-1
Closest Approach
Page 27 of 27


BOPCO, L.P.

REFERENCE WELLPATH IDENTIFICATION			
Operator	WTD - West Texas Division	Slot	No.482H SHL
Area	Eddy County, NM	Well	No.482H
Field	Poker Lake Unit	Wellbore	No.482H PWB
Facility	PLU Pad (482,483)		

POSITIONAL UNCERTAINTY - Offset Wellbore: No.21H AWB Offset Wellpath: No.21H AWP				
Slot Surface Uncertainty @1SD	Horizontal	0.100ft	Vertical	0.100ft
Facility Surface Uncertainty @1SD	Horizontal	3.000ft	Vertical	1.000ft


WELLPATH COMPOSITION - Offset Wellbore: No.21H AWB Offset Wellpath: No.21H AWP				
Start MD [ft]	End MD [ft]	Positional Uncertainty Model	Log Name/Comment	Wellbore
20.00	1019.00	Generic gyro - northseeking (Standard)	MS Gyro <100-1019>	No.21H AWB
1019.00	17150.00	NaviTrak (Standard)	BHI MWD NvaiTrak <1120-17150>	No.21H AWB
17150.00	17202.00	Blind Drilling (std)	Projection to bit	No.21H AWB

OFFSET WELLPATH MD REFERENCE - Offset Wellbore: No.21H AWB Offset Wellpath: No.21H AWP	
MD Reference: Rig on No.21H SHL (KB)	Offset TVD & local coordinates use Reference Wellpath settings (See WELLPATH DATUM on page 1 of this report)
Ellipse Start MD	20.00ft



13-5/8" X 3-M BOPE (2 Rams and Rotating Head) &
Closed Loop System Equipment Schematic
Diagram A

Note: all valves & lines on choke manifold are 3" unless otherwise noted. Exact manifold configuration may vary.




Note: all valves & lines on choke manifold are 3" unless otherwise noted. Exact manifold configuration may vary.

Latshaw 13-5/8" X 3-M BOPE (2 Rams and Rotating Head) & Closed Loop System Equipment Schematic
Diagram C

Latshaw 4 closed loop system, with Latshaw 18 addition "clouded."


Note: Dimensional information reflected on this drawing are estimated measurements only.



BOPCO
Project: South East New Mexico

CAMERON

NAME: Jeanette	DATE: 7-22-13	WITNESS: #	21077904
----------------	---------------	------------	----------



Midwest Hose
& Specialty, Inc.

Internal Hydrostatic Test Graph

April 3, 2012

Customer: Latchaw

Pick Ticket #: 81610

Hose Specifications

Hose Type

0

1.5

3"

3000 PSI

Length

30'

O.D.

4.15/22

Standard Safety: 3400 PSI/Applies

Verification

Type of Fittings

41/16 3K

Die Size

5.12"

Hose Serial #

6884

Coupling Method

Swage

Final Q.R.

5.16"

Hose Assembly Serial #

81610


Working Pressure

3000 PSI

Burst Pressure

Standard Safety: 3400 PSI/Applies

Pressure Test



Test Pressure
10000 PSI

Time Held at Test Pressure
5 1/4 Minutes

Actual Burst Pressure

Peak Pressure
10195 PSI

Comments: Hose assembly pressure tested with water at ambient temperature.

Tested By: Donnie McInerney

Approved By: Bobby Fink

M I D W E S T
HOSE AND SPECIALTY INC.

INTERNAL HYDROSTATIC TEST REPORT			
Customer: LATSHAW DRILLING		P.O. Number: RIG#4	
HOSE SPECIFICATIONS			
Type: CHOKER LINE		Length: 30'	
I.D. 3" INCHES		O.D. 6" INCHES	
WORKING PRESSURE 5,000 PSI	TEST PRESSURE 10,000 PSI	BURST PRESSURE PSI	
COUPLINGS			
Type of End Fitting 4 1/16 5K FLANGE			
Type of Coupling: SWEDGED		MANUFACTURED BY MIDWEST HOSE & SPECIALTY	
PROCEDURE			
<u>Hose assembly pressure tested with water at ambient temperature.</u>			
TIME HELD AT TEST PRESSURE 1 MIN.		ACTUAL BURST PRESSURE: 0 PSI	
COMMENTS: SO#81610 Hose is covered with stainless steel armour cover and wrapped with fire resistant vermiculite coated fiberglass insulation rated for 1500 degrees complete with lifting eyes			
Date: 3/2/2011	Tested By: BOBBY FINK	Approved: MENDI JACKSON	

TABLE OF CONTENTS

I. H₂S Contingency Plan

- A. Scope
- B. Objective
- C. Discussion of Plan

II. Emergency Procedures

- A. Emergency Procedures and Public Protection
- B. Emergency Procedures Implementation
- C. Simulated Blowout Control Drills

III. Ignition Procedures

- A. Responsibility
- B. Instructions

IV. Training Requirements

V. Emergency Equipment

VI. Evacuation Plan

- A. General Plan
- B. Emergency Phone Lists

VII. General Information

- A. H₂S Toxicity Table
- B. Respirator Use
- C. Emergency Rescue

H₂S CONTINGENCY PLAN SECTION

Scope:

This contingency plan provides an organized plan of action for alerting and protecting the public within an area of exposure prior to an intentional release, or following the accidental release of a potentially hazardous volume of hydrogen sulfide. The plan establishes guidelines for all personnel whose work activity may involve exposure to Hydrogen Sulfide Gas (H₂S).

Objective:

Prevent any and all accidents, and prevent the uncontrolled release of H₂S into the atmosphere.

Provide proper evacuation procedures to cope with emergencies.

Provide immediate and adequate medical attention should an injury occur.

Discussion of Plan:

Suspected Problem Zones:

Implementation: This plan, with all details, is to be fully implemented 500' above or three days prior to drilling into the first known sour zone

Emergency Response and Public Protection Procedure: This section outlines the conditions and denotes steps to be taken in the event of an emergency.

Emergency Equipment and Procedure: This section outlines the safety and emergency equipment that will be required for the drilling of this well.

Training Provisions: This section outlines the training provisions that must be adhered to 500 feet above or three days prior to drilling into the first known sour zone.

Emergency call lists: Included are the telephone numbers of all persons that would need to be contacted should an H₂S emergency occur.

Briefing: This section deals with the briefing of all persons involved with the drilling of this well.

Public Safety: Public Safety Personnel will be made aware of the drilling of this well.

EMERGENCY PROCEDURES AND PUBLIC PROTECTION SECTION

- I. In the event of any evidence of H₂S levels above 10 ppm, take the following steps immediately:
 - A. Secure breathing apparatus.
 - B. Order non-essential personnel out of the danger zone.
 - C. Take steps to determine if the H₂S level can be corrected or suppressed, and if so, proceed with normal operations.
- II. If uncontrollable conditions occur, proceed with the following:
 - A. Take steps to protect and/or remove any public downwind of the rig, including partial evacuation or isolation. Notify necessary public safety personnel and the New Mexico Oil & Gas of the situation.
 - B. Isolate area and prevent entry by unauthorized persons into the 100 ppm ROE.
 - C. Remove all personnel to the Safe Briefing Area.
 - D. Notify public safety personnel for help with maintaining roadblocks and implementing evacuation. Phone number list attached.
 - E. Determine and proceed with the best possible plan to regain control of the well. Maintain tight security and safety measures.
- III. Responsibility:
 - A. The Company Approved Supervisor shall be responsible for the total implementation of the plan.
 - B. The Company Approved Supervisor shall be in complete command during any emergency.
 - C. The Company Approved Supervisor shall designate a back up Supervisor in the event that he/she is not available.

EMERGENCY PROCEDURE IMPLEMENTATION

I. Drilling or Tripping

A. All Personnel

1. When alarm sounds, don escape unit and report to upwind Safe Briefing Area.
2. Check status of other personnel (buddy system).
3. Secure breathing apparatus.
4. Wait for orders from supervisor.

B. Drilling Foreman

1. Report to the upwind Safe Briefing Area.
2. Don Breathing Apparatus and return to the point of release with the Tool Pusher or Driller (buddy system).
3. Determine the concentration of H₂S.
4. Assess the situation and take appropriate control measures.

C. Tool Pusher

1. Report to the upwind Safe Briefing Area.
2. Don breathing apparatus and return to the point of release with the Drilling Foreman or the Driller (buddy system).
3. Determine the concentration.
4. Assess the situation and take appropriate control measures.

D. Driller

1. Check the status of other personnel (in a rescue attempt, always use the buddy system).
2. Assign the least essential person to notify the Drilling Foreman and Tool Pusher, in the event of their absence.

3. Assume the responsibility of the Drilling Foreman and the Tool Pusher until they arrive, in the event of their absence.

E. Derrick Man and Floor Hands

1. Remain in the upwind Safe Briefing Area until otherwise instructed by a supervisor.

F. Mud Engineer

1. Report to the upwind Safe Briefing Area.
2. When instructed, begin check of mud for pH level and H₂S level.

G. On-site Safety Personnel

1. Don Breathing Apparatus.
2. Check status of all personnel.
3. Wait for instructions from Drilling Foreman or Tool Pusher.

II. Taking a Kick

- A. All personnel report to the upwind Safe Briefing Area.
- B. Follow standard BOP procedures.

III. Open Hole Logging

- A. All unnecessary personnel should leave the rig floor.
- B. Drilling Foreman and Safety Personnel should monitor the conditions and make necessary safety equipment recommendations.

IV. Running Casing or Plugging

- A. Follow "Drilling or Tripping" procedures.
- B. Assure that all personnel have access to protective equipment.

SIMULATED BLOWOUT CONTROL DRILLS

All drills will be initiated by activating alarm devices (air horn). Use one long blast on the air horn for ACTUAL and SIMULATED Blowout Control Drills. This operation will be performed by the Drilling Foreman or Tool Pusher at least one time per week for each of the following conditions, with each crew:

Drill # 1 Bottom Drilling

Drill # 2 Tripping Drill Pipe

In each of these drills, the initial reaction time to shutting in the well shall be timed as well as the total time for the crew to complete its entire pit drill assignment. The times must be recorded on the IADC Driller's Log as "Blowout Control Drill".

Drill No.:		
Reaction Time to Shut-In:	minutes,	seconds.
Total Time to Complete Assignment:	minutes,	seconds.

I. Drill Overviews

A. Drill No. 1- Bottom Drilling

1. Sound the alarm immediately.
2. Stop the rotary and hoist kelly joint above the rotary table.
3. Stop the circulatory pump.
4. Close the drill pipe rams.
5. Record casing and drill pipe shut-in pressures and pit volume increases.

B. Drill No. 2 – Tripping Drill Pipe

1. Sound the alarm immediately.
2. Position the upper tool joint just above the rotary table and set the slips.

3. Install a full opening valve or inside blowout preventor tool in order to close the drill pipe.
4. Close the drill pipe rams.
5. Record the shut-in annular pressure.

II. Crew Assignments

A. Drill No. 1 – Bottom Drilling

1. Driller
 - a) Stop the rotary and hoist kelly joint above the rotary table.
 - b) Stop the circulatory pump.
 - c) Check flow.
 - d) If flowing, sound the alarm immediately.
 - e) Record the shut-in drill pipe pressure.
 - f) Determine the mud weight increase needed or other courses of action.
2. Derrickman
 - a) Open choke line valve at BOP.
 - b) Signal Floor Man # 1 at accumulator that choke line is open.
 - c) Close choke and upstream valve after pipe tams have been closed.
 - d) Read the shut-in annular pressure and report readings to Driller.
3. Floor Man # 1
 - a) Close the pipe rams after receiving the signal from the Derrickman.
 - b) Report to Driller for further instructions.

4. Floor Man # 2

- a) Notify the Tool Pusher and Operator Representative of the H₂S alarms.
- b) Check for open fires and, if safe to do so, extinguish them.
- c) Stop all welding operations.
- d) Turn-off all non-explosion proof lights and instruments.
- e) Report to Driller for further instructions.

5. Tool Pusher

- a) Report to the rig floor.
- b) Have a meeting with all crews.
- c) Compile and summarize all information.
- d) Calculate the proper kill weight.
- e) Ensure that proper well procedures are put into action.

6. Operator Representative

- a) Notify the Drilling Superintendent.
- b) Determine if an emergency exists and if so, activate the contingency plan.

B. Drill No. 2 – Tripping Pipe

1. Driller

- a) Sound the alarm immediately when mud volume increase has been detected.
- b) Position the upper tool joint just above the rotary table and set slips.
- c) Install a full opening valve or inside blowout preventor tool to close the drill pipe.
- d) Check flow.

- e) Record all data reported by the crew.
- f) Determine the course of action.

2. Derrickman

- a) Come down out of derrick.
- b) Notify Tool Pusher and Operator Representative.
- c) Check for open fires and, if safe to do so, extinguish them.
- d) Stop all welding operations.
- e) Report to Driller for further instructions.

3. Floor Man # 1

- a) Pick up full opening valve or inside blowout preventor tool and stab into tool joint above rotary table (with Floor Man # 2).
- b) Tighten valve with back-up tongs.
- c) Close pipe rams after signal from Floor Man # 2.
- d) Read accumulator pressure and check for possible high pressure fluid leaks in valves or piping.
- e) Report to Driller for further instructions.

4. Floor Man # 2

- a) Pick-up full opening valve or inside blowout preventor tool and stab into tool joint above rotary table (with Floor Man # 1).
- b) Position back-up tongs on drill pipe.
- c) Open choke line valve at BOP.
- d) Signal Floor Man # 1 at accumulator that choke line is open.
- e) Close choke and upstream valve after pipe rams have been closed.
- f) Check for leaks on BOP stack and choke manifold.

- g) Read annular pressure.
- h) Report readings to the Driller.

5. Tool Pusher

- a) *Report to the rig floor.*
- b) Have a meeting with all of the crews.
- c) Compile and summarize all information.
- d) See that proper well kill procedures are put into action.

6. Operator Representative

- a) Notify Drilling Superintendent
- b) Determine if an emergency exists, and if so, activate the contingency plan.

IGNITION PROCEDURES

Responsibility:

The decision to ignite the well is the responsibility of the DRILLING FOREMAN in concurrence with the STATE POLICE. The State Police shall be the Incident Command on the scene of any major release. Intentional ignition must be coordinated with the NMOCD and local officials. In the event the Drilling Foreman is incapacitated, it becomes the responsibility of the RIG TOOL PUSHER. This decision should be made only as a last resort and in a situation where it is clear that:

1. Human life and property are endangered.
2. There is no hope of controlling the blowout under the prevailing conditions.

If time permits, notify the main office, but do not delay if human life is in danger. Initiate the first phase of the evacuation plan.

Instructions for Igniting the Well:

1. Two people are required for the actual igniting operation. Both men must wear self-contained breathing apparatus and must use a full body harness and attach a retrievable safety line to the D-Ring in the back. One man must monitor the atmosphere for explosive gases with the LEL monitor, while the Drilling Foreman is responsible for igniting the well.
2. The primary method to ignite is a 25mm flare gun with a range of approximately 500 feet.
3. Ignite from upwind and do not approach any closer than is warranted.
4. Select the ignition site best suited for protection and which offers an easy escape route.
5. Before igniting, check for the presence of combustible gases.
6. After igniting, continue emergency actions and procedures as before.
7. All unassigned personnel will limit their actions to those directed by the Drilling Foreman.

NOTE: After the well is ignited, burning Hydrogen Sulfide will convert to Sulfur Dioxide (SO₂), which is also highly toxic. Do not assume the area is safe after the well is ignited.

TRAINING REQUIREMENTS

When working in an area where Hydrogen Sulfide (H_2S) might be encountered, definite training requirements must be carried out. The Company Supervisor will ensure that all personnel at the well site, whether regularly assigned, contracted, or employed on an unscheduled basis, have had adequate training by a qualified instructor in the following:

1. Hazards and Characteristics of Hydrogen Sulfide and Sulfur Dioxide.
2. Physicals effects of Hydrogen Sulfide on the human body.
3. Toxicity of Hydrogen Sulfide and Sulfur Dioxide.
4. H_2S detection, emergency alarm and sensor location.
5. Emergency rescue.
6. First aid and artificial resuscitation.
7. The effects of Hydrogen Sulfide on metals.
8. Location safety.

In addition, Supervisory Personnel will be trained in the following areas:

1. If high tensile tubular are to be used, personnel will be trained in their special maintenance requirements.
2. Corrective action and shut-in procedures when drilling or reworking a well as well as blowout prevention and well control procedures.
3. The contents and requirements of the H_2S Drilling Operations Contingency Plan and the Public Protection Plan.

Service company personnel and visiting personnel must be notified if the zone contains H_2S , and each service company must provide adequate training and equipment for their employees before they arrive at the well site.

EMERGENCY EQUIPMENT

As stated in the BLM Onshore Order 6, for wells located in a known H₂S areas, H₂S equipment will be rigged up after setting surface casing. For wells located inside known H₂S areas, the flare pit will be located 150' from the location and for wells located outside known H₂S areas, the flare pit will be located 100' away from the location. (See page 6 of Survey plat package and diagram B or C.)

It is not anticipated that any H₂S is in the area, however in the event that H₂S is encountered, the attached H₂S Contingency Plan will be implemented. (Please refer to diagrams B or C for choke manifold and closed loop system layout.) See H₂S location layout diagram for location of all H₂S equipment on location.

All H₂S safety equipment and systems will be installed, tested and be operational when drilling reaches a depth of 500' above, or three days prior to penetrating a known formation containing H₂S.

Lease Entrance Sign:

Caution signs should be located at all roads providing direct access to the location. Signs shall have a yellow background with black lettering and contain the words "CAUTION" and "POISON GAS" that is legible from a distance of at least 50 feet.

**LEASE NAME
CAUTION – POTENTIAL POISON GAS
HYDROGEN SULFIDE
NO ADMITTANCE WITHOUT AUTHORIZATION**

Windsocks or Wind Streamers:

- A minimum of two 10" windsocks located at strategic locations so that they may be seen from any point on location.
- Wind streamers (if preferred) should be placed at various locations on the well site to ensure wind consciousness at all times. (Corners of location)

Hydrogen Sulfide Detector and Alarms:

- H₂S monitors with alarms will be located on the rig floor, at the cellar, and at the mud pits. These monitors will be set to alarm at 10 PPM with a red light and to alarm at 15 PPM with a red light and audible alarm.

Well Condition Flags:

The Well Condition flags should be located at all roads providing direct access to the location. It should have three (3) color coded flags (green, yellow and red) that will be used to denote the following location conditions:

GREEN – Normal Operating Conditions
YELLOW – Potential Danger
RED – Danger, H₂S Gas Present

Respiratory Equipment:

- Fresh air breathing equipment should be placed at the company supervision trailer and the safe briefing areas and should include the following:
 - A minimum of two SCBA's at each briefing area and the supervisor company supervision trailer.
 - Enough air line units to operate safely, anytime the H₂S concentration reaches the IDLH level (100 PPM).
 - Cascade system with enough breathing air hose and manifolds to reach the rig floor, the derrickman and the other operation areas.

Fire Extinguishers:

Adequate fire extinguishers shall be located at strategic locations.

Mud Program:

The mud program has been designed to minimize the volume of H₂S circulated to the surface. Proper mud weight, safe drilling practices and the use of H₂S scavengers will minimize hazards when penetrating H₂S bearing zones.

Metallurgy:

All drill strings, casing, tubing, wellhead; blowout preventer, drilling spools, kill lines, choke manifold and lines, and valves shall be suitable for H₂S service.

Well Control Equipment:

- Flare Line (See page 6 of survey plat package for flare line reference).
- Choke manifold (See diagram B or C and refer to H2S location diagram for location of important H2S safety items).
- Blind rams and pipe rams to accommodate all pipe sizes with properly sized closing units.
- Auxiliary equipment may include, if applicable, annular preventer & rotating head.

Communication Equipment:

- Proper communication equipment such as cell phones or 2 – way radios should be available for communication between the company man's trailer, rig floor and tool pusher's trailer.

Well Testing:

- There will be no drill stem testing.

Evacuation Plan:

- Evacuation routes should be established prior to spudding the well.
- Should be discussed with all rig personnel.

Designated Areas:***Parking and Visitor area:***

- All vehicles are to be parked at a pre-determined safe distance from the wellhead.
- A smoking area will be designated at a pre-determined safe distance from the wellhead and any other possible flammable areas.

Safe Briefing Areas:

- Two Safe Briefing Areas shall be designated on either side of the location at the maximum allowable distance from the well bore so they offset prevailing winds or they are at a 180 degree angle if wind directions tend to shift in the area.

- Personal protective equipment should be stored at both briefing areas or if a moveable cascade trailer is used, it should be kept upwind of existing winds. When wind is from the prevailing direction, both briefing areas should be accessible.

NOTE:

- Additional equipment will be available at Indian Fire and Safety in Hobbs, NM or at Total Safety in Hobbs, NM.

EVACUATION PLAN

General Plan

The direct lines of action to protect the public from hazardous gas situations are as follows:

1. When the company approved supervisor (Drilling Foremen, Tool Pusher or Driller) determine that Hydrogen Sulfide gas cannot be limited to the well location, and the public will be involved, he will activate the evacuation plan. Escape routes are noted on the Area Map.
2. Company safety personnel or designee will notify the appropriate local government agency that a hazardous condition exists and evacuation needs to be implemented.
3. Company approved safety personnel that have been trained in the use of the proper emergency equipment will be utilized.
4. Law enforcement personnel (State Police, Local Police Department, Fire Department, and the Sheriff's Department) will be called to aid in setting up and maintaining road blocks. Also, they will aid in evacuation of the public if necessary.

NOTE: Law enforcement personnel will not be asked to come into a contaminated area. Their assistance will be limited to uncontaminated areas. Constant radio contact will be maintained with them.

5. After the discharge of gas has been controlled, Company approved safety personnel will determine when the area is safe for re-entry.

See Emergency Action Plan

Contacting Authorities

BOPCO L.P. personnel must liaison with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such as type and volume of release, wind direction, location of release, etc. Be prepared with all information available including directions to site. The following call list of essential and potential responders has been prepared for use during a release. (Operator Name)'s response must be in coordination with the State of New Mexico's "Hazardous Materials Emergency Response Plan" (HMER).

H₂S CONTINGENCY PLAN EMERGENCY CONTACTS

BOPCO L.P. Midland Office

432-683-2277

Key Personnel

Name	Title	Cell Phone Number
Stephen Martinez	Drilling & Completions Manager	432-556-0262
Charles Warne	Division Engineer	432-312-4431
Don Wood	Division Drilling Specialist	432-266-2674
Leo Bojorquez	Area Drilling Superintendent	702-280-4424
Chris Giese	Engineer	432-661-7328
Brian Braun	Engineer	210-683-9849
Jeremy Braden	Engineer	432-312-1113

Artesia

Ambulance	911
State Police	575-746-2703
City Police	575-746-2703
Sheriff's Office	575-746-9888
Fire Department	575-746-2701
Local Emergency Planning Committee	575-746-2122
New Mexico Oil Conservation Division	575-748-1283

Carlsbad

Ambulance	911
State Police	575-885-3137
City Police	575-885-2111
Sheriff's Office	575-887-7551
Fire Department	575-887-3798
Local Emergency Planning Committee	575-887-6544
US Bureau of Land Management	575-887-6544

New Mexico Emergency Response Commission (Santa Fe)	505-476-9600
24 Hour	505-827-9126
New Mexico State Emergency Operations Center	505-476-9635
National Emergency Response Center (Washington, DC)	800-424-8802

Other

Wild Well Control	432-550-6202 (Permian Basin)
Cudd PressureControl	432-580-3544 or 432-570-5300 (Permian Basin)
Flight For Life – 4000 24 th St. Lubbock, Texas	806-743-9911
Aerocare – R3, Box 49F, Lubbock, Texas	806-747-8923
Med Flight Air Amb – 2301 Yale Blvd SE #D3, Albuquerque, NM	505-842-4433
S B Air Med Service – 2505 Clark Carr Loop SE, Albuquerque, NM	505-842-4949
Indian Fire and Safety – 3317 NW Cnty Rd, Hobbs, NM	575-393-3093
Total Safety – 3229 Industrial Dr., Hobbs, NM	575-392-2973

TOXIC EFFECTS OF HYDROGEN SULFIDE

Hydrogen Sulfide is extremely toxic. The acceptable ceiling concentration for eight-hour exposure is 10 PPM, which is .001% by volume. Hydrogen Sulfide is heavier than air (specific gravity = 1.192) and colorless. It forms an explosive mixture with air between 4.3 and 46.0 percent by volume. Hydrogen sulfide is almost as toxic as hydrogen cyanide and is between five and six times more toxic than carbon monoxide. Toxicity data for hydrogen sulfide and various other gases are compared in Table I. Physical effects at various Hydrogen Sulfide exposure levels are shown in Table II.

Table I - TOXICITY OF VARIOUS GASES

Common Name	Chemical Formula	Specific Gravity (SC=1)	Threshold Limit (1)	Hazardous Limit (2)	Lethal Concentration (3)
Hydrogen Cyanide	HCN	0.94	10 PPM	150 PPM/HR	300 PPM
Hydrogen Sulfide	H ₂ S	1.18	10 PPM	250 PPM/HR	600 PPM
Sulfur Dioxide	SO ₂	2.21	5 PPM	--	1000 PPM
Chlorine	CL ₂	2.45	1 PPM	4 PPM/HR	1000 PPM
Carbon Monoxide	CO	0.97	50 PPM	400 PPM/HR	1000 PPM
Carbon Dioxide	CO ₂	1.52	5000 PPM	5%	10%
Methane	CH ₄	0.55	90,000 PPM	Combustible in air	Above 5%

- 1) Threshold Limit – Concentration at which it is believed that all worker may be repeatedly exposed day after day without adverse effects.
- 2) Hazardous Limit – Concentration that will cause death with short-term exposure.
- 3) Lethal Concentration – Concentration that will cause death with short-term exposure.

Table II – PHYSICAL EFFECTS OF HYDROGEN SULFIDE

Percent (%)	PPM	Concentration Grains 100 STD. FT3*	Physical Effects
0.001	< 10	00.65	Obvious & unpleasant odor.
0.002	10	01.30	Safe for 8 hours of exposure.
0.010	100	06.48	Kills smell in 3-15 minutes. May sting eyes & throat.
0.020	200	12.96	Kills smell shortly; stings eyes & throat.
0.050	500	32.96	Dizziness; Breathing ceases in a few minutes. Needs prompt artificial respiration.
0.070	700	45.36	Unconscious quickly; Death will result if not rescued promptly.
0.100	1000	64.30	Unconscious at once; Followed by death within minutes.

- At 15.00 PSIA and 60° F.

USE OF SELF-CONTAINED BREATHING APPARATUS

1. Anyone who uses an SCBA shall: Be approved by a physician or licensed health care practitioner; Pass a fit test; Be trained in donning and doffing, proper use, including how to ensure a proper face seal, conducting an inspection of the SCBA, and conduct proper maintenance.
2. Such items as facial hair (beard or sideburns) and eyeglasses will not allow a proper face mask seal.
3. Anyone reasonably expected to wear SCBA's shall have these items removed before entering a toxic atmosphere.
4. A special mask with a mount for prescription glasses must be obtained for anyone who must wear eyeglasses in order to see while using an SCBA.
5. SCBA's should be worn in H₂S concentrations above 10 PPM.

RESCUE & FIRST AID FOR H₂S POISONING


DO NOT PANIC – REMAIN CALM – THINK

1. Hold your breath – do not inhale first.
2. Put on SCBA.
3. Remove victim(s) to fresh air as quickly as possible. Go upwind from source or at right angle to the wind. Do not go downwind.
4. Briefly apply chest pressure – using arm lift method of artificial respiration to clean victim's lungs and to avoid inhaling any toxic gas directly from victim's lungs.
5. Provide artificial respiration if needed.
6. Provide for prompt transportation to the hospital and continue giving artificial respiration if needed.
7. Inform hospital/medical facilities of the possibility of H₂S gas poisoning before they treat.

Besides basic first aid, everyone on location should have a good working knowledge of artificial respiration and CPR, as well as first aid for eyes and skin contact with liquid H₂S.

Proposed H2S Safety Schematic

- 1) Location of windsocks.
- 2) Location of H2S alarms
- 3) Location of briefing areas.
- 4) Terrain of surrounding area (Please refer to page 2 of survey plat package also see point 11 of multi-surface use plan)
- 5) Location of flare line(s) and pit(s) (Please refer to diagram 2 choke manifold diagram and or page six of survey plat packet)
- 6) Location of caution and/or danger signs.
- 7) Location of Breathing Equipment



Location On-Site Notes

Location on-site conducted by Todd Carpenter- BOPCO, L.P., Jarrel Brooks- BOPCO, L.P., Jesse Bassett-BLM, and a crew with Basin Surveys on 07/09/2015. The Poker Lake Unit 482H 500'x500' pad was moved from its original center hole location of 660' FNL & 1980' FWL, to 382' FNL & 2057' FWL, Sec 16-25-30 to avoid a hillside. Location layout is as follows: v-door will face the east, access road will enter location from the north/northwest and topsoil will be stockpiled to the north side of location.

MULTI-POINT SURFACE USE PLAN

NAME OF WELL: Poker Lake Unit #482H

LEGAL DESCRIPTION

SURFACE: 382' FNL, 2057' FWL, Section 16, T25S, R30E, Eddy County, NM.

BHL: 660' FNL, 2590' FEL, Section 18, T25S, R30E, Eddy County, NM.

POINT 1: EXISTING ROADS

- A) Proposed Well Site Location:

See Form C-102 (Survey Plat).

- B) Existing Roads:

From the junction of Twin Wells and Buck Jackson go northwest on Twin Wells for 467 ft, then go southwest on Pipeline for 3.27 miles. Then go south on the proposed road to the proposed location.

- C) Existing Road Maintenance or Improvement Plan:

Existing roads will be maintained and kept in the same or better condition than before operations began. See the Well Pad Layout and Topo Map of the survey plat (Sheet 1 and 2 of plat package)

POINT 2: NEW PLANNED ACCESS ROUTE

- A) Route Location:

There will be 162.7' of new road built. (See the Well Pad Layout of the survey plat (Sheet 1 of plat package).

- B) Width

14' wide

- C) Maximum Grade

Grade to match existing topography or as per BLM requirements.

- D) Turnout Ditches

As required by BLM stipulations.

- E) Culverts, Cattle Guards, and Surfacing Equipment

If required, culverts and cattle guards will be set per BLM Specs.

POINT 3: LOCATION OF EXISTING WELLS

The following wells are located within a one-mile radius of the location site. See the One-Mile Radius Map (Sheet 5 of the plat package).

Existing wells..... 12 (Twelve)
Water wells..... 1 (One)

POINT 4: LOCATION OF EXISTING OR PROPOSED FACILITIES

- A) A BOPCO, L.P. operated production facility is not located within the ideal operating range of the Poke Lake Unit # 482H.

- B) In the Event of Production:

BOPCP, L.P. will construct a new production facility. Poker Lake Unit # 482H will pipe production to this battery (located in Sec.16, T25S, R30E). A new 3-1/2" in diameter steel flowline is to be laid approximately 750 feet. The flowline is expected to carry oil, water, and gas.

- C) Rehabilitation of Disturbed Areas Unnecessary for Production:

Following the construction, those access areas required for continued production will be graded to provide drainage and minimize erosion. The areas unnecessary for use will be graded to blend in with the surrounding topography (see Point 10).

POINT 5: LOCATION AND TYPE OF WATER SUPPLY

- A) Location and Type of Water Supply

Fresh water will be hauled from Johnson Station 50 miles east of Carlsbad, New Mexico or other commercial facilities. Brine water will be hauled from commercial facilities.

- B) Water Transportation System

Water hauling to the location will be over the existing and proposed roads.

POINT 6: SOURCE OF CONSTRUCTION MATERIALS

- A) Materials

On-site caliche will be used. If this is not sufficient, caliche will be hauled from a BLM approved pit.

- B) Land Ownership

Federally Owned

C) Materials Foreign to the Site

No construction materials foreign to this area are anticipated for this drill site.

D) Access Roads

See the Well Pad Layout and Aerial Map of the survey plat (Sheet 1 and 4 of plat package).

POINT 7: METHODS FOR HANDLING WASTE MATERIAL

A) Cuttings

Cuttings will be contained in the roll off bins and disposed at R360 Environmental located in Lea County, NM.

B) Drilling Fluids

Drilling fluids will be contained in the steel pits, frac tanks and disposed at licensed disposal sites.

C) Produced Fluids

Water production will be contained in the steel pits.

Hydrocarbon fluid or other fluids that may be produced during testing will be retained in test tanks. Prior to cleanup operations, any hydrocarbon material in the reserve pit will be removed by skimming or burning as the situation would dictate.

D) Sewage

Current laws and regulations pertaining to the disposal of human waste will be complied with.

E) Garbage

Portable containers will be utilized for garbage disposal during the drilling of this well.

F) Cleanup of Well Site

Upon release of the drilling rig, the surface of the drilling pad will be graded to accommodate a completion rig if electric log analysis indicate potential productive zones. Reasonable cleanup will be performed prior to the final restoration of the site.

POINT 8: ANCILLARY FACILITIES

None required.

POINT 9: WELL SITE LAYOUT

A) Rig Orientation and Layout

The "Rig Layout Schematic" (Sheet 6 of plat package) shows the dimensions of the well pad, closed loop system, and the location of major rig components. Only minor leveling of the well site will be required. No significant cuts or fills will be necessary. **The top soil will be stockpiled on the north side of the location.**

B) Locations of Access Road

See the Well Pad Layout, Topo Map, and Vicinity Map of the survey plat (Sheet 1, 2, and 3 of plat package).

C) Lining of the Pits

No reserve pits - closed loop system.

POINT 10: PLANS FOR RESTORATION OF THE SURFACE

A) Reserve Pit Cleanup - Not applicable. Closed loop drilling fluid system will be used

B) Restoration Plans - Production Developed

BOPCO, L.P. has no plans for interim reclamation to allow for additional wells to be drilled on this pad

C) Restoration Plans - No Production Developed

BOPCO, L.P. has no plans for interim reclamation to allow for additional wells to be drilled on this pad

POINT 11: OTHER INFORMATION

A) On-Site

Location on-site conducted by Todd Carpenter- BOPCO, L.P., Jarrel Brooks- BOPCO, L.P., Jesse Bassett-BLM, and a crew with Basin Surveys on 07/09/2015. The Poker Lake Unit 482H 500'x500' pad was moved from its original center hole location of 660' FNL & 1980' FWL, to 382' FNL & 2057' FWL, Sec 16-25-30 to avoid a hillside. Location layout is as follows: v-door will face the east, access road will enter location from the north/northwest and topsoil will be stockpiled to the north side of location.

B) Soil

Caliche and sand.

C) Vegetation

Sparse, primarily grasses and mesquite with very little grass.

D) Surface Use

Primarily grazing.

E) Surface Water

There are no ponds, lakes, streams or rivers within several miles of the wellsite.

F) Water Wells

There is one water wells located within a 1 mile radius of the proposed location.

G) Residences and Buildings

None in the immediate vicinity.

H) Historical Sites

None observed.

I) Archeological Resources

No independent archeological survey has been done. This well location is located in the area covered by Memorandum of Agreement – Permian Basin. A Payment of \$1,559.00 fee for this project is included in this application. Any location or construction conflicts will be resolved before construction begins. Please see diagram 4 for flowline route.

J) Surface Ownership

The well site is on federally owned land. There will be 162.7' of new road required for this location.

K) Well signs will be posted at the drilling site.

L) Open Pits

No open pits will be used for drilling or production. Any open top tanks will be netted.

M) Terrain

Slightly rolling hills.

POINT 12: OPERATOR'S FIELD REPRESENTATIVE

(Field personnel responsible for compliance with development plan for surface use).

DRILLING

Stephen Martinez
Box 2760
Midland, Texas 79702
(432) 683-2277

PRODUCTION

Gary Fletcher
3104 East Green Street
Carlsbad, New Mexico 88220
(575) 887-7329

Fritz Schoch
Box 2760
Midland, Texas 79702
(432) 683-2277


WBM

OPERATOR'S CERTIFICATION**APPLICATION FOR PERMIT TO DRILL****POKER LAKE UNIT #482H****382' FNL, 2057' FWL, Section 16, T25S, R30E, Eddy County, NM.**

In reference to the above captioned well, I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in the APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

Executed this 21st day of July, 2015.

If you have any questions regarding the accuracy of the plan provided herein, please do not hesitate to contact me at (432) 683-2277.



Whitney McKee
Engineering Assistant

PECOS DISTRICT CONDITIONS OF APPROVAL

OPERATOR'S NAME:	BOPCO, L.P.
LEASE NO.:	NMLC-065705B
WELL NAME & NO.:	Poker Lake Unit 482H
SURFACE HOLE FOOTAGE:	0382' FNL & 2057' FWL
BOTTOM HOLE FOOTAGE:	0660' FNL & 2590' FEL Sec. 18, T. 25 S., R 30 E.
LOCATION:	Section 16, T. 25 S., R 30 E., NMPM
COUNTY:	Eddy County, New Mexico

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- ☐ **General Provisions**
- ☐ **Permit Expiration**
- ☐ **Archaeology, Paleontology, and Historical Sites**
- ☐ **Noxious Weeds**
- ☒ **Special Requirements**
 - Commercial Well Determination
 - Unit Well Sign Specs
 - Lesser Prairie-Chicken Timing Stipulations
 - Ground-level Abandoned Well Marker
- ☐ **Construction**
 - Notification
 - Topsoil
 - Closed Loop System
 - Federal Mineral Material Pits
 - Well Pads
 - Roads
- ☐ **Road Section Diagram**
- ☒ **Drilling**
 - Cement Requirements
 - Logging Requirements
 - Waste Material and Fluids
- ☐ **Production (Post Drilling)**
 - Well Structures & Facilities
- ☒ **Interim Reclamation**
- ☐ **Final Abandonment & Reclamation**

I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

V. SPECIAL REQUIREMENT(S)

Commercial Well Determination

A commercial well determination shall be submitted after production has been established for at least six months:

Unit Wells

The well sign for a unit well shall include the unit number in addition to the surface and bottom hole lease numbers. This also applies to participating area numbers. If a participating area has not been established, the operator can use the general unit designation, but will replace the unit number with the participating area number when the sign is replaced.

Timing Limitation Stipulation / Condition of Approval for lesser prairie-chicken:

Oil and gas activities including 3-D geophysical exploration, and drilling will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Additionally, no new drilling will be allowed within up to 200 meters of leks known at the time of permitting. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 feet from the source of the noise.

Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well. For more installation details, contact the Carlsbad Field Office at 575-234-5972.

This authorization is subject to your Certificate of Participation and/or Certificate of Inclusion under the New Mexico Candidate Conservation Agreement. Because it involves surface disturbing activities covered under your Certificate, your Habitat Conservation Fund Account with the Center of Excellence for Hazardous Materials Management (CEHMM) will be debited according to Exhibit B Part 2 of the Certificate of Participation.

VI. CONSTRUCTION

A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. TOPSOIL

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

F. EXCLOSURE FENCING (CELLARS & PITS)

Exclosure Fencing

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

G. ON LEASE ACCESS ROADS**Road Width**

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

Ditching

Ditching shall be required on both sides of the road.

Turnouts


Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outslowing and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

Cattleguards

An appropriately sized cattleguard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattleguards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattleguards that are in place and are utilized during lease operations.

Fence Requirement

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Construction Steps

1. Salvage topsoil
2. Construct road

3. Redistribute topsoil
4. Revegetate slopes




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

VII. DRILLING

A. DRILLING OPERATIONS REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ **Eddy County**

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,
(575) 361-2822

1. **Hydrogen Sulfide (H₂S) monitors shall be installed prior to drilling out the surface shoe. If H₂S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.**
2. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval. **If the drilling rig is removed without approval – an Incident of Non-Compliance will be written and will be a “Major” violation.**
3. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works is located, this does not include the dog house or stairway area.
4. **The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.**

B. CASING

Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.

Centralizers required on surface casing per Onshore Order 2.III.B.1.f.

Wait on cement (WOC) for Water Basin:

After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements.

No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.

Possibility of water flows in the Salado and Delaware.

Possibility of lost circulation in the Red beds, Rustler, and Delaware.

1. The 13-3/8 inch surface casing shall be set at approximately 1050 feet (in a competent bed below the Magenta Dolomite, which is a Member of the Rustler, and if salt is encountered, set casing at least 25 feet above the salt) and cemented to the surface.
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry.
 - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.

- d. If cement falls back, remedial cementing will be done prior to drilling out that string.
2. The minimum required fill of cement behind the 9-5/8 inch intermediate casing is:
 - ☒ Cement to surface. If cement does not circulate see B.1.a, c-d above.

Centralizers required through the curve and a minimum of one every other joint.

3. The minimum required fill of cement behind the 7 inch production casing is:

Operator has proposed DV tool at depth of 5000', but will adjust cement proportionately if moved. DV tool shall be set a minimum of 50' below previous shoe and a minimum of 200' above current shoe. Operator shall submit sundry if DV tool depth cannot be set in this range.

- a. First stage to DV tool:

- ☒ Cement to circulate. If cement does not circulate, contact the appropriate BLM office before proceeding with second stage cement job. Operator should have plans as to how they will achieve approved top of cement on the next stage.

- b. Second stage above DV tool:

- ☒ Cement should tie-back at least 500 feet into previous casing string. Operator shall provide method of verification.

NOTE: Liner must tie back 100' minimum.

4. Cement not required on the 4-1/2" casing. **Packer system being used.**
5. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

C. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API 53.

2. Variance approved to use flex line from BOP to choke manifold. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. **Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.** If the BLM inspector questions the straightness of the hose, a BLM engineer will be contacted and will review in the field or via picture supplied by inspector to determine if changes are required (operator shall expect delays if this occurs).
3. **Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be 3000 (3M) psi.**
 - a. **Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.**
 - b. **If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.**
 - c. **Manufacturer representative shall install the test plug for the initial BOP test.**
 - d. **Operator shall perform the 9-5/8" and 7" casing integrity tests to 70% of the casing burst. This will test the multi-bowl seals.**
 - e. **If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.**
4. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).
 - b. The tests shall be done by an independent service company utilizing a test plug **not a cup or J-packer.**

- c. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- d. The results of the test shall be reported to the appropriate BLM office.
- e. All tests are required to be recorded on a calibrated test chart. **A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.**
- f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.

D. DRILL STEM TEST

If drill stem tests are performed, Onshore Order 2.III.D shall be followed.

E. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

JAM 082715

VIII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Exclosure Netting (Open-top Tanks)

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

Chemical and Fuel Secondary Containment and Exclosure Screening

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

Open-Vent Exhaust Stack Exclosures

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

Containment Structures

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the

largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

Painting Requirement

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

IX. INTERIM RECLAMATION

A. GENERAL CONDITIONS

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

B. DRILLING ADDITIONAL WELLS ON THIS PAD

The operator has indicated in the Surface Use Plan of Operations that there are currently no plans to conduct interim reclamation to allow for additional wells to be drilled on this pad. This deviation from standard practices has been approved by the BLM; thus, the requirement to conduct interim reclamation within 6 months of well completion date has been waived.

HOWEVER, if at any point the BLM determines that additional wells on this pad will not be applied for within two (2) years from the date of approval, **or** that interim reclamation is warranted for any reason, the BLM will issue an order to commence interim reclamation. At that point the operator will be required to submit an interim reclamation plan and to work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. These strategies will include reseeding the topsoil stockpile to enhance the probability of successful reclamation. Once these strategies are finalized the operator will be required to conduct interim reclamation.

X. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well.

Seed Mixture for LPC Sand/Shinnery Sites

Holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed shall be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed shall be either certified or registered seed. The seed container shall be tagged in accordance with State law(s) and available for inspection by the Authorized Officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). Holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. Seeding shall be repeated until a satisfactory stand is established as determined by the Authorized Officer. Evaluation of growth may not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed* per acre:

<u>Species</u>	<u>lb/acre</u>
Plains Bristlegrass	5lbs/A
Sand Bluestem	5lbs/A
Little Bluestem	3lbs/A
Big Bluestem	6lbs/A
Plains Coreopsis	2lbs/A
Sand Dropseed	1lbs/A

*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed