

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT
SUNDRY NOTICES AND REPORTS ON WELLS

OCD-ARTESIA

FORM APPROVED
OMB NO. 1004-0135
EXPIRES: NOVEMBER 30, 2000

Do not use this form for proposals to drill or to re-enter an abandoned well. Use Form 3160-3 (APD) for such proposals

SUBMIT IN TRIPLICATE

1a. Type of Well	<input type="checkbox"/> Oil Well	<input checked="" type="checkbox"/> Gas Well	<input type="checkbox"/> Other
2. Name of Operator Devon Energy Production Co., LP			
3. Address and Telephone No. 20 North Broadway, Ste 1500, Oklahoma City, OK 73102 405-552-7802			
4. Location of Well (Report location clearly and in accordance with Federal requirements)* Lot 32 Sec 4-T21S-R26E 1970' FSL & 660' FWL			

RECEIVED

MAR 29 2006

OCD-ARTESIA

5. Lease Serial No. NM-101094
6. If Indian, Allottee or Tribe Name
7. Unit or CA Agreement Name and No.
8. Well Name and No. Western Reserves Federal 3
9. API Well No. 30-015-30700
10. Field and Pool, or Exploratory Avalon (Upper Penn)
12. County or Parish 13. State Eddy NM

CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Fracture Treat	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other Drilling Operations
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input checked="" type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	


13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work and approximate duration thereof. If the proposal deepens directionally or recompletes horizontally, give subsurface location and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports shall be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompletion in a new interval, a Form 3160-4 shall be filed once testing has been completed. Final Abandonment Notices shall be filed only after all requirement, including reclamation, have been completed, and the operator has determined that the site is ready for final inspection)

Devon Energy Production Company, L.P. respectfully requests approval to run a MIT on the referenced well as follows: MURU pump track. Pressure up on casing to 500 psi for 30 minutes, using a chart type pressure recorder. RDMO pump truck.

CIBP will be set @ 9,398' with 35' cmt on top of CIBP.

Well can be evaluated as future producer when SWD capacity is added on. Evaluation to be done within the next year.

See attached wellbore schematic.



14. I hereby certify that the foregoing is true and correct

Signed		Name	Stephanie A. Ysasaga	Date	3/22/2006
		Title	Sr. Staff Engineering Technician		

(This space for Federal or State Office use)

Approved by _____ Title _____ Date _____
Conditions of approval, if any: _____

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make any department or agency of the United States any false, fictitious or fraudulent statements or representations to any matter within its jurisdiction.

*See Instruction on Reverse Side

DEVON ENERGY PRODUCTION COMPANY LP

Well Name: Western Reserves Federal #3

Field: Avalon (Morrow)

Location: Sec 4, T21S, R26E

County: Eddy

State: NM

Elevation: 3207' GL, 3223' KB

Spud Date: 7/3/01

Compl Date: 9/9/01

API#: 30-015-30700

Prepared by: Ronnie Slack

Date: 3/8/06

Rev:

PROPOSED TA

17-1/2" Hole

13-3/8", 48#, H40, ST&C, @ 605'

Cmt'd w/ 685 sxs. Cmt to surface.

12-1/2" Hole

8-5/8", 32#, J55, LT&C, @ 1976'

Cmt'd w/ 1080 sxs. Cmt to surface.

TOC @ 7742'

CISCO (11/13/04)

9448' - 9476' 11/13/04: 1.1 MMCFD

6 spf, 60° phase

MORROW

10,814' - 10,828'

7/13/04: acidized w/ 1750 gal 7.5% HCl

MORROW

10,874' - 10,891'

7-7/8" Hole

5-1/2", 17&15#, L80/J55, LT&C, @ 11,040'

Cmt'd w/ 1080 sxs. TOC @ 7742' (CBL)

PROPOSED:

CIBP @ 9398' + 35' cement on top

PBTD @ 10735'

Set CIBP @ 10770' + 35' cement (11/12/04)

CIBP @ 10,855' (no cement on top)

TD @ 11,040'