

RW4.9-18



U.S. Department of the Interior BUREAU OF LAND MANAGEMENT



APD ID: 10400024190

Operator Name: XTO ENERGY INCORPORATED

Well Name: CATTLE BARON FEDERAL

Well Number: 2H

Well Work Type: Drill

Submission Date: 11/01/2017

Highlighted data reflects the most recent changes

Show Final Text

Well Type: OIL WELL

Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical Depth	Measured Depth	Lithologies	Mineral Resources	Producing Formation
1		2905	0	0	ALLUVIUM,OTHER : Quaternary	NONE	No
2	RUSTLER	2630	275	275	SANDSTONE	USEABLE WATER	No
3	TOP SALT	2281	624	624	SALT	NONE	No
4	BASE OF SALT	374	2531	2531	SALT	NONE	No
5	DELAWARE	175	2730	2730	SANDSTONE	NATURAL GAS,OIL,OTHER : Produced Water	No
6	CHERRY CANYON	-732	3637	3637	SANDSTONE	NATURAL GAS,OIL,OTHER : Produced Water	No
7	BRUSHY CANYON	-2301	5206	5206	SANDSTONE	NATURAL GAS,OIL,OTHER : Produced Water	No
8	BONE SPRING 1ST	-3278	6183	6183	SANDSTONE	NATURAL GAS,POTASH,OTHER : Produced Water	No
9	BONE SPRING 2ND	-5314	8219	8219	SANDSTONE	NATURAL GAS,OIL,OTHER : Produced Water	No
10	BONE SPRING 3RD	-5568	8473	8473	SANDSTONE	NATURAL GAS,OIL,OTHER : Produced Water	Yes

Section 2 - Blowout Prevention

Pressure Rating (PSI): 3M

Rating Depth: 8473

Equipment: The blow out preventer equipment (BOP) for this well consists of a 13-5/8" minimum 3M Hydril and a 13-5/8" minimum 3M Double Ram BOP.

Requesting Variance? YES

Variance request: A variance is requested to allow use of a flex hose as the choke line from the BOP to the Choke Manifold. If this hose is used, a copy of the manufacturer's certification and pressure test chart will be kept on the rig. Attached is an example of a certification and pressure test chart. The manufacturer does not require anchors.

Testing Procedure: All BOP testing will be done by an independent service company. Annular pressure tests will be limited to 50% of the working pressure. When nippling up on the 13-5/8" 3M bradenhead and flange, the BOP test will be limited to 3000psi. When nippling up on the 9-5/8", the BOP will be tested to a minimum of 3000 psi. All BOP tests will include a low pressure test as per BLM regulations. The 3M BOP diagram is attached. Blind rams will be function tested each trip, pipe rams will be function tested each day.