

Carlsbad Field Office OCD Artesia

Form 3160-3
(March 2012)

FORM APPROVED
OMB No. 1004-0137
Expires October 31, 2014

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. NMLC0062300
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		6. If Indian, Allottee or Tribe Name
2. Name of Operator DEVON ENERGY PRODUCTION COMPANY LP		7. If Unit or CA Agreement, Name and No.
3a. Address 333 West Sheridan Avenue Oklahoma City OK	3b. Phone No. (include area code) (405)552-6571	8. Lease Name and Well No. <i>Com</i> BIG SINKS DRAW 25-24 FED 711H <i>317584</i>
4. Location of Well (Report location clearly and in accordance with any State requirements.) At surface SWNW / 2484 FNL / 985 FWL / LAT 32.1017025 / LONG -103.7370139 At proposed prod. zone SWNW / 330 FNL / 330 FWL / LAT 32.1221365 / LONG -103.7390657		9. API Well No. <i>30-015-45065</i>
10. Field and Pool, or Exploratory PURPLE SAGE / WOLFCAMP		11. Sec., T. R. M. or Blk. and Survey or Area SEC 25 / T25S / R31E / NMP
12. Distance in miles and direction from nearest town or post office*		12. County or Parish EDDY
13. State NM		
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 330 feet	16. No. of acres in lease 2479.82	17. Spacing Unit dedicated to this well 240
18. Distance from proposed location* to nearest well, drilling, completed, 425 feet applied for, on this lease, ft.	19. Proposed Depth 11838 feet / 19239 feet	20. BLM/BIA Bond No. on file FED: CO1104
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3338 feet	22. Approximate date work will start* 09/01/2018	23. Estimated duration 30 days
24. Attachments		

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No.1, must be attached to this form:

- | | |
|---|---|
| <ol style="list-style-type: none"> 1. Well plat certified by a registered surveyor. 2. A Drilling Plan. 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | <ol style="list-style-type: none"> 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). 5. Operator certification 6. Such other site specific information and/or plans as may be required by the BLM. |
|---|---|

25. Signature (Electronic Submission)	Name (Printed/Typed) Erin Workman / Ph: (405)552-7970	Date 12/01/2017
Title Regulatory Compliance Professional		
Approved by (Signature) (Electronic Submission)	Name (Printed/Typed) Cody Layton / Ph: (575)234-5959	Date 06/18/2018
Title Supervisor Multiple Resources Office CARLSBAD		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon. Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Continued on page 2)

*(Instructions on page 2)

APPROVED WITH CONDITIONS

Approval Date: 05/14/2018

NSP

NM OIL CONSERVATION
ARTESIA DISTRICT
JUN 27 2018

RECEIVED

RUP 6-29-18.

INSTRUCTIONS

GENERAL: This form is designed for submitting proposals to perform certain well operations, as indicated on Federal and Indian lands and leases for action by appropriate Federal agencies, pursuant to applicable Federal laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from local Federal offices.

ITEM 1: If the proposal is to redrill to the same reservoir at a different subsurface location or to a new reservoir, use this form with appropriate notations. Consult applicable Federal regulations concerning subsequent work proposals or reports on the well.

ITEM 4: Locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local Federal offices for specific instructions.

ITEM 14: Needed only when location of well cannot readily be found by road from the land or lease description. A plat, or plats, separate or on the reverse side, showing the roads to, and the surveyed location of, the well, and any other required information, should be furnished when required by Federal agency offices.

ITEMS 15 AND 18: If well is to be, or has been directionally drilled, give distances for subsurface location of hole in any present or objective productive zone.

ITEM 22: Consult applicable Federal regulations, or appropriate officials, concerning approval of the proposal before operations are started.

NOTICES

The Privacy Act of 1974 and regulation in 43 CFR 2.48(d) provide that you be furnished the following information in connection with information required by this application.

AUTHORITY: 30 U.S.C. 181 et seq., 25 U.S.C. 396; 43 CFR 3160

PRINCIPAL PURPOSES: The information will be used to: (1) process and evaluate your application for a permit to drill a new oil, gas, or service well or to reenter a plugged and abandoned well; and (2) document, for administrative use, information for the management, disposal and use of National Resource Lands and resources including (a) analyzing your proposal to discover and extract the Federal or Indian resources encountered; (b) reviewing procedures and equipment and the projected impact on the land involved; and (c) evaluating the effects of the proposed operation on the surface and subsurface water and other environmental impacts.

ROUTINE USE: Information from the record and/or the record will be transferred to appropriate Federal, State, and local or foreign agencies, when relevant to civil, criminal or regulatory investigations or prosecution, in connection with congressional inquiries and for regulatory responsibilities.

EFFECT OF NOT PROVIDING INFORMATION: Filing of this application and disclosure of the information is mandatory only if you elect to initiate a drilling or reentry operation on an oil and gas lease.

The Paperwork Reduction Act of 1995 requires us to inform you that:

The BLM collects this information to allow evaluation of the technical, safety, and environmental factors involved with drilling for oil and/or gas on Federal and Indian oil and gas leases. This information will be used to analyze and approve applications. Response to this request is mandatory only if the operator elects to initiate drilling or reentry operations on an oil and gas lease. The BLM would like you to know that you do not have to respond to this or any other Federal agency-sponsored information collection unless it displays a currently valid OMB control number.

BURDEN HOURS STATEMENT: Public reporting burden for this form is estimated to average 8 hours per response, including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding the burden estimate or any other aspect of this form to U.S. Department of the Interior, Bureau of Land Management (1004-0137), Bureau Information Collection Clearance Officer (WO-630), 1849 C Street, N.W., Mail Stop 401 LS, Washington, D.C. 20240.

Additional Operator Remarks

Location of Well

1. SHL: SWNW / 2484 FNL / 985 FWL / TWSP: 25S / RANGE: 31E / SECTION: 25 / LAT: 32.1017025 / LONG: -103.7370139 (TVD: 0 feet, MD: 0 feet)
PPP: SWNW / 0 FSL / 330 FWL / TWSP: 25S / RANGE: 31E / SECTION: 24 / LAT: 32.1157845 / LONG: -103.7390851 (TVD: 11838 feet, MD: 16928 feet)
PPP: SWNW / 2087 FNL / 330 FWL / TWSP: 25S / RANGE: 31E / SECTION: 25 / LAT: 32.1017025 / LONG: -103.7370139 (TVD: 11838 feet, MD: 12206 feet)
BHL: SWNW / 330 FNL / 330 FWL / TWSP: 25S / RANGE: 31E / SECTION: 24 / LAT: 32.1221365 / LONG: -103.7390857 (TVD: 11838 feet, MD: 19239 feet)

BLM Point of Contact

Name: Sipra Dahal

Title: Legal Instruments Examiner

Phone: 5752345983

Email: sdahal@blm.gov

CONFIDENTIAL

Review and Appeal Rights

A person contesting a decision shall request a State Director review. This request must be filed within 20 working days of receipt of the Notice with the appropriate State Director (see 43 CFR 3165.3). The State Director review decision may be appealed to the Interior Board of Land Appeals, 801 North Quincy Street, Suite 300, Arlington, VA 22203 (see 43 CFR 3165.4). Contact the above listed Bureau of Land Management office for further information.

CONFIDENTIAL

JUN 27 2018

**PECOS DISTRICT
DRILLING CONDITIONS OF APPROVAL**

RECEIVED

OPERATOR'S NAME:	Devon Energy Prod Co
LEASE NO.:	LC062300
WELL NAME & NO.:	711H – Big Sinks Draw 25-24 Fed
SURFACE HOLE FOOTAGE:	2484'/N & 985'/W
BOTTOM HOLE FOOTAGE:	330'/N & 330'/W, sec. 24
LOCATION:	Sec. 25, T. 25 S, R. 31 E
COUNTY:	Eddy County, New Mexico

COA

H2S	<input type="radio"/> Yes	<input checked="" type="radio"/> No	
Potash	<input checked="" type="radio"/> None	<input type="radio"/> Secretary	<input type="radio"/> R-111-P
Cave/Karst Potential	<input checked="" type="radio"/> Low	<input type="radio"/> Medium	<input type="radio"/> High
Variance	<input type="radio"/> None	<input checked="" type="radio"/> Flex Hose	<input type="radio"/> Other
Wellhead	<input type="radio"/> Conventional	<input checked="" type="radio"/> Multibowl	<input type="radio"/> Both
Other	<input type="checkbox"/> 4 String Area	<input type="checkbox"/> Capitan Reef	<input type="checkbox"/> WIPP

A. Hydrogen Sulfide

Hydrogen Sulfide (H2S) monitors shall be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.

B. CASING

1. The 13-3/8 inch surface casing shall be set at approximately 958 feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface.
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. Wait on cement (WOC) time for a primary cement job will be a minimum of 8 hours or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)

- c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
- d. If cement falls back, remedial cementing will be done prior to drilling out that string.

Operator shall fill 1/3rd casing with fluid while running intermediate casing to maintain collapse safety factor.

2. The minimum required fill of cement behind the 7-5/8 inch intermediate casing is:

OPTION 1

- Cement to surface. If cement does not circulate see B.1.a, c-d above. **Additional cement maybe required. Excess calculates to -40%.**

OPTION 2

Operator has proposed a DV tool, the depth may be adjusted as long as the cement is changed proportionally. The DV tool may be cancelled if cement circulates to surface on the first stage.

- a. First stage to DV tool: Cement to circulate. If cement does not circulate off the DV tool, contact the appropriate BLM office before proceeding with second stage cement job. **Additional cement maybe required. Excess calculates to 13%.**
- b. Cement to surface. If cement does not circulate, contact the appropriate BLM office. **Additional cement maybe required. Excess calculates to -71%.**

Variance is approved for the annular spacing between the 7 5/8 x 5 1/2 casing.

3. The minimum required fill of cement behind the 5-1/2 inch production casing is:
 - Cement should tie-back at least 200 feet into previous casing string. Operator shall provide method of verification.

PRESSURE CONTROL

1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).
2. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **3000 (3M) psi.**

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

Chaves and Roosevelt Counties
Call the Roswell Field Office, 2909 West Second St., Roswell NM 88201.
During office hours call (575) 627-0272.
After office hours call (575)

Eddy County
Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,
(575) 361-2822

Lea County
Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575)
393-3612

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
 - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
 - b. When the operator proposes to set surface casing with Spudder Rig
 - Notify the BLM when moving in and removing the Spudder Rig.
 - Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
 - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a

digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
 - e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after

installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).

- b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time, except the casing pressure test can be initiated immediately after bumping the plug (only applies to single stage cement jobs).
- c. The tests shall be done by an independent service company utilizing a test plug. The results of the test shall be reported to the appropriate BLM office.
- d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- e. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- f. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes. This test shall be performed prior to the test at full stack pressure.
- g. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

Waste Minimization Plan (WMP)

In the interest of resource development, submission of additional well gas capture development plan information is deferred but may be required by the BLM Authorized Officer at a later date.

ZS 051618



Stevens, Zota <zstevens@blm.gov>

[EXTERNAL] Big Sinks Well

Hart, Jamison <Jamison.Hart@dvn.com>

Wed, Jun 6, 2018 at 7:17 AM

To: "Workman, Erin" <Erin.Workman@dvn.com>, "zstevens@blm.gov" <zstevens@blm.gov>

Zota,

An annular clearance variance is requested to run 7-5/8" csg in 8-3/4" hole as well as to run 5.5" csg in 6-3/4" lateral.

Best Regards,

Jamie HartDrilling Engineer
Delaware Basin

Mobile: 405-230-0992

Office: 405-228-8370

**GEAUX TIGERS!****From:** Workman, Erin
Sent: Wednesday, June 06, 2018 8:01 AM
To: zstevens@blm.gov
Cc: Hart, Jamison <Jamison.Hart@dvn.com>
Subject: FW: Big Sinks Well

Good morning,

I just realized that I sent you the Big Sinks 25-24 Fed Com 611H. Attached is the information for the 711H, variance is requested on page 2. Should you need further assistance, please contact Jamison Hart @ (405)228-8370.

**PECOS DISTRICT
SURFACE USE
CONDITIONS OF APPROVAL**

**NM OIL CONSERVATION
ARTESIA DISTRICT
JUN 27 2018**

RECEIVED

OPERATOR'S NAME:	Devon Energy Prod Co
LEASE NO.:	LC062300
WELL NAME & NO.:	711H – Big Sinks Draw 25-24 Fed
SURFACE HOLE FOOTAGE:	2484'/N & 985'/W
BOTTOM HOLE FOOTAGE:	330'/N & 330'/W, sec.24
LOCATION:	Section 25, T. 25 S., R.319 E.
COUNTY:	Eddy County, New Mexico

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- General Provisions**
- Permit Expiration**
- Archaeology, Paleontology, and Historical Sites**
- Noxious Weeds**
- Special Requirements**
 - Lesser Prairie-Chicken Timing Stipulations
 - Ground-level Abandoned Well Marker
 - Range
 - Watershed
- Construction**
 - Notification
 - Topsoil
 - Closed Loop System
 - Federal Mineral Material Pits
 - Well Pads
 - Roads
- Road Section Diagram**
- Production (Post Drilling)**
 - Well Structures & Facilities
 - Pipelines
 - Electric Lines
- Interim Reclamation**
- Final Abandonment & Reclamation**

I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

V. SPECIAL REQUIREMENT(S)

In May 2008, the Pecos District Special Status Species Resource Management Plan Amendment (RMPA) was approved and is being implemented. In addition to the standard practices that minimize impacts, as listed above, the following COA will apply:

- Timing Limitation Stipulation / Condition of Approval for lesser prairie-chicken, to minimize noise associated impacts which could disrupt breeding and nesting activities.
- Upon abandonment, a low profile abandoned well marker will be installed to prevent raptor perching.

Wildlife Escape Ramps

Devon would need to construct and maintain escape ramps according to the following criteria:

- Earthen escape ramps would be required to be constructed to sufficiently support livestock at no more than a 30-degree slope and spaced no more than 500 feet apart.
- If trench is left open under an 8-hour time period, it would not be required to have an escape ramp; however, before the trench is backfilled, Devon would inspect the trench for wildlife and remove any species that are trapped at a distance of at least 100 yards away from the trench.

Raptor Nest Mitigation

- A BLM Wildlife Biologist must be contacted by the operator prior to construction activities to determine if the raptor nest is active.
- Determination to deconstruct inactive nest prior to pad construction will be made by BLM Wildlife Biologist.
- Raptor nests on special, natural habitat features, such as trees, large brush, cliff faces and escarpments, will be protected by not allowing surface disturbance within up to 200 meters of nests or by delaying activity for up to 90 days, or a combination of both. Exceptions to this requirement for raptor nests will be considered if the nests expected to be disturbed are inactive, the proposed activity is of short duration (e.g. habitat enhancement projects, fences, pipelines), and will not result in continuing activity in proximity to the nest.
- Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 ft. from the source of the noise.

Temporary Fencing Requirement

For the proposed Big Sinks 25 CTB 3 location, the BLM would require temporary fencing be installed before construction begins. This fencing would stay in place and be maintained throughout construction activities to protect nearby dune land habitat from harm.

Power Lines

Power lines shall be constructed and designed in accordance to standards outlined in "Suggested Practices for Avian Protection on Power lines: The State of the Art in 2006" Edison Electric Institute, APLIC, and the California Energy Commission 2006. The holder shall assume the burden and expense of proving that pole designs not shown in the above publication deter raptor perching, roosting, and nesting. Such proof shall be provided by a raptor expert approved by the Authorized Officer. The BLM reserves the right to require modification or additions to all power line structures placed on this right-of-way, should they be necessary to ensure the safety of large perching birds. The holder without liability or expense shall make such modifications and/or additions to the United States.

Watershed/Water Quality:

For all the proposed actions; the entire perimeter of the well pad and CTB sites will be bermed to prevent oil, salt, and other chemical contaminants from leaving the well pad.

- The compacted berm shall be constructed at a minimum of 12 inches high with impermeable mineral material (e.g. caliche).
- No water flow from the uphill side(s) of the pad shall be allowed to enter the well pad.
- The topsoil stockpile shall be located outside the bermed well pad.
- Topsoil, either from the well pad or surrounding area, shall not be used to construct the berm.
- No storm drains, tubing or openings shall be placed in the berm.
- If fluid collects within the bermed area, the fluid must be vacuumed into a safe container and disposed of properly at a state approved facility.
- The integrity of the berm shall be maintained around the surfaced pad throughout the life of the well and around the downsized pad after interim reclamation has been completed.
- Any access road entering the well pad shall be constructed so that the integrity of the berm height surrounding the well pad is not compromised. (Any access road crossing the berm cannot be lower than the berm height.)

Tank Battery:

- Tank battery locations will be lined and bermed. A 20 mil permanent liner will be installed with a 4 oz. felt backing to prevent tears or punctures. Tank battery berms must be large enough to contain 1 ½ times the content of the largest tank.
- Automatic shut off, check valves, or similar systems will be installed for tanks to minimize the effects of catastrophic line failures used in production or drilling.

Temporary Fence Crossing Requirement

Where entry is granted across a fence line, the fence must be braced and tied off on both sides of the passageway with H-braces prior to cutting. Once the work is completed, the fence will be restored to its prior condition, or better. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

Cattle Guard Requirement

Where entry is granted across a fence line for an access road, the fence must be braced and tied off on both sides of the passageway with H-braces prior to cutting. Once the work is completed, the fence will be restored to its prior condition with an appropriately sized cattle guard sufficient to carry out the project. Any new or existing cattle guards on the access route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattle guards that are in place and are utilized during lease operations. Once the road is abandoned, the fence would be restored to its prior condition, or better. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

Livestock Watering Requirement

Devon, in an agreement with the grazing allotment holder, would relocate a water pipeline affected by several proposed actions. Devon would also encase the water pipeline along its length where it would travel under access roads. See **Error! Reference source not found.** above.

Devon must contact the allotment holder prior to construction to identify the location of the pipelines. Devon must take measures to protect the pipelines from compression or other damages. If the pipelines are damaged or compromised in any way near the proposed project as a result of oil and gas activity, Devon is responsible for repairing the pipelines immediately. Devon must notify the BLM office (575-234-5972) and the private surface landowner or the grazing allotment holder if any damage occurs to structures that provide water to livestock.

During construction, Devon shall minimize disturbance to existing fences, water lines, troughs, windmills, and other improvements on public lands. Devon is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the grazing permittee/allottee prior to disturbing any range improvement projects. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

Temporary Fencing Requirement

For the proposed Big Sinks 25 CTB 3 location, the BLM would require temporary fencing be installed before construction begins. This fencing would stay in place and be maintained throughout construction activities to protect nearby dune land habitat from harm.

VI. CONSTRUCTION

A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. TOPSOIL

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

F. EXCLOSURE FENCING (CELLARS & PITS)

Exclosure Fencing

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

G. ON LEASE ACCESS ROADS**Road Width**

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

Ditching

Ditching shall be required on both sides of the road.

Turnouts


Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outslping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

Cattle guards

An appropriately sized cattle guard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattle guards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattle guards that are in place and are utilized during lease operations.

Fence Requirement

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Construction Steps

1. Salvage topsoil
2. Construct road

3. Redistribute topsoil
4. Revegetate slopes




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

VII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Exclosure Netting (Open-top Tanks)

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

Chemical and Fuel Secondary Containment and Exclosure Screening

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

Open-Vent Exhaust Stack Exclosures

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

Containment Structures

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

Painting Requirement

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

B. PIPELINES

BURIED PIPELINE STIPULATIONS

A copy of the application (Grant, APD, or Sundry Notice) and attachments, including conditions of approval, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The Holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. The Holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.
3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

4. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil or other pollutant, wherever found, shall be the responsibility of holder, regardless of fault. Upon failure of holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he deems necessary to control and clean up the discharge and restore the area, including where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve holder of any responsibility as provided herein.

5. All construction and maintenance activity will be confined to the authorized right-of-way.
6. The pipeline will be buried with a minimum cover of 36 inches between the top of the pipe and ground level.
7. The maximum allowable disturbance for construction in this right-of-way will be 30 feet:
 - Blading of vegetation within the right-of-way will be allowed: maximum width of blading operations will not exceed 20 feet. The trench is included in this area. (*Blading is defined as the complete removal of brush and ground vegetation.*)
 - Clearing of brush species within the right-of-way will be allowed: maximum width of clearing operations will not exceed 30 feet. The trench and bladed area are included in this area. (*Clearing is defined as the removal of brush while leaving ground vegetation (grasses, weeds, etc.) intact. Clearing is best accomplished by holding the blade 4 to 6 inches above the ground surface.*)
 - The remaining area of the right-of-way (if any) shall only be disturbed by compressing the vegetation. (*Compressing can be caused by vehicle tires, placement of equipment, etc.*)
8. The holder shall stockpile an adequate amount of topsoil where blading is allowed. The topsoil to be stripped is approximately 6 inches in depth. The topsoil will be segregated from other spoil piles from trench construction. The topsoil will be evenly distributed over the bladed area for the preparation of seeding.
9. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.
10. Vegetation, soil, and rocks left as a result of construction or maintenance activity will be randomly scattered on this right-of-way and will not be left in rows, piles, or berms, unless otherwise approved by the Authorized Officer. The entire right-of-way shall be recontoured to match the surrounding landscape. The backfilled soil shall be compacted and a 6 inch berm will be left over the ditch line to allow for settling back to grade.
11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.

12. The holder will reseed all disturbed areas. Seeding will be done according to the attached seeding requirements, using the following seed mix.

- | | |
|--|--|
| <input type="checkbox"/> seed mixture 1 | <input type="checkbox"/> seed mixture 3 |
| <input type="checkbox"/> seed mixture 2 | <input type="checkbox"/> seed mixture 4 |
| <input checked="" type="checkbox"/> seed mixture 2/LPC | <input type="checkbox"/> Aplomado Falcon Mixture |

13. All above-ground structures not subject to safety requirements shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be color which simulates "Standard Environmental Colors" – **Shale Green**, Munsell Soil Color No. 5Y 4/2.

14. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. All signs and information thereon will be posted in a permanent, conspicuous manner, and will be maintained in a legible condition for the life of the pipeline.

15. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder before maintenance begins. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway. As determined necessary during the life of the pipeline, the Authorized Officer may ask the holder to construct temporary deterrence structures.

16. Any cultural and/or paleontological resources (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

17. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes associated roads, pipeline corridor and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

18. Escape Ramps - The operator will construct and maintain pipeline/utility trenches that are not otherwise fenced, screened, or netted to prevent livestock, wildlife, and humans from becoming entrapped. At a minimum, the operator will construct and maintain escape ramps, ladders, or

other methods of avian and terrestrial wildlife escape in the trenches according to the following criteria:

- a. Any trench left open for eight (8) hours or less is not required to have escape ramps; however, before the trench is backfilled, the contractor/operator shall inspect the trench for wildlife, remove all trapped wildlife, and release them at least 100 yards from the trench.
- b. For trenches left open for eight (8) hours or more, earthen escape ramps (built at no more than a 30 degree slope and spaced no more than 500 feet apart) shall be placed in the trench.

19. Special Stipulations:

Lesser Prairie-Chicken

Oil and gas activities will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, geophysical exploration other than 3-D operations, and pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 ft. from the source of the noise.

This authorization is subject to your Certificate of Participation and/or Certificate of Inclusion under the New Mexico Candidate Conservation Agreement. Because it involves surface disturbing activities covered under your Certificate, your Habitat Conservation Fund Account with the Center of Excellence for Hazardous Materials Management (CEHMM) will be debited according to Exhibit B Part 2 of the Certificate of Participation.

STANDARD STIPULATIONS FOR SURFACE INSTALLED PIPELINES

A copy of the application (Grant, Sundry Notice, APD) and attachments, including stipulations, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. The holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 *et seq.* (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR, Part 702-799 and

especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.

3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to activity of the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

4. The holder shall be liable for damage or injury to the United States to the extent provided by 43 CFR Sec. 2883.1-4. The holder shall be held to a standard of strict liability for damage or injury to the United States resulting from pipe rupture, fire, or spills caused or substantially aggravated by any of the following within the right-of-way or permit area:

- a. Activities of the holder including, but not limited to construction, operation, maintenance, and termination of the facility.
- b. Activities of other parties including, but not limited to:
 - (1) Land clearing.
 - (2) Earth-disturbing and earth-moving work.
 - (3) Blasting.
 - (4) Vandalism and sabotage.
- c. Acts of God.

The maximum limitation for such strict liability damages shall not exceed one million dollars (\$1,000,000) for any one event, and any liability in excess of such amount shall be determined by the ordinary rules of negligence of the jurisdiction in which the damage or injury occurred.

This section shall not impose strict liability for damage or injury resulting primarily from an act of war or from the negligent acts or omissions of the United States.

5. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil, salt water, or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil, salt water, or other pollutant, wherever found, shall be the responsibility of

the holder, regardless of fault. Upon failure of the holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he deems necessary to control and clean up the discharge and restore the area, including, where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve the holder of any responsibility as provided herein.

6. All construction and maintenance activity will be confined to the authorized right-of-way width of 20 feet. If the pipeline route follows an existing road or buried pipeline right-of-way, the surface pipeline must be installed no farther than 10 feet from the edge of the road or buried pipeline right-of-way. If existing surface pipelines prevent this distance, the proposed surface pipeline must be installed immediately adjacent to the outer surface pipeline. All construction and maintenance activity will be confined to existing roads or right-of-ways.

7. No blading or clearing of any vegetation will be allowed unless approved in writing by the Authorized Officer.

8. The holder shall install the pipeline on the surface in such a manner that will minimize suspension of the pipeline across low areas in the terrain. In hummocky or dune areas, the pipeline will be "snaked" around hummocks and dunes rather than suspended across these features.

9. The pipeline shall be buried with a minimum of 24 inches under all roads, "two-tracks," and trails. Burial of the pipe will continue for 20 feet on each side of each crossing. The condition of the road, upon completion of construction, shall be returned to at least its former state with no bumps or dips remaining in the road surface.

10. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.

12. Excluding the pipe, all above-ground structures not subject to safety requirement shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be a color which simulates "Standard Environmental Colors" – **Shale Green**, Munsell Soil Color No. 5Y 4/2; designated by the Rocky Mountain Five State

Interagency Committee.

13. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. Signs will be maintained in a legible condition for the life of the pipeline.

14. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway.

15. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the authorized officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the authorized officer. An evaluation of the discovery will be made by the authorized officer to determine appropriate cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the authorized officer after consulting with the holder.

16. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, powerline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

17. Surface pipelines must be less than or equal to 4 inches and a working pressure below 125 psi.

18. Special Stipulations:

- a. **Lesser Prairie-Chicken:** Oil and gas activities will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities and pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Normal vehicle use on existing roads will not be restricted.
- b. This authorization is subject to your Certificate of Participation and/or Certificate of Inclusion under the New Mexico Candidate Conservation Agreement. Because it involves surface disturbing activities covered under your Certificate, your Habitat Conservation Fund Account with the Center of Excellence for Hazardous

Materials Management (CEHMM) will be debited according to Exhibit B Part 2 of the Certificate of Participation.

C. ELECTRIC LINES

STANDARD STIPULATIONS FOR OVERHEAD ELECTRIC DISTRIBUTION LINES

A copy of the grant and attachments, including stipulations, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. The holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR, Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.
3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.
4. There will be no clearing or blading of the right-of-way unless otherwise agreed to in writing by the Authorized Officer.
5. Power lines shall be constructed and designed in accordance to standards outlined in "Suggested Practices for Avian Protection on Power lines: The State of the Art in 2006" Edison Electric Institute, APLIC, and the California Energy Commission 2006 . The

holder shall assume the burden and expense of proving that pole designs not shown in the above publication deter raptor perching, roosting, and nesting. Such proof shall be provided by a raptor expert approved by the Authorized Officer. The BLM reserves the right to require modification or additions to all powerline structures placed on this right-of-way, should they be necessary to ensure the safety of large perching birds. Such modifications and/or additions shall be made by the holder without liability or expense to the United States.

Raptor deterrence will consist of but not limited to the following: triangle perch discouragers shall be placed on each side of the cross arms and a nonconductive perching deterrence shall be placed on all vertical poles that extend past the cross arms.

6. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

7. The BLM serial number assigned to this authorization shall be posted in a permanent, conspicuous manner where the power line crosses roads and at all serviced facilities. Numbers will be at least two inches high and will be affixed to the pole nearest the road crossing and at the facilities served.

8. Upon cancellation, relinquishment, or expiration of this grant, the holder shall comply with those abandonment procedures as prescribed by the Authorized Officer.

9. All surface structures (poles, lines, transformers, etc.) shall be removed within 180 days of abandonment, relinquishment, or termination of use of the serviced facility or facilities or within 180 days of abandonment, relinquishment, cancellation, or expiration of this grant, whichever comes first. This will not apply where the power line extends service to an active, adjoining facility or facilities.

10. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

11. Special Stipulations:

- For reclamation remove poles, lines, transformer, etc. and dispose of properly.

- Fill in any holes from the poles removed.

Timing Limitation Stipulation/Condition of Approval for Lesser Prairie-Chicken:

Oil and gas activities including 3-D geophysical exploration, and drilling will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, geophysical exploration other than 3-D operations, and pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Additionally, no new drilling will be allowed within up to 200 meters of leks known at the time of permitting. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 ft. from the source of the noise.

This authorization is subject to your Certificate of Participation and/or Certificate of Inclusion under the New Mexico Candidate Conservation Agreement. Because it involves surface disturbing activities covered under your Certificate, your Habitat Conservation Fund Account with the Center of Excellence for Hazardous Materials Management (CEHMM) will be debited according to Exhibit B Part 2 of the Certificate of Participation.

VIII. INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

IX. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well.

Seed Mixture for LPC Sand/Shinnery Sites

Holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed shall be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed shall be either certified or registered seed. The seed container shall be tagged in accordance with State law(s) and available for inspection by the Authorized Officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). Holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. Seeding shall be repeated until a satisfactory stand is established as determined by the Authorized Officer. Evaluation of growth may not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed* per acre:

<u>Species</u>	<u>lb/acre</u>
Plains Bristlegrass	5lbs/A
Sand Bluestem	5lbs/A
Little Bluestem	3lbs/A
Big Bluestem	6lbs/A
Plains Coreopsis	2lbs/A
Sand Dropseed	11lbs/A

*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed

**PECOS DISTRICT
SURFACE USE
CONDITIONS OF APPROVAL**

OPERATOR'S NAME:	Devon Energy Prod Co
LEASE NO.:	LC062300
WELL NAME & NO.:	711H – Big Sinks Draw 25-24 Fed
SURFACE HOLE FOOTAGE:	2484'/N & 985/W
BOTTOM HOLE FOOTAGE:	330'/N & 330'/W, sec.24
LOCATION:	Section 25, T. 25 S., R.319 E.
COUNTY:	Eddy County, New Mexico

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- General Provisions**
- Permit Expiration**
- Archaeology, Paleontology, and Historical Sites**
- Noxious Weeds**
- Special Requirements**
 - Lesser Prairie-Chicken Timing Stipulations
 - Ground-level Abandoned Well Marker
 - Range
 - Watershed
- Construction**
 - Notification
 - Topsoil
 - Closed Loop System
 - Federal Mineral Material Pits
 - Well Pads
 - Roads
- Road Section Diagram**
- Production (Post Drilling)**
 - Well Structures & Facilities
 - Pipelines
 - Electric Lines
- Interim Reclamation**
- Final Abandonment & Reclamation**

I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

V. SPECIAL REQUIREMENT(S)

In May 2008, the Pecos District Special Status Species Resource Management Plan Amendment (RMFA) was approved and is being implemented. In addition to the standard practices that minimize impacts, as listed above, the following COA will apply:

- Timing Limitation Stipulation / Condition of Approval for lesser prairie-chicken, to minimize noise associated impacts which could disrupt breeding and nesting activities.
- Upon abandonment, a low profile abandoned well marker will be installed to prevent raptor perching.

Wildlife Escape Ramps

Devon would need to construct and maintain escape ramps according to the following criteria:

- Earthen escape ramps would be required to be constructed to sufficiently support livestock at no more than a 30-degree slope and spaced no more than 500 feet apart.
- If trench is left open under an 8-hour time period, it would not be required to have an escape ramp; however, before the trench is backfilled, Devon would inspect the trench for wildlife and remove any species that are trapped at a distance of at least 100 yards away from the trench.

Raptor Nest Mitigation

- A BLM Wildlife Biologist must be contacted by the operator prior to construction activities to determine if the raptor nest is active.
- Determination to deconstruct inactive nest prior to pad construction will be made by BLM Wildlife Biologist.
- Raptor nests on special, natural habitat features, such as trees, large brush, cliff faces and escarpments, will be protected by not allowing surface disturbance within up to 200 meters of nests or by delaying activity for up to 90 days, or a combination of both. Exceptions to this requirement for raptor nests will be considered if the nests expected to be disturbed are inactive, the proposed activity is of short duration (e.g. habitat enhancement projects, fences, pipelines), and will not result in continuing activity in proximity to the nest.
- Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 ft. from the source of the noise.

Temporary Fencing Requirement

For the proposed Big Sinks 25 CTB 3 location, the BLM would require temporary fencing be installed before construction begins. This fencing would stay in place and be maintained throughout construction activities to protect nearby dune land habitat from harm.

Power Lines

Power lines shall be constructed and designed in accordance to standards outlined in "Suggested Practices for Avian Protection on Power lines: The State of the Art in 2006" Edison Electric Institute, APLIC, and the California Energy Commission 2006. The holder shall assume the burden and expense of proving that pole designs not shown in the above publication deter raptor perching, roosting, and nesting. Such proof shall be provided by a raptor expert approved by the Authorized Officer. The BLM reserves the right to require modification or additions to all power line structures placed on this right-of-way, should they be necessary to ensure the safety of large perching birds. The holder without liability or expense shall make such modifications and/or additions to the United States.

Watershed/Water Quality:

For all the proposed actions; the entire perimeter of the well pad and CTB sites will be bermed to prevent oil, salt, and other chemical contaminants from leaving the well pad.

- The compacted berm shall be constructed at a minimum of 12 inches high with impermeable mineral material (e.g. caliche).
- No water flow from the uphill side(s) of the pad shall be allowed to enter the well pad.
- The topsoil stockpile shall be located outside the bermed well pad.
- Topsoil, either from the well pad or surrounding area, shall not be used to construct the berm.
- No storm drains, tubing or openings shall be placed in the berm.
- If fluid collects within the bermed area, the fluid must be vacuumed into a safe container and disposed of properly at a state approved facility.
- The integrity of the berm shall be maintained around the surfaced pad throughout the life of the well and around the downsized pad after interim reclamation has been completed.
- Any access road entering the well pad shall be constructed so that the integrity of the berm height surrounding the well pad is not compromised. (Any access road crossing the berm cannot be lower than the berm height.)

Tank Battery:

- Tank battery locations will be lined and bermed. A 20 mil permanent liner will be installed with a 4 oz. felt backing to prevent tears or punctures. Tank battery berms must be large enough to contain 1 ½ times the content of the largest tank.
- Automatic shut off, check valves, or similar systems will be installed for tanks to minimize the effects of catastrophic line failures used in production or drilling.

Temporary Fence Crossing Requirement

Where entry is granted across a fence line, the fence must be braced and tied off on both sides of the passageway with H-braces prior to cutting. Once the work is completed, the fence will be restored to its prior condition, or better. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

Cattle Guard Requirement

Where entry is granted across a fence line for an access road, the fence must be braced and tied off on both sides of the passageway with H-braces prior to cutting. Once the work is completed, the fence will be restored to its prior condition with an appropriately sized cattle guard sufficient to carry out the project. Any new or existing cattle guards on the access route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattle guards that are in place and are utilized during lease operations. Once the road is abandoned, the fence would be restored to its prior condition, or better. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

Livestock Watering Requirement

Devon, in an agreement with the grazing allotment holder, would relocate a water pipeline affected by several proposed actions. Devon would also encase the water pipeline along its length where it would travel under access roads. See **Error! Reference source not found.** above.

Devon must contact the allotment holder prior to construction to identify the location of the pipelines. Devon must take measures to protect the pipelines from compression or other damages. If the pipelines are damaged or compromised in any way near the proposed project as a result of oil and gas activity, Devon is responsible for repairing the pipelines immediately. Devon must notify the BLM office (575-234-5972) and the private surface landowner or the grazing allotment holder if any damage occurs to structures that provide water to livestock.

During construction, Devon shall minimize disturbance to existing fences, water lines, troughs, windmills, and other improvements on public lands. Devon is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the grazing permittee/allottee prior to disturbing any range improvement projects. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

Temporary Fencing Requirement

For the proposed Big Sinks 25 CTB 3 location, the BLM would require temporary fencing be installed before construction begins. This fencing would stay in place and be maintained throughout construction activities to protect nearby dune land habitat from harm.

VI. CONSTRUCTION

A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. TOPSOIL

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

F. EXCLOSURE FENCING (CELLARS & PITS)

Exclosure Fencing

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

G. ON LEASE ACCESS ROADS**Road Width**

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

Ditching

Ditching shall be required on both sides of the road.

Turnouts


Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill out sloping and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

Cattle guards

An appropriately sized cattle guard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattle guards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattle guards that are in place and are utilized during lease operations.

Fence Requirement

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.

Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.

Construction Steps

1. Salvage topsoil
2. Construct road

3. Redistribute topsoil
4. Revegetate slopes




Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

VII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Exclosure Netting (Open-top Tanks)

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

Chemical and Fuel Secondary Containment and Exclosure Screening

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

Open-Vent Exhaust Stack Exclosures

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

Containment Structures

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

Painting Requirement

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

B. PIPELINES

BURIED PIPELINE STIPULATIONS

A copy of the application (Grant, APD, or Sundry Notice) and attachments, including conditions of approval, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The Holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. The Holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.
3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C.6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

4. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil or other pollutant, wherever found, shall be the responsibility of holder, regardless of fault. Upon failure of holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he deems necessary to control and clean up the discharge and restore the area, including where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve holder of any responsibility as provided herein.

5. All construction and maintenance activity will be confined to the authorized right-of-way.
6. The pipeline will be buried with a minimum cover of 36 inches between the top of the pipe and ground level.
7. The maximum allowable disturbance for construction in this right-of-way will be 30 feet:
 - Blading of vegetation within the right-of-way will be allowed: maximum width of blading operations will not exceed 20 feet. The trench is included in this area. (*Blading is defined as the complete removal of brush and ground vegetation.*)
 - Clearing of brush species within the right-of-way will be allowed: maximum width of clearing operations will not exceed 30 feet. The trench and bladed area are included in this area. (*Clearing is defined as the removal of brush while leaving ground vegetation (grasses, weeds, etc.) intact. Clearing is best accomplished by holding the blade 4 to 6 inches above the ground surface.*)
 - The remaining area of the right-of-way (if any) shall only be disturbed by compressing the vegetation. (*Compressing can be caused by vehicle tires, placement of equipment, etc.*)
8. The holder shall stockpile an adequate amount of topsoil where blading is allowed. The topsoil to be stripped is approximately 6 inches in depth. The topsoil will be segregated from other spoil piles from trench construction. The topsoil will be evenly distributed over the bladed area for the preparation of seeding.
9. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.
10. Vegetation, soil, and rocks left as a result of construction or maintenance activity will be randomly scattered on this right-of-way and will not be left in rows, piles, or berms, unless otherwise approved by the Authorized Officer. The entire right-of-way shall be recontoured to match the surrounding landscape. The backfilled soil shall be compacted and a 6 inch berm will be left over the ditch line to allow for settling back to grade.
11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.

12. The holder will reseed all disturbed areas. Seeding will be done according to the attached seeding requirements, using the following seed mix.

- | | |
|--|--|
| <input type="checkbox"/> seed mixture 1 | <input type="checkbox"/> seed mixture 3 |
| <input type="checkbox"/> seed mixture 2 | <input type="checkbox"/> seed mixture 4 |
| <input checked="" type="checkbox"/> seed mixture 2/LPC | <input type="checkbox"/> Aplomado Falcon Mixture |

13. All above-ground structures not subject to safety requirements shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be color which simulates "Standard Environmental Colors" – **Shale Green**, Munsell Soil Color No. 5Y 4/2.

14. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. All signs and information thereon will be posted in a permanent, conspicuous manner, and will be maintained in a legible condition for the life of the pipeline.

15. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder before maintenance begins. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway. As determined necessary during the life of the pipeline, the Authorized Officer may ask the holder to construct temporary deterrence structures.

16. Any cultural and/or paleontological resources (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

17. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes associated roads, pipeline corridor and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

18. Escape Ramps - The operator will construct and maintain pipeline/utility trenches that are not otherwise fenced, screened, or netted to prevent livestock, wildlife, and humans from becoming entrapped. At a minimum, the operator will construct and maintain escape ramps, ladders, or

other methods of avian and terrestrial wildlife escape in the trenches according to the following criteria:

- a. Any trench left open for eight (8) hours or less is not required to have escape ramps; however, before the trench is backfilled, the contractor/operator shall inspect the trench for wildlife, remove all trapped wildlife, and release them at least 100 yards from the trench.
- b. For trenches left open for eight (8) hours or more, earthen escape ramps (built at no more than a 30 degree slope and spaced no more than 500 feet apart) shall be placed in the trench.

19. Special Stipulations:

Lesser Prairie-Chicken

Oil and gas activities will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, geophysical exploration other than 3-D operations, and pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 ft. from the source of the noise.

This authorization is subject to your Certificate of Participation and/or Certificate of Inclusion under the New Mexico Candidate Conservation Agreement. Because it involves surface disturbing activities covered under your Certificate, your Habitat Conservation Fund Account with the Center of Excellence for Hazardous Materials Management (CEHMM) will be debited according to Exhibit B Part 2 of the Certificate of Participation.

STANDARD STIPULATIONS FOR SURFACE INSTALLED PIPELINES

A copy of the application (Grant, Sundry Notice, APD) and attachments, including stipulations, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. The holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 *et seq.* (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR, Part 702-799 and

especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.

3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to activity of the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

4. The holder shall be liable for damage or injury to the United States to the extent provided by 43 CFR Sec. 2883.1-4. The holder shall be held to a standard of strict liability for damage or injury to the United States resulting from pipe rupture, fire, or spills caused or substantially aggravated by any of the following within the right-of-way or permit area:

- a. Activities of the holder including, but not limited to construction, operation, maintenance, and termination of the facility.
- b. Activities of other parties including, but not limited to:
 - (1) Land clearing.
 - (2) Earth-disturbing and earth-moving work.
 - (3) Blasting.
 - (4) Vandalism and sabotage.
- c. Acts of God.

The maximum limitation for such strict liability damages shall not exceed one million dollars (\$1,000,000) for any one event, and any liability in excess of such amount shall be determined by the ordinary rules of negligence of the jurisdiction in which the damage or injury occurred.

This section shall not impose strict liability for damage or injury resulting primarily from an act of war or from the negligent acts or omissions of the United States.

5. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil, salt water, or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil, salt water, or other pollutant, wherever found, shall be the responsibility of

the holder, regardless of fault. Upon failure of the holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he deems necessary to control and clean up the discharge and restore the area, including, where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve the holder of any responsibility as provided herein.

6. All construction and maintenance activity will be confined to the authorized right-of-way width of 20 feet. If the pipeline route follows an existing road or buried pipeline right-of-way, the surface pipeline must be installed no farther than 10 feet from the edge of the road or buried pipeline right-of-way. If existing surface pipelines prevent this distance, the proposed surface pipeline must be installed immediately adjacent to the outer surface pipeline. All construction and maintenance activity will be confined to existing roads or right-of-ways.

7. No blading or clearing of any vegetation will be allowed unless approved in writing by the Authorized Officer.

8. The holder shall install the pipeline on the surface in such a manner that will minimize suspension of the pipeline across low areas in the terrain. In hummocky or dune areas, the pipeline will be "snaked" around hummocks and dunes rather than suspended across these features.

9. The pipeline shall be buried with a minimum of 24 inches under all roads, "two-tracks," and trails. Burial of the pipe will continue for 20 feet on each side of each crossing. The condition of the road, upon completion of construction, shall be returned to at least its former state with no bumps or dips remaining in the road surface.

10. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.

12. Excluding the pipe, all above-ground structures not subject to safety requirement shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be a color which simulates "Standard Environmental Colors" – **Shale Green**, Munsell Soil Color No. 5Y 4/2; designated by the Rocky Mountain Five State

Interagency Committee.

13. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. Signs will be maintained in a legible condition for the life of the pipeline.

14. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway.

15. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the authorized officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the authorized officer. An evaluation of the discovery will be made by the authorized officer to determine appropriate cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the authorized officer after consulting with the holder.

16. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, powerline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

17. Surface pipelines must be less than or equal to 4 inches and a working pressure below 125 psi.

18. Special Stipulations:

- a. **Lesser Prairie-Chicken:** Oil and gas activities will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities and pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Normal vehicle use on existing roads will not be restricted.
- b. This authorization is subject to your Certificate of Participation and/or Certificate of Inclusion under the New Mexico Candidate Conservation Agreement. Because it involves surface disturbing activities covered under your Certificate, your Habitat Conservation Fund Account with the Center of Excellence for Hazardous

Materials Management (CEHMM) will be debited according to Exhibit B Part 2 of the Certificate of Participation.

C. ELECTRIC LINES

STANDARD STIPULATIONS FOR OVERHEAD ELECTRIC DISTRIBUTION LINES

A copy of the grant and attachments, including stipulations, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.

2. The holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR, Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.

3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

4. There will be no clearing or blading of the right-of-way unless otherwise agreed to in writing by the Authorized Officer.

5. Power lines shall be constructed and designed in accordance to standards outlined in "Suggested Practices for Avian Protection on Power lines: The State of the Art in 2006" Edison Electric Institute, APLIC, and the California Energy Commission 2006 . The

holder shall assume the burden and expense of proving that pole designs not shown in the above publication deter raptor perching, roosting, and nesting. Such proof shall be provided by a raptor expert approved by the Authorized Officer. The BLM reserves the right to require modification or additions to all powerline structures placed on this right-of-way, should they be necessary to ensure the safety of large perching birds. Such modifications and/or additions shall be made by the holder without liability or expense to the United States.

Raptor deterrence will consist of but not limited to the following: triangle perch discouragers shall be placed on each side of the cross arms and a nonconductive perching deterrent shall be placed on all vertical poles that extend past the cross arms.

6. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

7. The BLM serial number assigned to this authorization shall be posted in a permanent, conspicuous manner where the power line crosses roads and at all serviced facilities. Numbers will be at least two inches high and will be affixed to the pole nearest the road crossing and at the facilities served.

8. Upon cancellation, relinquishment, or expiration of this grant, the holder shall comply with those abandonment procedures as prescribed by the Authorized Officer.

9. All surface structures (poles, lines, transformers, etc.) shall be removed within 180 days of abandonment, relinquishment, or termination of use of the serviced facility or facilities or within 180 days of abandonment, relinquishment, cancellation, or expiration of this grant, whichever comes first. This will not apply where the power line extends service to an active, adjoining facility or facilities.

10. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

11. Special Stipulations:

- For reclamation remove poles, lines, transformer, etc. and dispose of properly.

- Fill in any holes from the poles removed.

Timing Limitation Stipulation/Condition of Approval for Lesser Prairie-Chicken:

Oil and gas activities including 3-D geophysical exploration, and drilling will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, geophysical exploration other than 3-D operations, and pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Additionally, no new drilling will be allowed within up to 200 meters of leks known at the time of permitting. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 ft. from the source of the noise.

This authorization is subject to your Certificate of Participation and/or Certificate of Inclusion under the New Mexico Candidate Conservation Agreement. Because it involves surface disturbing activities covered under your Certificate, your Habitat Conservation Fund Account with the Center of Excellence for Hazardous Materials Management (CEHMM) will be debited according to Exhibit B Part 2 of the Certificate of Participation.

VIII. INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

IX. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well.

Seed Mixture for LPC Sand/Shinnery Sites

Holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed shall be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed shall be either certified or registered seed. The seed container shall be tagged in accordance with State law(s) and available for inspection by the Authorized Officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). Holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. Seeding shall be repeated until a satisfactory stand is established as determined by the Authorized Officer. Evaluation of growth may not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed* per acre:

<u>Species</u>	<u>lb/acre</u>
Plains Bristlegrass	5lbs/A
Sand Bluestem	5lbs/A
Little Bluestem	3lbs/A
Big Bluestem	6lbs/A
Plains Coreopsis	2lbs/A
Sand Dropseed	1lbs/A

*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Operator Certification

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

NAME: Erin Workman

Signed on: 11/30/2017

Title: Regulatory Compliance Professional

Street Address: 333 West Sheridan Avenue

City: Oklahoma City

State: OK

Zip: 73102

Phone: (405)552-7970

Email address: Erin.Workman@dvn.com

Field Representative

Representative Name: Ray Vaz

Street Address: 6488 Seven Rivers Hwy

City: Artesia

State: NM

Zip: 88210

Phone: (575)748-1871

Email address: ray.vaz@dvn.com



APD ID: 10400024301

Submission Date: 12/01/2017

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BIG SINKS DRAW 25-24 FED COM

Well Number: 711H

Well Type: OIL WELL

Well Work Type: Drill

Show Final Text

Section 1 - General

APD ID: 10400024301

Tie to previous NOS?

Submission Date: 12/01/2017

BLM Office: CARLSBAD

User: Erin Workman

Title: Regulatory Compliance
Professional

Federal/Indian APD: FED

Is the first lease penetrated for production Federal or Indian? FED

Lease number: NMLC0062300

Lease Acres: 2479.82

Surface access agreement in place?

Allotted?

Reservation:

Agreement in place? NO

Federal or Indian agreement:

Agreement number:

Agreement name:

Keep application confidential? YES

Permitting Agent? NO

APD Operator: DEVON ENERGY PRODUCTION COMPANY LP

Operator letter of designation:

Operator Info

Operator Organization Name: DEVON ENERGY PRODUCTION COMPANY LP

Operator Address: 333 West Sheridan Avenue

Zip: 73102

Operator PO Box:

Operator City: Oklahoma City State: OK

Operator Phone: (405)552-6571

Operator Internet Address:

Section 2 - Well Information

[Redacted]

Master Development Plan name: Cotton Draw 2 MDP

Well in Master SUPO? NO

Master SUPO name:

Well in Master Drilling Plan? NO

Master Drilling Plan name:

Well Name: BIG SINKS DRAW 25-24 FED COM

Well Number: 711H

Well API Number:

Field/Pool or Exploratory? Field and Pool

Field Name: PURPLE SAGE

Pool Name: WOLFCAMP

Is the proposed well in an area containing other mineral resources? NATURAL GAS,OIL

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BIG SINKS DRAW 25-24 FED COM

Well Number: 711H

Describe other minerals:

Is the proposed well in a Helium production area? N Use Existing Well Pad? NO New surface disturbance?

Type of Well Pad: MULTIPLE WELL

Multiple Well Pad Name: BIG Number: 1

Well Class: HORIZONTAL

SINKS DRAW CTB

Number of Legs: 1

Well Work Type: Drill

Well Type: OIL WELL

Describe Well Type:

Well sub-Type: APPRAISAL

Describe sub-type:

Distance to town:

Distance to nearest well: 425 FT

Distance to lease line: 330 FT

Reservoir well spacing assigned acres Measurement: 240 Acres

Well plat: BSD_25_24_Fed_Com_711H_C_102_signed_20171130054514.pdf

Well work start Date: 09/01/2018

Duration: 30 DAYS

Section 3 - Well Location Table

Survey Type: RECTANGULAR

Describe Survey Type:

Datum: NAD83

Vertical Datum: NAVD88

Survey number: 5661

	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD
SHL Leg #1	248 4	FNL	985	FWL	25S	31E	25	Aliquot SWN W	32.10170 25	- 103.7370 139	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMLC0 062300	333 8	0	0
KOP Leg #1	265 9	FNL	330	FWL	25S	31E	25	Aliquot NWS W	32.10170 25	- 103.7370 139	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMLC0 062300	- 792 7	113 06	112 65
PPP Leg #1	208 7	FNL	330	FWL	25S	31E	25	Aliquot SWN W	32.10170 25	- 103.7370 139	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMLC0 062300	- 850 0	122 06	118 38

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BIG SINKS DRAW 25-24 FED COM

Well Number: 711H

	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD
PPP Leg #1	0	FSL	330	FWL	25S	31E	24	Aliquot SWN W	32.11578 45	- 103.7390 851	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 125634	- 850 0	169 28	118 38
EXIT Leg #1	330	FNL	330	FWL	25S	31E	24	Aliquot SWN W	32.12213 65	- 103.7390 657	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMLC0 061869	- 850 0	192 39	118 38
BHL Leg #1	330	FNL	330	FWL	25S	31E	24	Aliquot SWN W	32.12213 65	- 103.7390 657	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMLC0 061869	- 850 0	192 39	118 38

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BIG SINKS DRAW 25-24 FED COM

Well Number: 711H

broken the system must be tested.

Choke Diagram Attachment:

BSD_25_24_Fed_Com_711H_5M_BOPE_Ck_20180502135528.pdf

BOP Diagram Attachment:

BSD_25_24_Fed_Com_711H_5M_BOPE_Ck_20180502135555.pdf

Pressure Rating (PSI): 5M

Rating Depth: 12762

Equipment: BOP/BOPE will be installed per Onshore Oil & Gas Order #2 requirements prior to drilling below 13-3/8" surface casing, a 13-5/8" BOP/BOPE system with a minimum rating of 3M will be installed on the wellhead system. BOP/BOPE will be tested by an independent service company per Onshore Oil & Gas Order #2 requirements and MASP (Maximum Anticipated Surface Pressure) calculations. If the system is upgraded, all the components installed will be functional and tested.

Requesting Variance? YES

Variance request: A variance is requested for the use of a flexible choke line from the BOP stack to the choke manifold. See attached for specs for hydrostatic test chart.

Testing Procedure: A multibowl wellhead may be used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested.

Choke Diagram Attachment:

BSD_25_24_Fed_Com_711H_5M_BOPE_Ck_20171106070309.pdf

BOP Diagram Attachment:

BSD_25_24_Fed_Com_711H_5M_BOPE_Ck_20171106070334.pdf

Section 3 - Casing

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	14.75	10.75	NEW	API	N	0	958	0	958			958	J-55	40.5	STC	1.125	1.25	BUOY	1.6	BUOY	1.6
2	INTERMEDIATE	9.875	7.625	NEW	NON API	N	0	8400	0	8370			8400	P-110	29.7	OTHER - BTC	1.125	1.25	BUOY	1.6	BUOY	1.6
3	INTERMEDIATE	8.75	7.625	NEW	NON API	N	8400	12000	8370	11801			3600	P-110	29.7	OTHER - FLUSHMAX	1.125	1.25	BUOY	1.6	BUOY	1.6
4	PRODUCTION	6.75	5.5	NEW	NON API	N	0	19238	0	11838			19238	P-110	20	OTHER - VAM SG	1.125	1.25	BUOY	1.6	BUOY	1.6

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BIG SINKS DRAW 25-24 FED COM

Well Number: 711H

Casing Attachments

Casing ID: 1 **String Type:** SURFACE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

BSD_25_24_Fed_Com_711H_SurfCsg_Ass_20171109112613.pdf

Casing ID: 2 **String Type:** INTERMEDIATE

Inspection Document:

Spec Document:

BSD_25_24_Fed_Com_711H_VAMSG_20180502152205.pdf

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

BSD_25_24_Fed_Com_711H_Int_Csg_Ass_20180504145140.pdf

Casing ID: 3 **String Type:** INTERMEDIATE

Inspection Document:

Spec Document:

BSD_25_24_Fed_Com_711H_Flushmax_20171109112804.pdf

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

BSD_25_24_Fed_Com_711H_Int_Csg_Ass_20171109112850.pdf

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BIG SINKS DRAW 25-24 FED COM

Well Number: 711H

Casing Attachments

Casing ID: 4 String Type: PRODUCTION

Inspection Document:

Spec Document:

BSD_25_24_Fed_Com_711H_VAMSG_20171109113006.pdf

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

BSD_25_24_Fed_Com_711H_ProdCasing_Ass_20171109113046.pdf

Section 4 - Cement

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
INTERMEDIATE	Lead		0	0	0	0	0	0	0		N/A
CONCRETE	Lead		0	958	397	1.34	14.8	797	50	G	1% Galv. 1% S.C. 1% S.C.
INTERMEDIATE	Lead		0	1050	419	3.27	9	1374	30	TURBID	TURBIDITY
INTERMEDIATE	Tail		1050	1200	163	1.2	14.5	195	30	H	1% Zn (by Ash) + 0.5% (by wt) HALAD 344 + 0.4% (by wt) CL 100 + 0.2% (by wt) CL 100 + 0.04% (by wt) (by wt) CL 100 + 2% (by wt) (by wt) CL 100
PRODUCTION	Lead		1200	1928	607	1.33	14.8	808	25	H	0.12% (by wt) (by wt) CL 100 + 1% (by wt) (by wt) CL 100

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BIG SINKS DRAW 25-24 FED COM

Well Number: 711H

Section 5 - Circulating Medium

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with Onshore Order #2:

Diagram of the equipment for the circulating system in accordance with Onshore Order #2:

Describe what will be on location to control well or mitigate other conditions: Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

Describe the mud monitoring system utilized: PVT/Pason/Visual Monitoring

Circulating Medium Table

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
0	958	WATER-BASED MUD	8.5	9							
958	4403	SALT SATURATED	10	11							
4403	1831 4	WATER-BASED MUD	8.5	9.3							

Section 6 - Test, Logging, Coring

List of production tests including testing procedures, equipment and safety measures:

Will run GR/CNL from TD to surface (horizontal well – vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.

List of open and cased hole logs run in the well:

CBL

Coring operation description for the well:

N/A

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BIG SINKS DRAW 25-24 FED COM

Well Number: 711H

Section 7 - Pressure

Anticipated Bottom Hole Pressure: 8002

Anticipated Surface Pressure: 5397.64

Anticipated Bottom Hole Temperature(F): 165

Anticipated abnormal pressures, temperatures, or potential geologic hazards? NO

Describe:

Contingency Plans geohazards description:

Contingency Plans geohazards attachment:

Hydrogen Sulfide drilling operations plan required? YES

Hydrogen sulfide drilling operations plan:

BSD_25_24_Fed_Com_711H_H2S_Plan_20171109113625.pdf

Section 8 - Other Information

Proposed horizontal/directional/multi-lateral plan submission:

BSD_25_24_Fed_Com_711H_Prelim_36x48WM_20171109113742.PDF

BSD_25_24_Fed_Com_711H_Prelim_Dir_Plan_20171109113756.pdf

BSD_25_24_Fed_Com_711H_Prelim_WP_Rpt_20171109113936.pdf

BSD_25_24_Fed_Com_711H_Prelim_AC_Rpt_20171109113948.pdf

Other proposed operations facets description:

MULTI-LATERAL DRILLING PLAN
5M BOPE
MB VERB
CLOSURE
Drilling Plan
See for details of the proposed program for each drilling

Other proposed operations facets attachment:

BSD_25_24_Fed_Com_711H_Clsd_Loop_20171109114105.pdf

BSD_25_24_Fed_Com_711H_MB_Verb_5M_20180313122109.pdf

BSD_25_24_Fed_Com_711H_5M_BOPE_Ck_20180504150239.pdf

BSD_25_24_Fed_Com_711H_MB_Wellhd_5M_WC_20180504151228.pdf


Big_Sinks_Draw_25_24_Fed_Com_711H_Drilling_Plan_V2_20180504151435.pdf

Other Variance attachment:


BSD_25_24_Fed_Com_711H_Co_flex_20171109114119.pdf

BSD_25_24_Fed_Com_711H_Spudder_Rig_20171109114135.pdf


13-5/8" 5M BOPE & Closed Loop Equipment Schematic




13-5/8" 5M BOPE & Closed Loop Equipment Schematic



13-5/8" 5M BOPE & Closed Loop Equipment Schematic



13-5/8" 5M BOPE & Closed Loop Equipment Schematic





Connection Data Sheet

OD 5 1/2 in.	Weight 20.00 lb/ft	Wall Th. 0.361 in.	Grade P110 EC	API Drift 4.653 in.	Connection VAM® SG
------------------------	------------------------------	------------------------------	-------------------------	-------------------------------	------------------------------

PIPE PROPERTIES	
Nominal OD	5.500 in.
Nominal ID	4.778 in.
Nominal Cross Section Area	5.828 sqin.
Grade Type	High Yield
Min. Yield Strength	125 ksi
Max. Yield Strength	140 ksi
Min. Ultimate Tensile Strength	135 ksi


CONNECTION PROPERTIES	
Connection Type	Premium integral semi-flush
Connection OD (nom)	5.697 in.
Connection ID (nom)	4.711 in.
Make-up Loss	6.336 in.
Tension Efficiency	87 % of pipe
Compression Efficiency	61 % of pipe
Internal Pressure Efficiency	100 % of pipe
External Pressure Efficiency	70 % of pipe

CONNECTION PERFORMANCES	
Tensile Yield Strength	634 klb
Compression Resistance	446 klb
Internal Yield Pressure	14360 psi
External pressure resistance	8463 psi
Max. bending with sealability	40 °/100 ft

TORQUE VALUES	
Min. Make-up torque	8100 ft.lb
Opti. Make-up torque	9800 ft.lb
Max. Make-up torque	11500 ft.lb
Maximum Torque with Sealability	12500 ft.lb

The single solution for Shale Play needs

VAM® SG brings VAM® premium sealing performance to a semi-flush connection with extremely high Tension performance and increase Torque capacity, validated to the specific Shale drilling requirements, while remaining highly competitive in North American Shale play economics.



Do you need help on this product? - Remember no one knows VAM® like VAM

canada@vamfieldservice.com
 usa@vamfieldservice.com
 mexico@vamfieldservice.com
 brazil@vamfieldservice.com

uk@vamfieldservice.com
 dubai@vamfieldservice.com
 nigeria@vamfieldservice.com
 angola@vamfieldservice.com

china@vamfieldservice.com
 baku@vamfieldservice.com
 singapore@vamfieldservice.com
 australia@vamfieldservice.com

Over 140 VAM® Specialists available worldwide 24/7 for Rig Site Assistance



FLUSHMAX-III

Geometry

Imperial


S.I.

Pipe Body

Grade	P110		P110	
Pipe OD (D)	7 5/8	in	193.68	mm
Weight	29.70	lb/ft	44.20	kg/m
Actual weight	29.04		43.21	kg/m
Wall Thickness (t)	0.375	in	9.53	mm
Pipe ID (d)	6.875	in	174.63	mm
Pipe body cross section	8.537	in ²	5,508	mm ²
Drift Dia.	6.750	in	171.45	mm

Connection

Box OD (W)	7.625	in	193.68	mm
PIN ID	6.875	in	174.63	mm
Make up Loss	3.040	in	77.22	mm
Box Critical Area	4.424	in ²	2854	mm ²
Joint load efficiency	60	%	60	%
Thread Taper	1 / 16 (3/4" per ft)			
Number of Threads	5 TPI			



Performance Properties for Pipe Body

M.I.Y.P.	9,470	psi	65.31	MPa
----------	-------	-----	-------	-----

Note S.M.Y.S.= Specified Minimum YIELD Strength of Pipe body
M.I.Y.P. = Minimum Internal Yield Pressure of Pipe body

Performance Properties for Connection

Min. Compression Yield	563 kips (60% of S.M.Y.S.)
External Pressure	100% of Collapse Strength

Recommended Torque

Opti.	17,200	ft-lb	23,300	N-m
Operational Max.	23,600	ft-lb	32,000	N-m

Note : Operational Max. torque can be applied for high torque application

Legal Notice

The use of this information is at the reader/user's risk and no warranty is implied or expressed by Metal One Corporation or its parents, subsidiaries or affiliates (herein collectively referred to as "Metal One") with respect to the use of information contained herein. The information provided on this Connection Data Sheet is for informational purposes only, and was prepared by reference to engineering information that is specific to the subject products, without regard to safety-related factors, all of which are the sole responsibility of the operators and users of the subject connectors. Metal One assumes no responsibility for any errors with respect to this information.

Statements regarding the suitability of products for certain types of applications are based on Metal One's knowledge of typical requirements that are often placed on Metal One products in standard well configurations. Such statements are not binding statements about the suitability of products for a particular application. It is the customer's responsibility to validate that a particular product with the properties described in the product specification is suitable for use in a particular application

The products described in this Connection Data Sheet are not recommended for use in deep water offshore applications. For more information, please refer to http://www.mtlo.co.jp/mo-con/images/top/WebsiteTerms_Active_20333287_1.pdf the contents of which are incorporated by reference into this Connection Data Sheet.



Connection Data Sheet

OD 5 1/2 in.	Weight 20.00 lb/ft	Wall Th. 0.361 in.	Grade P110 EC	API Drift 4.653 in.	Connection VAM® SG
------------------------	------------------------------	------------------------------	-------------------------	-------------------------------	------------------------------

PIPE PROPERTIES	
Nominal OD	5.500 in.
Nominal ID	4.778 in.
Nominal Cross Section Area	5.828 sqin.
Grade Type	High Yield
Min. Yield Strength	125 ksi
Max. Yield Strength	140 ksi
Min. Ultimate Tensile Strength	135 ksi


CONNECTION PROPERTIES	
Connection Type	Premium integral semi-flush
Connection OD (nom)	5.697 in.
Connection ID (nom)	4.711 in.
Make-up Loss	6.336 in.
Tension Efficiency	87 % of pipe
Compression Efficiency	61 % of pipe
Internal Pressure Efficiency	100 % of pipe
External Pressure Efficiency	70 % of pipe

CONNECTION PERFORMANCES	
Tensile Yield Strength	634 klb
Compression Resistance	446 klb
Internal Yield Pressure	14360 psi
External pressure resistance	8463 psi
Max. bending with sealability	40 °/100 ft

TORQUE VALUES	
Min. Make-up torque	8100 ft.lb
Opti. Make-up torque	9800 ft.lb
Max. Make-up torque	11500 ft.lb
Maximum Torque with Sealability	12500 ft.lb

The single solution for Shale Play needs

VAM® SG brings VAM® premium sealing performance to a semi-flush connection with extremely high Tension performance and increase Torque capacity, validated to the specific Shale drilling requirements, while remaining highly competitive in North American Shale play economics.



Do you need help on this product? - Remember no one knows VAM® like VAM

canada@vamfieldservice.com
usa@vamfieldservice.com
mexico@vamfieldservice.com
brazil@vamfieldservice.com

uk@vamfieldservice.com
dubai@vamfieldservice.com
nigeria@vamfieldservice.com
angola@vamfieldservice.com

china@vamfieldservice.com
baku@vamfieldservice.com
singapore@vamfieldservice.com
australia@vamfieldservice.com

Over 140 VAM® Specialists available worldwide 24/7 for Rig Site Assistance



Casing Assumptions and Load Cases

Production

All casing design assumptions were ran in Stress Check to determine safety factor which meet or exceed both Devon Energy and BLM minimum requirements. All casing strings will be filled while running in hole in order to not exceed collapse rating of the pipe.

Production Casing Burst Design		
Load Case	External Pressure	Internal Pressure
Pressure Test	Formation Pore Pressure	Fluid in hole (water or produced water) + test psi
Tubing Leak	Formation Pore Pressure	Packer @ KOP, leak below surface 8.6 ppg packer fluid
Stimulation	Formation Pore Pressure	Max frac pressure with heaviest frac fluid

Production Casing Collapse Design		
Load Case	External Pressure	Internal Pressure
Full Evacuation	Water gradient in cement, mud above TOC.	None
Cementing	Wet cement weight	Water (8.33ppg)

Production Casing Tension Design	
Load Case	Assumptions
Overpull	100kips
Runing in hole	2 ft/s
Service Loads	N/A

Casing Assumptions and Load Cases

Surface

All casing design assumptions were ran in Stress Check to determine safety factor which meet or exceed both Devon Energy and BLM minimum requirements. All casing strings will be filled while running in hole in order to not exceed collapse rating of the pipe.

Surface Casing Burst Design		
Load Case	External Pressure	Internal Pressure
Pressure Test	Formation Pore Pressure	Max mud weight of next hole-section plus Test psi
Drill Ahead	Formation Pore Pressure	Max mud weight of next hole section
Displace to Gas	Formation Pore Pressure	Dry gas from next casing point

Surface Casing Collapse Design		
Load Case	External Pressure	Internal Pressure
Full Evacuation	Water gradient in cement, mud above TOC	None
Cementing	Wet cement weight	Water (8.33ppg)

Surface Casing Tension Design	
Load Case	Assumptions
Overpull	100kips
Runing in hole	3 ft/s
Service Loads	N/A

Casing Assumptions and Load Cases

Intermediate

All casing design assumptions were ran in Stress Check to determine safety factor which meet or exceed both Devon Energy and BLM minimum requirements. All casing strings will be filled while running in hole in order to not exceed collapse rating of the pipe.

Intermediate Casing Burst Design		
Load Case	External Pressure	Internal Pressure
Pressure Test	Formation Pore Pressure	Max mud weight of next hole-section plus Test psi
Drill Ahead	Formation Pore Pressure	Max mud weight of next hole section
Fracture @ Shoe	Formation Pore Pressure	Dry gas

Intermediate Casing Collapse Design		
Load Case	External Pressure	Internal Pressure
Full Evacuation	Water gradient in cement, mud above TOC	None
Cementing	Wet cement weight	Water (8.33ppg)

Intermediate Casing Tension Design	
Load Case	Assumptions
Overpull	100kips
Runing in hole	2 ft/s
Service Loads	N/A

Casing Assumptions and Load Cases

Intermediate

All casing design assumptions were ran in Stress Check to determine safety factor which meet or exceed both Devon Energy and BLM minimum requirements. All casing strings will be filled while running in hole in order to not exceed collapse rating of the pipe.

Intermediate Casing Burst Design		
Load Case	External Pressure	Internal Pressure
Pressure Test	Formation Pore Pressure	Max mud weight of next hole-section plus Test psi
Drill Ahead	Formation Pore Pressure	Max mud weight of next hole section
Fracture @ Shoe	Formation Pore Pressure	Dry gas

Intermediate Casing Collapse Design		
Load Case	External Pressure	Internal Pressure
Full Evacuation	Water gradient in cement, mud above TOC	None
Cementing	Wet cement weight	Water (8.33ppg)

Intermediate Casing Tension Design	
Load Case	Assumptions
Overpull	100kips
Runing in hole	2 ft/s
Service Loads	N/A



**Devon Energy Center
333 West Sheridan Avenue
Oklahoma City, Oklahoma 73102-5015**

Hydrogen Sulfide (H₂S) Contingency Plan

For



Big Sinks Draw 25-24 Fed Com 711H

**Sec-25 T-25S R-31E
2484' FNL & 985' FWL
LAT. = 32.1017025' N (NAD83)
LONG = 103.7370139' W**

Eddy County NM

Big Sinks Draw 25-24 Fed Com 711H

This is an open drilling site. H₂S monitoring equipment and emergency response equipment will be used within 500' of zones known to contain H₂S, including warning signs, wind indicators and H₂S monitor.



Escape

Crews shall escape upwind of escaping gas in the event of an emergency release of gas. Escape can be facilitated from the location entrance road. Crews should then block the entrance to the location from the lease road so as not to allow anyone traversing into a hazardous area. The blockade should be at a safe distance outside of the ROE. There are no homes or buildings in or near the ROE.

Assumed 100 ppm ROE = 3000'

100 ppm H₂S concentration shall trigger activation of this plan.

Emergency Procedures

In the event of a release of gas containing H₂S, the first responder(s) must

- **Isolate the area and prevent entry by other persons into the 100 ppm ROE.**
- **Evacuate any public places encompassed by the 100 ppm ROE.**
- **Be equipped with H₂S monitors and air packs in order to control the release.**
- **Use the “buddy system” to ensure no injuries occur during the response**
- **Take precautions to avoid personal injury during this operation.**
- **Contact operator and/or local officials to aid in operation. See list of phone numbers attached.**
- **Have received training in the**
 - **Detection of H₂S, and**
 - **Measures for protection against the gas,**
 - **Equipment used for protection and emergency response.**

Ignition of Gas Source

Should control of the well be considered lost and ignition considered, take care to protect against exposure to Sulfur Dioxide (SO₂). Intentional ignition must be coordinated with the NMOCD and local officials. Additionally the NM State Police may become involved. NM State Police shall be the Incident Command on scene of any major release. Take care to protect downwind whenever there is an ignition of the gas

Characteristics of H₂S and SO₂

Common Name	Chemical Formula	Specific Gravity	Threshold Limit	Hazardous Limit	Lethal Concentration
Hydrogen Sulfide	H₂S	1.189 Air = 1	10 ppm	100 ppm/hr	600 ppm
Sulfur Dioxide	SO₂	2.21 Air = 1	2 ppm	N/A	1000 ppm

Contacting Authorities

Devon Energy Corp. personnel must liaison with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such as type and volume of release, wind direction, location of release, etc. Be prepared with all information available. The following call list of essential and potential responders has been prepared for use during a release. Devon Energy Corp. Company response must be in coordination with the State of New Mexico's 'Hazardous Materials Emergency Response Plan' (HMER)

Hydrogen Sulfide Drilling Operation Plan

I. HYDROGEN SULFIDE (H₂S) TRAINING

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on this well:

1. The hazards and characteristics of hydrogen sulfide (H₂S)
2. The proper use and maintenance of personal protective equipment and life support systems.
3. The proper use of H₂S detectors, alarms, warning systems, briefing areas, evacuation procedures, and prevailing winds.
4. The proper techniques for first aid and rescue procedures.

In addition, supervisory personnel will be trained in the following areas:

1. The effects of H₂S metal components. If high tensile tubulars are to be used, personnel will be trained in their special maintenance requirements.
2. Corrective action and shut-in procedures when drilling or reworking a well and blowout prevention and well control procedures.
3. The contents and requirements of the H₂S Drilling Operations Plan and Public Protection Plan.

There will be an initial training session just prior to encountering a known or probable H₂S zone (within 3 days or 500 feet) and weekly H₂S and well control drills for all personnel in each crew. The initial training session shall include a review of the site specific H₂S Drilling Operations Plan and the Public Protection Plan.

II. HYDROGEN SULFIDE TRAINING

Note: All H₂S safety equipment and systems will be installed, tested, and operational when drilling reaches a depth of 500 feet above, or three days prior to penetrating the first zone containing or reasonably expected to contain H₂S.

1. Well Control Equipment

- A. Flare line
- B. Choke manifold – Remotely Operated
- C. Blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit
- D. Auxiliary equipment may include if applicable: annular preventer and rotating head.
- E. Mud/Gas Separator

2. Protective equipment for essential personnel:

30-minute SCBA units located at briefing areas, as indicated on well site diagram, with escape units available in the top doghouse. As it may be difficult to communicate audibly while wearing these units, hand signals shall be utilized.

3. H₂S detection and monitoring equipment:

Portable H₂S monitors positioned on location for best coverage and response. These units have warning lights which activate when H₂S levels reach 10 ppm and audible sirens which activate at 15 ppm. Sensor locations:

- Bell nipple
- Shale shaker
- Trip tank
- Suction pit
- Rig floor
- Cellar
- Choke manifold
- Living Quarters (usually the company man's trailer stairs.)

Visual warning systems:

- A. Wind direction indicators as shown on well site diagram
- B. Caution/ Danger signs shall be posted on roads providing direct access to locations. Signs will be painted a high visibility yellow with black lettering of sufficient size to be reasonable distance from the immediate location. Bilingual signs will be used when appropriate.

4. Mud program:

The mud program has been designed to minimize the volume of H₂S circulated to surface. Proper mud weight, safe drilling practices and the use of H₂S scavengers will minimize hazards when penetrating H₂S bearing zones.

5. Metallurgy:

- A. All drill strings, casings, tubing, wellhead, blowout preventer, drilling spool, kill lines, choke manifold lines, and valves shall be H₂S trim.
- B. All elastomers used for packing and seals shall be H₂S trim.

6. Communication:

- A. Company personnel have/use cellular telephones in the field.
- B. Land line (telephone) communications at Office

7. Well testing:

- A. Drill stem testing will be performed with a minimum number of personnel in the immediate vicinity, which are necessary to safety and adequately conduct the test. The drill stem testing will be conducted during daylight hours and formation fluids will not be flowed to the surface. All drill-stem-testing operations conducted in an H₂S environment will use the closed chamber method of testing.
- B. There will be no drill stem testing.


Devon Energy Corp. Company Call List		
Drilling Supervisor – Basin – Mark Kramer		405-823-4796
Jerry Matthews – Day: 575-748-0161 Cell: 575-748-5234		
EHS Professional – Jason Robison		405-541-2841
Agency Call List		
Lea County (575)	Hobbs	
	Lea County Communication Authority	393-3981
	State Police	392-5588
	City Police	397-9265
	Sheriff's Office	393-2515
	Ambulance	911
	Fire Department	397-9308
	LEPC (Local Emergency Planning Committee)	393-2870
	NMOCD	393-6161
	US Bureau of Land Management	393-3612
Eddy County (575)	Carlsbad	
	State Police	885-3137
	City Police	885-2111
	Sheriff's Office	887-7551
	Ambulance	911
	Fire Department	885-3125
	LEPC (Local Emergency Planning Committee)	887-3798
	US Bureau of Land Management	887-6544
	NM Emergency Response Commission (Santa Fe)	(505) 476-9600
	24 HR	(505) 827-9126
	National Emergency Response Center	(800) 424-8802
	National Pollution Control Center: Direct	(703) 872-6000
	For Oil Spills	(800) 280-7118
	Emergency Services	
	Wild Well Control	(281) 784-4700
	Cudd Pressure Control	(915) 699-0139 (915) 563-3356
	Halliburton	(575) 746-2757
	B. J. Services	(575) 746-3569
Give GPS position:	Native Air – Emergency Helicopter – Hobbs	(575) 392-6429
	Flight For Life - Lubbock, TX	(806) 743-9911
	Aerocare - Lubbock, TX	(806) 747-8923
	Med Flight Air Amb - Albuquerque, NM	(575) 842-4433
	Lifeguard Air Med Svc. Albuquerque, NM	(800) 222-1222
	Poison Control (24/7)	(575) 272-3115
	Oil & Gas Pipeline 24 Hour Service	(800) 364-4366
	NOAA – Website - www.nhc.noaa.gov	

Prepared in conjunction with
Dave Small





Devon Energy Corp.
Eddy County, NM (NAD83)
Big Sinks Draw 25-24
711H
Prelim Plan
Rig TBD



RKB Elevation: GL 3332+KB 26' @ 3358.00usf (Rig TBD)

+N/-S	+E/-W	Northing	Easting	Latitude	Longitude	Slot
0.00	0.00	401246.61	725986.54	32.1017025	-103.7370139	

WELLBORE TARGET DETAILS (MAP CO-ORDINATES)

Name	TVD	+N/-S	+E/-W	Northing	Easting
BHL - BSD 711H	11838.00	7430.01	-676.33	408676.62	725310.21

SECTION DETAILS

Sec	MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	VSect	Target
1	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
2	4300.00	0.00	0.00	4300.00	0.00	0.00	0.00	0.00	
3	5038.41	7.38	255.02	5036.37	-12.28	-45.90	1.00	-12.14	
4	9568.28	7.38	255.02	9528.67	-162.72	-608.31	0.00	-160.92	
5	10306.69	0.00	0.00	10265.04	-175.00	-654.21	1.00	-173.06	
6	11306.69	0.00	0.00	11265.04	-175.00	-654.21	0.00	-173.06	
7	12206.69	90.00	359.83	11838.00	397.96	-655.88	10.00	399.90	
8	19238.78	90.00	359.83	11838.00	7430.01	-676.33	0.00	7431.98	BHL - BSD 711H

FORMATION TOP DETAILS

TVDPath	MDPath	Formation	DipAngle
933.00	933.00	Rustler	0.00
1253.00	1253.00	Salado	0.00
4303.00	4303.00	Base of Salt	0.00
4338.00	4338.00	Delaware	0.00
8348.00	8377.74	1st BSPG Lime	0.00
11673.00	11760.69	Wolfcamp	0.00
11838.00	12206.69	Wolfcamp 100	0.00

CASING DETAILS

No casing data is available

Map System: US State Plane 1983
Datum: North American Datum 1983
Ellipsoid: GRS 1980
Zone Name: New Mexico Eastern Zone



Local Origin: Well 711H, Grid North

Latitude: 32.1017025
Longitude: -103.7370139

Grid East: 725986.54
Grid North: 401246.61
Scale Factor: 1.000

Geomagnetic Model: HDGM
Sample Date: 01-Nov-17
Magnetic Declination: 6.82°
Dip Angle from Horizontal: 59.82°
Magnetic Field Strength: 47969.30nT

To convert a Magnetic Direction to a Grid Direction, Add 6.50°
To convert a Magnetic Direction to a True Direction, Add 6.82° East
To convert a True Direction to a Grid Direction, Subtract 0.32°



36" x 48"

Vertical Section at 359.83° (200 usf/in)



Pro Directional
Planning Report



Database: WellPlanner1
 Company: Devon Energy Corp.
 Project: Eddy County, NM (NAD83)
 Site: Big Sinks Draw 25-24
 Well: 711H
 Wellbore: OH
 Design: Prelim Plan

Local Co-ordinate Reference: Well 711H
 TVD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
 MD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature

Project	Eddy County, NM (NAD83)		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Eastern Zone		

Site	Big Sinks Draw 25-24				
Site Position:		Northing:	401,246.29 usft	Latitude:	32.1017026
From:	Map	Easting:	725,926.51 usft	Longitude:	-103.7372077
Position Uncertainty:	0.00 usft	Slot Radius:	13-3/16 "	Grid Convergence:	0.32 °

Well	711H					
Well Position	+N/-S	0.32 usft	Northing:	401,246.61 usft	Latitude:	32.1017025
	+E/-W	60.03 usft	Easting:	725,986.54 usft	Longitude:	-103.7370139
Position Uncertainty	0.00 usft		Wellhead Elevation:		Ground Level:	3,332.00 usft

Wellbore	OH				
Magnetics	Model Name	Sample Date	Declination (°)	Dip Angle (°)	Field Strength (nT)
	HDGM	11/1/2017	6.82	59.82	47,969.30

Design	Prelim Plan				
Audit Notes:					
Version:	Phase:	PLAN	Tie On Depth:	0.00	
Vertical Section:	Depth From (TVD) (usft)	+N/-S (usft)	+E/-W (usft)	Direction (°)	
	0.00	0.00	0.00	359.83	

Plan Survey Tool Program	Date	11/2/2017			
Depth From (usft)	Depth To (usft)	Survey (Wellbore)	Tool Name	Remarks	
1 0.00	19,238.78	Prelim Plan (OH)	MWD+HDGM OWSG MWD + HDGM		

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
4,300.00	0.00	0.00	4,300.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
5,038.41	7.38	255.02	5,036.37	-12.28	-45.90	1.00	1.00	0.00	255.02	
9,568.28	7.38	255.02	9,528.67	-162.72	-608.31	0.00	0.00	0.00	0.00	
10,306.69	0.00	0.00	10,265.04	-175.00	-654.21	1.00	-1.00	0.00	180.00	
11,306.69	0.00	0.00	11,265.04	-175.00	-654.21	0.00	0.00	0.00	0.00	
12,206.69	90.00	359.83	11,838.00	397.96	-655.88	10.00	10.00	-0.02	359.83	
19,238.78	90.00	359.83	11,838.00	7,430.01	-676.33	0.00	0.00	0.00	0.00	BHL - BSD 711H



Pro Directional
Planning Report



Database: WellPlanner1
 Company: Devon Energy Corp.
 Project: Eddy County, NM (NAD83)
 Site: Big Sinks Draw 25-24
 Well: 711H
 Wellbore: OH
 Design: Prelim Plan

Local Co-ordinate Reference: Well 711H
 TVD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
 MD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00	0.00
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00
600.00	0.00	0.00	600.00	0.00	0.00	0.00	0.00	0.00	0.00
700.00	0.00	0.00	700.00	0.00	0.00	0.00	0.00	0.00	0.00
800.00	0.00	0.00	800.00	0.00	0.00	0.00	0.00	0.00	0.00
900.00	0.00	0.00	900.00	0.00	0.00	0.00	0.00	0.00	0.00
933.00	0.00	0.00	933.00	0.00	0.00	0.00	0.00	0.00	0.00
Rustler									
1,000.00	0.00	0.00	1,000.00	0.00	0.00	0.00	0.00	0.00	0.00
1,100.00	0.00	0.00	1,100.00	0.00	0.00	0.00	0.00	0.00	0.00
1,200.00	0.00	0.00	1,200.00	0.00	0.00	0.00	0.00	0.00	0.00
1,253.00	0.00	0.00	1,253.00	0.00	0.00	0.00	0.00	0.00	0.00
Salado									
1,300.00	0.00	0.00	1,300.00	0.00	0.00	0.00	0.00	0.00	0.00
1,400.00	0.00	0.00	1,400.00	0.00	0.00	0.00	0.00	0.00	0.00
1,500.00	0.00	0.00	1,500.00	0.00	0.00	0.00	0.00	0.00	0.00
1,600.00	0.00	0.00	1,600.00	0.00	0.00	0.00	0.00	0.00	0.00
1,700.00	0.00	0.00	1,700.00	0.00	0.00	0.00	0.00	0.00	0.00
1,800.00	0.00	0.00	1,800.00	0.00	0.00	0.00	0.00	0.00	0.00
1,900.00	0.00	0.00	1,900.00	0.00	0.00	0.00	0.00	0.00	0.00
2,000.00	0.00	0.00	2,000.00	0.00	0.00	0.00	0.00	0.00	0.00
2,100.00	0.00	0.00	2,100.00	0.00	0.00	0.00	0.00	0.00	0.00
2,200.00	0.00	0.00	2,200.00	0.00	0.00	0.00	0.00	0.00	0.00
2,300.00	0.00	0.00	2,300.00	0.00	0.00	0.00	0.00	0.00	0.00
2,400.00	0.00	0.00	2,400.00	0.00	0.00	0.00	0.00	0.00	0.00
2,500.00	0.00	0.00	2,500.00	0.00	0.00	0.00	0.00	0.00	0.00
2,600.00	0.00	0.00	2,600.00	0.00	0.00	0.00	0.00	0.00	0.00
2,700.00	0.00	0.00	2,700.00	0.00	0.00	0.00	0.00	0.00	0.00
2,800.00	0.00	0.00	2,800.00	0.00	0.00	0.00	0.00	0.00	0.00
2,900.00	0.00	0.00	2,900.00	0.00	0.00	0.00	0.00	0.00	0.00
3,000.00	0.00	0.00	3,000.00	0.00	0.00	0.00	0.00	0.00	0.00
3,100.00	0.00	0.00	3,100.00	0.00	0.00	0.00	0.00	0.00	0.00
3,200.00	0.00	0.00	3,200.00	0.00	0.00	0.00	0.00	0.00	0.00
3,300.00	0.00	0.00	3,300.00	0.00	0.00	0.00	0.00	0.00	0.00
3,400.00	0.00	0.00	3,400.00	0.00	0.00	0.00	0.00	0.00	0.00
3,500.00	0.00	0.00	3,500.00	0.00	0.00	0.00	0.00	0.00	0.00
3,600.00	0.00	0.00	3,600.00	0.00	0.00	0.00	0.00	0.00	0.00
3,700.00	0.00	0.00	3,700.00	0.00	0.00	0.00	0.00	0.00	0.00
3,800.00	0.00	0.00	3,800.00	0.00	0.00	0.00	0.00	0.00	0.00
3,900.00	0.00	0.00	3,900.00	0.00	0.00	0.00	0.00	0.00	0.00
4,000.00	0.00	0.00	4,000.00	0.00	0.00	0.00	0.00	0.00	0.00
4,100.00	0.00	0.00	4,100.00	0.00	0.00	0.00	0.00	0.00	0.00
4,200.00	0.00	0.00	4,200.00	0.00	0.00	0.00	0.00	0.00	0.00
4,300.00	0.00	0.00	4,300.00	0.00	0.00	0.00	0.00	0.00	0.00
Start Build 1.00									
4,303.00	0.03	255.02	4,303.00	0.00	0.00	0.00	1.00	1.00	0.00
Base of Salt									
4,338.00	0.38	255.02	4,338.00	-0.03	-0.12	-0.03	1.00	1.00	0.00
Delaware									



Pro Directional
Planning Report



Database: WellPlanner1
 Company: Devon Energy Corp.
 Project: Eddy County, NM (NAD83)
 Site: Big Sinks Draw 25-24
 Well: 711H
 Wellbore: OH
 Design: Prelim Plan

Local Co-ordinate Reference: Well 711H
 TVD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
 MD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
4,400.00	1.00	255.02	4,400.00	-0.23	-0.84	-0.22	1.00	1.00	0.00
4,500.00	2.00	255.02	4,499.96	-0.90	-3.37	-0.89	1.00	1.00	0.00
4,600.00	3.00	255.02	4,599.86	-2.03	-7.59	-2.01	1.00	1.00	0.00
4,700.00	4.00	255.02	4,699.68	-3.61	-13.48	-3.57	1.00	1.00	0.00
4,800.00	5.00	255.02	4,799.37	-5.63	-21.06	-5.57	1.00	1.00	0.00
4,900.00	6.00	255.02	4,898.90	-8.11	-30.32	-8.02	1.00	1.00	0.00
5,000.00	7.00	255.02	4,998.26	-11.04	-41.26	-10.91	1.00	1.00	0.00
5,038.41	7.38	255.02	5,036.37	-12.28	-45.90	-12.14	1.00	1.00	0.00
Start 4529.88 hold at 5038.41 MD									
5,100.00	7.38	255.02	5,097.45	-14.32	-53.55	-14.17	0.00	0.00	0.00
5,200.00	7.38	255.02	5,196.62	-17.65	-65.96	-17.45	0.00	0.00	0.00
5,300.00	7.38	255.02	5,295.79	-20.97	-78.38	-20.73	0.00	0.00	0.00
5,400.00	7.38	255.02	5,394.96	-24.29	-90.80	-24.02	0.00	0.00	0.00
5,500.00	7.38	255.02	5,494.13	-27.61	-103.21	-27.30	0.00	0.00	0.00
5,600.00	7.38	255.02	5,593.30	-30.93	-115.63	-30.59	0.00	0.00	0.00
5,700.00	7.38	255.02	5,692.47	-34.25	-128.04	-33.87	0.00	0.00	0.00
5,800.00	7.38	255.02	5,791.64	-37.57	-140.46	-37.16	0.00	0.00	0.00
5,900.00	7.38	255.02	5,890.81	-40.89	-152.87	-40.44	0.00	0.00	0.00
6,000.00	7.38	255.02	5,989.98	-44.21	-165.29	-43.72	0.00	0.00	0.00
6,100.00	7.38	255.02	6,089.15	-47.54	-177.70	-47.01	0.00	0.00	0.00
6,200.00	7.38	255.02	6,188.32	-50.86	-190.12	-50.29	0.00	0.00	0.00
6,300.00	7.38	255.02	6,287.50	-54.18	-202.53	-53.58	0.00	0.00	0.00
6,400.00	7.38	255.02	6,386.67	-57.50	-214.95	-56.86	0.00	0.00	0.00
6,500.00	7.38	255.02	6,485.84	-60.82	-227.37	-60.15	0.00	0.00	0.00
6,600.00	7.38	255.02	6,585.01	-64.14	-239.78	-63.43	0.00	0.00	0.00
6,700.00	7.38	255.02	6,684.18	-67.46	-252.20	-66.71	0.00	0.00	0.00
6,800.00	7.38	255.02	6,783.35	-70.78	-264.61	-70.00	0.00	0.00	0.00
6,900.00	7.38	255.02	6,882.52	-74.10	-277.03	-73.28	0.00	0.00	0.00
7,000.00	7.38	255.02	6,981.69	-77.43	-289.44	-76.57	0.00	0.00	0.00
7,100.00	7.38	255.02	7,080.86	-80.75	-301.86	-79.85	0.00	0.00	0.00
7,200.00	7.38	255.02	7,180.03	-84.07	-314.27	-83.13	0.00	0.00	0.00
7,300.00	7.38	255.02	7,279.20	-87.39	-326.69	-86.42	0.00	0.00	0.00
7,400.00	7.38	255.02	7,378.37	-90.71	-339.11	-89.70	0.00	0.00	0.00
7,500.00	7.38	255.02	7,477.54	-94.03	-351.52	-92.99	0.00	0.00	0.00
7,600.00	7.38	255.02	7,576.71	-97.35	-363.94	-96.27	0.00	0.00	0.00
7,700.00	7.38	255.02	7,675.88	-100.67	-376.35	-99.56	0.00	0.00	0.00
7,800.00	7.38	255.02	7,775.06	-103.99	-388.77	-102.84	0.00	0.00	0.00
7,900.00	7.38	255.02	7,874.23	-107.32	-401.18	-106.12	0.00	0.00	0.00
8,000.00	7.38	255.02	7,973.40	-110.64	-413.60	-109.41	0.00	0.00	0.00
8,100.00	7.38	255.02	8,072.57	-113.96	-426.01	-112.69	0.00	0.00	0.00
8,200.00	7.38	255.02	8,171.74	-117.28	-438.43	-115.98	0.00	0.00	0.00
8,300.00	7.38	255.02	8,270.91	-120.60	-450.84	-119.26	0.00	0.00	0.00
8,377.74	7.38	255.02	8,348.00	-123.18	-460.50	-121.81	0.00	0.00	0.00
1st BSPG Lime									
8,400.00	7.38	255.02	8,370.08	-123.92	-463.26	-122.55	0.00	0.00	0.00
8,500.00	7.38	255.02	8,469.25	-127.24	-475.68	-125.83	0.00	0.00	0.00
8,600.00	7.38	255.02	8,568.42	-130.56	-488.09	-129.11	0.00	0.00	0.00
8,700.00	7.38	255.02	8,667.59	-133.88	-500.51	-132.40	0.00	0.00	0.00
8,800.00	7.38	255.02	8,766.76	-137.21	-512.92	-135.68	0.00	0.00	0.00
8,900.00	7.38	255.02	8,865.93	-140.53	-525.34	-138.97	0.00	0.00	0.00
9,000.00	7.38	255.02	8,965.10	-143.85	-537.75	-142.25	0.00	0.00	0.00
9,100.00	7.38	255.02	9,064.27	-147.17	-550.17	-145.54	0.00	0.00	0.00
9,200.00	7.38	255.02	9,163.45	-150.49	-562.58	-148.82	0.00	0.00	0.00
9,300.00	7.38	255.02	9,262.62	-153.81	-575.00	-152.10	0.00	0.00	0.00



Pro Directional
Planning Report



Database: WellPlanner1
Company: Devon Energy Corp.
Project: Eddy County, NM (NAD83)
Site: Big Sinks Draw 25-24
Well: 711H
Wellbore: OH
Design: Prelim Plan

Local Co-ordinate Reference: Well 711H
TVD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
MD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
North Reference: Grid
Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
9,400.00	7.38	255.02	9,361.79	-157.13	-587.41	-155.39	0.00	0.00	0.00
9,500.00	7.38	255.02	9,460.96	-160.45	-599.83	-158.67	0.00	0.00	0.00
9,568.28	7.38	255.02	9,528.67	-162.72	-608.31	-160.92	0.00	0.00	0.00
Start Drop -1.00									
9,600.00	7.07	255.02	9,560.14	-163.75	-612.16	-161.94	1.00	-1.00	0.00
9,700.00	6.07	255.02	9,659.48	-166.71	-623.21	-164.86	1.00	-1.00	0.00
9,800.00	5.07	255.02	9,759.01	-169.21	-632.58	-167.34	1.00	-1.00	0.00
9,900.00	4.07	255.02	9,858.69	-171.27	-640.27	-169.37	1.00	-1.00	0.00
10,000.00	3.07	255.02	9,958.50	-172.88	-646.28	-170.96	1.00	-1.00	0.00
10,100.00	2.07	255.02	10,058.39	-174.04	-650.61	-172.11	1.00	-1.00	0.00
10,200.00	1.07	255.02	10,158.35	-174.74	-653.25	-172.80	1.00	-1.00	0.00
10,306.69	0.00	0.00	10,265.04	-175.00	-654.21	-173.06	1.00	-1.00	0.00
Start 1000.00 hold at 10306.69 MD									
10,400.00	0.00	0.00	10,358.35	-175.00	-654.21	-173.06	0.00	0.00	0.00
10,500.00	0.00	0.00	10,458.35	-175.00	-654.21	-173.06	0.00	0.00	0.00
10,600.00	0.00	0.00	10,558.35	-175.00	-654.21	-173.06	0.00	0.00	0.00
10,700.00	0.00	0.00	10,658.35	-175.00	-654.21	-173.06	0.00	0.00	0.00
10,800.00	0.00	0.00	10,758.35	-175.00	-654.21	-173.06	0.00	0.00	0.00
10,900.00	0.00	0.00	10,858.35	-175.00	-654.21	-173.06	0.00	0.00	0.00
11,000.00	0.00	0.00	10,958.35	-175.00	-654.21	-173.06	0.00	0.00	0.00
11,100.00	0.00	0.00	11,058.35	-175.00	-654.21	-173.06	0.00	0.00	0.00
11,200.00	0.00	0.00	11,158.35	-175.00	-654.21	-173.06	0.00	0.00	0.00
11,306.69	0.00	0.00	11,265.04	-175.00	-654.21	-173.06	0.00	0.00	0.00
Start DLS 10.00 TFO 359.83									
11,350.00	4.33	359.83	11,308.31	-173.36	-654.21	-171.42	10.00	10.00	0.00
11,400.00	9.33	359.83	11,357.94	-167.42	-654.23	-165.48	10.00	10.00	0.00
11,450.00	14.33	359.83	11,406.86	-157.17	-654.26	-155.23	10.00	10.00	0.00
11,500.00	19.33	359.83	11,454.70	-142.70	-654.30	-140.76	10.00	10.00	0.00
11,550.00	24.33	359.83	11,501.10	-124.11	-654.36	-122.17	10.00	10.00	0.00
11,600.00	29.33	359.83	11,545.70	-101.55	-654.42	-99.61	10.00	10.00	0.00
11,650.00	34.33	359.83	11,588.17	-75.19	-654.50	-73.25	10.00	10.00	0.00
11,700.00	39.33	359.83	11,628.18	-45.23	-654.59	-43.28	10.00	10.00	0.00
11,750.00	44.33	359.83	11,665.42	-11.89	-654.68	-9.95	10.00	10.00	0.00
11,760.69	45.40	359.83	11,673.00	-4.35	-654.71	-2.41	10.00	10.00	0.00
Wolfcamp									
11,800.00	49.33	359.83	11,699.62	24.57	-654.79	26.51	10.00	10.00	0.00
11,850.00	54.33	359.83	11,730.51	63.86	-654.90	65.81	10.00	10.00	0.00
11,900.00	59.33	359.83	11,757.86	105.70	-655.03	107.65	10.00	10.00	0.00
11,950.00	64.33	359.83	11,781.45	149.77	-655.15	151.71	10.00	10.00	0.00
12,000.00	69.33	359.83	11,801.12	195.72	-655.29	197.66	10.00	10.00	0.00
12,050.00	74.33	359.83	11,816.71	243.21	-655.43	245.15	10.00	10.00	0.00
12,100.00	79.33	359.83	11,828.09	291.88	-655.57	293.82	10.00	10.00	0.00
12,150.00	84.33	359.83	11,835.20	341.36	-655.71	343.30	10.00	10.00	0.00
12,200.00	89.33	359.83	11,837.96	391.26	-655.86	393.21	10.00	10.00	0.00
12,206.69	90.00	359.83	11,838.00	397.96	-655.88	399.90	10.00	10.00	0.00
Start 7032.08 hold at 12206.69 MD - Wolfcamp 100									
12,300.00	90.00	359.83	11,838.00	491.26	-656.15	493.21	0.00	0.00	0.00
12,400.00	90.00	359.83	11,838.00	591.26	-656.44	593.21	0.00	0.00	0.00
12,500.00	90.00	359.83	11,838.00	691.26	-656.73	693.21	0.00	0.00	0.00
12,600.00	90.00	359.83	11,838.00	791.26	-657.02	793.21	0.00	0.00	0.00
12,700.00	90.00	359.83	11,838.00	891.26	-657.31	893.21	0.00	0.00	0.00
12,800.00	90.00	359.83	11,838.00	991.26	-657.60	993.21	0.00	0.00	0.00
12,900.00	90.00	359.83	11,838.00	1,091.26	-657.89	1,093.21	0.00	0.00	0.00



Pro Directional
Planning Report



Database: WellPlanner1
Company: Devon Energy Corp.
Project: Eddy County, NM (NAD83)
Site: Big Sinks Draw 25-24
Well: 711H
Wellbore: OH
Design: Prelim Plan

Local Co-ordinate Reference: Well 711H
TVD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
MD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
North Reference: Grid
Survey Calculation Method: Minimum Curvature

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
13,000.00	90.00	359.83	11,838.00	1,191.26	-658.18	1,193.21	0.00	0.00	0.00
13,100.00	90.00	359.83	11,838.00	1,291.26	-658.47	1,293.21	0.00	0.00	0.00
13,200.00	90.00	359.83	11,838.00	1,391.26	-658.77	1,393.21	0.00	0.00	0.00
13,300.00	90.00	359.83	11,838.00	1,491.26	-659.06	1,493.21	0.00	0.00	0.00
13,400.00	90.00	359.83	11,838.00	1,591.26	-659.35	1,593.21	0.00	0.00	0.00
13,500.00	90.00	359.83	11,838.00	1,691.26	-659.64	1,693.21	0.00	0.00	0.00
13,600.00	90.00	359.83	11,838.00	1,791.26	-659.93	1,793.21	0.00	0.00	0.00
13,700.00	90.00	359.83	11,838.00	1,891.26	-660.22	1,893.21	0.00	0.00	0.00
13,800.00	90.00	359.83	11,838.00	1,991.26	-660.51	1,993.21	0.00	0.00	0.00
13,900.00	90.00	359.83	11,838.00	2,091.26	-660.80	2,093.21	0.00	0.00	0.00
14,000.00	90.00	359.83	11,838.00	2,191.26	-661.09	2,193.21	0.00	0.00	0.00
14,100.00	90.00	359.83	11,838.00	2,291.26	-661.38	2,293.21	0.00	0.00	0.00
14,200.00	90.00	359.83	11,838.00	2,391.26	-661.67	2,393.21	0.00	0.00	0.00
14,288.00	90.00	359.83	11,838.00	2,479.26	-661.93	2,481.21	0.00	0.00	0.00
32.1085276, -103.7391073 - 14288' MD, 11838' TVD - Entering NMM125634									
14,300.00	90.00	359.83	11,838.00	2,491.26	-661.97	2,493.21	0.00	0.00	0.00
14,400.00	90.00	359.83	11,838.00	2,591.25	-662.26	2,593.21	0.00	0.00	0.00
14,500.00	90.00	359.83	11,838.00	2,691.25	-662.55	2,693.21	0.00	0.00	0.00
14,600.00	90.00	359.83	11,838.00	2,791.25	-662.84	2,793.21	0.00	0.00	0.00
14,700.00	90.00	359.83	11,838.00	2,891.25	-663.13	2,893.21	0.00	0.00	0.00
14,800.00	90.00	359.83	11,838.00	2,991.25	-663.42	2,993.21	0.00	0.00	0.00
14,900.00	90.00	359.83	11,838.00	3,091.25	-663.71	3,093.21	0.00	0.00	0.00
15,000.00	90.00	359.83	11,838.00	3,191.25	-664.00	3,193.21	0.00	0.00	0.00
15,100.00	90.00	359.83	11,838.00	3,291.25	-664.29	3,293.21	0.00	0.00	0.00
15,200.00	90.00	359.83	11,838.00	3,391.25	-664.58	3,393.21	0.00	0.00	0.00
15,300.00	90.00	359.83	11,838.00	3,491.25	-664.87	3,493.21	0.00	0.00	0.00
15,400.00	90.00	359.83	11,838.00	3,591.25	-665.16	3,593.21	0.00	0.00	0.00
15,500.00	90.00	359.83	11,838.00	3,691.25	-665.46	3,693.21	0.00	0.00	0.00
15,600.00	90.00	359.83	11,838.00	3,791.25	-665.75	3,793.21	0.00	0.00	0.00
15,700.00	90.00	359.83	11,838.00	3,891.25	-666.04	3,893.21	0.00	0.00	0.00
15,800.00	90.00	359.83	11,838.00	3,991.25	-666.33	3,993.21	0.00	0.00	0.00
15,900.00	90.00	359.83	11,838.00	4,091.25	-666.62	4,093.21	0.00	0.00	0.00
16,000.00	90.00	359.83	11,838.00	4,191.25	-666.91	4,193.21	0.00	0.00	0.00
16,100.00	90.00	359.83	11,838.00	4,291.25	-667.20	4,293.21	0.00	0.00	0.00
16,200.00	90.00	359.83	11,838.00	4,391.25	-667.49	4,393.21	0.00	0.00	0.00
16,300.00	90.00	359.83	11,838.00	4,491.25	-667.78	4,493.21	0.00	0.00	0.00
16,400.00	90.00	359.83	11,838.00	4,591.25	-668.07	4,593.21	0.00	0.00	0.00
16,500.00	90.00	359.83	11,838.00	4,691.25	-668.36	4,693.21	0.00	0.00	0.00
16,600.00	90.00	359.83	11,838.00	4,791.25	-668.65	4,793.21	0.00	0.00	0.00
16,700.00	90.00	359.83	11,838.00	4,891.24	-668.95	4,893.21	0.00	0.00	0.00
16,800.00	90.00	359.83	11,838.00	4,991.24	-669.24	4,993.21	0.00	0.00	0.00
16,900.00	90.00	359.83	11,838.00	5,091.24	-669.53	5,093.21	0.00	0.00	0.00
16,928.00	90.00	359.83	11,838.00	5,119.24	-669.61	5,121.21	0.00	0.00	0.00
32.1157845, -103.7390851 - 16928' MD, 11838' TVD, 330' FWL - Entering NMLC061869									
17,000.00	90.00	359.83	11,838.00	5,191.24	-669.82	5,193.21	0.00	0.00	0.00
17,100.00	90.00	359.83	11,838.00	5,291.24	-670.11	5,293.21	0.00	0.00	0.00
17,200.00	90.00	359.83	11,838.00	5,391.24	-670.40	5,393.21	0.00	0.00	0.00
17,300.00	90.00	359.83	11,838.00	5,491.24	-670.69	5,493.21	0.00	0.00	0.00
17,400.00	90.00	359.83	11,838.00	5,591.24	-670.98	5,593.21	0.00	0.00	0.00
17,500.00	90.00	359.83	11,838.00	5,691.24	-671.27	5,693.21	0.00	0.00	0.00
17,600.00	90.00	359.83	11,838.00	5,791.24	-671.56	5,793.21	0.00	0.00	0.00
17,700.00	90.00	359.83	11,838.00	5,891.24	-671.85	5,893.21	0.00	0.00	0.00
17,800.00	90.00	359.83	11,838.00	5,991.24	-672.15	5,993.21	0.00	0.00	0.00
17,900.00	90.00	359.83	11,838.00	6,091.24	-672.44	6,093.21	0.00	0.00	0.00



Pro Directional
Planning Report



Database: WellPlanner1
Company: Devon Energy Corp.
Project: Eddy County, NM (NAD83)
Site: Big Sinks Draw 25-24
Well: 711H
Wellbore: OH
Design: Prelim Plan

Local Co-ordinate Reference: Well 711H
TVD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
MD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
North Reference: Grid
Survey Calculation Method: Minimum Curvature

Planned Survey

Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
18,000.00	90.00	359.83	11,838.00	6,191.24	-672.73	6,193.21	0.00	0.00	0.00
18,100.00	90.00	359.83	11,838.00	6,291.24	-673.02	6,293.21	0.00	0.00	0.00
18,200.00	90.00	359.83	11,838.00	6,391.24	-673.31	6,393.21	0.00	0.00	0.00
18,300.00	90.00	359.83	11,838.00	6,491.24	-673.60	6,493.21	0.00	0.00	0.00
18,400.00	90.00	359.83	11,838.00	6,591.24	-673.89	6,593.21	0.00	0.00	0.00
18,500.00	90.00	359.83	11,838.00	6,691.24	-674.18	6,693.21	0.00	0.00	0.00
18,600.00	90.00	359.83	11,838.00	6,791.24	-674.47	6,793.21	0.00	0.00	0.00
18,700.00	90.00	359.83	11,838.00	6,891.24	-674.76	6,893.21	0.00	0.00	0.00
18,800.00	90.00	359.83	11,838.00	6,991.24	-675.05	6,993.21	0.00	0.00	0.00
18,900.00	90.00	359.83	11,838.00	7,091.24	-675.34	7,093.21	0.00	0.00	0.00
19,000.00	90.00	359.83	11,838.00	7,191.24	-675.64	7,193.21	0.00	0.00	0.00
19,100.00	90.00	359.83	11,838.00	7,291.23	-675.93	7,293.21	0.00	0.00	0.00
19,200.00	90.00	359.83	11,838.00	7,391.23	-676.22	7,393.21	0.00	0.00	0.00
19,238.78	90.00	359.83	11,838.00	7,430.01	-676.33	7,431.98	0.00	0.00	0.00
TD at 19238.78									

Formations

Measured Depth (usft)	Vertical Depth (usft)	Name	Lithology	Dip (°)	Dip Direction (°)
933.00	933.00	Rustler		0.00	
1,253.00	1,253.00	Salado		0.00	
4,303.00	4,303.00	Base of Salt		0.00	
4,338.00	4,338.00	Delaware		0.00	
8,377.74	8,348.00	1st BSPG Lime		0.00	
11,760.69	11,673.00	Wolfcamp		0.00	
12,206.69	11,838.00	Wolfcamp 100		0.00	

Plan Annotations

Measured Depth (usft)	Vertical Depth (usft)	Local Coordinates		Comment
		+N/-S (usft)	+E/-W (usft)	
4,300.00	4,300.00	0.00	0.00	Start Build 1.00
5,038.41	5,036.37	-12.28	-45.90	Start 4529.88 hold at 5038.41 MD
9,568.28	9,528.67	-162.72	-608.31	Start Drop -1.00
10,306.69	10,265.04	-175.00	-654.21	Start 1000.00 hold at 10306.69 MD
11,306.69	11,265.04	-175.00	-654.21	Start DLS 10.00 TFO 359.83
12,206.69	11,838.00	397.96	-655.88	Start 7032.08 hold at 12206.69 MD
14,288.00	11,838.00	2,479.26	-661.93	32.1085276, -103.7391073
14,288.00	11,838.00	2,479.26	-661.93	14288' MD, 11838' TVD
14,288.00	11,838.00	2,479.26	-661.93	Entering NMNM125634
16,928.00	11,838.00	5,119.24	-669.61	32.1157845, -103.7390851
16,928.00	11,838.00	5,119.24	-669.61	16928' MD, 11838' TVD, 330' FWL
16,928.00	11,838.00	5,119.24	-669.61	Entering NMLC061869
19,238.78	11,838.00	7,430.01	-676.33	TD at 19238.78

Client.....: Devon Energy Corp.
 Location.....: Eddy County, NM (NAD83)
 Site.....: Big Sinks Draw 25-24
 Well.....: 711H

--- Depth reference ---
 Permanent datum.....: Mean Sea Level
 Depth reference.....: GL 3332'+KB 26'
 GL above permanent.....: 3332.00 usft
 KB above permanent.....: 3358.00 usft

--- Surface Location ---
 Northing (+N/S).....: 401246.61 usft
 Easting (+E/W).....: 725986.54 usft

MD	Inc	Azimuth	TVD	Subsea	N/S	E/W	VS	DLS	X	Y	Latitude	Longitude	Comments
0	0	0	0	3358	0	0	0	0	725986.5	401246.6	32.102	-103.737	
100	0	0	100	3258	0	0	0	0	725986.5	401246.6	32.102	-103.737	
200	0	0	200	3158	0	0	0	0	725986.5	401246.6	32.102	-103.737	
300	0	0	300	3058	0	0	0	0	725986.5	401246.6	32.102	-103.737	
400	0	0	400	2958	0	0	0	0	725986.5	401246.6	32.102	-103.737	
500	0	0	500	2858	0	0	0	0	725986.5	401246.6	32.102	-103.737	
600	0	0	600	2758	0	0	0	0	725986.5	401246.6	32.102	-103.737	
700	0	0	700	2658	0	0	0	0	725986.5	401246.6	32.102	-103.737	
800	0	0	800	2558	0	0	0	0	725986.5	401246.6	32.102	-103.737	
900	0	0	900	2458	0	0	0	0	725986.5	401246.6	32.102	-103.737	
1000	0	0	1000	2358	0	0	0	0	725986.5	401246.6	32.102	-103.737	
1100	0	0	1100	2258	0	0	0	0	725986.5	401246.6	32.102	-103.737	
1200	0	0	1200	2158	0	0	0	0	725986.5	401246.6	32.102	-103.737	
1300	0	0	1300	2058	0	0	0	0	725986.5	401246.6	32.102	-103.737	
1400	0	0	1400	1958	0	0	0	0	725986.5	401246.6	32.102	-103.737	
1500	0	0	1500	1858	0	0	0	0	725986.5	401246.6	32.102	-103.737	
1600	0	0	1600	1758	0	0	0	0	725986.5	401246.6	32.102	-103.737	
1700	0	0	1700	1658	0	0	0	0	725986.5	401246.6	32.102	-103.737	
1800	0	0	1800	1558	0	0	0	0	725986.5	401246.6	32.102	-103.737	
1900	0	0	1900	1458	0	0	0	0	725986.5	401246.6	32.102	-103.737	
2000	0	0	2000	1358	0	0	0	0	725986.5	401246.6	32.102	-103.737	
2100	0	0	2100	1258	0	0	0	0	725986.5	401246.6	32.102	-103.737	
2200	0	0	2200	1158	0	0	0	0	725986.5	401246.6	32.102	-103.737	
2300	0	0	2300	1058	0	0	0	0	725986.5	401246.6	32.102	-103.737	
2400	0	0	2400	958	0	0	0	0	725986.5	401246.6	32.102	-103.737	
2500	0	0	2500	858	0	0	0	0	725986.5	401246.6	32.102	-103.737	
2600	0	0	2600	758	0	0	0	0	725986.5	401246.6	32.102	-103.737	
2700	0	0	2700	658	0	0	0	0	725986.5	401246.6	32.102	-103.737	
2800	0	0	2800	558	0	0	0	0	725986.5	401246.6	32.102	-103.737	
2900	0	0	2900	458	0	0	0	0	725986.5	401246.6	32.102	-103.737	
3000	0	0	3000	358	0	0	0	0	725986.5	401246.6	32.102	-103.737	
3100	0	0	3100	258	0	0	0	0	725986.5	401246.6	32.102	-103.737	
3200	0	0	3200	158	0	0	0	0	725986.5	401246.6	32.102	-103.737	
3300	0	0	3300	58	0	0	0	0	725986.5	401246.6	32.102	-103.737	
3400	0	0	3400	-42	0	0	0	0	725986.5	401246.6	32.102	-103.737	
3500	0	0	3500	-142	0	0	0	0	725986.5	401246.6	32.102	-103.737	
3600	0	0	3600	-242	0	0	0	0	725986.5	401246.6	32.102	-103.737	
3700	0	0	3700	-342	0	0	0	0	725986.5	401246.6	32.102	-103.737	
3800	0	0	3800	-442	0	0	0	0	725986.5	401246.6	32.102	-103.737	
3900	0	0	3900	-542	0	0	0	0	725986.5	401246.6	32.102	-103.737	
4000	0	0	4000	-642	0	0	0	0	725986.5	401246.6	32.102	-103.737	
4100	0	0	4100	-742	0	0	0	0	725986.5	401246.6	32.102	-103.737	
4200	0	0	4200	-842	0	0	0	0	725986.5	401246.6	32.102	-103.737	
4300	0	0	4300	-942	0	0	0	0	725986.5	401246.6	32.102	-103.737	Start Build 1.00
4400	1	255.02	4399.99	-1041.99	-0.23	-0.84	-0.22	1	725985.7	401246.4	32.102	-103.737	
4500	2	255.02	4499.96	-1141.96	-0.9	-3.37	-0.89	1	725983.2	401245.7	32.102	-103.737	
4600	3	255.02	4599.86	-1241.86	-2.03	-7.59	-2.01	1	725979	401244.6	32.102	-103.737	
4700	4	255.02	4699.68	-1341.68	-3.61	-13.48	-3.57	1	725973.1	401243	32.102	-103.737	
4800	5	255.02	4799.37	-1441.37	-5.63	-21.06	-5.57	1	725965.5	401241	32.102	-103.737	
4900	6	255.02	4898.9	-1540.9	-8.11	-30.32	-8.02	1	725956.2	401238.5	32.102	-103.737	
5000	7	255.02	4998.26	-1640.26	-11.04	-41.26	-10.91	1	725945.3	401235.6	32.102	-103.737	
5038.41	7.38	255.02	5036.37	-1678.37	-12.28	-45.9	-12.14	1	725940.6	401234.3	32.102	-103.737	Start 4529.88 hold at 5038.41 MD
5100	7.38	255.02	5097.45	-1739.45	-14.32	-53.55	-14.17	0	725933	401232.3	32.102	-103.737	
5200	7.38	255.02	5196.62	-1838.62	-17.65	-65.96	-17.45	0	725920.6	401229	32.102	-103.737	
5300	7.38	255.02	5295.79	-1937.79	-20.97	-78.38	-20.73	0	725908.2	401225.6	32.102	-103.737	
5400	7.38	255.02	5394.96	-2036.96	-24.29	-90.8	-24.02	0	725895.7	401222.3	32.102	-103.737	
5500	7.38	255.02	5494.13	-2136.13	-27.61	-103.21	-27.3	0	725883.3	401219	32.102	-103.737	
5600	7.38	255.02	5593.3	-2235.3	-30.93	-115.63	-30.59	0	725870.9	401215.7	32.102	-103.737	
5700	7.38	255.02	5692.47	-2334.47	-34.25	-128.04	-33.87	0	725858.5	401212.4	32.102	-103.737	
5800	7.38	255.02	5791.64	-2433.64	-37.57	-140.46	-37.16	0	725846.1	401209	32.102	-103.737	
5900	7.38	255.02	5890.81	-2532.81	-40.89	-152.87	-40.44	0	725833.7	401205.7	32.102	-103.738	
6000	7.38	255.02	5989.98	-2631.98	-44.21	-165.29	-43.72	0	725821.3	401202.4	32.102	-103.738	
6100	7.38	255.02	6089.15	-2731.15	-47.54	-177.7	-47.01	0	725808.8	401199.1	32.102	-103.738	
6200	7.38	255.02	6188.32	-2830.32	-50.86	-190.12	-50.29	0	725796.4	401195.8	32.102	-103.738	
6300	7.38	255.02	6287.5	-2929.5	-54.18	-202.53	-53.58	0	725784	401192.4	32.102	-103.738	
6400	7.38	255.02	6386.67	-3028.67	-57.5	-214.95	-56.86	0	725771.6	401189.1	32.102	-103.738	
6500	7.38	255.02	6485.84	-3127.84	-60.82	-227.37	-60.15	0	725759.2	401185.8	32.102	-103.738	
6600	7.38	255.02	6585.01	-3227.01	-64.14	-239.78	-63.43	0	725746.8	401182.5	32.102	-103.738	
6700	7.38	255.02	6684.18	-3326.18	-67.46	-252.2	-66.71	0	725734.3	401179.2	32.102	-103.738	
6800	7.38	255.02	6783.35	-3425.35	-70.78	-264.61	-70	0	725721.9	401175.8	32.102	-103.738	
6900	7.38	255.02	6882.52	-3524.52	-74.1	-277.03	-73.28	0	725709.5	401172.5	32.102	-103.738	
7000	7.38	255.02	6981.69	-3623.69	-77.43	-289.44	-76.57	0	725697.1	401169.2	32.101	-103.738	
7100	7.38	255.02	7080.86	-3722.86	-80.75	-301.86	-79.85	0	725684.7	401165.9	32.101	-103.738	
7200	7.38	255.02	7180.03	-3822.03	-84.07	-314.27	-83.13	0	725672.3	401162.5	32.101	-103.738	
7300	7.38	255.02	7279.2	-3921.2	-87.39	-326.69	-86.42	0	725659.9	401159.2	32.101	-103.738	
7400	7.38	255.02	7378.37	-4020.37	-90.71	-339.11	-89.7	0	725647.4	401155.9	32.101	-103.738	
7500	7.38	255.02	7477.54	-4119.54	-94.03	-351.52	-92.99	0	725635	401152.6	32.101	-103.738	
7600	7.38	255.02	7576.71	-4218.71	-97.35	-363.94	-96.27	0	725622.6	401149.3	32.101	-103.738	

7700	7.28	255.02	7575.88	-4317.88	-100.67	-376.35	99.56	0	725610.2	401145.9	32.101	-103.738
7800	7.28	255.02	7775.06	-4417.06	-103.99	-388.77	-102.84	0	725597.8	401142.6	32.101	-103.738
7900	7.28	255.02	7874.23	-4516.23	-107.32	-401.18	-106.12	0	725585.4	401139.3	32.101	-103.738
8000	7.28	255.02	7973.4	-4615.4	-110.64	-413.6	-109.41	0	725572.9	401136	32.101	-103.738
8100	7.28	255.02	8072.57	-4714.57	-113.96	-426.01	-112.69	0	725560.5	401132.7	32.101	-103.738
8200	7.28	255.02	8171.74	-4813.74	-117.28	-438.43	-115.98	0	725548.1	401129.3	32.101	-103.738
8300	7.28	255.02	8270.91	-4912.91	-120.6	-450.84	-119.26	0	725535.7	401126	32.101	-103.738
8400	7.28	255.02	8370.08	-5012.08	-123.92	-463.26	-122.55	0	725523.3	401122.7	32.101	-103.738
8500	7.28	255.02	8469.25	-5111.25	-127.24	-475.68	-125.83	0	725510.9	401119.4	32.101	-103.738
8600	7.28	255.02	8568.42	-5210.42	-130.56	-488.09	-129.11	0	725498.5	401116.1	32.101	-103.738
8700	7.28	255.02	8667.59	-5309.59	-133.88	-500.51	-132.4	0	725486.1	401112.7	32.101	-103.738
8800	7.28	255.02	8766.76	-5408.76	-137.21	-512.92	-135.68	0	725473.7	401109.4	32.101	-103.738
8900	7.28	255.02	8865.93	-5507.93	-140.53	-525.34	-138.97	0	725461.2	401106.1	32.101	-103.738
9000	7.28	255.02	8965.1	-5607.1	-143.85	-537.75	-142.25	0	725448.8	401102.8	32.101	-103.738
9100	7.28	255.02	9064.27	-5706.27	-147.17	-550.17	-145.54	0	725436.4	401099.4	32.101	-103.738
9200	7.28	255.02	9163.45	-5805.45	-150.49	-562.58	-148.82	0	725424.0	401096.1	32.101	-103.738
9300	7.28	255.02	9262.62	-5904.62	-153.81	-575	-152.1	0	725411.5	401092.8	32.101	-103.738
9400	7.28	255.02	9361.79	-6003.79	-157.13	-587.41	-155.39	0	725399.1	401089.5	32.101	-103.738
9500	7.28	255.02	9460.96	-6102.96	-160.45	-599.83	-158.67	0	725386.7	401086.2	32.101	-103.738
9600	7.28	255.02	9560.14	-6202.14	-163.78	-612.21	-161.94	0	725374.2	401082.9	32.101	-103.738
9700	6.07	255.02	9659.48	-6301.48	-166.71	-624.21	-164.86	1	725361.8	401079.4	32.101	-103.738
9800	5.07	255.02	9759.01	-6401.01	-169.21	-635.58	-167.34	1	725349.3	401075.3	32.101	-103.738
9900	4.07	255.02	9858.69	-6500.69	-171.27	-646.27	-169.37	1	725346.3	401071.6	32.101	-103.738
10000	3.07	255.02	9958.49	-6600.49	-172.88	-656.28	-170.96	1	725340.3	401073.7	32.101	-103.738
10100	2.07	255.02	10058.29	-6700.29	-174.04	-665.61	-172.11	1	725335.9	401072.6	32.101	-103.738
10200	1.07	255.02	10158.35	-6800.35	-174.74	-673.25	-172.8	1	725333.3	401071.9	32.101	-103.738
10300	0	0	10265.04	-6907.04	-175	-680.21	-173.06	0	725332.3	401071.6	32.101	-103.738
10400	0	0	10368.35	-7000.35	-175	-684.21	-173.06	0	725332.3	401071.6	32.101	-103.738
10500	0	0	10468.35	-7100.35	-175	-684.21	-173.06	0	725332.3	401071.6	32.101	-103.738
10600	0	0	10568.35	-7200.35	-175	-684.21	-173.06	0	725332.3	401071.6	32.101	-103.738
10700	0	0	10668.35	-7300.35	-175	-684.21	-173.06	0	725332.3	401071.6	32.101	-103.738
10800	0	0	10768.35	-7400.35	-175	-684.21	-173.06	0	725332.3	401071.6	32.101	-103.738
10900	0	0	10868.35	-7500.35	-175	-684.21	-173.06	0	725332.3	401071.6	32.101	-103.738
11000	0	0	10968.35	-7600.35	-175	-684.21	-173.06	0	725332.3	401071.6	32.101	-103.738
11100	0	0	11068.35	-7700.35	-175	-684.21	-173.06	0	725332.3	401071.6	32.101	-103.738
11200	0	0	11168.35	-7800.35	-175	-684.21	-173.06	0	725332.3	401071.6	32.101	-103.738
11300	0	0	11265.04	-7907.04	-175	-684.21	-173.06	0	725332.3	401071.6	32.101	-103.738
11400	4.33	359.83	11308.31	-7950.31	-173.36	-684.21	-173.06	10	725332.3	401073.3	32.101	-103.738
11500	9.33	359.83	11357.94	-7999.94	-167.42	-684.21	-165.48	10	725332.3	401079.2	32.101	-103.738
11600	14.33	359.83	11406.86	-8048.86	-157.17	-684.21	-155.33	10	725332.3	401084.4	32.101	-103.738
11700	19.33	359.83	11454.7	-8096.7	-142.7	-684.21	-140.76	10	725332.3	401103.9	32.101	-103.738
11800	24.33	359.83	11501.1	-8143.1	-124.11	-684.21	-122.17	10	725332.3	401122.5	32.101	-103.738
11900	29.33	359.83	11545.7	-8187.7	-101.55	-684.21	-99.61	10	725332.3	401145.1	32.101	-103.738
12000	34.33	359.83	11588.17	-8230.17	-75.19	-684.21	-73.25	10	725332.3	401171.4	32.101	-103.738
12100	39.33	359.83	11628.18	-8270.18	-45.23	-684.21	-43.28	10	725332.3	401201.4	32.101	-103.738
12200	44.33	359.83	11665.42	-8307.42	-11.89	-684.21	-9.85	10	725332.3	401234.7	32.101	-103.738
12300	49.33	359.83	11699.62	-8341.62	24.57	-684.21	26.51	10	725331.8	401271.2	32.101	-103.738
12400	54.33	359.83	11730.51	-8372.51	63.86	-684.21	65.81	10	725331.6	401310.5	32.101	-103.738
12500	59.33	359.83	11757.86	-8399.86	105.7	-684.21	107.65	10	725331.5	401352.3	32.101	-103.738
12600	64.33	359.83	11781.45	-8423.45	149.77	-684.21	151.71	10	725331.4	401396.4	32.101	-103.738
12700	69.33	359.83	11801.12	-8443.12	195.72	-684.21	195.66	10	725331.3	401442.3	32.101	-103.738
12800	74.33	359.83	11816.71	-8458.71	243.21	-684.21	245.15	10	725331.1	401489.8	32.101	-103.738
12900	79.33	359.83	11828.09	-8470.09	291.88	-684.21	293.82	10	725331	401538.5	32.101	-103.738
13000	84.33	359.83	11835.2	-8477.2	341.36	-684.21	343.3	10	725330.7	401588	32.101	-103.738
13100	89.33	359.83	11837.86	-8479.86	391.76	-684.21	393.21	10	725330.7	401637.9	32.101	-103.738
13200	94.33	359.83	11838	-8480	442.15	-684.21	445.1	10	725330.4	401684.6	32.101	-103.738
13300	99.33	359.83	11838	-8480	492.54	-684.21	495.21	0	725330.4	401737.9	32.101	-103.738
13400	104.33	359.83	11838	-8480	542.93	-684.21	548.21	0	725330.4	401797.9	32.101	-103.738
13500	109.33	359.83	11838	-8480	593.32	-684.21	599.3	0	725330.4	401867.9	32.101	-103.738
13600	114.33	359.83	11838	-8480	643.71	-684.21	650.3	0	725330.4	401937.9	32.101	-103.738
13700	119.33	359.83	11838	-8480	694.1	-684.21	701.3	0	725330.4	402007.9	32.101	-103.738
13800	124.33	359.83	11838	-8480	744.5	-684.21	751.7	0	725330.4	402077.9	32.101	-103.738
13900	129.33	359.83	11838	-8480	794.9	-684.21	802.1	0	725330.4	402147.9	32.101	-103.738
14000	134.33	359.83	11838	-8480	845.3	-684.21	852.5	0	725330.4	402217.9	32.101	-103.738
14100	139.33	359.83	11838	-8480	895.7	-684.21	902.9	0	725330.4	402287.9	32.101	-103.738
14200	144.33	359.83	11838	-8480	946.1	-684.21	953.3	0	725330.4	402357.9	32.101	-103.738
14300	149.33	359.83	11838	-8480	996.5	-684.21	1003.7	0	725330.4	402427.9	32.101	-103.738
14400	154.33	359.83	11838	-8480	1046.9	-684.21	1054.1	0	725330.4	402497.9	32.101	-103.738
14500	159.33	359.83	11838	-8480	1097.3	-684.21	1104.5	0	725330.4	402567.9	32.101	-103.738
14600	164.33	359.83	11838	-8480	1147.7	-684.21	1154.9	0	725330.4	402637.9	32.101	-103.738
14700	169.33	359.83	11838	-8480	1198.1	-684.21	1205.3	0	725330.4	402707.9	32.101	-103.738
14800	174.33	359.83	11838	-8480	1248.5	-684.21	1255.7	0	725330.4	402777.9	32.101	-103.738
14900	179.33	359.83	11838	-8480	1298.9	-684.21	1306.1	0	725330.4	402847.9	32.101	-103.738
15000	184.33	359.83	11838	-8480	1349.3	-684.21	1356.5	0	725330.4	402917.9	32.101	-103.738
15100	189.33	359.83	11838	-8480	1399.7	-684.21	1406.9	0	725330.4	402987.9	32.101	-103.738
15200	194.33	359.83	11838	-8480	1450.1	-684.21	1457.3	0	725330.4	403057.9	32.101	-103.738
15300	199.33	359.83	11838	-8480	1500.5	-684.21	1507.7	0	725330.4	403127.9	32.101	-103.738
15400	204.33	359.83	11838	-8480	1550.9	-684.21	1558.1	0	725330.4	403197.9	32.101	-103.738
15500	209.33	359.83	11838	-8480	1601.3	-684.21	1608.5	0	725330.4	403267.9	32.101	-103.738
15600	214.33	359.83	11838	-8480	1651.7	-684.21	1658.9	0	725330.4	403337.9	32.101	-103.738
15700	219.33	359.83	11838	-8480	1702.1	-684.21	1709.3	0	725330.4	403407.9	32.101	-103.738
15800	224.33	359.83	11838	-8480	1752.5	-684.21	1759.7	0	725330.4	403477.9	32.101	-103.738
15900	229.33	359.83	11838	-8480	1802.9	-684.21	1810.1	0	725330.4	403547.9	32.101	-103.738
16000	234.33	359.83	11838	-8480	1853.3	-684.21	1860.5	0	725330.4	403617.9	32.101	-103.738
16100	239.33	359.83	11838	-8480	1903.7	-684.21	1910.9	0	725330.4	403687.9	32.101	-103.738
16200	244.33	359.83	11838	-8480	1954.1	-684.21	196					

16400	90	359.83	11838	-8480	4591.25	-668.07	4593.21	0	725318.5	405837.9	32.114	-103.739
16500	90	359.83	11838	-8480	4691.25	-668.36	4693.21	0	725318.2	405937.9	32.115	-103.739
16600	90	359.83	11838	-8480	4791.25	-668.65	4793.21	0	725317.9	406037.9	32.115	-103.739
16700	90	359.83	11838	-8480	4891.24	-668.95	4893.21	0	725317.6	406137.9	32.115	-103.739
16800	90	359.83	11838	-8480	4991.24	-669.24	4993.21	0	725317.3	406237.9	32.115	-103.739
16900	90	359.83	11838	-8480	5091.24	-669.53	5093.21	0	725317	406337.9	32.116	-103.739
16928	90	359.83	11838	-8480	5119.24	-669.61	5121.21	0	725316.9	406365.9	32.116	-103.739
17000	90	359.83	11838	-8480	5191.24	-669.82	5193.21	0	725316.7	406437.9	32.116	-103.739
17100	90	359.83	11838	-8480	5291.24	-670.11	5293.21	0	725316.4	406537.9	32.116	-103.739
17200	90	359.83	11838	-8480	5391.24	-670.4	5393.21	0	725316.1	406637.9	32.117	-103.739
17300	90	359.83	11838	-8480	5491.24	-670.69	5493.21	0	725315.9	406737.9	32.117	-103.739
17400	90	359.83	11838	-8480	5591.24	-670.98	5593.21	0	725315.6	406837.9	32.117	-103.739
17500	90	359.83	11838	-8480	5691.24	-671.27	5693.21	0	725315.3	406937.9	32.117	-103.739
17600	90	359.83	11838	-8480	5791.24	-671.56	5793.21	0	725315	407037.9	32.118	-103.739
17700	90	359.83	11838	-8480	5891.24	-671.85	5893.21	0	725314.7	407137.9	32.118	-103.739
17800	90	359.83	11838	-8480	5991.24	-672.15	5993.21	0	725314.4	407237.9	32.118	-103.739
17900	90	359.83	11838	-8480	6091.24	-672.44	6093.21	0	725314.1	407337.9	32.118	-103.739
18000	90	359.83	11838	-8480	6191.24	-672.73	6193.21	0	725313.8	407437.9	32.119	-103.739
18100	90	359.83	11838	-8480	6291.24	-673.02	6293.21	0	725313.5	407537.9	32.119	-103.739
18200	90	359.83	11838	-8480	6391.24	-673.31	6393.21	0	725313.2	407637.9	32.119	-103.739
18300	90	359.83	11838	-8480	6491.24	-673.6	6493.21	0	725312.9	407737.9	32.12	-103.739
18400	90	359.83	11838	-8480	6591.24	-673.89	6593.21	0	725312.7	407837.9	32.12	-103.739
18500	90	359.83	11838	-8480	6691.24	-674.18	6693.21	0	725312.4	407937.9	32.12	-103.739
18600	90	359.83	11838	-8480	6791.24	-674.47	6793.21	0	725312.1	408037.9	32.12	-103.739
18700	90	359.83	11838	-8480	6891.24	-674.76	6893.21	0	725311.8	408137.9	32.121	-103.739
18800	90	359.83	11838	-8480	6991.24	-675.05	6993.21	0	725311.5	408237.9	32.121	-103.739
18900	90	359.83	11838	-8480	7091.24	-675.34	7093.21	0	725311.2	408337.9	32.121	-103.739
19000	90	359.83	11838	-8480	7191.24	-675.64	7193.21	0	725310.9	408437.9	32.121	-103.739
19100	90	359.83	11838	-8480	7291.23	-675.93	7293.21	0	725310.6	408537.8	32.122	-103.739
19200	90	359.83	11838	-8480	7391.23	-676.22	7393.21	0	725310.3	408637.8	32.122	-103.739
19238.78	90	359.83	11838	-8480	7430.01	-676.33	7431.98	0	725310.2	408676.6	32.122	-103.739

32.1157845, -103.7390851 - 16928' MD, 11838' TVD, 330' FWL - Entering NMLC061869

TD at 19238.78

All data are in feet unless otherwise stated. Directions and coordinates are relative to Grid North.
Vertical depths are relative to GL 3332+KB 26'. Northings and Eastings are relative to Well.

The Dogleg Severity is in Degrees per 100 feet.
Vertical Section is from Slot and calculated along an Azimuth of 359.830° (Grid).

Coordinate System is North American Datum 1983 US State Plane 1983, New Mexico Eastern Zone.
Grid Convergence at Surface is 0.317°.

Based upon Minimum Curvature type calculations, at a Measured Depth of 19238.78ft.,
the Bottom Hole Displacement is 7460.73ft., in the Direction of 359.830° (Grid).



Pro Directional
Anticollision Report



Company: Devon Energy Corp.
Project: Eddy County, NM (NAD83)
Reference Site: Big Sinks Draw 25-24
Site Error: 0.00 usft
Reference Well: 711H
Well Error: 0.00 usft
Reference Wellbore: OH
Reference Design: Prelim Plan

Local Co-ordinate Reference: Well 711H
TVD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
MD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at: 2.00 sigma
Database: WellPlanner1
Offset TVD Reference: Reference Datum

Reference	Prelim Plan		
Filter type:	NO GLOBAL FILTER: Using user defined selection & filtering criteria		
Interpolation Method:	MD Interval 100.00usft	Error Model:	ISCWSA
Depth Range:	Unlimited	Scan Method:	Closest Approach 3D
Results Limited by:	Maximum center-center distance of 2,485.72 usft	Error Surface:	Pedal Curve
Warning Levels Evaluated at:	2.00 Sigma	Casing Method:	Not applied

Survey Tool Program	Date 11/2/2017		
From (usft)	To (usft)	Survey (Wellbore)	Tool Name
0.00	19,238.78	Prelim Plan (OH)	MWD+HDGM
			Description
			OWSG MWD + HDGM

Site Name	Reference		Distance		Separation Factor	Warning
	Measured Depth (usft)	Offset Measured Depth (usft)	Between Centres (usft)	Between Ellipses (usft)		
Big Sinks Draw 25-24						
1H - OH - Surveys	10,344.33	10,394.98	76.72	17.19	1.289	Level 3, CC, ES, SF
331H - OH - Prelim Plan	1,000.00	1,000.00	60.03	53.31	8.936	CC
331H - OH - Prelim Plan	1,100.00	1,099.49	60.45	53.02	8.140	ES
331H - OH - Prelim Plan	8,300.00	8,277.97	256.10	196.37	4.287	SF
521H - OH - Prelim Plan	1,000.00	1,000.00	161.39	154.67	24.024	CC
521H - OH - Prelim Plan	1,200.00	1,198.93	162.04	153.92	19.946	ES
521H - OH - Prelim Plan	8,324.25	8,308.11	338.92	278.88	5.645	SF
531H - OH - Prelim Plan	1,500.00	1,500.00	152.89	142.58	14.840	CC
531H - OH - Prelim Plan	1,900.00	1,901.12	154.41	141.29	11.766	ES
531H - OH - Prelim Plan	6,000.00	6,007.94	194.06	151.72	4.583	SF
611H - OH - Prelim Plan	1,500.00	1,500.00	29.97	19.67	2.909	CC
611H - OH - Prelim Plan	1,600.00	1,599.74	30.41	19.40	2.762	ES
611H - OH - Prelim Plan	19,238.78	18,795.54	250.00	122.98	1.968	SF

Offset Design													Offset Site Error:	0.00 usft
Big Sinks Draw 25-24 - 1H - OH - Surveys													Offset Well Error:	0.00 usft
Survey Program: 100-NS-GYRO-MS, 9997-MWD														
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis			Distance				Separation Factor	Warning		
				Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			Minimum Separation (usft)	
0.00	0.00	11.01	0.21	0.00	0.01	-85.21	40.67	-485.02	486.72					
100.00	100.00	112.71	101.91	0.13	0.13	-85.16	41.00	-484.75	486.48	486.22	0.26	1,863.943		
200.00	200.00	213.33	202.53	0.49	0.39	-85.13	41.29	-484.29	486.05	485.18	0.88	554.367		
300.00	300.00	315.19	304.38	0.85	0.65	-85.06	41.78	-483.44	485.27	483.77	1.50	323.233		
400.00	400.00	413.00	402.19	1.21	0.91	-84.99	42.31	-482.79	484.64	482.53	2.12	229.105		
500.00	500.00	514.45	503.64	1.57	1.16	-84.97	42.42	-482.13	484.00	481.28	2.72	177.621		
600.00	600.00	613.07	602.25	1.92	1.40	-84.94	42.67	-481.48	483.37	480.04	3.33	145.353		
671.78	671.78	682.60	671.78	2.18	1.55	-84.90	42.95	-481.29	483.20	479.47	3.73	129.510		
700.00	700.00	710.13	699.31	2.28	1.60	-84.89	43.04	-481.30	483.23	479.35	3.88	124.557		
800.00	800.00	808.98	798.17	2.64	1.70	-84.88	43.19	-481.55	483.49	479.15	4.34	111.413		
900.00	900.00	908.26	897.44	3.00	1.81	-84.83	43.59	-481.97	483.94	479.14	4.81	100.678		
1,000.00	1,000.00	1,003.60	992.77	3.36	1.93	-84.83	43.71	-482.98	485.01	479.72	5.29	91.765		
1,100.00	1,100.00	1,103.91	1,093.07	3.72	2.02	-84.88	43.40	-484.47	486.46	480.73	5.74	84.780		
1,200.00	1,200.00	1,200.32	1,189.47	4.08	2.14	-84.94	43.09	-486.25	488.27	482.05	6.22	78.536		
1,300.00	1,300.00	1,301.91	1,291.03	4.43	2.30	-84.99	42.84	-488.31	490.27	483.53	6.73	72.833		

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation



Pro Directional
Anticollision Report



Company: Devon Energy Corp.
Project: Eddy County, NM (NAD83)
Reference Site: Big Sinks Draw 25-24
Site Error: 0.00 usft
Reference Well: 711H
Well Error: 0.00 usft
Reference Wellbore: OH
Reference Design: Prelim Plan

Local Co-ordinate Reference: Well 711H
TVD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
MD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at: 2.00 sigma
Database: WellPlanner1
Offset TVD Reference: Reference Datum

Offset Design													Offset Site Error:	0.00 usft
Survey Program: 100-NS-GYRO-MS, 9997-MWD													Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis			Distance						Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	Offset Wellbore Centre +E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor		
1,400.00	1,400.00	1,398.39	1,387.49	4.79	2.47	-85.03	42.67	-490.45	492.46	485.20	7.26	67.852		
1,500.00	1,500.00	1,500.10	1,489.17	5.15	2.66	-85.06	42.57	-492.88	494.83	487.02	7.81	63.343		
1,600.00	1,600.00	1,599.52	1,588.57	5.51	2.86	-85.11	42.34	-495.14	497.08	488.71	8.37	59.391		
1,700.00	1,700.00	1,701.79	1,690.80	5.87	3.07	-85.21	41.65	-497.33	499.15	490.22	8.93	55.889		
1,800.00	1,800.00	1,803.18	1,792.18	6.23	3.27	-85.34	40.71	-499.14	500.85	491.36	9.49	52.772		
1,900.00	1,900.00	1,902.79	1,891.77	6.59	3.47	-85.49	39.52	-500.84	502.46	492.42	10.05	50.004		
2,000.00	2,000.00	2,003.65	1,992.60	6.94	3.67	-85.67	38.08	-502.52	504.02	493.41	10.61	47.501		
2,100.00	2,100.00	2,101.07	2,089.99	7.30	3.87	-85.87	36.44	-504.34	505.76	494.58	11.17	45.272		
2,200.00	2,200.00	2,200.14	2,189.02	7.66	4.09	-86.07	34.82	-506.51	507.83	496.08	11.75	43.229		
2,300.00	2,300.00	2,297.79	2,286.63	8.02	4.31	-86.27	33.19	-508.96	510.22	497.89	12.33	41.390		
2,400.00	2,400.00	2,395.70	2,384.48	8.38	4.54	-86.48	31.51	-511.84	513.04	500.13	12.91	39.729		
2,500.00	2,500.00	2,493.24	2,481.96	8.74	4.78	-86.63	30.30	-515.09	516.30	502.79	13.51	38.225		
2,600.00	2,600.00	2,593.52	2,582.17	9.09	5.03	-86.80	28.97	-518.66	519.78	505.67	14.11	36.836		
2,700.00	2,700.00	2,693.46	2,682.04	9.45	5.27	-87.00	27.33	-522.18	523.21	508.49	14.71	35.558		
2,800.00	2,800.00	2,792.54	2,781.05	9.81	5.52	-87.16	26.04	-525.73	526.72	511.40	15.32	34.385		
2,900.00	2,900.00	2,892.69	2,881.12	10.17	5.77	-87.30	24.94	-529.38	530.31	514.38	15.93	33.294		
3,000.00	3,000.00	2,992.70	2,981.05	10.53	6.03	-87.46	23.64	-533.00	533.86	517.32	16.54	32.280		
3,100.00	3,100.00	3,095.31	3,083.59	10.89	6.28	-87.64	22.08	-536.47	537.18	520.02	17.16	31.312		
3,200.00	3,200.00	3,198.73	3,186.95	11.25	6.54	-87.86	20.11	-539.39	539.92	522.15	17.77	30.382		
3,300.00	3,300.00	3,308.13	3,296.31	11.60	6.79	-88.12	17.73	-541.17	541.47	523.09	18.38	29.462		
3,400.00	3,400.00	3,408.56	3,396.70	11.96	6.99	-88.42	14.95	-541.96	542.18	523.24	18.94	28.625		
3,500.00	3,500.00	3,507.65	3,495.71	12.32	7.19	-88.84	10.97	-542.78	542.91	523.41	19.50	27.844		
3,600.00	3,600.00	3,609.50	3,597.39	12.68	7.39	-89.45	5.18	-543.51	543.54	523.48	20.06	27.097		
3,700.00	3,700.00	3,709.86	3,697.45	13.04	7.59	-90.26	-2.52	-544.03	544.04	523.42	20.62	26.389		
3,800.00	3,800.00	3,812.26	3,799.32	13.40	7.80	-91.35	-12.87	-544.21	544.37	523.19	21.18	25.705		
3,900.00	3,900.00	3,915.76	3,901.99	13.75	8.00	-92.73	-25.88	-543.44	544.06	522.32	21.74	25.026		
3,922.55	3,922.55	3,936.52	3,922.55	13.84	8.04	-93.03	-28.78	-543.25	544.02	522.15	21.86	24.883		
4,000.00	4,000.00	4,007.66	3,992.88	14.11	8.19	-94.15	-39.40	-543.04	544.52	522.23	22.29	24.432		
4,100.00	4,100.00	4,099.08	4,082.91	14.47	8.39	-95.81	-55.28	-543.64	546.71	523.87	22.84	23.938		
4,200.00	4,200.00	4,196.38	4,178.24	14.83	8.61	-97.81	-74.73	-544.71	550.24	526.83	23.41	23.504		
4,300.00	4,300.00	4,284.30	4,264.10	15.19	8.81	-99.72	-93.55	-546.31	555.42	531.47	23.95	23.189		
4,400.00	4,400.00	4,379.10	4,356.53	15.54	9.04	-3.20	-114.45	-549.16	561.77	537.26	24.51	22.922		
4,500.00	4,499.96	4,485.61	4,460.48	15.87	9.31	1.00	-137.45	-551.97	566.71	541.60	25.11	22.570		
4,600.00	4,599.86	4,593.35	4,566.22	16.21	9.57	-0.97	-158.04	-553.52	568.78	543.07	25.71	22.120		
4,700.00	4,699.68	4,699.13	4,670.51	16.55	9.83	-2.68	-175.73	-554.20	568.21	541.90	26.31	21.598		
4,800.00	4,799.37	4,790.69	4,761.07	16.89	10.05	-3.97	-189.18	-555.45	566.32	539.47	26.85	21.091		
4,900.00	4,898.90	4,902.07	4,871.47	17.23	10.33	-5.39	-203.74	-557.26	562.75	535.28	27.48	20.481		
5,000.00	4,998.26	4,999.61	4,968.26	17.58	10.57	-6.65	-215.86	-557.97	556.64	528.59	28.05	19.848		
5,100.00	5,097.45	5,098.68	5,066.64	17.93	10.82	-7.89	-227.47	-559.08	549.49	520.87	28.62	19.198		
5,200.00	5,196.62	5,202.66	5,170.02	18.28	11.08	-9.12	-238.51	-560.24	542.03	512.81	29.22	18.550		
5,300.00	5,295.79	5,310.84	5,277.73	18.63	11.34	-10.33	-248.55	-560.56	533.49	503.67	29.82	17.888		
5,400.00	5,394.96	5,408.09	5,374.64	18.99	11.58	-11.37	-256.64	-560.67	524.58	494.19	30.40	17.259		
5,500.00	5,494.13	5,503.94	5,470.21	19.34	11.81	-12.32	-263.92	-561.63	516.30	485.33	30.97	16.670		
5,600.00	5,593.30	5,610.01	5,576.02	19.70	12.08	-13.34	-271.24	-562.58	507.76	476.18	31.58	16.080		
5,700.00	5,692.47	5,708.16	5,673.97	20.06	12.32	-14.26	-277.37	-563.30	498.89	466.73	32.16	15.512		
5,800.00	5,791.64	5,808.58	5,774.24	20.42	12.58	-15.13	-282.89	-564.40	490.11	457.36	32.76	14.962		
5,900.00	5,890.81	5,913.17	5,878.70	20.78	12.83	-16.07	-288.14	-564.86	480.63	447.28	33.36	14.409		
6,000.00	5,989.98	6,009.95	5,975.36	21.15	13.07	-16.94	-292.68	-565.30	471.12	437.18	33.94	13.880		
6,100.00	6,089.15	6,109.37	6,074.70	21.51	13.32	-17.75	-296.73	-566.44	461.97	427.43	34.54	13.375		
6,200.00	6,188.32	6,210.70	6,175.95	21.88	13.58	-18.60	-300.60	-567.45	452.67	417.52	35.14	12.880		
6,300.00	6,287.50	6,310.93	6,276.11	22.25	13.84	-19.48	-304.31	-568.21	443.19	407.44	35.74	12.399		
6,400.00	6,386.67	6,413.07	6,378.20	22.62	14.09	-20.39	-307.57	-568.70	433.29	396.95	36.35	11.921		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Pro Directional

Anticollision Report



Company: Devon Energy Corp.
Project: Eddy County, NM (NAD83)
Reference Site: Big Sinks Draw 25-24
Site Error: 0.00 usft
Reference Well: 711H
Well Error: 0.00 usft
Reference Wellbore: OH
Reference Design: Prelim Plan

Local Co-ordinate Reference: Well 711H
TVD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
MD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at 2.00 sigma
Database: WellPlanner1
Offset TVD Reference: Reference Datum

Offset Design													Offset Site Error:	0.00 usft
Big Sinks Draw 25-24 - 1H - OH - Surveys													Offset Well Error:	0.00 usft
Survey Program: 100-NS-GYRO-MS, 9997-MWD														
Reference				Offset		Semi Major Axis			Distance				Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor		
6,500.00	6,485.84	6,512.08	6,477.16	22.99	14.33	-21.32	-310.70	-568.93	423.30	386.36	36.94	11.459		
6,600.00	6,585.01	6,613.81	6,578.84	23.36	14.58	-22.35	-313.88	-568.80	413.11	375.58	37.53	11.007		
6,700.00	6,684.18	6,714.39	6,679.37	23.73	14.81	-23.44	-316.83	-568.16	402.54	364.43	38.12	10.561		
6,800.00	6,783.35	6,812.26	6,777.20	24.10	15.04	-24.56	-319.68	-567.63	392.19	353.49	38.70	10.134		
6,900.00	6,882.52	6,911.81	6,876.72	24.48	15.28	-25.64	-322.08	-567.60	382.05	342.75	39.30	9.721		
7,000.00	6,981.69	7,009.96	6,974.85	24.85	15.53	-26.61	-323.78	-568.32	372.17	332.26	39.91	9.326		
7,100.00	7,080.86	7,108.89	7,073.76	25.23	15.78	-27.58	-325.33	-569.48	362.61	322.09	40.52	8.949		
7,200.00	7,180.03	7,208.76	7,173.61	25.60	16.04	-28.61	-326.88	-570.60	353.14	312.00	41.14	8.584		
7,300.00	7,279.20	7,305.69	7,270.52	25.98	16.29	-29.71	-328.81	-571.73	344.10	302.35	41.75	8.241		
7,400.00	7,378.37	7,404.32	7,369.11	26.36	16.55	-30.93	-331.25	-572.98	335.62	293.25	42.38	7.920		
7,500.00	7,477.54	7,503.53	7,468.28	26.74	16.80	-32.23	-333.82	-574.30	327.44	284.44	43.00	7.615		
7,600.00	7,576.71	7,603.25	7,567.95	27.12	17.06	-33.60	-336.36	-575.65	319.42	275.79	43.62	7.322		
7,700.00	7,675.88	7,704.92	7,669.58	27.50	17.32	-35.16	-338.98	-576.32	311.15	266.91	44.25	7.032		
7,800.00	7,775.06	7,804.27	7,768.90	27.88	17.57	-36.82	-341.41	-576.56	302.77	257.90	44.87	6.748		
7,900.00	7,874.23	7,903.41	7,868.02	28.26	17.82	-38.54	-343.75	-576.89	294.64	249.15	45.50	6.476		
8,000.00	7,973.40	8,004.03	7,968.61	28.64	18.08	-40.37	-345.89	-577.18	286.58	240.45	46.13	6.213		
8,100.00	8,072.57	8,102.96	8,067.53	29.02	18.33	-42.21	-347.71	-577.59	278.64	231.87	46.76	5.959		
8,200.00	8,171.74	8,201.97	8,166.53	29.41	18.59	-44.13	-349.52	-578.19	271.10	223.70	47.40	5.719		
8,300.00	8,270.91	8,302.86	8,267.39	29.79	18.85	-46.20	-351.18	-578.59	263.63	215.58	48.04	5.487		
8,400.00	8,370.08	8,402.34	8,366.87	30.17	19.08	-48.21	-352.19	-579.48	256.18	207.50	48.67	5.263		
8,500.00	8,469.25	8,502.53	8,467.05	30.56	19.30	-50.13	-352.59	-581.15	248.82	199.54	49.27	5.050		
8,600.00	8,568.42	8,604.76	8,569.26	30.94	19.45	-52.25	-352.34	-582.36	240.98	191.18	49.81	4.838		
8,700.00	8,667.59	8,699.93	8,664.43	31.33	19.61	-54.39	-352.49	-583.46	233.84	183.44	50.40	4.640		
8,800.00	8,766.76	8,799.30	8,763.78	31.71	19.86	-56.86	-353.52	-584.48	227.86	176.81	51.05	4.463		
8,900.00	8,865.93	8,899.35	8,863.83	32.10	20.12	-59.62	-354.57	-584.92	222.19	170.47	51.72	4.296		
9,000.00	8,965.10	8,996.17	8,960.64	32.49	20.37	-62.37	-355.89	-585.61	217.42	165.02	52.40	4.149		
9,100.00	9,064.27	9,094.61	9,059.05	32.87	20.63	-65.05	-357.84	-587.27	213.98	160.91	53.07	4.032		
9,200.00	9,163.45	9,196.34	9,160.74	33.26	20.87	-67.73	-359.44	-589.64	210.71	156.98	53.73	3.922		
9,300.00	9,262.62	9,295.01	9,259.37	33.65	21.11	-70.43	-360.60	-591.77	207.49	153.11	54.39	3.815		
9,400.00	9,361.79	9,393.55	9,357.87	34.04	21.36	-73.28	-362.20	-593.64	205.20	150.14	55.06	3.727		
9,500.00	9,460.96	9,492.70	9,457.00	34.42	21.62	-76.30	-364.11	-595.18	203.75	148.02	55.73	3.656		
9,600.00	9,560.14	9,592.76	9,557.03	34.81	21.88	-79.35	-365.95	-596.76	202.81	146.40	56.41	3.595		
9,700.00	9,659.48	9,693.29	9,657.53	35.20	22.13	-81.97	-367.41	-598.69	202.20	145.14	57.07	3.543		
9,800.00	9,759.01	9,793.69	9,757.90	35.57	22.37	-84.13	-368.44	-600.64	201.77	144.07	57.70	3.497		
9,900.00	9,858.69	9,893.94	9,858.14	35.94	22.61	-86.01	-369.06	-601.86	201.49	143.16	58.33	3.454		
10,000.00	9,958.50	10,029.36	9,992.61	36.31	22.75	-90.30	-365.25	-598.10	192.64	134.65	57.99	3.322		
10,100.00	10,058.39	10,160.82	10,117.28	36.67	22.77	-99.43	-316.66	-588.19	166.44	110.09	56.36	2.953		
10,200.00	10,158.35	10,274.21	10,214.89	37.02	22.85	-115.65	-259.66	-581.65	124.64	69.39	55.25	2.256		
10,300.00	10,258.35	10,364.29	10,282.70	37.36	22.97	-146.29	-200.71	-578.42	83.65	25.36	58.30	1.435	Level 3	
10,344.33	10,302.67	10,394.98	10,302.72	37.51	23.03	-163.18	-177.48	-577.57	76.72	17.19	59.53	1.289	Level 3, CC, ES, SF	
10,400.00	10,358.35	10,426.67	10,321.49	37.70	23.10	73.42	-151.97	-576.86	88.72	33.66	55.06	1.611		
10,500.00	10,458.35	10,470.00	10,343.72	38.04	23.22	52.47	-114.81	-575.87	151.33	105.66	45.67	3.313		
10,600.00	10,558.35	10,502.00	10,357.62	38.38	23.33	41.69	-86.01	-574.96	233.44	191.55	41.89	5.573		
10,700.00	10,658.35	10,526.13	10,366.88	38.72	23.42	35.68	-63.74	-574.33	322.05	281.80	40.24	8.003		
10,800.00	10,758.35	10,547.22	10,374.14	39.06	23.51	31.52	-43.94	-573.83	413.82	374.29	39.54	10.467		
10,900.00	10,858.35	10,565.00	10,379.69	39.40	23.59	28.62	-27.06	-573.48	507.46	468.24	39.22	12.940		
11,000.00	10,958.35	10,578.68	10,383.59	39.74	23.65	26.70	-13.95	-573.22	602.37	563.29	39.07	15.416		
11,100.00	11,058.35	10,596.00	10,388.03	40.09	23.74	24.58	2.79	-572.88	698.25	659.07	39.18	17.822		
11,200.00	11,158.35	10,596.00	10,388.03	40.43	23.74	24.58	2.79	-572.88	794.74	755.64	39.10	20.325		
11,300.00	11,258.35	10,610.08	10,391.25	40.77	23.81	23.09	16.49	-572.56	891.73	852.40	39.34	22.670		
11,400.00	11,357.94	10,628.00	10,394.90	41.11	23.90	13.13	34.03	-572.06	987.31	947.73	39.57	24.949		
11,500.00	11,454.70	10,637.42	10,396.62	41.42	23.95	8.98	43.29	-571.76	1,077.47	1,037.84	39.63	27.185		

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation



Pro Directional
Anticollision Report



Company: Devon Energy Corp.
Project: Eddy County, NM (NAD83)
Reference Site: Big Sinks Draw 25-24
Site Error: 0.00 usft
Reference Well: 711H
Well Error: 0.00 usft
Reference Wellbore: OH
Reference Design: Prelim Plan

Local Co-ordinate Reference: Well 711H
TVD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
MD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at: 2.00 sigma
Database: WellPlanner1
Offset TVD Reference: Reference Datum

Offset Design												Offset Site Error:	0.00 usft	
Big Sinks Draw 25-24 - 1H - OH - Surveys												Offset Well Error:	0.00 usft	
Survey Program: 100-NS-GYRO-MS, 9997-MWD														
Reference		Offset		Semi Major Axis			Distance					Warning		
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor		
11,600.00	11,545.70	10,660.00	10,400.21	41.69	24.08	6.77	65.56	-571.01	1,160.62	1,120.85	39.77	29.181		
11,700.00	11,628.18	10,677.90	10,402.44	41.92	24.19	5.52	83.31	-570.33	1,235.33	1,195.45	39.89	30.970		
11,800.00	11,699.62	10,699.48	10,404.29	42.08	24.32	4.73	104.79	-569.40	1,300.62	1,260.55	40.07	32.459		
11,900.00	11,757.86	10,727.08	10,405.37	42.20	24.50	4.21	132.35	-568.39	1,355.52	1,315.19	40.33	33.607		
12,000.00	11,801.12	10,787.48	10,405.86	42.28	24.93	3.87	192.73	-567.15	1,398.04	1,357.39	40.65	34.392		
12,100.00	11,828.09	10,860.41	10,405.13	42.34	25.48	3.69	265.64	-565.60	1,426.04	1,385.06	40.98	34.800		
12,200.00	11,837.96	10,952.07	10,403.19	42.47	26.25	3.65	357.27	-564.24	1,438.09	1,396.78	41.31	34.811		
12,300.00	11,838.00	11,069.62	10,401.22	42.67	27.25	3.68	474.80	-563.72	1,439.84	1,398.18	41.66	34.562		
12,400.00	11,838.00	11,190.23	10,400.56	42.94	28.33	3.70	595.41	-563.44	1,440.45	1,398.37	42.08	34.232		
12,500.00	11,838.00	11,289.49	10,401.14	43.27	29.33	3.73	694.67	-562.95	1,439.92	1,397.37	42.56	33.837		
12,526.85	11,838.00	11,313.22	10,401.18	43.36	29.58	3.74	718.39	-562.82	1,439.89	1,397.20	42.69	33.728		
12,600.00	11,838.00	11,363.72	10,400.84	43.64	30.17	3.76	768.89	-562.46	1,440.44	1,397.36	43.08	33.440		
12,700.00	11,838.00	11,433.51	10,399.01	44.05	31.00	3.80	838.65	-561.59	1,443.12	1,399.47	43.66	33.057		
12,800.00	11,838.00	11,511.58	10,395.63	44.51	31.95	3.86	916.63	-560.16	1,447.58	1,403.30	44.28	32.690		
12,900.00	11,838.00	11,628.31	10,390.60	45.01	33.37	3.94	1,033.23	-557.97	1,452.00	1,407.08	44.92	32.328		
13,000.00	11,838.00	11,721.51	10,386.87	45.55	34.56	4.01	1,126.35	-556.30	1,456.15	1,410.54	45.61	31.926		
13,100.00	11,838.00	11,810.49	10,382.57	46.12	35.74	4.11	1,215.18	-553.67	1,461.18	1,414.83	46.35	31.526		
13,200.00	11,838.00	11,927.71	10,377.63	46.74	37.28	4.25	1,332.23	-550.09	1,465.59	1,418.48	47.12	31.106		
13,300.00	11,838.00	12,046.32	10,373.45	47.39	38.88	4.35	1,450.75	-547.59	1,469.34	1,421.41	47.93	30.654		
13,400.00	11,838.00	12,167.11	10,371.21	48.08	40.54	4.40	1,571.50	-546.39	1,471.27	1,422.47	48.80	30.150		
13,500.00	11,838.00	12,258.70	10,369.88	48.79	41.82	4.47	1,663.07	-544.68	1,472.88	1,423.21	49.68	29.650		
13,600.00	11,838.00	12,354.38	10,368.07	49.54	43.20	4.57	1,758.71	-542.33	1,474.98	1,424.39	50.59	29.157		
13,700.00	11,838.00	12,472.45	10,366.27	50.32	44.93	4.65	1,876.75	-540.49	1,476.66	1,425.10	51.56	28.641		
13,800.00	11,838.00	12,579.04	10,365.78	51.13	46.48	4.75	1,983.31	-538.10	1,477.32	1,424.77	52.55	28.112		
13,900.00	11,838.00	12,681.16	10,365.27	51.97	48.01	4.85	2,085.40	-535.76	1,478.04	1,424.48	53.56	27.595		
14,000.00	11,838.00	12,811.55	10,366.15	52.83	49.99	4.93	2,215.77	-534.11	1,477.52	1,422.86	54.66	27.032		
14,100.00	11,838.00	12,913.74	10,368.13	53.72	51.57	4.96	2,317.94	-534.01	1,475.62	1,419.90	55.72	26.485		
14,200.00	11,838.00	13,014.91	10,370.04	54.63	53.13	5.00	2,419.09	-533.32	1,473.83	1,417.03	56.80	25.950		
14,300.00	11,838.00	13,118.50	10,372.28	55.56	54.74	5.09	2,522.64	-531.49	1,471.85	1,413.94	57.91	25.417		
14,400.00	11,838.00	13,213.94	10,374.37	56.52	56.23	5.19	2,618.04	-529.43	1,469.89	1,410.87	59.02	24.903		
14,500.00	11,838.00	13,317.06	10,376.62	57.49	57.85	5.32	2,721.09	-526.56	1,467.99	1,407.81	60.18	24.392		
14,600.00	11,838.00	13,408.45	10,378.34	58.49	59.31	5.40	2,812.45	-524.97	1,466.31	1,404.98	61.33	23.910		
14,690.96	11,838.00	13,478.63	10,378.94	59.41	60.44	5.45	2,882.62	-523.88	1,465.68	1,403.33	62.35	23.508		
14,700.00	11,838.00	13,485.66	10,378.96	59.50	60.55	5.46	2,889.64	-523.74	1,465.69	1,403.24	62.45	23.470		
14,800.00	11,838.00	13,562.86	10,378.48	60.53	61.79	5.55	2,966.81	-521.60	1,466.60	1,403.00	63.59	23.062		
14,900.00	11,838.00	13,660.41	10,376.82	61.58	63.36	5.69	3,064.28	-518.05	1,468.67	1,403.86	64.81	22.661		
15,000.00	11,838.00	13,757.16	10,375.23	62.65	64.93	5.76	3,161.00	-516.35	1,470.51	1,404.48	66.03	22.271		
15,100.00	11,838.00	13,845.81	10,373.10	63.73	66.37	5.77	3,249.63	-516.21	1,472.95	1,405.73	67.22	21.911		
15,200.00	11,838.00	13,937.39	10,370.24	64.82	67.87	5.79	3,341.16	-515.55	1,476.16	1,407.71	68.44	21.567		
15,300.00	11,838.00	14,023.14	10,367.08	65.93	69.28	5.81	3,426.85	-515.01	1,479.93	1,410.28	69.66	21.246		
15,400.00	11,838.00	14,133.10	10,362.15	67.05	71.08	5.84	3,536.69	-514.11	1,484.57	1,413.62	70.94	20.926		
15,500.00	11,838.00	14,271.17	10,359.00	68.18	73.30	5.87	3,674.72	-513.29	1,486.90	1,414.58	72.32	20.561		
15,600.00	11,838.00	14,388.72	10,358.46	69.32	75.18	5.93	3,792.27	-512.07	1,487.50	1,413.84	73.66	20.194		
15,700.00	11,838.00	14,490.54	10,358.94	70.48	76.83	5.98	3,894.07	-511.00	1,487.17	1,412.20	74.97	19.836		
15,723.91	11,838.00	14,512.08	10,358.98	70.76	77.18	6.00	3,915.61	-510.78	1,487.15	1,411.87	75.28	19.755		
15,800.00	11,838.00	14,572.74	10,358.82	71.65	78.19	6.03	3,976.27	-510.05	1,487.49	1,411.25	76.24	19.510		
15,900.00	11,838.00	14,669.99	10,357.44	72.82	79.80	6.10	4,073.49	-508.24	1,489.12	1,411.55	77.57	19.197		
16,000.00	11,838.00	14,813.49	10,358.07	74.01	82.15	6.20	4,216.97	-506.14	1,488.86	1,409.83	79.03	18.838		
16,100.00	11,838.00	14,932.95	10,361.41	75.20	84.13	6.25	4,336.38	-505.59	1,486.09	1,405.66	80.43	18.477		
16,200.00	11,838.00	15,005.00	10,363.07	76.41	85.34	6.26	4,408.41	-505.87	1,483.86	1,402.16	81.70	18.162		
16,276.90	11,838.00	15,065.46	10,363.55	77.34	86.35	6.25	4,468.86	-506.12	1,483.28	1,400.59	82.69	17.937		
16,300.00	11,838.00	15,082.14	10,363.52	77.62	86.63	6.25	4,485.54	-506.17	1,483.33	1,400.34	82.99	17.874		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Pro Directional

Anticollision Report



Company: Devon Energy Corp.
Project: Eddy County, NM (NAD83)
Reference Site: Big Sinks Draw 25-24
Site Error: 0.00 usft
Reference Well: 711H
Well Error: 0.00 usft
Reference Wellbore: OH
Reference Design: Prelim Plan

Local Co-ordinate Reference: Well 711H
TVD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
MD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at 2.00 sigma
Database: WellPlanner1
Offset TVD Reference: Reference Datum

Offset Design Big Sinks Draw 25-24 - 1H - OH - Surveys													Offset Site Error:	0.00 usft
Survey Program: 100-NS-GYRO-MS, 9997-MWD													Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis			Distance						Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toofface (")	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor		
16,400.00	11,838.00	15,183.84	10,362.93	78.84	88.32	6.26	4,587.25	-506.22	1,483.93	1,399.59	84.34	17.594		
16,500.00	11,838.00	15,268.95	10,362.37	80.07	89.72	6.27	4,672.35	-506.07	1,484.65	1,398.98	85.66	17.331		
16,600.00	11,838.00	15,380.29	10,361.14	81.30	91.58	6.29	4,783.69	-505.88	1,485.82	1,398.75	87.07	17.065		
16,700.00	11,838.00	15,501.70	10,361.42	82.54	93.60	6.31	4,905.10	-505.67	1,485.64	1,397.14	88.50	16.786		
16,712.52	11,838.00	15,516.91	10,361.58	82.70	93.85	6.31	4,920.30	-505.64	1,485.52	1,396.83	88.68	16.751		
16,800.00	11,838.00	15,575.00	10,361.25	83.79	94.82	6.36	4,978.38	-504.63	1,485.96	1,396.13	89.83	16.542		
16,900.00	11,838.00	15,671.49	10,360.40	85.05	96.44	6.41	5,074.86	-503.38	1,487.00	1,395.78	91.22	16.301		
17,000.00	11,838.00	15,734.48	10,358.98	86.31	97.50	6.44	5,137.83	-502.67	1,489.40	1,396.90	92.50	16.102		
17,100.00	11,838.00	15,828.12	10,355.12	87.57	99.08	6.51	5,231.37	-500.81	1,493.71	1,399.82	93.89	15.909		
17,200.00	11,838.00	15,943.40	10,351.30	88.84	101.02	6.56	5,346.58	-499.28	1,497.19	1,401.81	95.37	15.699		
17,300.00	11,838.00	16,077.29	10,348.84	90.12	103.24	6.66	5,480.41	-496.79	1,499.32	1,402.39	96.93	15.468		
17,400.00	11,838.00	16,209.84	10,349.96	91.40	105.47	6.72	5,612.95	-495.76	1,498.47	1,400.01	98.46	15.219		
17,500.00	11,838.00	16,330.89	10,352.48	92.69	107.51	6.75	5,733.97	-495.63	1,496.48	1,396.55	99.94	14.974		
17,600.00	11,838.00	16,423.85	10,355.01	93.98	109.06	6.79	5,826.90	-495.14	1,493.88	1,392.51	101.36	14.738		
17,700.00	11,838.00	16,514.53	10,356.95	95.28	110.59	6.82	5,917.56	-494.80	1,491.83	1,389.05	102.78	14.514		
17,800.00	11,838.00	16,637.55	10,360.18	96.58	112.66	6.86	6,040.53	-494.59	1,489.27	1,384.99	104.28	14.282		
17,900.00	11,838.00	16,733.30	10,363.42	97.89	114.27	6.89	6,136.23	-494.39	1,485.97	1,380.25	105.72	14.056		
18,000.00	11,838.00	16,810.82	10,365.28	99.20	115.58	6.93	6,213.72	-493.67	1,483.73	1,376.59	107.14	13.849		
18,100.00	11,838.00	16,890.34	10,366.05	100.51	116.92	6.98	6,293.23	-492.83	1,482.94	1,374.39	108.55	13.661		
18,107.12	11,838.00	16,895.99	10,366.06	100.60	117.02	6.98	6,298.88	-492.79	1,482.94	1,374.29	108.65	13.649		
18,200.00	11,838.00	16,969.54	10,365.70	101.83	118.26	7.02	6,372.42	-492.01	1,483.54	1,373.59	109.95	13.493		
18,300.00	11,838.00	17,064.12	10,364.35	103.15	119.87	7.07	6,466.99	-490.81	1,485.15	1,373.74	111.41	13.331		
18,400.00	11,838.00	17,190.08	10,363.54	104.47	122.00	7.11	6,592.94	-490.02	1,485.88	1,372.91	112.97	13.153		
18,407.81	11,838.00	17,196.72	10,363.55	104.57	122.11	7.11	6,599.58	-489.98	1,485.88	1,372.80	113.08	13.140		
18,500.00	11,838.00	17,278.01	10,363.29	105.80	123.49	7.15	6,680.87	-489.19	1,486.30	1,371.89	114.41	12.991		
18,600.00	11,838.00	17,397.98	10,363.89	107.13	125.53	7.20	6,800.83	-488.39	1,485.84	1,369.89	115.96	12.814		
18,645.18	11,838.00	17,434.11	10,364.04	107.73	126.15	7.21	6,836.96	-488.20	1,485.70	1,369.11	116.60	12.742		
18,700.00	11,838.00	17,476.31	10,363.93	108.46	126.87	7.22	6,879.16	-487.91	1,485.92	1,368.55	117.37	12.660		
18,800.00	11,838.00	17,548.08	10,362.75	109.79	128.09	7.25	6,950.91	-487.15	1,487.72	1,368.97	118.74	12.529		
18,900.00	11,838.00	17,680.65	10,360.92	111.13	130.33	7.33	7,083.46	-485.41	1,489.26	1,368.88	120.38	12.371		
19,000.00	11,838.00	17,768.95	10,360.53	112.47	131.81	7.39	7,171.74	-483.98	1,489.98	1,368.12	121.85	12.228		
19,100.00	11,838.00	17,849.23	10,359.17	113.82	133.17	7.44	7,235.54	-482.74	1,492.44	1,369.11	123.32	12.102		
19,200.00	11,838.00	17,932.68	10,355.68	115.16	134.59	7.51	7,335.36	-480.65	1,496.21	1,371.48	124.73	11.996		
19,238.78	11,838.00	17,971.42	10,354.33	115.69	135.25	7.54	7,374.07	-479.84	1,497.67	1,372.35	125.32	11.951		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Pro Directional
Anticollision Report



Company: Devon Energy Corp.
Project: Eddy County, NM (NAD83)
Reference Site: Big Sinks Draw 25-24
Site Error: 0.00 usft
Reference Well: 711H
Well Error: 0.00 usft
Reference Wellbore: OH
Reference Design: Prelim Plan

Local Co-ordinate Reference: Well 711H
TVD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
MD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at: 2.00 sigma
Database: WellPlanner1
Offset TVD Reference: Reference Datum

Table with columns: Measured Depth, Vertical Depth, Reference, Offset, Semi Major Axis, Highside Toolface, Offset Wellbore Centre, Distance (Between Centres, Between Ellipses, Minimum Separation, Separation Factor), Warning. Includes data for various depths from 0.00 to 5,100.00.

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation



Pro Directional Anticollision Report



Company: Devon Energy Corp.
 Project: Eddy County, NM (NAD83)
 Reference Site: Big Sinks Draw 25-24
 Site Error: 0.00 usft
 Reference Well: 711H
 Well Error: 0.00 usft
 Reference Wellbore: OH
 Reference Design: Prelim Plan

Local Co-ordinate Reference: Well 711H
 TVD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
 MD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature
 Output errors are at: 2.00 sigma
 Database: WellPlanner1
 Offset TVD Reference: Reference Datum

Offset Design Big Sinks Draw 25-24 - 331H - OH - Prelim Plan													Offset Site Error:	0.00 usft
Survey Program: 0-MWD+HDGM													Offset Well Error:	0.00 usft
Reference				Offset			Semi Major Axis			Distance				Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centras (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor		
5,200.00	5,196.62	5,187.08	5,178.14	18.28	18.61	33.92	68.40	-315.73	264.82	228.26	36.56	7.243		
5,300.00	5,295.79	5,286.79	5,277.60	18.63	18.98	35.39	70.21	-322.47	261.20	223.92	37.27	7.008		
5,400.00	5,394.96	5,386.50	5,377.07	18.99	19.35	36.89	72.02	-329.20	257.75	219.76	37.98	6.786		
5,500.00	5,494.13	5,486.20	5,476.53	19.34	19.72	38.44	73.83	-335.93	254.48	215.78	38.70	6.576		
5,600.00	5,593.30	5,585.91	5,575.99	19.70	20.09	40.03	75.64	-342.67	251.41	211.99	39.42	6.378		
5,700.00	5,692.47	5,685.61	5,675.45	20.06	20.46	41.65	77.45	-349.40	248.53	208.39	40.14	6.192		
5,800.00	5,791.64	5,785.32	5,774.91	20.42	20.83	43.31	79.26	-356.13	245.86	205.00	40.86	6.017		
5,900.00	5,890.81	5,885.03	5,874.38	20.78	21.19	45.01	81.07	-362.87	243.40	201.81	41.59	5.852		
6,000.00	5,989.98	5,984.73	5,973.84	21.15	21.56	46.74	82.88	-369.60	241.16	198.84	42.32	5.698		
6,100.00	6,089.15	6,084.44	6,073.30	21.51	21.93	48.50	84.69	-376.34	239.14	196.09	43.05	5.555		
6,200.00	6,188.32	6,184.15	6,172.76	21.88	22.30	50.28	86.50	-383.07	237.36	193.57	43.79	5.420		
6,300.00	6,287.50	6,283.85	6,272.22	22.25	22.67	52.10	88.31	-389.80	235.81	191.28	44.53	5.295		
6,400.00	6,386.67	6,383.56	6,371.69	22.62	23.04	53.93	90.12	-396.54	234.50	189.23	45.27	5.180		
6,500.00	6,485.84	6,483.26	6,471.15	22.99	23.41	55.78	91.93	-403.27	233.43	187.41	46.02	5.072		
6,600.00	6,585.01	6,582.97	6,570.61	23.36	23.78	57.65	93.74	-410.00	232.62	185.85	46.77	4.974		
6,700.00	6,684.18	6,682.68	6,670.07	23.73	24.14	59.53	95.55	-416.74	232.05	184.53	47.52	4.883		
6,800.00	6,783.35	6,782.38	6,769.53	24.10	24.51	61.41	97.36	-423.47	231.73	183.46	48.28	4.800		
6,874.80	6,857.53	6,856.96	6,843.93	24.38	24.79	62.83	98.71	-428.51	231.66	182.82	48.84	4.743		
6,900.00	6,882.52	6,882.09	6,869.00	24.48	24.88	63.30	99.17	-430.20	231.67	182.84	49.03	4.725		
7,000.00	6,981.69	6,981.79	6,968.46	24.85	25.25	65.19	100.98	-436.94	231.86	182.07	49.79	4.657		
7,100.00	7,080.86	7,081.50	7,067.92	25.23	25.62	67.07	102.79	-443.67	232.30	181.75	50.55	4.595		
7,200.00	7,180.03	7,181.21	7,167.38	25.60	25.99	68.95	104.60	-450.41	233.00	181.68	51.32	4.540		
7,300.00	7,279.20	7,280.91	7,266.84	25.98	26.36	70.81	106.41	-457.14	233.94	181.86	52.08	4.492		
7,400.00	7,378.37	7,380.62	7,366.31	26.36	26.73	72.65	108.22	-463.87	235.13	182.28	52.84	4.449		
7,500.00	7,477.54	7,480.32	7,465.77	26.74	27.10	74.48	110.03	-470.61	236.56	182.95	53.61	4.413		
7,600.00	7,576.71	7,580.03	7,565.23	27.12	27.47	76.28	111.84	-477.34	238.23	183.85	54.38	4.381		
7,700.00	7,675.88	7,679.74	7,664.69	27.50	27.84	78.05	113.65	-484.07	240.13	184.99	55.14	4.355		
7,800.00	7,775.06	7,779.44	7,764.15	27.88	28.20	79.79	115.46	-490.81	242.26	186.35	55.91	4.333		
7,900.00	7,874.23	7,879.15	7,863.62	28.26	28.57	81.51	117.27	-497.54	244.61	187.94	56.68	4.316		
8,000.00	7,973.40	7,978.86	7,963.08	28.64	28.94	83.18	119.08	-504.27	247.18	189.74	57.44	4.303		
8,100.00	8,072.57	8,078.56	8,062.54	29.02	29.31	84.83	120.89	-511.01	249.95	191.75	58.21	4.294		
8,200.00	8,171.74	8,178.27	8,162.00	29.41	29.68	86.43	122.70	-517.74	252.93	193.96	58.97	4.289		
8,300.00	8,270.91	8,277.97	8,261.46	29.79	30.05	88.00	124.51	-524.48	256.10	196.37	59.73	4.287 SF		
8,400.00	8,370.08	8,377.68	8,360.93	30.17	30.42	89.53	126.32	-531.21	259.46	198.96	60.50	4.289		
8,500.00	8,469.25	8,477.39	8,460.39	30.56	30.79	91.01	128.13	-537.94	263.00	201.74	61.26	4.293		
8,600.00	8,568.42	8,577.09	8,559.85	30.94	31.16	92.46	129.94	-544.68	266.71	204.69	62.02	4.300		
8,700.00	8,667.59	8,676.80	8,659.31	31.33	31.53	93.87	131.75	-551.41	270.59	207.81	62.78	4.310		
8,800.00	8,766.76	8,776.50	8,758.77	31.71	31.90	95.24	133.56	-558.14	274.63	211.09	63.54	4.322		
8,900.00	8,865.93	8,876.21	8,858.24	32.10	32.27	96.56	135.37	-564.88	278.82	214.52	64.29	4.337		
9,000.00	8,965.10	8,975.92	8,957.70	32.49	32.63	97.85	137.18	-571.61	283.15	218.10	65.05	4.353		
9,100.00	9,064.27	9,075.62	9,057.16	32.87	33.00	99.10	138.99	-578.34	287.63	221.82	65.80	4.371		
9,200.00	9,163.45	9,175.33	9,156.62	33.26	33.37	100.31	140.80	-585.08	292.23	225.68	66.56	4.391		
9,300.00	9,262.62	9,275.03	9,256.08	33.65	33.74	101.48	142.61	-591.81	296.97	229.66	67.31	4.412		
9,400.00	9,361.79	9,374.74	9,355.55	34.04	34.11	102.61	144.42	-598.55	301.82	233.76	68.06	4.435		
9,500.00	9,460.96	9,474.45	9,455.01	34.42	34.48	103.71	146.23	-605.28	306.78	237.97	68.81	4.458		
9,600.00	9,560.14	9,574.16	9,554.48	34.81	34.85	104.77	148.04	-612.01	311.84	242.28	69.56	4.483		
9,700.00	9,659.48	9,673.95	9,654.02	35.20	35.22	105.60	149.85	-618.75	316.63	246.33	70.30	4.504		
9,800.00	9,759.01	9,773.82	9,753.65	35.57	35.59	106.10	151.66	-625.50	321.00	249.95	71.05	4.518		
9,900.00	9,858.69	9,873.74	9,853.32	35.94	35.96	106.29	153.47	-632.25	324.89	253.10	71.78	4.526		
10,000.00	9,958.50	9,973.68	9,953.02	36.31	36.33	106.18	155.29	-638.99	328.29	255.77	72.52	4.527		
10,100.00	10,058.39	10,074.44	10,053.56	36.67	36.70	105.82	157.04	-645.50	331.15	257.89	73.25	4.521		
10,200.00	10,158.35	10,175.86	10,154.84	37.02	37.07	105.44	158.37	-650.48	333.15	259.17	73.98	4.503		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Pro Directional
Anticollision Report



Company: Devon Energy Corp.
Project: Eddy County, NM (NAD83)
Reference Site: Big Sinks Draw 25-24
Site Error: 0.00 usft
Reference Well: 711H
Well Error: 0.00 usft
Reference Wellbore: OH
Reference Design: Prelim Plan

Local Co-ordinate Reference: Well 711H
TVD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
MD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at: 2.00 sigma
Database: WellPlanner1
Offset TVD Reference: Reference Datum

Table with columns: Measured Depth (usft), Vertical Depth (usft), Offset, Semi Major Axis, Highside Toolface (degrees), Offset Wellbore Centre (+N/-S, +E/-W), Distance (Between Centres, Between Ellipses), Minimum Separation, Separation Factor, Warning. Includes 'Offset Design' and 'Survey Program: 0-MWD+HDGM' headers.

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Pro Directional Anticollision Report



Company: Devon Energy Corp.
 Project: Eddy County, NM (NAD83)
 Reference Site: Big Sinks Draw 25-24
 Site Error: 0.00 usft
 Reference Well: 711H
 Well Error: 0.00 usft
 Reference Wellbore: OH
 Reference Design: Prelim Plan

Local Co-ordinate Reference: Well 711H
 TVD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
 MD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature
 Output errors are at: 2.00 sigma
 Database: WellPlanner1
 Offset TVD Reference: Reference Datum

Offset Design Big Sinks Draw 25-24 - 331H - OH - Prelim Plan													Offset Site Error:	0.00 usft
Survey Program: 0-MWD+HDGM													Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis			Distance						Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Tooface (°)	Offset Wellbore Centre +N/-S (usft)	Offset Wellbore Centre +E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor		
15,300.00	11,838.00	14,374.76	11,268.00	65.93	64.11	-0.01	3,491.25	-664.96	570.00	497.66	72.34	7.880		
15,400.00	11,838.00	14,474.76	11,268.00	67.05	65.24	-0.01	3,591.25	-665.25	570.00	496.49	73.51	7.754		
15,500.00	11,838.00	14,574.76	11,268.00	68.18	66.38	-0.01	3,691.25	-665.54	570.00	495.29	74.71	7.630		
15,600.00	11,838.00	14,674.76	11,268.00	69.32	67.53	-0.01	3,791.25	-665.82	570.00	494.09	75.91	7.509		
15,700.00	11,838.00	14,774.76	11,268.00	70.48	68.69	-0.01	3,891.25	-666.11	570.00	492.87	77.13	7.390		
15,800.00	11,838.00	14,874.76	11,268.00	71.65	69.87	-0.01	3,991.25	-666.40	570.00	491.64	78.36	7.274		
15,900.00	11,838.00	14,974.76	11,268.00	72.82	71.05	-0.01	4,091.25	-666.69	570.00	490.39	79.61	7.160		
16,000.00	11,838.00	15,074.76	11,268.00	74.01	72.24	-0.01	4,191.25	-666.98	570.00	489.14	80.86	7.049		
16,100.00	11,838.00	15,174.76	11,268.00	75.20	73.44	-0.01	4,291.25	-667.27	570.00	487.87	82.13	6.940		
16,200.00	11,838.00	15,274.76	11,268.00	76.41	74.66	-0.01	4,391.25	-667.56	570.00	486.59	83.41	6.834		
16,300.00	11,838.00	15,374.76	11,268.00	77.62	75.88	-0.01	4,491.25	-667.85	570.00	485.31	84.69	6.730		
16,400.00	11,838.00	15,474.76	11,268.00	78.84	77.10	-0.01	4,591.25	-668.13	570.00	484.01	85.99	6.629		
16,500.00	11,838.00	15,574.76	11,268.00	80.07	78.34	-0.01	4,691.25	-668.42	570.00	482.71	87.29	6.530		
16,600.00	11,838.00	15,674.76	11,268.00	81.30	79.58	-0.01	4,791.25	-668.71	570.00	481.39	88.61	6.433		
16,700.00	11,838.00	15,774.76	11,268.00	82.54	80.83	-0.01	4,891.25	-669.00	570.00	480.07	89.93	6.338		
16,800.00	11,838.00	15,874.76	11,268.00	83.79	82.08	-0.01	4,991.24	-669.29	570.00	478.74	91.26	6.246		
16,900.00	11,838.00	15,974.76	11,268.00	85.05	83.35	-0.01	5,091.24	-669.58	570.00	477.41	92.59	6.156		
17,000.00	11,838.00	16,074.76	11,268.00	86.31	84.61	0.00	5,191.24	-669.87	570.00	476.06	93.94	6.068		
17,100.00	11,838.00	16,174.76	11,268.00	87.57	85.89	0.00	5,291.24	-670.16	570.00	474.71	95.29	5.982		
17,200.00	11,838.00	16,274.76	11,268.00	88.84	87.17	0.00	5,391.24	-670.44	570.00	473.35	96.65	5.898		
17,300.00	11,838.00	16,374.76	11,268.00	90.12	88.45	0.00	5,491.24	-670.73	570.00	471.99	98.01	5.816		
17,400.00	11,838.00	16,474.76	11,268.00	91.40	89.74	0.00	5,591.24	-671.02	570.00	470.62	99.38	5.736		
17,500.00	11,838.00	16,574.76	11,268.00	92.69	91.03	0.00	5,691.24	-671.31	570.00	469.24	100.76	5.657		
17,600.00	11,838.00	16,674.76	11,268.00	93.98	92.33	0.00	5,791.24	-671.60	570.00	467.86	102.14	5.581		
17,700.00	11,838.00	16,774.76	11,268.00	95.28	93.63	0.00	5,891.24	-671.89	570.00	466.48	103.53	5.506		
17,800.00	11,838.00	16,874.76	11,268.00	96.58	94.94	0.00	5,991.24	-672.18	570.00	465.08	104.92	5.433		
17,900.00	11,838.00	16,974.76	11,268.00	97.89	96.25	0.00	6,091.24	-672.46	570.00	463.69	106.31	5.361		
18,000.00	11,838.00	17,074.76	11,268.00	99.20	97.57	0.00	6,191.24	-672.75	570.00	462.28	107.72	5.292		
18,100.00	11,838.00	17,174.76	11,268.00	100.51	98.89	0.00	6,291.24	-673.04	570.00	460.88	109.12	5.224		
18,200.00	11,838.00	17,274.76	11,268.00	101.83	100.21	0.00	6,391.24	-673.33	570.00	459.47	110.53	5.157		
18,300.00	11,838.00	17,374.76	11,268.00	103.15	101.53	0.00	6,491.24	-673.62	570.00	458.05	111.95	5.092		
18,400.00	11,838.00	17,474.76	11,268.00	104.47	102.86	0.00	6,591.24	-673.91	570.00	456.63	113.37	5.028		
18,500.00	11,838.00	17,574.76	11,268.00	105.80	104.20	0.00	6,691.24	-674.20	570.00	455.21	114.79	4.966		
18,600.00	11,838.00	17,674.76	11,268.00	107.13	105.53	0.00	6,791.24	-674.49	570.00	453.78	116.22	4.905		
18,700.00	11,838.00	17,774.76	11,268.00	108.46	106.87	0.00	6,891.24	-674.77	570.00	452.35	117.65	4.845		
18,800.00	11,838.00	17,874.76	11,268.00	109.79	108.21	0.00	6,991.24	-675.06	570.00	450.92	119.08	4.787		
18,900.00	11,838.00	17,974.76	11,268.00	111.13	109.55	0.00	7,091.24	-675.35	570.00	449.48	120.52	4.730		
19,000.00	11,838.00	18,074.76	11,268.00	112.47	110.90	0.00	7,191.24	-675.64	570.00	448.04	121.96	4.674		
19,100.00	11,838.00	18,174.76	11,268.00	113.82	112.25	0.00	7,291.24	-675.93	570.00	446.60	123.40	4.619		
19,200.00	11,838.00	18,274.76	11,268.00	115.16	113.60	0.00	7,391.23	-676.22	570.00	445.15	124.85	4.566		
19,238.78	11,838.00	18,313.53	11,268.00	115.69	114.13	0.00	7,430.01	-676.33	570.00	444.59	125.41	4.545		



Pro Directional
Anticollision Report



Company: Devon Energy Corp.
Project: Eddy County, NM (NAD83)
Reference Site: Big Sinks Draw 25-24
Site Error: 0.00 usft
Reference Well: 711H
Well Error: 0.00 usft
Reference Wellbore: OH
Reference Design: Prelim Plan

Local Co-ordinate Reference: Well 711H
TVD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
MD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at: 2.00 sigma
Database: WellPlanner1
Offset TVD Reference: Reference Datum

Table with columns: Reference, Offset, Semi Major Axis, Distance, Warning. Includes sub-headers for Measured Depth, Vertical Depth, Reference, Offset, Highside Tooface, Offset Wellbore Centre, Between Centres, Between Ellipses, Minimum Separation, Separation Factor.

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation



Pro Directional Anticollision Report



Company: Devon Energy Corp.
Project: Eddy County, NM (NAD83)
Reference Site: Big Sinks Draw 25-24
Site Error: 0.00 usft
Reference Well: 711H
Well Error: 0.00 usft
Reference Wellbore: OH
Reference Design: Prelim Plan

Local Co-ordinate Reference: Well 711H
TVD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
MD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at 2.00 sigma
Database: WellPlanner1
Offset TVD Reference: Reference Datum

Offset Design Big Sinks Draw 25-24 - 521H - OH - Prelim Plan													Offset Site Error:	0.00 usft
Survey Program: 0-MWD+HDGM													Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis			Distance						Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor		
5,200.00	5,196.62	5,173.31	5,161.01	18.28	18.65	44.28	149.64	-360.34	340.45	303.90	36.55	9.314		
5,300.00	5,295.79	5,273.26	5,260.23	18.63	19.03	44.80	149.64	-372.34	341.73	304.46	37.28	9.168		
5,400.00	5,394.96	5,373.20	5,359.45	18.99	19.42	45.31	149.64	-384.34	343.05	305.04	38.00	9.027		
5,500.00	5,494.13	5,473.14	5,458.67	19.34	19.81	45.83	149.64	-396.34	344.38	305.65	38.73	8.892		
5,600.00	5,593.30	5,573.09	5,557.89	19.70	20.19	46.33	149.64	-408.34	345.75	306.29	39.46	8.762		
5,700.00	5,692.47	5,673.03	5,657.11	20.06	20.58	46.84	149.64	-420.35	347.14	306.95	40.19	8.637		
5,800.00	5,791.64	5,772.98	5,756.33	20.42	20.97	47.34	149.64	-432.35	348.56	307.64	40.93	8.517		
5,900.00	5,890.81	5,872.92	5,855.55	20.78	21.36	47.83	149.64	-444.35	350.01	308.35	41.66	8.401		
6,000.00	5,989.98	5,972.86	5,954.77	21.15	21.74	48.32	149.64	-456.35	351.48	309.08	42.40	8.290		
6,100.00	6,089.15	6,072.81	6,054.00	21.51	22.13	48.81	149.64	-468.36	352.98	309.84	43.14	8.182		
6,200.00	6,188.32	6,172.75	6,153.22	21.88	22.52	49.29	149.64	-480.36	354.50	310.62	43.88	8.079		
6,300.00	6,287.50	6,272.70	6,252.44	22.25	22.91	49.77	149.64	-492.36	356.05	311.42	44.62	7.979		
6,400.00	6,386.67	6,372.64	6,351.66	22.62	23.30	50.24	149.64	-504.36	357.62	312.25	45.37	7.882		
6,500.00	6,485.84	6,472.58	6,450.88	22.99	23.69	50.71	149.64	-516.37	359.22	313.10	46.12	7.789		
6,600.00	6,585.01	6,572.53	6,550.10	23.36	24.08	51.18	149.64	-528.37	360.84	313.97	46.87	7.699		
6,700.00	6,684.18	6,672.47	6,649.32	23.73	24.47	51.64	149.64	-540.37	362.48	314.87	47.62	7.613		
6,800.00	6,783.35	6,772.42	6,748.54	24.10	24.86	52.10	149.64	-552.37	364.15	315.78	48.37	7.529		
6,900.00	6,882.52	6,872.36	6,847.76	24.48	25.25	52.55	149.64	-564.37	365.84	316.72	49.12	7.448		
7,000.00	6,981.69	6,972.30	6,946.98	24.85	25.64	53.00	149.64	-576.38	367.55	317.68	49.88	7.369		
7,100.00	7,080.86	7,072.25	7,046.20	25.23	26.03	53.45	149.64	-588.38	369.29	318.66	50.63	7.294		
7,200.00	7,180.03	7,172.19	7,145.42	25.60	26.42	53.89	149.64	-600.38	371.04	319.66	51.39	7.220		
7,300.00	7,279.20	7,272.14	7,244.64	25.98	26.81	54.32	149.64	-612.38	372.82	320.68	52.15	7.149		
7,400.00	7,378.37	7,376.69	7,348.53	26.36	27.21	54.85	149.64	-624.20	374.09	321.14	52.95	7.065		
7,500.00	7,477.54	7,481.83	7,453.19	26.74	27.62	55.56	149.64	-634.19	373.99	320.25	53.74	6.959		
7,600.00	7,576.71	7,586.82	7,557.86	27.12	28.01	56.47	149.64	-642.24	372.58	318.04	54.53	6.832		
7,700.00	7,675.88	7,691.58	7,662.45	27.50	28.39	57.59	149.64	-648.37	369.90	314.59	55.32	6.687		
7,800.00	7,775.06	7,796.07	7,766.85	27.88	28.77	58.92	149.64	-652.57	366.05	309.95	56.09	6.526		
7,900.00	7,874.23	7,900.19	7,870.95	28.26	29.13	60.49	149.64	-654.86	361.10	304.24	56.86	6.351		
8,000.00	7,973.40	8,002.64	7,973.40	28.64	29.48	62.29	149.64	-655.34	355.22	297.61	57.62	6.165		
8,100.00	8,072.57	8,101.81	8,072.57	29.02	29.81	64.14	149.64	-655.34	349.39	291.02	58.37	5.986		
8,200.00	8,171.74	8,200.98	8,171.74	29.41	30.14	66.05	149.64	-655.34	343.94	284.81	59.13	5.817		
8,300.00	8,270.91	8,291.85	8,262.60	29.79	30.44	67.89	149.91	-655.34	339.21	279.32	59.88	5.664		
8,324.25	8,294.96	8,308.11	8,278.85	29.88	30.49	68.29	150.64	-655.34	338.92	278.88	60.04	5.645 SF		
8,400.00	8,370.08	8,358.26	8,328.71	30.17	30.66	69.80	155.78	-655.36	341.83	281.49	60.34	5.665		
8,500.00	8,469.25	8,421.99	8,391.12	30.56	30.87	72.24	168.57	-655.39	354.84	294.55	60.29	5.886		
8,600.00	8,568.42	8,481.77	8,448.01	30.94	31.05	74.89	186.80	-655.45	378.45	318.75	59.70	6.340		
8,700.00	8,667.59	8,536.77	8,498.43	31.33	31.21	77.47	208.72	-655.51	412.33	353.70	58.63	7.033		
8,800.00	8,766.76	8,586.66	8,542.16	31.71	31.35	79.83	232.70	-655.58	455.66	398.44	57.22	7.963		
8,900.00	8,865.93	8,631.46	8,579.53	32.10	31.46	81.88	257.41	-655.65	507.31	451.66	55.65	9.117		
9,000.00	8,965.10	8,671.46	8,611.16	32.49	31.56	83.62	281.88	-655.72	566.07	512.04	54.02	10.478		
9,100.00	9,064.27	8,700.00	8,632.65	32.87	31.63	84.80	300.65	-655.78	630.87	578.75	52.11	12.106		
9,200.00	9,163.45	8,750.00	8,667.95	33.26	31.73	86.71	336.04	-655.88	700.66	649.14	51.52	13.599		
9,300.00	9,262.62	8,786.84	8,679.13	33.65	31.77	87.31	348.63	-655.91	774.25	724.56	49.69	15.583		
9,400.00	9,361.79	8,800.00	8,700.03	34.04	31.83	88.43	374.37	-655.99	851.54	802.70	48.84	17.435		
9,500.00	9,460.96	8,814.35	8,708.61	34.42	31.86	88.89	385.87	-656.02	931.48	883.99	47.49	19.615		
9,600.00	9,560.14	8,834.46	8,720.14	34.81	31.90	89.97	402.34	-656.07	1,013.90	967.30	46.60	21.759		
9,700.00	9,659.48	8,850.00	8,728.65	35.20	31.93	91.97	415.35	-656.11	1,098.32	1,052.58	45.74	24.010		
9,800.00	9,759.01	8,869.26	8,738.71	35.57	31.96	94.09	431.78	-656.15	1,184.38	1,139.21	45.17	26.220		
9,900.00	9,858.69	8,900.00	8,753.59	35.94	32.02	96.39	458.67	-656.23	1,272.13	1,227.09	45.04	28.242		
10,000.00	9,958.50	8,900.00	8,753.59	36.31	32.02	98.26	458.67	-656.23	1,360.42	1,316.24	44.18	30.791		
10,100.00	10,058.39	8,900.00	8,753.59	36.67	32.02	100.26	458.67	-656.23	1,450.12	1,406.65	43.48	33.353		
10,200.00	10,158.35	8,923.02	8,763.78	37.02	32.07	102.49	479.31	-656.29	1,540.33	1,496.92	43.42	35.477		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Pro Directional
Anticollision Report



Company: Devon Energy Corp.
 Project: Eddy County, NM (NAD83)
 Reference Site: Big Sinks Draw 25-24
 Site Error: 0.00 usft
 Reference Well: 711H
 Well Error: 0.00 usft
 Reference Wellbore: OH
 Reference Design: Prelim Plan

Local Co-ordinate Reference: Well 711H
 TVD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
 MD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature
 Output errors are at: 2.00 sigma
 Database: WellPlanner1
 Offset TVD Reference: Reference Datum

Offset Design													Offset Site Error:	0.00 usft
Survey Program: D-MWD+HDGM													Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis			Distance						Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	Offset Wellbore Centre +E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor		
10,300.00	10,258.35	8,950.00	8,774.66	37.36	32.13	104.65	503.99	-656.36	1,631.68	1,588.19	43.49	37.518		
10,400.00	10,358.35	8,950.00	8,774.66	37.70	32.13	-0.18	503.99	-656.36	1,723.11	1,680.05	43.07	40.011		
10,500.00	10,458.35	8,950.00	8,774.66	38.04	32.13	-0.18	503.99	-656.36	1,815.45	1,772.71	42.74	42.481		
10,600.00	10,558.35	8,950.00	8,774.66	38.38	32.13	-0.18	503.99	-656.36	1,908.56	1,866.07	42.49	44.921		
10,700.00	10,658.35	8,970.27	8,782.06	38.72	32.17	-0.18	522.86	-656.42	2,001.87	1,959.24	42.63	46.958		
10,800.00	10,758.35	8,977.75	8,784.62	39.06	32.19	-0.18	529.89	-656.44	2,095.83	2,053.22	42.61	49.191		
10,900.00	10,858.35	9,000.00	8,791.69	39.40	32.25	-0.18	550.98	-656.50	2,190.46	2,147.63	42.83	51.139		
11,000.00	10,958.35	9,000.00	8,791.69	39.74	32.25	-0.18	550.98	-656.50	2,285.05	2,242.28	42.77	53.422		
11,100.00	11,058.35	9,000.00	8,791.69	40.09	32.25	-0.18	550.98	-656.50	2,380.08	2,337.32	42.76	55.665		
11,200.00	11,158.35	9,000.00	8,791.69	40.43	32.25	-0.18	550.98	-656.50	2,475.50	2,432.72	42.78	57.865		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Pro Directional Anticollision Report



Company: Devon Energy Corp.
Project: Eddy County, NM (NAD83)
Reference Site: Big Sinks Draw 25-24
Site Error: 0.00 usft
Reference Well: 711H
Well Error: 0.00 usft
Reference Wellbore: OH
Reference Design: Prelim Plan

Local Co-ordinate Reference: Well 711H
TVD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
MD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at: 2.00 sigma
Database: WellPlanner1
Offset TVD Reference: Reference Datum

Offset Design Big Sinks Draw 25-24 - 531H - OH - Prelm Plan													Offset Site Error:	0.00 usft
Survey Program: 0-MWD+HDGM													Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis			Distance				Warning			
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Tooface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)		Minimum Separation (usft)	Separation Factor	
0.00	0.00	0.00	0.00	0.00	0.00	-11.49	149.82	-30.46	152.89					
100.00	100.00	100.00	100.00	0.13	-0.13	-11.49	149.82	-30.46	152.89	152.62	0.27	576.339		
200.00	200.00	200.00	200.00	0.49	0.49	-11.49	149.82	-30.46	152.89	151.90	0.98	155.654		
300.00	300.00	300.00	300.00	0.85	0.85	-11.49	149.82	-30.46	152.89	151.19	1.70	89.977		
400.00	400.00	400.00	400.00	1.21	1.21	-11.49	149.82	-30.46	152.89	150.47	2.42	63.278		
500.00	500.00	500.00	500.00	1.57	1.57	-11.49	149.82	-30.46	152.89	149.75	3.13	48.798		
600.00	600.00	600.00	600.00	1.92	1.92	-11.49	149.82	-30.46	152.89	149.04	3.85	39.711		
700.00	700.00	700.00	700.00	2.28	2.28	-11.49	149.82	-30.46	152.89	148.32	4.57	33.477		
800.00	800.00	800.00	800.00	2.64	2.64	-11.49	149.82	-30.46	152.89	147.60	5.28	28.934		
900.00	900.00	900.00	900.00	3.00	3.00	-11.49	149.82	-30.46	152.89	146.88	6.00	25.477		
1,000.00	1,000.00	1,000.00	1,000.00	3.36	3.36	-11.49	149.82	-30.46	152.89	146.17	6.72	22.758		
1,100.00	1,100.00	1,100.00	1,100.00	3.72	3.72	-11.49	149.82	-30.46	152.89	145.45	7.43	20.564		
1,200.00	1,200.00	1,200.00	1,200.00	4.08	4.08	-11.49	149.82	-30.46	152.89	144.73	8.15	18.755		
1,300.00	1,300.00	1,300.00	1,300.00	4.43	4.43	-11.49	149.82	-30.46	152.89	144.02	8.87	17.239		
1,400.00	1,400.00	1,400.00	1,400.00	4.79	4.79	-11.49	149.82	-30.46	152.89	143.30	9.59	15.950		
1,500.00	1,500.00	1,500.00	1,500.00	5.15	5.15	-11.49	149.82	-30.46	152.89	142.58	10.30	14.840	CC	
1,600.00	1,600.00	1,599.73	1,599.73	5.51	5.50	-11.65	149.82	-30.89	152.97	141.96	11.01	13.894		
1,700.00	1,700.00	1,699.45	1,699.44	5.87	5.84	-12.13	149.82	-32.20	153.24	141.53	11.71	13.087		
1,800.00	1,800.00	1,799.14	1,799.10	6.23	6.19	-12.92	149.82	-34.36	153.71	141.30	12.41	12.385		
1,900.00	1,900.00	1,901.12	1,898.81	6.59	6.54	-14.00	149.82	-37.36	154.41	141.29	13.12	11.766	ES	
2,000.00	2,000.00	2,001.17	1,998.70	6.94	6.89	-15.14	149.82	-40.55	155.22	141.39	13.83	11.223		
2,100.00	2,100.00	2,101.22	2,098.60	7.30	7.24	-16.28	149.82	-43.75	156.08	141.54	14.54	10.736		
2,200.00	2,200.00	2,201.27	2,198.50	7.66	7.59	-17.40	149.82	-46.94	157.01	141.76	15.25	10.298		
2,300.00	2,300.00	2,301.32	2,298.40	8.02	7.94	-18.50	149.82	-50.14	157.99	142.04	15.96	9.901		
2,400.00	2,400.00	2,401.37	2,398.29	8.38	8.29	-19.59	149.82	-53.33	159.04	142.37	16.67	9.542		
2,500.00	2,500.00	2,501.42	2,498.19	8.74	8.64	-20.67	149.82	-56.53	160.14	142.76	17.38	9.214		
2,600.00	2,600.00	2,601.47	2,598.09	9.09	9.00	-21.73	149.82	-59.72	161.30	143.20	18.09	8.916		
2,700.00	2,700.00	2,701.52	2,697.99	9.45	9.35	-22.78	149.82	-62.92	162.51	143.70	18.80	8.642		
2,800.00	2,800.00	2,801.58	2,797.89	9.81	9.71	-23.81	149.82	-66.11	163.77	144.25	19.52	8.391		
2,900.00	2,900.00	2,901.63	2,897.78	10.17	10.06	-24.83	149.82	-69.31	165.09	144.86	20.23	8.160		
3,000.00	3,000.00	3,001.68	2,997.68	10.53	10.42	-25.82	149.82	-72.50	166.46	145.51	20.94	7.947		
3,100.00	3,100.00	3,101.73	3,097.58	10.89	10.78	-26.81	149.82	-75.70	167.87	146.22	21.66	7.751		
3,200.00	3,200.00	3,201.78	3,197.48	11.25	11.13	-27.77	149.82	-78.89	169.34	146.97	22.37	7.569		
3,300.00	3,300.00	3,301.83	3,297.37	11.60	11.49	-28.72	149.82	-82.09	170.85	147.77	23.09	7.400		
3,400.00	3,400.00	3,401.88	3,397.27	11.96	11.85	-29.65	149.82	-85.28	172.41	148.61	23.80	7.243		
3,500.00	3,500.00	3,501.93	3,497.17	12.32	12.20	-30.56	149.82	-88.48	174.02	149.50	24.52	7.097		
3,600.00	3,600.00	3,601.98	3,597.07	12.68	12.56	-31.46	149.82	-91.67	175.67	150.43	25.23	6.961		
3,700.00	3,700.00	3,702.04	3,696.97	13.04	12.92	-32.34	149.82	-94.87	177.36	151.41	25.95	6.834		
3,800.00	3,800.00	3,802.09	3,796.86	13.40	13.28	-33.21	149.82	-98.06	179.09	152.42	26.67	6.716		
3,900.00	3,900.00	3,902.14	3,896.76	13.75	13.64	-34.05	149.82	-101.26	180.86	153.48	27.38	6.605		
4,000.00	4,000.00	4,002.19	3,996.66	14.11	13.99	-34.88	149.82	-104.45	182.67	154.57	28.10	6.501		
4,100.00	4,100.00	4,102.24	4,096.56	14.47	14.35	-35.70	149.82	-107.65	184.51	155.70	28.81	6.404		
4,200.00	4,200.00	4,202.29	4,196.45	14.83	14.71	-36.50	149.82	-110.84	186.40	156.87	29.53	6.312		
4,300.00	4,300.00	4,302.34	4,296.35	15.19	15.07	-37.28	149.82	-114.04	188.32	158.07	30.25	6.226		
4,400.00	4,400.00	4,402.37	4,396.27	15.54	15.43	-37.16	149.82	-117.23	189.93	158.98	30.95	6.136		
4,500.00	4,499.96	4,502.38	4,496.22	15.87	15.79	-37.12	149.82	-120.43	190.88	159.23	31.65	6.031		
4,600.00	4,599.86	4,602.39	4,596.15	16.21	16.15	-37.56	149.82	-123.63	191.15	158.80	32.34	5.910		
4,700.00	4,699.68	4,697.56	4,696.05	16.55	16.49	-38.50	149.82	-126.82	190.78	157.76	33.02	5.777		
4,800.00	4,799.37	4,802.56	4,795.88	16.89	16.87	-39.93	149.82	-130.01	189.86	156.12	33.74	5.627		
4,900.00	4,899.90	4,902.78	4,895.61	17.23	17.23	-41.89	149.82	-133.20	188.51	154.07	34.45	5.472		
5,000.00	4,998.26	5,003.12	4,995.22	17.58	17.59	-44.38	149.82	-136.39	186.91	151.75	35.16	5.317		
5,100.00	5,097.45	5,103.59	5,094.70	17.93	17.95	-47.31	149.82	-139.57	185.34	149.47	35.87	5.167		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Pro Directional
Anticollision Report



Company: Devon Energy Corp.
Project: Eddy County, NM (NAD83)
Reference Site: Big Sinks Draw 25-24
Site Error: 0.00 usft
Reference Well: 711H
Well Error: 0.00 usft
Reference Wellbore: OH
Reference Design: Prelim Plan

Local Co-ordinate Reference: Well 711H
TVD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
MD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at: 2.00 sigma
Database: WellPlanner1
Offset TVD Reference: Reference Datum

Table with columns: Reference, Offset, Semi Major Axis, Distance, Measured Depth, Vertical Depth, Reference, Offset, Highside Tooface, Offset Wellbore Centre, Between Centres, Between Ellipse, Minimum Separation, Separation Factor, Warning. Includes data rows for various depths from 5,200.00 to 10,200.00.

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Pro Directional
Anticollision Report



Company: Devon Energy Corp.
Project: Eddy County, NM (NAD83)
Reference Site: Big Sinks Draw 25-24
Site Error: 0.00 usft
Reference Well: 711H
Well Error: 0.00 usft
Reference Wellbore: OH
Reference Design: Prelim Plan

Local Co-ordinate Reference: Well 711H
TVD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
MD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at: 2.00 sigma
Database: WellPlanner1
Offset TVD Reference: Reference Datum

Offset Design													Offset Site Error:	0.00 usft
Big Sinks Draw 25-24 - 531H - OH - Prelm Plan													Offset Well Error:	0.00 usft
Survey Program: 0-MWD+HDGM														
Reference		Offset		Semi Major Axis			Distance						Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor		
10,300.00	10,258.35	9,150.00	9,026.33	37.36	32.12	138.07	464.19	-236.44	1,449.47	1,402.74	46.73	31.015		
10,400.00	10,358.35	9,150.00	9,026.33	37.70	32.12	33.17	464.19	-236.44	1,535.38	1,489.41	45.97	33.403		
10,500.00	10,458.35	9,170.32	9,035.17	38.04	32.19	32.43	482.48	-236.44	1,622.42	1,576.69	45.73	35.479		
10,600.00	10,558.35	9,181.09	9,039.60	38.38	32.23	32.05	492.30	-236.44	1,710.68	1,665.29	45.39	37.691		
10,700.00	10,658.35	9,200.00	9,046.92	38.72	32.29	31.39	509.73	-236.44	1,800.03	1,754.76	45.27	39.763		
10,800.00	10,758.35	9,200.00	9,046.92	39.06	32.29	31.39	509.73	-236.44	1,890.08	1,845.18	44.90	42.100		
10,900.00	10,858.35	9,200.00	9,046.92	39.40	32.29	31.39	509.73	-236.44	1,981.08	1,936.48	44.60	44.415		
11,000.00	10,958.35	9,200.00	9,046.92	39.74	32.29	31.39	509.73	-236.44	2,072.91	2,028.53	44.39	46.702		
11,100.00	11,058.35	9,223.86	9,055.32	40.09	32.37	30.58	532.06	-236.44	2,164.85	2,120.29	44.55	48.589		
11,200.00	11,158.35	9,230.89	9,057.56	40.43	32.39	30.35	538.52	-236.44	2,257.64	2,213.12	44.52	50.705		
11,300.00	11,258.35	9,250.00	9,063.46	40.77	32.45	29.72	556.90	-236.44	2,351.12	2,306.43	44.69	52.609		
11,400.00	11,357.94	9,250.00	9,063.46	41.11	32.45	21.15	556.90	-236.44	2,442.09	2,397.51	44.58	54.784		



Pro Directional
Anticollision Report



Company: Devon Energy Corp.
Project: Eddy County, NM (NAD83)
Reference Site: Big Sinks Draw 25-24
Site Error: 0.00 usft
Reference Well: 711H
Well Error: 0.00 usft
Reference Wellbore: OH
Reference Design: Prelim Plan

Local Co-ordinate Reference: Well 711H
TVD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
MD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at: 2.00 sigma
Database: WellPlanner1
Offset TVD Reference: Reference Datum

Offset Design Big Sinks Draw 25-24 - 611H - OH - Prelim Plan													Offset Site Error:	0.00 usft
Survey Program: 0-MWD+HDGM													Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis			Distance						Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor		
0.00	0.00	0.00	0.00	0.00	0.00	-90.31	-0.16	-29.97	29.97					
100.00	100.00	100.00	100.00	0.13	0.13	-90.31	-0.16	-29.97	29.97	29.71	0.27	112.981		
200.00	200.00	200.00	200.00	0.49	0.49	-90.31	-0.16	-29.97	29.97	28.99	0.98	30.513		
300.00	300.00	300.00	300.00	0.85	0.85	-90.31	-0.16	-29.97	29.97	28.27	1.70	17.638		
400.00	400.00	400.00	400.00	1.21	1.21	-90.31	-0.16	-29.97	29.97	27.55	2.42	12.404		
500.00	500.00	500.00	500.00	1.57	1.57	-90.31	-0.16	-29.97	29.97	26.84	3.13	9.566		
600.00	600.00	600.00	600.00	1.92	1.92	-90.31	-0.16	-29.97	29.97	26.12	3.85	7.785		
700.00	700.00	700.00	700.00	2.28	2.28	-90.31	-0.16	-29.97	29.97	25.40	4.57	6.562		
800.00	800.00	800.00	800.00	2.64	2.64	-90.31	-0.16	-29.97	29.97	24.69	5.28	5.672		
900.00	900.00	900.00	900.00	3.00	3.00	-90.31	-0.16	-29.97	29.97	23.97	6.00	4.994		
1,000.00	1,000.00	1,000.00	1,000.00	3.36	3.36	-90.31	-0.16	-29.97	29.97	23.25	6.72	4.461		
1,100.00	1,100.00	1,100.00	1,100.00	3.72	3.72	-90.31	-0.16	-29.97	29.97	22.54	7.43	4.031		
1,200.00	1,200.00	1,200.00	1,200.00	4.08	4.08	-90.31	-0.16	-29.97	29.97	21.82	8.15	3.677		
1,300.00	1,300.00	1,300.00	1,300.00	4.43	4.43	-90.31	-0.16	-29.97	29.97	21.10	8.87	3.379		
1,400.00	1,400.00	1,400.00	1,400.00	4.79	4.79	-90.31	-0.16	-29.97	29.97	20.38	9.59	3.127		
1,500.00	1,500.00	1,500.00	1,500.00	5.15	5.15	-90.31	-0.16	-29.97	29.97	19.67	10.30	2.909 CC		
1,600.00	1,600.00	1,599.74	1,599.74	5.51	5.50	-90.30	-0.16	-30.40	30.41	19.40	11.01	2.762 ES		
1,700.00	1,700.00	1,699.46	1,699.45	5.87	5.84	-90.29	-0.16	-31.71	31.71	20.00	11.71	2.709		
1,800.00	1,800.00	1,799.15	1,799.12	6.23	6.19	-90.27	-0.16	-33.87	33.89	21.48	12.41	2.731		
1,900.00	1,900.00	1,898.80	1,898.72	6.59	6.53	-90.25	-0.16	-36.91	36.93	23.82	13.11	2.818		
2,000.00	2,000.00	1,998.38	1,998.22	6.94	6.88	-90.22	-0.16	-40.81	40.85	27.04	13.81	2.958		
2,100.00	2,100.00	2,097.89	2,097.62	7.30	7.23	-90.20	-0.16	-45.56	45.63	31.12	14.51	3.145		
2,200.00	2,200.00	2,197.31	2,196.88	7.66	7.58	-90.18	-0.16	-51.18	51.28	36.07	15.21	3.372		
2,300.00	2,300.00	2,296.63	2,295.99	8.02	7.93	-90.16	-0.16	-57.65	57.79	41.88	15.91	3.633		
2,400.00	2,400.00	2,404.06	2,395.02	8.38	8.31	-90.14	-0.16	-64.96	65.15	48.52	16.63	3.917		
2,500.00	2,500.00	2,504.36	2,494.44	8.74	8.67	-90.13	-0.16	-72.57	72.79	55.44	17.34	4.196		
2,600.00	2,600.00	2,595.35	2,593.86	9.09	9.00	-90.11	-0.16	-80.19	80.42	62.40	18.02	4.462		
2,700.00	2,700.00	2,704.94	2,693.28	9.45	9.39	-90.10	-0.16	-87.80	88.06	69.29	18.77	4.692		
2,800.00	2,800.00	2,805.23	2,792.69	9.81	9.75	-90.10	-0.16	-95.42	95.70	76.22	19.48	4.912		
2,900.00	2,900.00	2,905.52	2,892.11	10.17	10.12	-90.09	-0.16	-103.03	103.33	83.14	20.19	5.117		
3,000.00	3,000.00	3,005.82	2,991.53	10.53	10.48	-90.08	-0.16	-110.65	110.97	90.06	20.91	5.307		
3,100.00	3,100.00	3,106.11	3,090.94	10.89	10.85	-90.08	-0.16	-118.26	118.61	96.98	21.62	5.485		
3,200.00	3,200.00	3,206.40	3,190.36	11.25	11.21	-90.07	-0.16	-125.87	126.24	103.91	22.34	5.651		
3,300.00	3,300.00	3,306.69	3,289.78	11.60	11.58	-90.07	-0.16	-133.49	133.88	110.83	23.05	5.807		
3,400.00	3,400.00	3,406.98	3,389.19	11.96	11.94	-90.06	-0.16	-141.10	141.52	117.75	23.77	5.954		
3,500.00	3,500.00	3,507.28	3,488.61	12.32	12.31	-90.06	-0.16	-148.72	149.15	124.67	24.49	6.092		
3,600.00	3,600.00	3,607.57	3,588.03	12.68	12.68	-90.06	-0.16	-156.33	156.79	131.59	25.20	6.221		
3,700.00	3,700.00	3,692.14	3,687.44	13.04	12.99	-90.06	-0.16	-163.95	164.43	138.57	25.86	6.358		
3,800.00	3,800.00	3,808.15	3,786.86	13.40	13.41	-90.05	-0.16	-171.56	172.06	145.43	26.64	6.460		
3,900.00	3,900.00	3,908.44	3,886.28	13.75	13.78	-90.05	-0.16	-179.18	179.70	152.35	27.35	6.570		
4,000.00	4,000.00	4,008.74	3,985.69	14.11	14.15	-90.05	-0.16	-186.79	187.34	159.27	28.07	6.674		
4,100.00	4,100.00	4,109.03	4,085.11	14.47	14.52	-90.05	-0.16	-194.40	194.97	166.19	28.79	6.773		
4,200.00	4,200.00	4,209.32	4,184.53	14.83	14.89	-90.05	-0.16	-202.02	202.61	173.11	29.50	6.867		
4,300.00	4,300.00	4,290.39	4,283.94	15.19	15.19	-90.04	-0.16	-209.63	210.25	180.09	30.15	6.973		
4,400.00	4,400.00	4,409.85	4,383.42	15.54	15.63	14.98	-0.16	-217.25	217.04	186.11	30.93	7.017		
4,500.00	4,499.96	4,509.98	4,482.99	15.87	16.00	15.14	-0.16	-224.88	222.16	190.53	31.62	7.025		
4,600.00	4,599.86	4,589.95	4,582.64	16.21	16.30	15.41	-0.16	-232.51	225.59	193.34	32.25	6.995		
4,700.00	4,699.68	4,689.93	4,682.31	16.55	16.67	15.80	-0.16	-240.14	227.35	194.41	32.95	6.901		
4,800.00	4,799.37	4,789.90	4,782.00	16.89	17.04	16.31	-0.16	-247.78	227.45	193.80	33.64	6.760		
4,900.00	4,898.90	4,889.86	4,881.66	17.23	17.41	16.95	-0.16	-255.41	225.89	191.55	34.34	6.577		
5,000.00	4,998.26	4,989.76	4,981.27	17.58	17.78	17.74	-0.16	-263.04	222.70	187.66	35.04	6.355		
5,100.00	5,097.45	5,089.60	5,080.82	17.93	18.14	18.67	-0.16	-270.67	218.21	182.47	35.75	6.105		

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation



Pro Directional Anticollision Report



Company: Devon Energy Corp.
Project: Eddy County, NM (NAD83)
Reference Site: Big Sinks Draw 25-24
Site Error: 0.00 usft
Reference Well: 711H
Well Error: 0.00 usft
Reference Wellbore: OH
Reference Design: Prelim Plan

Local Co-ordinate Reference: Well 711H
TVD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
MD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at 2.00 sigma
Database: WellPlanner1
Offset TVD Reference: Reference Datum

Offset Design Big Sinks Draw 25-24 - 611H - OH - Prelim Plan													Offset Site Error:	0.00 usft
Survey Program: 0-MWD+HDGM													Offset Well Error:	0.00 usft
Reference				Offset			Semi Major Axis			Distance				Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centras (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor		
5,200.00	5,196.62	5,189.42	5,180.36	18.28	18.51	19.65	-0.16	-278.29	213.66	177.21	36.45	5.862		
5,300.00	5,295.79	5,289.25	5,279.89	18.63	18.88	20.66	-0.16	-285.91	209.18	172.02	37.16	5.630		
5,400.00	5,394.96	5,389.08	5,379.43	18.99	19.25	21.72	-0.16	-293.54	204.76	166.90	37.86	5.408		
5,500.00	5,494.13	5,488.91	5,478.97	19.34	19.62	22.82	-0.16	-301.16	200.42	161.85	38.57	5.196		
5,600.00	5,593.30	5,588.74	5,578.51	19.70	19.99	23.98	-0.16	-308.79	196.15	156.87	39.28	4.993		
5,700.00	5,692.47	5,688.57	5,678.04	20.06	20.37	25.18	-0.16	-316.41	191.97	151.97	40.00	4.800		
5,800.00	5,791.64	5,788.40	5,777.58	20.42	20.74	26.44	-0.16	-324.03	187.88	147.16	40.71	4.614		
5,900.00	5,890.81	5,888.23	5,877.12	20.78	21.11	27.75	-0.16	-331.66	183.88	142.44	41.43	4.438		
6,000.00	5,989.98	5,988.06	5,976.66	21.15	21.48	29.12	-0.16	-339.28	179.98	137.82	42.16	4.269		
6,100.00	6,089.15	6,087.89	6,076.19	21.51	21.85	30.55	-0.16	-346.90	176.18	133.30	42.88	4.109		
6,200.00	6,188.32	6,187.72	6,175.73	21.88	22.22	32.04	-0.16	-354.53	172.51	128.90	43.61	3.956		
6,300.00	6,287.50	6,287.55	6,275.27	22.25	22.59	33.60	-0.16	-362.15	168.95	124.61	44.34	3.811		
6,400.00	6,386.67	6,387.37	6,374.81	22.62	22.96	35.22	-0.16	-369.77	165.53	120.45	45.07	3.672		
6,500.00	6,485.84	6,487.20	6,474.35	22.99	23.33	36.90	-0.16	-377.40	162.24	116.43	45.81	3.542		
6,600.00	6,585.01	6,587.03	6,573.88	23.36	23.70	38.66	-0.16	-385.02	159.10	112.55	46.55	3.418		
6,700.00	6,684.18	6,686.86	6,673.42	23.73	24.07	40.48	-0.16	-392.65	156.11	108.81	47.30	3.301		
6,800.00	6,783.35	6,786.69	6,772.96	24.10	24.44	42.38	-0.16	-400.27	153.29	105.24	48.05	3.190		
6,900.00	6,882.52	6,886.52	6,872.50	24.48	24.82	44.34	-0.16	-407.89	150.65	101.84	48.80	3.087		
7,000.00	6,981.69	6,986.35	6,972.03	24.85	25.19	46.37	-0.16	-415.52	148.18	98.62	49.56	2.990		
7,100.00	7,080.86	7,086.18	7,071.57	25.23	25.56	48.46	-0.16	-423.14	145.91	95.59	50.32	2.900		
7,200.00	7,180.03	7,186.01	7,171.11	25.60	25.93	50.62	-0.16	-430.76	143.84	92.75	51.09	2.815		
7,300.00	7,279.20	7,285.84	7,270.65	25.98	26.30	52.84	-0.16	-438.39	141.98	90.12	51.86	2.738		
7,400.00	7,378.37	7,385.67	7,370.18	26.36	26.67	55.11	-0.16	-446.01	140.34	87.71	52.63	2.666		
7,500.00	7,477.54	7,485.50	7,469.72	26.74	27.04	57.43	-0.16	-453.64	138.93	85.51	53.41	2.601		
7,600.00	7,576.71	7,585.33	7,569.26	27.12	27.42	59.80	-0.16	-461.26	137.74	83.55	54.19	2.542		
7,700.00	7,675.88	7,685.15	7,668.80	27.50	27.79	62.20	-0.16	-468.88	136.80	81.83	54.98	2.488		
7,800.00	7,775.06	7,784.98	7,768.34	27.88	28.16	64.63	-0.16	-476.51	136.11	80.35	55.76	2.441		
7,900.00	7,874.23	7,884.81	7,867.87	28.26	28.53	67.08	-0.16	-484.13	135.66	79.11	56.55	2.399		
8,000.00	7,973.40	7,984.64	7,967.41	28.64	28.90	69.55	-0.16	-491.75	135.46	78.13	57.33	2.363		
8,028.71	8,001.87	8,013.30	7,995.98	28.75	29.01	70.26	-0.16	-493.94	135.45	77.89	57.56	2.353		
8,100.00	8,072.57	8,084.47	8,066.95	29.02	29.27	72.01	-0.16	-499.38	135.51	77.39	58.12	2.332		
8,200.00	8,171.74	8,184.30	8,166.49	29.41	29.65	74.47	-0.16	-507.00	135.82	76.91	58.91	2.306		
8,300.00	8,270.91	8,284.13	8,266.02	29.79	30.02	76.92	-0.16	-514.62	136.37	76.68	59.69	2.285		
8,400.00	8,370.08	8,383.96	8,365.56	30.17	30.39	79.34	-0.16	-522.25	137.17	76.70	60.47	2.268		
8,500.00	8,469.25	8,483.79	8,465.10	30.56	30.76	81.73	-0.16	-529.87	138.22	76.97	61.25	2.257		
8,600.00	8,568.42	8,583.62	8,564.64	30.94	31.13	84.07	-0.16	-537.50	139.50	77.47	62.03	2.249		
8,700.00	8,667.59	8,683.45	8,664.17	31.33	31.51	86.38	-0.16	-545.12	141.01	78.21	62.80	2.245		
8,800.00	8,766.76	8,783.28	8,763.71	31.71	31.88	88.63	-0.16	-552.74	142.75	79.18	63.57	2.246		
8,900.00	8,865.93	8,883.11	8,863.25	32.10	32.25	90.82	-0.16	-560.37	144.70	80.36	64.33	2.249		
9,000.00	8,965.10	8,982.93	8,962.79	32.49	32.62	92.95	-0.16	-567.99	146.85	81.76	65.09	2.256		
9,100.00	9,064.27	9,082.76	9,062.33	32.87	32.99	95.02	-0.16	-575.61	149.21	83.36	65.85	2.266		
9,200.00	9,163.45	9,182.59	9,161.86	33.26	33.37	97.02	-0.16	-583.24	151.75	85.15	66.60	2.278		
9,300.00	9,262.62	9,282.42	9,261.40	33.65	33.74	98.95	-0.16	-590.86	154.47	87.12	67.35	2.293		
9,400.00	9,361.79	9,382.25	9,360.94	34.04	34.11	100.81	-0.16	-598.49	157.36	89.26	68.10	2.311		
9,500.00	9,460.96	9,482.08	9,460.48	34.42	34.48	102.61	-0.16	-606.11	160.42	91.57	68.84	2.330		
9,600.00	9,560.14	9,581.91	9,560.02	34.81	34.86	104.32	-0.16	-613.73	163.60	94.02	69.58	2.351		
9,700.00	9,659.48	9,681.81	9,659.62	35.20	35.23	105.53	-0.16	-621.36	166.56	96.23	70.32	2.368		
9,800.00	9,759.01	9,781.76	9,759.28	35.57	35.60	106.14	-0.16	-628.99	169.09	98.03	71.06	2.379		
9,900.00	9,858.69	9,881.74	9,858.97	35.94	35.97	106.16	-0.16	-636.63	171.15	99.35	71.81	2.384		
10,000.00	9,958.50	9,981.68	9,958.66	36.31	36.34	105.82	-0.16	-643.69	172.74	100.20	72.54	2.381		
10,100.00	10,058.39	10,081.63	10,058.46	36.67	36.71	105.49	-0.16	-649.03	173.88	100.61	73.27	2.373		
10,200.00	10,158.35	10,181.60	10,158.37	37.02	37.07	105.17	-0.16	-652.64	174.58	100.60	73.99	2.360		

CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation



Pro Directional
Anticollision Report



Company: Devon Energy Corp.
Project: Eddy County, NM (NAD83)
Reference Site: Big Sinks Draw 25-24
Site Error: 0.00 usft
Reference Well: 711H
Well Error: 0.00 usft
Reference Wellbore: OH
Reference Design: Prelim Plan

Local Co-ordinate Reference: Well 711H
TVD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
MD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at: 2.00 sigma
Database: WellPlanner1
Offset TVD Reference: Reference Datum

Offset Design Big Sinks Draw 25-24 - 611H - OH - Prelim Plan													Offset Site Error:	0.00 usft
Survey Program: 0-MWD+HDGM													Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis			Distance						Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	Offset Wellbore Centre +E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor		
10,300.00	10,258.35	10,281.60	10,258.35	37.36	37.42	104.88	-0.16	-654.50	174.84	100.15	74.69	2.341		
10,400.00	10,358.35	10,381.60	10,358.35	37.70	37.76	-0.19	-0.16	-654.78	174.84	99.47	75.37	2.320		
10,500.00	10,458.35	10,481.60	10,458.35	38.04	38.10	-0.19	-0.16	-654.78	174.84	98.79	76.05	2.299		
10,600.00	10,558.35	10,581.60	10,558.35	38.38	38.44	-0.19	-0.16	-654.78	174.84	98.11	76.73	2.279		
10,700.00	10,658.35	10,681.60	10,658.35	38.72	38.78	-0.19	-0.16	-654.78	174.84	97.43	77.41	2.259		
10,800.00	10,758.35	10,781.60	10,758.35	39.06	39.11	-0.19	-0.16	-654.78	174.84	96.75	78.09	2.239		
10,900.00	10,858.35	10,881.60	10,858.35	39.40	39.45	-0.19	-0.16	-654.78	174.84	96.07	78.77	2.220		
11,000.00	10,958.35	10,981.60	10,958.35	39.74	39.79	-0.19	-0.16	-654.78	174.84	95.39	79.45	2.201		
11,001.19	10,959.54	10,982.79	10,959.54	39.75	39.80	-0.19	-0.16	-654.78	174.84	95.38	79.46	2.200		
11,100.00	11,058.35	11,071.44	11,048.17	40.09	40.10	-0.19	0.80	-654.78	176.09	96.11	79.99	2.201		
11,200.00	11,158.35	11,146.78	11,122.88	40.43	40.35	-0.19	10.08	-654.81	188.45	108.78	79.67	2.365		
11,300.00	11,258.35	11,218.52	11,192.31	40.77	40.58	-0.18	27.95	-654.86	213.43	134.91	78.52	2.718		
11,400.00	11,357.94	11,286.85	11,255.87	41.11	40.78	-0.01	52.91	-654.93	242.82	166.11	76.71	3.165		
11,500.00	11,454.70	11,350.00	11,311.60	41.42	40.96	-0.01	82.56	-655.02	266.87	192.98	73.89	3.612		
11,600.00	11,545.70	11,420.29	11,369.36	41.69	41.13	-0.01	122.54	-655.14	285.15	213.74	71.41	3.993		
11,700.00	11,628.18	11,486.02	11,418.57	41.92	41.28	-0.01	166.05	-655.26	297.61	229.50	68.12	4.369		
11,800.00	11,699.62	11,550.00	11,461.38	42.08	41.40	-0.01	213.55	-655.40	304.09	239.68	64.41	4.721		
11,900.00	11,757.86	11,616.67	11,500.07	42.20	41.51	-0.01	267.80	-655.56	304.51	243.56	60.95	4.996		
12,000.00	11,801.12	11,682.02	11,531.64	42.28	41.62	-0.01	324.99	-655.72	298.88	241.43	57.46	5.202		
12,100.00	11,828.09	11,750.00	11,557.34	42.34	41.75	-0.01	387.87	-655.91	287.27	232.71	54.56	5.265		
12,200.00	11,837.96	11,813.89	11,574.55	42.47	41.88	-0.01	449.37	-656.08	269.75	217.85	51.89	5.198		
12,300.00	11,838.00	11,881.71	11,585.21	42.67	42.05	-0.01	516.31	-656.28	254.03	203.60	50.43	5.038		
12,400.00	11,838.00	11,956.76	11,588.00	42.94	42.26	-0.01	591.26	-656.50	250.00	199.77	50.23	4.977		
12,500.00	11,838.00	12,056.76	11,588.00	43.27	42.57	-0.01	691.26	-656.79	250.00	199.44	50.56	4.945		
12,600.00	11,838.00	12,156.76	11,588.00	43.64	42.93	-0.01	791.26	-657.08	250.00	199.07	50.93	4.908		
12,700.00	11,838.00	12,256.76	11,588.00	44.05	43.33	-0.01	891.26	-657.37	250.00	198.65	51.35	4.868		
12,800.00	11,838.00	12,356.76	11,588.00	44.51	43.78	-0.01	991.26	-657.66	250.00	198.19	51.81	4.825		
12,900.00	11,838.00	12,456.76	11,588.00	45.01	44.27	-0.01	1,091.26	-657.95	250.00	197.68	52.32	4.778		
13,000.00	11,838.00	12,556.76	11,588.00	45.55	44.80	-0.01	1,191.26	-658.24	250.00	197.13	52.87	4.729		
13,100.00	11,838.00	12,656.76	11,588.00	46.12	45.37	-0.01	1,291.26	-658.53	250.00	196.54	53.46	4.677		
13,200.00	11,838.00	12,756.76	11,588.00	46.74	45.97	-0.01	1,391.26	-658.82	250.00	195.92	54.08	4.623		
13,300.00	11,838.00	12,856.76	11,588.00	47.39	46.62	-0.01	1,491.26	-659.11	250.00	195.25	54.75	4.566		
13,400.00	11,838.00	12,956.76	11,588.00	48.08	47.30	-0.01	1,591.26	-659.40	250.00	194.55	55.45	4.509		
13,500.00	11,838.00	13,056.76	11,588.00	48.79	48.01	-0.01	1,691.26	-659.69	250.00	193.81	56.19	4.450		
13,600.00	11,838.00	13,156.76	11,588.00	49.54	48.76	-0.01	1,791.26	-659.98	250.00	193.04	56.96	4.389		
13,700.00	11,838.00	13,256.76	11,588.00	50.32	49.53	-0.01	1,891.26	-660.27	250.00	192.24	57.76	4.328		
13,800.00	11,838.00	13,356.76	11,588.00	51.13	50.34	-0.01	1,991.26	-660.56	250.00	191.41	58.59	4.267		
13,900.00	11,838.00	13,456.76	11,588.00	51.97	51.17	-0.01	2,091.26	-660.85	250.00	190.54	59.46	4.205		
14,000.00	11,838.00	13,556.76	11,588.00	52.83	52.03	-0.01	2,191.26	-661.14	250.00	189.65	60.35	4.143		
14,100.00	11,838.00	13,656.76	11,588.00	53.72	52.92	-0.01	2,291.26	-661.43	250.00	188.73	61.27	4.080		
14,200.00	11,838.00	13,756.76	11,588.00	54.63	53.83	-0.01	2,391.26	-661.72	250.00	187.79	62.21	4.018		
14,300.00	11,838.00	13,856.76	11,588.00	55.56	54.76	-0.01	2,491.26	-662.01	250.00	186.82	63.18	3.957		
14,400.00	11,838.00	13,956.76	11,588.00	56.52	55.71	-0.01	2,591.25	-662.30	250.00	185.82	64.18	3.895		
14,500.00	11,838.00	14,056.76	11,588.00	57.49	56.69	-0.01	2,691.25	-662.59	250.00	184.81	65.19	3.835		
14,600.00	11,838.00	14,156.76	11,588.00	58.49	57.69	-0.01	2,791.25	-662.88	250.00	183.77	66.23	3.775		
14,700.00	11,838.00	14,256.76	11,588.00	59.50	58.70	-0.01	2,891.25	-663.17	250.00	182.71	67.29	3.715		
14,800.00	11,838.00	14,356.76	11,588.00	60.53	59.73	-0.01	2,991.25	-663.46	250.00	181.63	68.37	3.657		
14,900.00	11,838.00	14,456.76	11,588.00	61.58	60.78	-0.01	3,091.25	-663.75	250.00	180.53	69.47	3.599		
15,000.00	11,838.00	14,556.76	11,588.00	62.65	61.85	-0.01	3,191.25	-664.04	250.00	179.42	70.58	3.542		
15,100.00	11,838.00	14,656.76	11,588.00	63.73	62.93	-0.01	3,291.25	-664.33	250.00	178.29	71.71	3.486		
15,200.00	11,838.00	14,756.76	11,588.00	64.82	64.02	-0.01	3,391.25	-664.62	250.00	177.14	72.86	3.431		
15,300.00	11,838.00	14,856.76	11,588.00	65.93	65.13	-0.01	3,491.25	-664.91	250.00	175.97	74.03	3.377		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation



Pro Directional
Anticollision Report



Company: Devon Energy Corp.
Project: Eddy County, NM (NAD83)
Reference Site: Big Sinks Draw 25-24
Site Error: 0.00 usft
Reference Well: 711H
Well Error: 0.00 usft
Reference Wellbore: OH
Reference Design: Prelim Plan

Local Co-ordinate Reference: Well 711H
TVD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
MD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at: 2.00 sigma
Database: WellPlanner1
Offset TVD Reference: Reference Datum

Offset Design Big Sinks Draw 25-24 - 611H - OH - Prelim Plan													Offset Site Error:	0.00 usft
Survey Program: 0-MWD+HDGM													Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis			Distance						Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	Offset Wellbore Centre +E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor		
15,400.00	11,838.00	14,956.76	11,588.00	67.05	66.25	-0.01	3,591.25	-665.20	250.00	174.79	75.21	3.324		
15,500.00	11,838.00	15,056.76	11,588.00	68.18	67.39	-0.01	3,691.25	-665.49	250.00	173.60	76.40	3.272		
15,600.00	11,838.00	15,156.76	11,588.00	69.32	68.53	-0.01	3,791.25	-665.78	250.00	172.40	77.60	3.221		
15,700.00	11,838.00	15,256.76	11,588.00	70.48	69.69	-0.01	3,891.25	-666.07	250.00	171.18	78.82	3.172		
15,800.00	11,838.00	15,356.76	11,588.00	71.65	70.86	-0.01	3,991.25	-666.36	250.00	169.94	80.06	3.123		
15,900.00	11,838.00	15,456.76	11,588.00	72.82	72.04	-0.01	4,091.25	-666.65	250.00	168.70	81.30	3.075		
16,000.00	11,838.00	15,556.76	11,588.00	74.01	73.23	-0.01	4,191.25	-666.94	250.00	167.45	82.55	3.028		
16,100.00	11,838.00	15,656.76	11,588.00	75.20	74.42	-0.01	4,291.25	-667.23	250.00	166.18	83.82	2.983		
16,200.00	11,838.00	15,756.76	11,588.00	76.41	75.63	-0.01	4,391.25	-667.52	250.00	164.91	85.09	2.938		
16,300.00	11,838.00	15,856.76	11,588.00	77.62	76.84	-0.01	4,491.25	-667.81	250.00	163.62	86.38	2.894		
16,400.00	11,838.00	15,956.76	11,588.00	78.84	78.06	-0.01	4,591.25	-668.10	250.00	162.33	87.67	2.852		
16,500.00	11,838.00	16,056.76	11,588.00	80.07	79.29	-0.01	4,691.25	-668.39	250.00	161.03	88.97	2.810		
16,600.00	11,838.00	16,156.76	11,588.00	81.30	80.53	-0.01	4,791.25	-668.68	250.00	159.72	90.28	2.769		
16,700.00	11,838.00	16,256.76	11,588.00	82.54	81.78	0.00	4,891.25	-668.97	250.00	158.40	91.60	2.729		
16,800.00	11,838.00	16,356.76	11,588.00	83.79	83.03	0.00	4,991.24	-669.26	250.00	157.07	92.93	2.690		
16,900.00	11,838.00	16,456.76	11,588.00	85.05	84.28	0.00	5,091.24	-669.55	250.00	155.74	94.26	2.652		
17,000.00	11,838.00	16,556.76	11,588.00	86.31	85.55	0.00	5,191.24	-669.84	250.00	154.39	95.61	2.615		
17,100.00	11,838.00	16,656.76	11,588.00	87.57	86.81	0.00	5,291.24	-670.13	250.00	153.04	96.96	2.579		
17,200.00	11,838.00	16,756.76	11,588.00	88.84	88.09	0.00	5,391.24	-670.42	250.00	151.69	98.31	2.543		
17,300.00	11,838.00	16,856.76	11,588.00	90.12	89.37	0.00	5,491.24	-670.71	250.00	150.33	99.67	2.508		
17,400.00	11,838.00	16,956.76	11,588.00	91.40	90.65	0.00	5,591.24	-671.00	250.00	148.96	101.04	2.474		
17,500.00	11,838.00	17,056.76	11,588.00	92.69	91.94	0.00	5,691.24	-671.29	250.00	147.59	102.41	2.441		
17,600.00	11,838.00	17,156.76	11,588.00	93.98	93.24	0.00	5,791.24	-671.58	250.00	146.21	103.79	2.409		
17,700.00	11,838.00	17,256.76	11,588.00	95.28	94.54	0.00	5,891.24	-671.87	250.00	144.82	105.18	2.377		
17,800.00	11,838.00	17,356.76	11,588.00	96.58	95.84	0.00	5,991.24	-672.16	250.00	143.44	106.56	2.346		
17,900.00	11,838.00	17,456.76	11,588.00	97.89	97.15	0.00	6,091.24	-672.45	250.00	142.04	107.96	2.316		
18,000.00	11,838.00	17,556.76	11,588.00	99.20	98.46	0.00	6,191.24	-672.74	250.00	140.64	109.36	2.286		
18,100.00	11,838.00	17,656.76	11,588.00	100.51	99.77	0.00	6,291.24	-673.03	250.00	139.24	110.76	2.257		
18,200.00	11,838.00	17,756.76	11,588.00	101.83	101.09	0.00	6,391.24	-673.32	250.00	137.83	112.17	2.229		
18,300.00	11,838.00	17,856.76	11,588.00	103.15	102.41	0.00	6,491.24	-673.61	250.00	136.42	113.58	2.201		
18,400.00	11,838.00	17,956.76	11,588.00	104.47	103.74	0.00	6,591.24	-673.90	250.00	135.00	115.00	2.174		
18,500.00	11,838.00	18,056.76	11,588.00	105.80	105.07	0.00	6,691.24	-674.19	250.00	133.58	116.42	2.147		
18,600.00	11,838.00	18,156.76	11,588.00	107.13	106.40	0.00	6,791.24	-674.48	250.00	132.16	117.84	2.121		
18,700.00	11,838.00	18,256.76	11,588.00	108.46	107.73	0.00	6,891.24	-674.77	250.00	130.73	119.27	2.096		
18,800.00	11,838.00	18,356.76	11,588.00	109.79	109.07	0.00	6,991.24	-675.06	250.00	129.30	120.70	2.071		
18,900.00	11,838.00	18,456.76	11,588.00	111.13	110.41	0.00	7,091.24	-675.35	250.00	127.86	122.14	2.047		
19,000.00	11,838.00	18,556.76	11,588.00	112.47	111.75	0.00	7,191.24	-675.64	250.00	126.43	123.57	2.023		
19,100.00	11,838.00	18,656.76	11,588.00	113.82	113.10	0.00	7,291.23	-675.93	250.00	124.99	125.01	2.000		
19,200.00	11,838.00	18,756.76	11,588.00	115.16	114.45	0.00	7,391.23	-676.22	250.00	123.54	126.46	1.977		
19,238.78	11,838.00	18,795.54	11,588.00	115.69	114.97	0.00	7,430.01	-676.33	250.00	122.98	127.02	1.968 SF		


CC - Min centre to center distance or covergent point, SF - min separation factor, ES - min ellipse separation

Company: Devon Energy Corp.
 Project: Eddy County, NM (NAD83)
 Reference Site: Big Sinks Draw 25-24
 Site Error: 0.00 usft
 Reference Well: 711H
 Well Error: 0.00 usft
 Reference Wellbore: OH
 Reference Design: Prelim Plan

Local Co-ordinate Reference: Well 711H
 TVD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
 MD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
 North Reference: Grid
 Survey Calculation Method: Minimum Curvature
 Output errors are at: 2.00 sigma
 Database: WellPlanner1
 Offset TVD Reference: Reference Datum

Reference Depths are relative to GL 3332'+KB 26' @ 3358.00usft (Rig)
 Offset Depths are relative to Offset Datum
 Central Meridian is -104.3333333

Coordinates are relative to: 711H
 Coordinate System is US State Plane 1983, New Mexico Eastern Zone
 Grid Convergence at Surface is: 0.32°





Pro Directional Anticollision Report




Company: Devon Energy Corp.
Project: Eddy County, NM (NAD83)
Reference Site: Big Sinks Draw 25-24
Site Error: 0.00 usft
Reference Well: 711H
Well Error: 0.00 usft
Reference Wellbore: OH
Reference Design: Prelim Plan

Local Co-ordinate Reference: Well 711H
TVD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
MD Reference: GL 3332'+KB 26' @ 3358.00usft (Rig TBD)
North Reference: Grid
Survey Calculation Method: Minimum Curvature
Output errors are at: 2.00 sigma
Database: WellPlanner1
Offset TVD Reference: Reference Datum

Reference Depths are relative to GL 3332'+KB 26' @ 3358.00usft (Rig)
 Offset Depths are relative to Offset Datum
 Central Meridian is -104.3333333

Coordinates are relative to: 711H
 Coordinate System is US State Plane 1983, New Mexico Eastern Zone
 Grid Convergence at Surface is: 0.32°

Separation Factor Plot




LEGEND

331H, OH, Prelim Plan VO
 531H, OH, Prelim Plan VO
 521H, OH, Prelim Plan VO
 1H, OH, Surveys VO



Commitment Runs Deep



Design Plan
Operation and Maintenance Plan
Closure Plan

SENM - Closed Loop Systems
June 2010

I. Design Plan

Devon uses MI SWACO closed loop system (CLS). The MI SWACO CLS is designed to maintain drill solids at or below 5%. The equipment is arranged to progressively remove solids from the largest to the smallest size. Drilling fluids can thus be reused and savings is realized on mud and disposal costs. Dewatering may be required with the centrifuges to insure removal of ultra fine solids.

The drilling location is constructed to allow storm water to flow to a central sump normally the cellar. This insures no contamination leaves the drilling pad in the event of a spill. Storm water is reused in the mud system or stored in a reserve fluid tank farm until it can be reused. All lubricants, oils, or chemicals are removed immediately from the ground to prevent the contamination of storm water. An oil trap is normally installed on the sump if an oil spill occurs during a storm.

A tank farm is utilized to store drilling fluids including fresh water and brine fluids. The tank farm is constructed on a 20 ml plastic lined, bermed pad to prevent the contamination of the drilling site during a spill. Fluids from other sites may be stored in these tanks for processing by the solids control equipment and reused in the mud system. At the end of the well the fluids are transported from the tank farm to an adjoining well or to the next well for the rig.

Prior to installing a closed-loop system on site, the topsoil, if present, will be stripped and stockpiled for use as the final cover or fill at the time of closure.

Signs will be posted on the fence surrounding the closed-loop system unless the closed-loop system is located on a site where there is an existing well, that is operated by Devon.


II. Operations and Maintenance Plan

Primary Shakers: The primary shakers make the first removal of drill solids from the drilling mud as it leaves the well bore. The shakers are sized to handle maximum drilling rate at optimal screen size. The shakers normally remove solids down to 74 microns.

Mud Cleaner: The Mud Cleaner cleans the fluid after it leaves the shakers. A set of hydrocyclones are sized to handle 1.25 to 1.5 times the maximum circulating rate. This ensures all the fluid is being processed to an average cut point of 25 microns. The wet discharged is dewatered on a shaker equipped with ultra fine mesh screens and generally cut at 40 microns.



Closed Loop Schematic



Centrifuges: The centrifuges can be one or two in number depending on the well geometry or depth of well. The centrifuges are sized to maintain low gravity solids at 5% or below. They may or may not need a dewatering system to enhance the removal rates. The centrifuges can make a cut point of 8-10 microns depending on bowl speed, feed rate, solids loading and other factors.

The centrifuge system is designed to work on the active system and be flexible to process incoming fluids from other locations. This set-up is also dependant on well factors.

Dewatering System: The dewatering system is a chemical mixing and dosing system designed to enhance the solids removal of the centrifuge. Not commonly used in shallow wells. It may contain pH adjustment, coagulant mixing and dosing, and polymer mixing and dosing. Chemical flocculation binds ultra fine solids into a mass that is within the centrifuge operating design. The

dewatering system improves the centrifuge cut point to infinity or allows for the return of clear water or brine fluid. This ability allows for the ultimate control of low gravity solids.

Cuttings Boxes: Cuttings boxes are utilized to capture drill solids that are discarded from the solids control equipment. These boxes are set upon a rail system that allows for the removal and replacement of a full box of cuttings with an empty one. They are equipped with a cover that insures no product is spilled into the environment during the transportation phase.

Process Tank: (Optional) The process tank allows for the holding and process of fluids that are being transferred into the mud system. Additionally, during times of lost circulation the process tank may hold active fluids that are removed for additional treatment. It can further be used as a mixing tank during well control conditions.

Sump and Sump Pump: The sump is used to collect storm water and the pump is used to transfer this fluid to the active system or to the tank for to hold in reserve. It can also be used to collect fluids that may escape during spills. The location contains drainage ditches that allow the location fluids to drain to the sump.

Reserve Fluids (Tank Farm): A series of frac tanks are used to replace the reserve pit. These are steel tanks that are equipped with a manifold system and a transfer pump. These tanks can contain any number of fluids used during the drilling process. These can include fresh water, cut brine, and saturated salt fluid. The fluid can be from the active well or reclaimed fluid from other locations. A 20 ml liner and berm system is employed to ensure the fluids do not migrate to the environment during a spill.

If a leak develops, the appropriate division district office will be notified within 48 hours of the discovery and the leak will be addressed. Spill prevention is accomplished by maintaining pump packing, hoses, and pipe fittings to insure no leaks are occurring. During an upset condition the source of the spill is isolated and repaired as soon as it is discovered. Free liquid is removed by a diaphragm pump and returned to the mud system. Loose topsoil may be used to stabilize the spill and the contaminated soil is excavated and placed in the cuttings boxes. After the well is finished and the rig has moved, the entire location is scrapped and testing will be performed to determine if a release has occurred.

All trash is kept in a wire mesh enclosure and removed to an approved landfill when full. All spent motor oils are kept in separate containers and they are removed and sent to an approved recycling center. Any spilled lubricants, pipe

dope, or regulated chemicals are removed from soil and sent to landfills approved for these products.

These operations are monitored by Mi Swaco service technicians. Daily logs are maintained to ensure optimal equipment operation and maintenance. Screen and chemical use is logged to maintain inventory control. Fluid properties are monitored and recorded and drilling mud volumes are accounted for in the mud storage farm. This data is kept for end of well review to insure performance goals are met. Lessons learned are logged and used to help with continuous improvement.

A MI SWACO field supervisor manages from 3-5 wells. They are responsible for training personnel, supervising installations, and inspecting sites for compliance of MI SWACO safety and operational policy.

III. Closure Plan

A maximum 340' X 340' caliche pad is built per well. All of the trucks and steel tanks fit on this pad. All fluid cuttings go to the steel tanks to be hauled by various trucking companies to an agency approved disposal.

A multibowl wellhead may be used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested.

Devon proposes using a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be 5000 (5M) psi.

- Wellhead will be installed by wellhead representatives.
- If the welding is performed by a third party, the wellhead representative will monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
- Wellhead representative will install the test plug for the initial BOP test.
- Wellhead company will install a solid steel body pack-off to completely isolate the lower head after cementing intermediate casing. After installation of the pack-off, the pack-off and the lower flange will be tested to 5M, as shown on the attached schematic. Everything above the pack-off will not have been altered whatsoever from the initial nipple up. Therefore the BOP components will not be retested at that time.
- If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head will be cut and top out operations will be conducted.
- Devon will pressure test all seals above and below the mandrel (but still above the casing) to full working pressure rating.
- Devon will test the casing to 0.22 psi/ft or 1500 psi, whichever is greater, as per Onshore Order #2.


After running the 13-3/8" surface casing, a 13-5/8" BOP/BOPE system with a minimum rating of 5M will be installed on the wellhead system and will undergo a 250 psi low pressure test followed by a 5,000 psi high pressure test. The 5,000 psi high and 250 psi low test will cover testing requirements a maximum of 30 days, as per Onshore Order #2. If the well is not complete within 30 days of this BOP test, another full BOP test will be conducted, as per Onshore Order #2.


After running the 9-5/8' intermediate casing with a mandrel hanger, the 13-5/8" BOP/BOPE system with a minimum rating of 5M will already be installed on the wellhead.

The pipe rams will be operated and checked each 24 hour period and each time the drill pipe is out of the hole. These tests will be logged in the daily driller's log. A 2" kill line and 3" choke line will be incorporated into the drilling spool below the ram BOP. In addition to the rams and annular preventer, additional BOP accessories include a kelly cock, floor safety valve, choke lines, and choke manifold rated at 5,000 psi WP.

Devon's proposed wellhead manufacturers will be FMC Technologies, Cactus Wellhead, or Cameron.

13-5/8" 5M BOPE & Closed Loop Equipment Schematic





Devon Energy Prod. Co., L.P. – Big Sinks Draw 25-24 Fed Com 711H

1. Geologic Formations

TVD of target	11,838	Pilot hole depth	
MD at TD:	19,238	Deepest expected fresh water:	400'

Basin

Formation	Depth (TVD) from KB	Water/Mineral Bearing/ Target Zone?	Hazards*
Rustler	933		
Salado	1253		
Base of Salt	4303		
Delaware	4338		
1 st Bone Spring Lime	8348		
Wolfcamp	11673		
Wolfcamp 100	11838		

*H2S, water flows, loss of circulation, abnormal pressures, etc.

Devon Energy Prod. Co., L.P. – Big Sinks Draw 25-24 Fed Com 711H

2. Casing Program

Hole Size	Casing Interval		Csg. Size	Weight (lbs)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
	From	To							
14.75"	0	958'	10.75"	40.5	J-55	STC	1.125	1.25	1.6
9.875"	0	8,400'	7.625"	29.7	P110	BTC	1.125	1.25	1.6
8.75"	8400'	12,000'	7.625"	29.7	P110	Flushmax III	1.125	1.25	1.6
6.75"	0	19,238'	5.5"	20	P110	SF/Flush	1.125	1.25	1.6

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

Rustler top will be validated via drilling parameters (i.e. reduction in ROP) and surface casing setting depth revised accordingly if needed.

A variance is requested to wave the centralizer requirement for the 7-5/8" flush casing in the 8-3/4" hole and the 5-1/2" SF/Flush casing in the 6-3/4" hole.

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Does casing meet API specifications? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the intermediate pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 rd string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 nd string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

Devon Energy Prod. Co., L.P. – Big Sinks Draw 25-24 Fed Com 711H

2. Cementing Program

Casing	# Sks	Wt. lb/gal	H ₂ O gal/sk	Yld ft ³ /sack	Slurry Description
10-3/4" Surface	597	14.8	6.34	1.34	Tail: Class C Cement + 1% Calcium Chloride
7-5/8" Int	419	9	13.5	3.27	Lead: Tuned Light [®] Cement
	163	14.5	5.31	1.2	Tail: (50:50) Class H Cement: Poz (Fly Ash) + 0.5% bwoc HALAD-344 + 0.4% bwoc CFR-3 + 0.2% BWOC HR-601 + 2% bwoc Bentonite
7-5/8" Int Two Stage	154	10.9	20.6	3.31	1 st Stage Lead: (50:40:10) Class C: Silicalite: Enhancer 923 + 10% BWOC Bentonite + 0.05% BWOC SA-1015 + 0.3% BWOC HR-800 + 0.2% BWOC FE-2 + 0.125 lb/sk Pol-E-Flake + 0.5 lb/sk D-Air 5000
	292	14.5	5.31	1.2	1 st Stage Tail: (50:50) Class H Cement: Poz (Fly Ash) + 0.5% bwoc HALAD-344 + 0.4% bwoc CFR-3 + 0.2% BWOC HR-601 + 2% bwoc Bentonite
	150	10.9	20.6	3.31	2 nd Stage Lead: (50:40:10) Class C: Silicalite: Enhancer 923 + 10% BWOC Bentonite + 0.05% BWOC SA-1015 + 0.3% BWOC HR-800 + 0.2% BWOC FE-2 + 0.125 lb/sk Pol-E-Flake + 0.5 lb/sk D-Air 5000
	30	14.8	6.32	1.33	2 nd Stage Tail: Class C Cement + 0.125 lbs/sack Poly-E-Flake
5-1/2" Prod	607	14.8	6.32	1.33	Tail: Class H Cement + 0.125 lbs/sack Poly-E-Flake

If a DV tool is used, depth(s) will be adjusted based on hole conditions and cement volumes will be adjusted proportionally. DV tool will be set a minimum of 50 feet below previous casing and a minimum of 200 feet above current shoe. Lab reports with the 500 psi compressive strength time for the cement will be onsite for review.

Casing String	TOC	% Excess
10-3/4" Surface	0'	50%
7-5/8" Intermediate	0'	30%
7-5/8" Intermediate Two Stage Option	1 st Stage = 4200' / 2 nd Stage = 0'	30%
5-1/2" Production Casing	11500'	25%

4. Pressure Control Equipment

4. Pressure Control Equipment

N	A variance is requested for the use of a diverter on the surface casing. See attached for schematic.
---	--

BOP installed and tested before drilling which hole?	Size?	Min. Required WP	Type	✓	Tested to:
9-7/8" & 8-3/4"	13-5/8"	5M	Annular	X	50% of rated working pressure
			Blind Ram	X	5M
			Pipe Ram	X	
			Double Ram	X	
			Other*		
6-3/4"	13-5/8"	5M	Annular (5M)	X	50% of rated working pressure
			Blind Ram	X	5M
			Pipe Ram	X	
			Double Ram	X	
			Other*		
			Annular		
			Blind Ram		
			Pipe Ram		
			Double Ram		
			Other*		

*Specify if additional ram is utilized.

BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

Y	Formation integrity test will be performed per Onshore Order #2. On Exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.i.
---	--

Devon Energy Prod. Co., L.P. – Big Sinks Draw 25-24 Fed Com 711H

Y	A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.
Y	Are anchors required by manufacturer?
Y	<p>A multibowl wellhead may be used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested.</p> <p>Devon proposes using a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be 5000 (5M) psi.</p> <ul style="list-style-type: none"> • Wellhead will be installed by wellhead representatives. • If the welding is performed by a third party, the wellhead representative will monitor the temperature to verify that it does not exceed the maximum temperature of the seal. • Wellhead representative will install the test plug for the initial BOP test. • Wellhead company will install a solid steel body pack-off to completely isolate the lower head after cementing intermediate casing. After installation of the pack-off, the pack-off and the lower flange will be tested to 3M, as shown on the attached schematic. Everything above the pack-off will not have been altered whatsoever from the initial nipple up. Therefore the BOP components will not be retested at that time. • If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head will be cut and top out operations will be conducted. • Devon will pressure test all seals above and below the mandrel (but still above the casing) to full working pressure rating. • Devon will test the casing to 0.22 psi/ft or 1500 psi, whichever is greater, as per Onshore Order #2. <p>After running the 10-3/4" surface casing, a 13-5/8" BOP/BOPE system with a minimum rating of 5M will be installed on the wellhead system and will undergo a 250 psi low pressure test followed by a 5,000 psi high pressure test. The 5,000 psi high and 250 psi low test will cover testing requirements a maximum of 30 days, as per Onshore Order #2. If the well is not complete within 30 days of this BOP test, another full BOP test will be conducted, as per Onshore Order #2.</p> <p>After running the 7-5/8" intermediate casing with a mandrel hanger, the 13-5/8" BOP/BOPE system with a minimum rating of 5M will be installed on the wellhead.</p> <p>The pipe rams will be operated and checked each 24 hour period and each time the drill pipe is out of the hole. These tests will be logged in the daily driller's log. A 2" kill line and 3" choke line will be incorporated into the drilling spool below the ram BOP. In addition to the rams and annular preventer, additional BOP accessories include a kelly cock, floor safety valve, choke lines, and choke manifold rated at 3,000 psi WP.</p>

Devon Energy Prod. Co., L.P. – Big Sinks Draw 25-24 Fed Com 711H

	<p>Devon’s proposed wellhead manufactures will be FMC Technologies, Cactus Wellhead, or Cameron.</p> <p>Devon requests a variance to use a flexible line with flanged ends between the BOP and the choke manifold (choke line). The line will be kept as straight as possible with minimal turns.</p>
--	---

5. Mud Program

Depth		Type	Weight (ppg)	Viscosity	Water Loss
From	To				
0	958’	FW Gel	8.6-8.8	28-34	N/C
958’	12,000’	OBM/Cut Brine	8.6-10	34-65	N/C – 6
12,000’	19,238’	OBM	10-11.5	45-65	N/C – 6

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	PVT/Pason/Visual Monitoring
---	-----------------------------

6. Logging and Testing Procedures

Logging, Coring and Testing.	
x	Will run GR/CNL from TD to surface (horizontal well – vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
	No Logs are planned based on well control or offset log information.
	Drill stem test? If yes, explain
	Coring? If yes, explain

Additional logs planned	Interval
Resistivity	Int. shoe to KOP
Density	Int. shoe to KOP
X CBL	Production casing
X Mud log	Int shoe to TD
PEX	

7. Drilling Conditions

Condition	Specify what type and where?
BH Pressure at deepest TVD	7079 psi
Abnormal Temperature	No

Devon Energy Prod. Co., L.P. – Big Sinks Draw 25-24 Fed Com 711H

Mitigation measure for abnormal conditions. Describe. Lost circulation material/sweeps/mud scavengers.

Hydrogen Sulfide (H2S) monitors will be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.	
N	H2S is present
Y	H2S Plan attached

8. Other facets of operation

Is this a walking operation? Yes

1. In the event the spudder rig is unable to drill the surface holes the drilling rig will batch drill the surface holes and run/cement surface casing; walking the rig to next wells on the pad.
2. The drilling rig will then batch drill the intermediate sections with either OBM or cut brine and run/cement intermediate casing; the wellbore will be isolated with a blind flange and pressure gauge installed for monitoring the well before walking to the next well.
3. The drilling rig will then batch drill the production hole sections on the wells with OBM, run/cement production casing, and install TA caps or tubing heads for completions.

NOTE: During batch operations the drilling rig will be moved from well to well however, it will not be removed from the pad until all wells have production casing run/cemented.

Attachments

- Directional Plan
 Other, describe



Fluid Technology

ContiTech Beattie Corp.
Website: www.contitechbeattie.com

Monday, June 14, 2010

RE: Drilling & Production Hoses
Lifting & Safety Equipment

To Helmerich & Payne,

A Continental ContiTech hose assembly can perform as intended and suitable for the application regardless of whether the hose is secured or unsecured in its configuration. As a manufacturer of High Pressure Hose Assemblies for use in Drilling & Production, we do offer the corresponding lifting and safety equipment, this has the added benefit of easing the lifting and handling of each hose assembly whilst affording hose longevity by ensuring correct handling methods and procedures as well as securing the hose in the unlikely event of a failure; but in no way does the lifting and safety equipment affect the performance of the hoses providing the hoses have been handled and installed correctly. It is good practice to use lifting & safety equipment but not mandatory.


Should you have any questions or require any additional information/clarifications then please do not hesitate to contact us.

ContiTech Beattie is part of the Continental AG Corporation and can offer the full support resources associated with a global organization.

Best regards,

Robin Hodgson
Sales Manager
ContiTech Beattie Corp

ContiTech Beattie Corp,
11535 Brittonmoore Park Drive,
Houston, TX 77041
Phone: +1 (832) 327-0141
Fax: +1 (832) 327-0148
www.contitechbeattie.com



RIG 212



QUALITY DOCUMENT

PHOENIX RUBBER INDUSTRIAL LTD.

6728 Szeged, Budapesti út 10. Hungary • H-6701 Szeged, P. O. Box 152
Phone: (3662) 566-737 • Fax: (3662) 568-738

SALES & MARKETING: H-1092 Budapest, Ráday u. 42-44. Hungary • H-1440 Budapest, P. O. Box 26
Phone: (361) 458-4200 • Fax: (361) 217-2972, 458-4273 • www.taurusemergo.hu

QUALITY CONTROL INSPECTION AND TEST CERTIFICATE		CERT. N°:	552
PURCHASER: Phoenix Beattie Co.		P.O. N°:	1519FA-871
PHOENIX RUBBER order N°:	170466	HOSE TYPE:	3" ID Choke and Kill Hose
HOSE SERIAL N°:	34128	NOMINAL / ACTUAL LENGTH:	11,43 m
W.P. 68,96 MPa	10000 psi	T.P. 103,4 MPa	15000 psi
		Duration:	60 min.
Pressure test with water at ambient temperature <p style="text-align: center;">See attachment. (1 page)</p>			
↑ 10 mm = 10 Min. → 10 mm = 25 MPa			
COUPLINGS			
Type	Serial N°	Quality	Heat N°
3" coupling with 4 1/16" Flange end	720 719	AISI 4130	C7628
		AISI 4130	47357
API Spec 16 C Temperature rate: "B"			
All metal parts are flawless			
WE CERTIFY THAT THE ABOVE HOSE HAS BEEN MANUFACTURED IN ACCORDANCE WITH THE TERMS OF THE ORDER AND PRESSURE TESTED AS ABOVE WITH SATISFACTORY RESULT.			
Date:	Inspector	Quality Control	
29. April. 2002.		PHOENIX RUBBER Industrial Ltd. Hose Inspection and PHOENIX RUBBER S.C.	

Devon Energy
APD VARIANCE DATA

OPERATOR NAME: Devon Energy

1. SUMMARY OF Variance:

Devon Energy respectfully requests approval for the following additions to the drilling plan:

1. Potential utilization of a spudder rig to pre-set surface casing.

2. Description of Operations

1. A spudder rig contractor may move in their rig to drill the surface hole section and pre-set surface casing on this well.
 - a. After drilling the surface hole section, the rig will run casing and cement following all of the applicable rules and regulations (OnShore Order 2, all COAs and NMOCD regulations).
 - b. Rig will utilize fresh water based mud to drill surface hole to TD.
2. The wellhead will be installed and tested once the surface casing is cut off and the WOC time has been reached.
3. A blind flange with the same pressure rating as the wellhead will be installed to seal the wellbore. Pressure will be monitored with needle valves installed on two wingvalves.
 - a. A means for intervention will be maintained while the drilling rig is not over the well.
4. The BLM will be contacted and notified 24 hours prior to commencing spudder rig operations.
5. Drilling operation will be performed with the big rig. At that time an approved BOP stack will be nipped up and tested on the wellhead before drilling operations commences on each well.
 - a. The BLM will be contacted / notified 24 hours before the big rig moves back on to the pad with the pre-set surface casing.
6. Devon Energy will have supervision on the rig to ensure compliance with all BLM and NMOCD regulations and to oversee operations.
7. Once the rig is removed, Devon Energy will secure the wellhead area by placing a guard rail around the cellar area.

APD ID: 10400024301

Submission Date: 12/01/2017

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BIG SINKS DRAW 25-24 FED COM

Well Number: 711H

Well Type: OIL WELL

Well Work Type: Drill

[Show Final Text](#)**Section 1 - Existing Roads**

Will existing roads be used? YES

Existing Road Map:

BSD_25_24_Fed_Com_711H_Ex_Access_Rd_20171109114332.pdf

Existing Road Purpose: ACCESS,FLUID TRANSPORT

Row(s) Exist? NO

ROW ID(s)

ID:

Do the existing roads need to be improved? YES

Existing Road Improvement Description: Improve road to accommodate Drilling and Completion operations.

Existing Road Improvement Attachment:

Section 2 - New or Reconstructed Access Roads

Will new roads be needed? YES

New Road Map:

BSD_25_24_Fed_Com_711H_Access_Rd_20171109114457.pdf

New road type: COLLECTOR,RESOURCE

Length: 486

Feet

Width (ft.): 30

Max slope (%): 6

Max grade (%): 4

Army Corp of Engineers (ACOE) permit required? NO

ACOE Permit Number(s):

New road travel width: 30

New road access erosion control: WATER DRAINAGE DITCH

New road access plan or profile prepared? NO

New road access plan attachment:

Access road engineering design? NO

Access road engineering design attachment:

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BIG SINKS DRAW 25-24 FED COM

Well Number: 711H

Access surfacing type: GRAVEL

Access topsoil source: ONSITE

Access surfacing type description:

Access onsite topsoil source depth: 6

Offsite topsoil source description:

Onsite topsoil removal process: SEE INTERIM RECLAMATION DIAGRAM

Access other construction information:

Access miscellaneous information:

Number of access turnouts:

Access turnout map:

Drainage Control

New road drainage crossing: OTHER

Drainage Control comments: N/A

Road Drainage Control Structures (DCS) description: N/A

Road Drainage Control Structures (DCS) attachment:

Access Additional Attachments

Additional Attachment(s):

Section 3 - Location of Existing Wells

Existing Wells Map? YES

Attach Well map:

BSD_25_24_Fed_Com_711H_1mile_map_20171109114547.pdf

Existing Wells description:

Section 4 - Location of Existing and/or Proposed Production Facilities

Submit or defer a Proposed Production Facilities plan? DEFER

Estimated Production Facilities description: ALL FLOWLINES WILL BE BURIED GOING TO THE BIG SINKS DRAW 25 CTB 1.

Section 5 - Location and Types of Water Supply

Water Source Table

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BIG SINKS DRAW 25-24 FED COM

Well Number: 711H

Water source use type: STIMULATION

Water source type: RECYCLED

Describe type:

Source latitude:

Source longitude:

Source datum:

Water source permit type: OTHER

Source land ownership: FEDERAL

Water source transport method: PIPELINE,TRUCKING

Source transportation land ownership: FEDERAL

Water source volume (barrels): 320000

Source volume (acre-feet): 41.245792

Source volume (gal): 13440000

Water source and transportation map:

BSD_25_24_Fed_Com_711H_Wtr_Xfr_Map_20171109114737.pdf

Water source comments: The attached Water Transfer Map is a proposal only and the final route and documentation will be provided by a Devon contractor prior to installation. When available Devon will always follow existing disturbance.

New water well? NO

New Water Well Info

Well latitude:

Well Longitude:

Well datum:

Well target aquifer:

Est. depth to top of aquifer(ft):

Est thickness of aquifer:

Aquifer comments:

Aquifer documentation:

Well depth (ft):

Well casing type:

Well casing outside diameter (in.):

Well casing inside diameter (in.):

New water well casing?

Used casing source:

Drilling method:

Drill material:

Grout material:

Grout depth:

Casing length (ft.):

Casing top depth (ft.):

Well Production type:

Completion Method:

Water well additional information:

State appropriation permit:

Additional information attachment:

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BIG SINKS DRAW 25-24 FED COM

Well Number: 711H

Section 6 - Construction Materials

Construction Materials description: Dirt fill and caliche will be used to construct well pad.

Construction Materials source location attachment:

BSD_25_24_Fed_Com_711H_Caliche_Pit_20171109115513.pdf

Section 7 - Methods for Handling Waste

Waste type: DRILLING

Waste content description: Water Based Cuttings

Amount of waste: 1740 barrels

Waste disposal frequency : Daily

Safe containment description: N/A

Safe containmant attachment:

Waste disposal type: HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** COMMERCIAL FACILITY

Disposal type description:

Disposal location description: All cuttings will disposed of at R360, Sundance, or equivalent.

Waste type: COMPLETIONS/STIMULATION

Waste content description: FLOW BACK WATER DURING COMPLETION OPERATIONS

Amount of waste: 3000 barrels

Waste disposal frequency : One Time Only

Safe containment description: N/A

Safe containmant attachment:

Waste disposal type: HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** COMMERCIAL FACILITY

Disposal type description:

Disposal location description: VARIOUS DISPOSAL LOCATIONS IN LEA AND EDDY COUNTIES.

Waste type: FLOWBACK

Waste content description: Produced water during flowback operations. This amount is a daily average during flowback (BWPD). Any sand production is taken to R360 for solids disposal

Amount of waste: 2500 barrels

Waste disposal frequency : Daily

Safe containment description: N/A

Safe containmant attachment:

Waste disposal type: ON-LEASE INJECTION **Disposal location ownership:** PRIVATE

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BIG SINKS DRAW 25-24 FED COM

Well Number: 711H

Disposal type description:

Disposal location description: Devon owned disposal Cotton Draw 32-2 SWD

Waste type: PRODUCED WATER

Waste content description: Average daily water production over the first year of production (BWPD).

Amount of waste: 1800 barrels

Waste disposal frequency : Daily

Safe containment description: N.A

Safe containmant attachment:

Waste disposal type: ON-LEASE INJECTION **Disposal location ownership:** PRIVATE

Disposal type description:

Disposal location description: Devon owned disposal Cotton Draw 32-2 SWD

Reserve Pit

Reserve Pit being used? NO

Temporary disposal of produced water into reserve pit?

Reserve pit length (ft.) **Reserve pit width (ft.)**

Reserve pit depth (ft.) **Reserve pit volume (cu. yd.)**

Is at least 50% of the reserve pit in cut?

Reserve pit liner

Reserve pit liner specifications and installation description

Cuttings Area

Cuttings Area being used? NO

Are you storing cuttings on location? NO

Description of cuttings location

Cuttings area length (ft.) **Cuttings area width (ft.)**

Cuttings area depth (ft.) **Cuttings area volume (cu. yd.)**

Is at least 50% of the cuttings area in cut?

WCuttings area liner

Cuttings area liner specifications and installation description

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BIG SINKS DRAW 25-24 FED COM

Well Number: 711H

Section 8 - Ancillary Facilities

Are you requesting any Ancillary Facilities?: NO

Ancillary Facilities attachment:

Comments:

Section 9 - Well Site Layout

Well Site Layout Diagram:

BSD_25_24_Fed_Com_711H_Rig_Layout_20171109121426.pdf

Comments:

Section 10 - Plans for Surface Reclamation

Type of disturbance: New Surface Disturbance

Multiple Well Pad Name: BIG SINKS DRAW CTB

Multiple Well Pad Number: 1

Recontouring attachment:

BSD_25_24_Fed_Com_711H_Reclamation_20171128073852.pdf

Drainage/Erosion control construction: All areas disturbed shall be reclaimed as early and as nearly as practicable to their original condition or their final land use and shall be maintained to control dust and minimize erosion to the extent practicable.

Drainage/Erosion control reclamation: Topsoils and subsoils shall be replaced to their original relative positions and contoured so as to achieve erosion control, long-term stability and preservation of surface water flow patterns. The disturbed area then shall be reseeded in the first favorable growing season.

Well pad proposed disturbance (acres): 5.109	Well pad interim reclamation (acres): 1.912	Well pad long term disturbance (acres): 3.197
Road proposed disturbance (acres): 0.335	Road interim reclamation (acres): 0	Road long term disturbance (acres): 0.335
Powerline proposed disturbance (acres): 0.277	Powerline interim reclamation (acres): 0	Powerline long term disturbance (acres): 0
Pipeline proposed disturbance (acres): 0.291	Pipeline interim reclamation (acres): 0	Pipeline long term disturbance (acres): 0.291
Other proposed disturbance (acres): 0	Other interim reclamation (acres): 0	Other long term disturbance (acres): 0
Total proposed disturbance: 6.012	Total interim reclamation: 1.912	Total long term disturbance: 3.823

Disturbance Comments:

Reconstruction method: Operator will use Best Management Practices "BMP" to mechanically recontour to obtain the desired outcome.

Topsoil redistribution: Topsoils shall be replaced to their original relative positions and contoured so as to achieve erosion control, long-term stability and preservation of surface water flow patterns.

Soil treatment: Topsoils shall be replaced to their original relative positions and contoured so as to achieve erosion control, long-term stability and preservation of surface water flow patterns.

Existing Vegetation at the well pad:

Existing Vegetation at the well pad attachment:

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BIG SINKS DRAW 25-24 FED COM

Well Number: 711H

Existing Vegetation Community at the road:

Existing Vegetation Community at the road attachment:

Existing Vegetation Community at the pipeline:

Existing Vegetation Community at the pipeline attachment:

Existing Vegetation Community at other disturbances:

Existing Vegetation Community at other disturbances attachment:

Non native seed used? NO

Non native seed description:

Seedling transplant description:

Will seedlings be transplanted for this project? NO

Seedling transplant description attachment:

Will seed be harvested for use in site reclamation? NO

Seed harvest description:

Seed harvest description attachment:

Seed Management

Seed Table

Seed type:

Seed source:

Seed name:

Source name:

Source address:

Source phone:

Seed cultivar:

Seed use location:

PLS pounds per acre:

Proposed seeding season:

Seed Summary

Total pounds/Acre:

Seed Type	Pounds/Acre
------------------	--------------------

Seed reclamation attachment:

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BIG SINKS DRAW 25-24 FED COM

Well Number: 711H

Operator Contact/Responsible Official Contact Info

First Name: JACOB

Last Name: OCHOA

Phone: (575)748-9934

Email: jacob.ochoa@dvn.com

Seedbed prep:

Seed BMP:

Seed method:

Existing invasive species? NO

Existing invasive species treatment description:

Existing invasive species treatment attachment:

Weed treatment plan description: Maintain weeds on an as need basis.

Weed treatment plan attachment:

Monitoring plan description: Monitor as needed.

Monitoring plan attachment:

Success standards: N/A

Pit closure description: N/A

Pit closure attachment:

Section 11 - Surface Ownership

Disturbance type: NEW ACCESS ROAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BIG SINKS DRAW 25-24 FED COM

Well Number: 711H

Disturbance type: EXISTING ACCESS ROAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Disturbance type: WELL PAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BIG SINKS DRAW 25-24 FED COM

Well Number: 711H

Disturbance type: PIPELINE

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Section 12 - Other Information

Right of Way needed? NO

Use APD as ROW?

ROW Type(s):

ROW Applications

SUPO Additional Information: ELECTRIC SURVEY FLOWLINE SURVEY GAS CAPTURE PLAN GRADING PLAN & X-SECTION MISC PLATS

Use a previously conducted onsite? NO

Previous Onsite information:

Other SUPO Attachment

BSD_25_24_Fed_Com_711H_Electric_20171109121716.pdf

BSD_25_24_Fed_Com_711H_Flowline_20171109121727.pdf

BSD_25_24_Fed_Com_711H_GasCapturePlan_20171109121736.pdf

BSD_25_24_Fed_Com_711H_Grading_Plan_X_Sec_20171109121748.pdf


Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BIG SINKS DRAW 25-24 FED COM

Well Number: 711H

BSD_25_24_Fed_Com_711H_Misc_Plats_20171109121759.pdf

SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO
 ACCESS AERIAL ROUTE MAP



NOT TO SCALE
 AERIAL PHOTO:
 GOOGLE EARTH
 NOVEMBER 2015

DEVON ENERGY PRODUCTION COMPANY, L.P.
BIG SINKS DRAW 25-24 FED COM 711H
 LOCATED 2484 FT. FROM THE NORTH LINE
 AND 985 FT. FROM THE WEST LINE OF
 SECTION 25, TOWNSHIP 25 SOUTH,
 RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO


OCTOBER 11, 2017

SURVEY NO. 5661

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO


ACCESS ROAD PLAT
 ACCESS ROAD TO THE BIG SINKS DRAW 25-24 FED COM 711H

DEVON ENERGY PRODUCTION COMPANY, L.P.
 CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
 SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO
 OCTOBER 11, 2017



SEC 25
 T.25S., R.31E.
 BLM

SEE NEXT SHEET (2-2) FOR DESCRIPTION



GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SURVEYOR CERTIFICATE

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 20 DAY OF OCTOBER 2017

Filmon F. Jaramillo
 FILMON F. JARAMILLO, P.E.S. 12797

MADRON SURVEYING, INC.
 301 SOUTH CANAL
 CARLSBAD, NEW MEXICO 88220
 Phone (575) 234-3341

SURVEY NO. 5661

SHEET: 1-2

MADRON SURVEYING, INC. CARLSBAD, NEW MEXICO

301 SOUTH CANAL
 (575) 234-3341

ACCESS ROAD PLAT
ACCESS ROAD TO THE BIG SINKS DRAW 25-24 FED COM 711H

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
OCTOBER 11, 2017

DESCRIPTION

A STRIP OF LAND 30 FEET WIDE CROSSING BUREAU OF LAND MANAGEMENT LAND IN SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, STATE OF NEW MEXICO AND BEING 15 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

BEGINNING AT A POINT WITHIN THE SW/4 NW/4 OF SAID SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE WEST QUARTER CORNER OF SAID SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S85°35'39"W, A DISTANCE OF 290.14 FEET;

THENCE N89°32'49"E A DISTANCE OF 486.72 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE WEST QUARTER CORNER OF SAID SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S88°04'15"W, A DISTANCE OF 776.43 FEET;

SAID STRIP OF LAND BEING 486.72 FEET OR 29.50 RODS IN LENGTH, CONTAINING 0.335 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

SW/4 NW/4 486.72 L.F. 29.50 RODS 0.335 ACRES

GENERAL NOTES

1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.

2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 20 DAY OF OCTOBER 2017


FILIMON F. JARAMILLO, PLS. 12797
PROFESSIONAL SURVEYOR

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SHEET: 2-2

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
(575) 234-3341 SURVEY NO. 5661

PLAT

One Mile Radius Map



This map is for illustrative purposes only and is neither a legally recorded map nor a survey and is not intended to be used as one. Devon makes no warranty, representation, or guarantee of any kind regarding this map.

GCS North American 1983
Datum: North American 1983; Units: Degree
Created by: lemois
Map is current as of 10/26/2017.




Miles
0 0.3 1 inch = 0 miles

**BIG SINKS DRAW 25-24 FED COM 711H
WA017086295**

BIG SINKS DRAW 25 FED COM 1H
Nearest wellbore to SHL: 482 ft.

BIG SINKS DRAW 25 FED COM 1H
Nearest wellbore to BHL: 197 ft.

- SHL
- × BHL



BIG SINKS DRAW 25-24 FED COM 711H

 devon

This map is for illustrative purposes only and is neither a legally recorded map nor survey and is not intended to be used as one. Devon makes no warranty, representation, or guarantee of any kind regarding this map.

WGS_1984_Web_Mercator_Auxiliary_Sphere
Prepared by: _User
Map is current as of: 25-Oct-2017



Miles

0 0.28 0.56 1.12 1:56,913

TRIONYX TW POND


COTTON DRAW FW POND

TW LINE 35,620'


**DURATION 30 DAYS: INSTALL DAYS PRIOR TO COMPLETION
DEVON WILL CONTACT BLM IF ADDITIONAL TIME IS NEEDED
DISTURBANC: EXISTING
CONTENTS: TREATED WATER AND FRESH WATER
SIZE OF PIPE: 10" OR 12" LAY FLAT
LENGTH OF PIPE: 35,620' TW & 34,239' FW**

BIG SINKS DRAW 25-24 FED COM 711H

- State pit 616 and 617 32- 23S- 32E




- Fed pit 25- 23S- 31E




- Private pit 26- 23S- 31E

**SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
INTERIM SITE BUILD PLAN**

- A - BIG SINKS DRAW 25-24
FED COM 521H
- B - BIG SINKS DRAW 25-24
FED COM 531H
- C - BIG SINKS DRAW 25-24
FED COM 331H
- D - BIG SINKS DRAW 25-24
FED COM 611H



 DENOTES INTERIM PAD RECLAMATION AREA

 DENOTES GRADING SITE RECLAMATION AREA

0 12 60 120 240
SCALE 1" = 120'

**DEVON ENERGY PRODUCTION COMPANY, L.P.
BIG SINKS DRAW 25-24 FED COM 711H
LOCATED 2484 FT. FROM THE NORTH LINE
AND 985 FT. FROM THE WEST LINE OF
SECTION 25, TOWNSHIP 25 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO**


1.829± ACRES INTERIM PAD RECLAMATION AREA
3.239± ACRES GRADING SITE RECLAMATION AREA
3.197± ACRES NON-RECLAIMED AREA
8.265± ACRES COTTON DRAW MDP2 BIG SINKS PAD 25-1

OCTOBER 11, 2017

SURVEY NO. 5661

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 **CARLSBAD, NEW MEXICO**

EXHIBIT "A"
 PAGE 1 of 4
 ELECTRIC LINE PLAT
 SECTION 25, T25S-R31E, N.M.P.M.
 EDDY COUNTY, NEW MEXICO




30' EASEMENT AREA = 0.277 ACRE(S)
 402.22 FEET OR 24.38 RODS

SEE THE ATTACHED LEGAL DESCRIPTION


Note: All bearings recited herein are based on the New Mexico State Plane Coordinate System, NAD 83, New Mexico East Zone 3001, US Survey Feet, all distances are grid.

I, B.L. Laman, New Mexico PLS No. 22404 hereby certify this survey to reflect an actual survey made on the ground under my supervision. This survey meets the minimum standards of surveying in New Mexico.



B.L. Laman PLS #22404
 Date Signed: 07-05-2017
 Horizonrow, LLC
 924 Richardson Dr., Jasper, TX
 (803) 388-3045 75951
 Employee of Horizonrow, LLC

- 0+00.0 P.O.B./XCEL TO BIG SINKS DRAW 25 BS BATTERY LATERAL ELECTRIC LINE
- 0+29.8 VAN DOO DAH LATERAL
- 0+36.4 EXISTING PIPELINE
- 0+67.5 FIBER OPTIC LINE
- 1+02.4 EDGE OF ROAD
- 1+13.6 C/L ACCESS ROAD
- 1+25.2 EDGE OF ROAD
- 1+69.4 STAKED POWER POLE
- 3+40.2 STAKED POWER POLE
- 3+70.2 EXISTING PIPELINE
- 3+81.0 EXISTING PIPELINE
- 4+02.2 P.O.E./BIG SINKS 25-1 PAD



HORIZON ROW LLC

Drawn for:



Drawn by:
 CHRIS MAAS

Date: 06/21/2017

DEVON ENERGY PRODUCTION COMPANY, L.P.

COTTON DRAW MDP2 WELLPAD
 25-1 ELECTRIC LINE

PROPOSED 30' EASEMENT
 ON THE PROPERTY OF
 BUREAU OF LAND MANAGEMENT
 SECTION 25, T25S-R31E, N.M.P.M.

LINE NUMBER:
 EL7961

WBS NUMBER:
 XX-124737.AL

SCALE:
 1" = 1000'

REVISIONS:

SHEET:
 1 OF 4

**SECTION 25, T25S-R31E, N.M.P.M.,
EDDY COUNTY, NEW MEXICO**

ELECTRIC LINE PLAT

LEGAL DESCRIPTION

FOR

DEVON ENERGY PRODUCTION COMPANY, L.P.

BUREAU OF LAND MANAGEMENT

30' EASEMENT DESCRIPTION:

BEING an easement thirty (30) feet in width lying fifteen (15) feet on the right side and fifteen (15) feet on the left side of the survey centerline described below, being out of the southwest quarter (SW ¼) and the northwest quarter (NW ¼) of Section 25, Township 25 South, Range 31 East, N.M.P.M., Eddy County, New Mexico, and being out of a parcel of land owned by the Bureau of Land Management. Said centerline of easement being more particularly described as follows:

Commencing from a 2" iron pipe w/BC for the southwest corner of Section 25, T25S-R31E, N.M.P.M., Eddy County, New Mexico;

Thence N 14°12'26" E a distance of 2646.94' to the **Point of Beginning** of this easement having coordinates of Northing=401008.18 feet, Easting=725661.29 feet and continuing the following courses;

Thence N 08°57'36" E a distance of 340.24' to an angle point;

Thence N 89°22'34" E a distance of 61.98' to the **Point of Ending** having coordinates of Northing=401344.94 feet, Easting=725776.26 feet, from said point a 2" iron pipe w/BC for the northwest corner of Section 25, T25S-R31E bears N 18°13'08" W a distance of 2504.21', covering **402.22' or 24.38 rods** and having an area of **0.277 acres**.

NOTES:

Bearings, distances and coordinates shown herein are based on New Mexico State Plane Coordinate System, NAD 83, East Zone 3001, US Survey Feet, all distances are grid.


I, B.L. Laman, New Mexico PLS No. 22404, hereby certify this survey to reflect an actual survey made on the ground under my supervision. This survey meets the minimum standards for surveying in New Mexico.



B.L. Laman PLS 22404
Date Signed: 07/05/2017
Horizon Row, LLC
924 Richardson Dr., Jasper, TX
(903) 388-3045 75951
Employee of Horizon Row, LLC



EXHIBIT "A"
PAGE 3 of 4



QUAD MAP

SECTION 25, T25S-R31E, N.M.P.M.
EDDY COUNTY, NEW MEXICO

HORIZON ROW LLC	
DEVON ENERGY PRODUCTION CO., L.P.	
PROPOSED 30' EASEMENT	
Drawn by: CHRIS MAAS	Date: 06/21/2017

Drawn for:



LINE NUMBER: EL7961
WBS NUMBER: XX-124757.AL
SCALE: 1" = 2000'
REVISIONS:
SHEET: 3 OF 4

EXHIBIT "A"
PAGE 4 of 4

SEC. 23,
T25S-R31E

SEC. 24,
T25S-R31E

SEC. 19,
T25S-R32E

EDDY COUNTY, N.M.
LEA COUNTY, N.M.

BIG SINKS DRAW
TRUNKLINE
(GAS AND WATER)

BUREAU OF
LAND MANAGEMENT

COTTON DRAW MDP2
WTB 25-1 ELECTRIC LINE

BIG SINKS 25-1 #1H
WELL PAD

COTTON DRAW MDP2
WELLPAD 25-1
ELECTRIC LINE

SEC. 26,
T25S-R31E

SEC. 25,
T25S-R31E

VAN DOO DAH
LATERAL
WELL TO BIG SINKS DRAW
25-1B BATTERY LATERAL
ELECTRIC LINE

SEC. 30,
T25S-R32E

SEC. 35,
T25S-R31E

SEC. 34,
T25S-R31E

SEC. 18,
T25S-R32E

R-31-E
R-32-E

AERIAL MAP

SECTION 25, T25S-R31E, N.M.P.M.
EDDY COUNTY, NEW MEXICO

HORIZON ROW LLC	
DEVON ENERGY PRODUCTION CO., L.P.	
PROPOSED 30' EASEMENT	
Drawn by: CHRIS MAAS	Date: 06/21/2017

Drawn for:




LINE NUMBER: EL7961
WBS NUMBER: XX-124757.AL
SCALE: 1" = 2000'
REVISIONS:
SHEET: 4 OF 4


FLOWLINE PLAT

FIVE-4" POLY FLEX FLOWLINES AND ONE-6" GAS LIFT LINE BURIED IN THE SAME DITCH FROM BIG SINKS DRAW 25-24 FED COM 331H, 521H, 531H, 611H, & 711H TO COTTON DRAW MDP2 BIG SINKS 25 CTB 1

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF A PIPELINE CROSSING
SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
OCTOBER 26, 2017



SEE NEXT SHEET (2-4) FOR DESCRIPTION



GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 26 DAY OF OCTOBER 2017.

(Signature of Filimon F. Jaramillo)
 12797
 FILIMON F. JARAMILLO PLS. 12797

MADRON SURVEYING, INC.
 301 SOUTH CANAL
 CARLSBAD, NEW MEXICO 88220
 Phone (575) 234-3341

SHEET: 1-4

MADRON SURVEYING, INC. CARLSBAD, NEW MEXICO

SURVEY NO. 5690

FLOWLINE PLAT

FIVE-4" POLY FLEX FLOWLINES AND ONE-6" GAS LIFT LINE BURIED IN THE SAME DITCH FROM BIG SINKS DRAW 25-24 FED COM 331H, 521H, 531H, 611H, & 711H TO COTTON DRAW MDP2 BIG SINKS 25 CTB 1

**DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF A PIPELINE CROSSING
SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
OCTOBER 26, 2017**

DESCRIPTION

A STRIP OF LAND 30 FEET WIDE CROSSING BUREAU OF LAND MANAGEMENT LAND IN SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, STATE OF NEW MEXICO AND BEING 15 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

BEGINNING AT A POINT WITHIN THE SW/4 NW/4 OF SAID SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE WEST QUARTER CORNER OF SAID SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S61°41'12"W, A DISTANCE OF 1081.54 FEET;
THENCE N00°00'31"E A DISTANCE OF 100.05 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;
THENCE S89°59'08"E A DISTANCE OF 286.78 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;
THENCE N00°12'44"E A DISTANCE OF 35.92 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE NORTHWEST CORNER OF SAID SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS N32°04'29"W, A DISTANCE OF 2350.32 FEET;

SAID STRIP OF LAND BEING 422.75 FEET OR 25.62 RODS IN LENGTH, CONTAINING 0.291 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

SW/4 NW/4 422.75 L.F. 25.62 RODS 0.291 ACRES

GENERAL NOTES

1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.

2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SHEET: 2-4

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO (975) 234-3341

SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO THIS _____ DAY OF OCTOBER 2017

(Signature)
12797
FILIMON F. JARAMILLO, PLS. 12797
301 SOUTH CANAL
(975) 234-3341


MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SURVEY NO. 5690

FLOWLINE PLAT


FIVE-4" POLY FLEX FLOWLINES AND ONE-6" GAS LIFT LINE BURIED IN THE SAME DITCH FROM BIG SINKS
DRAW 25-24 FED COM 331H, 521H, 531H, 611H, & 711H TO COTTON DRAW MDP2 BIG SINKS 25 CTB 1

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF A PIPELINE CROSSING
SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
OCTOBER 26, 2017




SEC 25
T.25S., R.31E.

PLAN VIEW



- A BIG SINKS DRAW 25-24
FED COM 521H
- B BIG SINKS DRAW 25-24
FED COM 531H
- C BIG SINKS DRAW 25-24
FED COM 331H
- D BIG SINKS DRAW 25-24
FED COM 611H
- E BIG SINKS DRAW 25-24
FED COM 711H

DEVON ENERGY PRODUCTION COMPANY, L.P.
 GRADING PLAN AND CROSS SECTIONS
BIG SINKS DRAW 25-24 FED COM 711H
 SECTION 25, TOWNSHIP 25 SOUTH,
 RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO






CUT	FILL	NET
5422 CU. YD	11752 CU. YD	6330 CU. YD (FILL)

EARTHWORK QUANTITIES ARE ESTIMATED


OCTOBER 11, 2017
 MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
 (575) 234-3341

SHEET 1-2
 SURVEY NO. 5661

CROSS SECTIONS



DEVON ENERGY PRODUCTION COMPANY, L.P.
GRADING PLAN AND CROSS SECTIONS
BIG SINKS DRAW 25-24 FED COM 711H
 SECTION 25, TOWNSHIP 25 SOUTH,
 RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO



CUT	FILL	NET
5422 CU. YD	11752 CU. YD	6330 CU. YD (FILL)

EARTHWORK QUANTITIES ARE ESTIMATED

OCTOBER 11, 2017



MADRON SURVEYING, INC. 301 SOUTH CANAL
 (575) 234-3341 **CARLSBAD, NEW MEXICO**

SHEET 2-2
 SURVEY NO. 5661

**SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
SITE MAP**

NOTE: LATITUDE AND LONGITUDE COORDINATES ARE SHOWN USING THE NORTH AMERICAN DATUM OF 1983 (NAD83) LISTED NEW MEXICO STATE PLANE EAST COORDINATES ARE GRID (NAD83). BASIS OF BEARING AND DISTANCES USED ARE NEW MEXICO STATE PLANE EAST COORDINATES MODIFIED TO THE SURFACE. VERTICAL DATUM NAVD88.

- A - BIG SINKS DRAW 25-24
FED COM 521H
- B - BIG SINKS DRAW 25-24
FED COM 531H
- C - BIG SINKS DRAW 25-24
FED COM 331H
- D - BIG SINKS DRAW 25-24
FED COM 611H



SCALE 1" = 120'
DIRECTIONS TO LOCATION

FROM STATE HIGHWAY 128 AND CR 1 (ORLA ROAD) GO SOUTH ON CR 1 6.2 MILES, TURN RIGHT ON CALICHE ROAD (MONSANTO ROAD) AND GO WEST 2.1 MILES, TURN RIGHT AND GO NORTH 0.4 OF A MILE, CROSS A CATTLE GUARD, CONTINUE NORTH 0.4 OF A MILE, ROAD BENDS LEFT (WEST) CONTINUE WEST 2.0 MILES TO AN INTERSECTION, CONTINUE SOUTHWEST THROUGH INTERSECTION, ROAD BENDS SOUTH, CROSS A CATTLE GUARD, 3.45 MILES FROM INTERSECTION TURN LEFT ON CALICHE ROAD AND GO EAST 1.0 MILE TO A PROPOSED ROAD SURVEY AND FOLLOW FLAGS NORTH 3500' THEN EAST 310' TO THE SOUTHWEST CORNER OF BIG SINKS DRAW 25 FED COM 1H, CONTINUE EAST 487' TO THE SOUTHWEST PAD CORNER FOR THIS LOCATION.


**DEVON ENERGY PRODUCTION COMPANY, L.P.
BIG SINKS DRAW 25-24 FED COM 711H
LOCATED 2484 FT. FROM THE NORTH LINE
AND 985 FT. FROM THE WEST LINE OF
SECTION 25, TOWNSHIP 25 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO**

OCTOBER 11, 2017

SURVEY NO. 5661

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 **CARLSBAD, NEW MEXICO**

SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
LOCATION VERIFICATION MAP



USGS QUAD MAP:
PADUCA BREAKS WEST

NOT TO SCALE


DEVON ENERGY PRODUCTION COMPANY, L.P.
BIG SINKS DRAW 25-24 FED COM 711H
LOCATED 2484 FT. FROM THE NORTH LINE
AND 985 FT. FROM THE WEST LINE OF
SECTION 25, TOWNSHIP 25 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

OCTOBER 11, 2017

SURVEY NO. 5661

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
(575) 234-3341

SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO
 VICINITY MAP



DISTANCES IN MILES

NOT TO SCALE

DEVON ENERGY PRODUCTION COMPANY, L.P.
BIG SINKS DRAW 25-24 FED COM 711H
 LOCATED 2484 FT. FROM THE NORTH LINE
 AND 985 FT. FROM THE WEST LINE OF
 SECTION 25, TOWNSHIP 25 SOUTH,
 RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO

OCTOBER 11, 2017


SURVEY NO. 5661

DIRECTIONS TO LOCATION

FROM STATE HIGHWAY 128 AND CR 1 (ORLA ROAD) GO SOUTH ON CR 1 6.2 MILES, TURN RIGHT ON CALICHE ROAD (MONSANTO ROAD) AND GO WEST 2.1 MILES, TURN RIGHT AND GO NORTH 0.4 OF A MILE, CROSS A CATTLE GUARD, CONTINUE NORTH 0.4 OF A MILE, ROAD BENDS LEFT (WEST) CONTINUE WEST 2.0 MILES TO AN INTERSECTION, CONTINUE SOUTHWEST THROUGH INTERSECTION, ROAD BENDS SOUTH, CROSS A CATTLE GUARD, 3.45 MILES FROM INTERSECTION TURN LEFT ON CALICHE ROAD AND GO EAST 1.0 MILE TO A PROPOSED ROAD SURVEY AND FOLLOW FLAGS NORTH 3500' THEN EAST 310' TO THE SOUTHWEST CORNER OF BIG SINKS DRAW 25 FED COM 1H, CONTINUE EAST 487' TO THE SOUTHWEST PAD CORNER FOR THIS LOCATION.

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO

SECTION 25, TOWNSHIP 25 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
AERIAL PHOTO



NOT TO SCALE
AERIAL PHOTO:
GOOGLE EARTH
NOVEMBER 2015

DEVON ENERGY PRODUCTION COMPANY, L.P.
BIG SINKS DRAW 25-24 FED COM 711H
LOCATED 2484 FT. FROM THE NORTH LINE
AND 985 FT. FROM THE WEST LINE OF
SECTION 25, TOWNSHIP 25 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

OCTOBER 11, 2017

SURVEY NO. 5661

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
(575) 234-3341

Section 1 - General

Would you like to address long-term produced water disposal? NO

Section 2 - Lined Pits

Would you like to utilize Lined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Lined pit PWD on or off channel:

Lined pit PWD discharge volume (bbl/day):

Lined pit specifications:

Pit liner description:

Pit liner manufacturers information:

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal permit:

Lined pit precipitated solids disposal schedule:

Lined pit precipitated solids disposal schedule attachment:

Lined pit reclamation description:

Lined pit reclamation attachment:

Leak detection system description:

Leak detection system attachment:

Lined pit Monitor description:

Lined pit Monitor attachment:

Lined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Lined pit bond number:

Lined pit bond amount:

Additional bond information attachment:

Section 3 - Unlined Pits

Would you like to utilize Unlined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Unlined pit PWD on or off channel:

Unlined pit PWD discharge volume (bbl/day):

Unlined pit specifications:

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal permit:

Unlined pit precipitated solids disposal schedule:

Unlined pit precipitated solids disposal schedule attachment:

Unlined pit reclamation description:

Unlined pit reclamation attachment:

Unlined pit Monitor description:

Unlined pit Monitor attachment:

Do you propose to put the produced water to beneficial use?

Beneficial use user confirmation:

Estimated depth of the shallowest aquifer (feet):

Does the produced water have an annual average Total Dissolved Solids (TDS) concentration equal to or less than that of the existing water to be protected?

TDS lab results:

Geologic and hydrologic evidence:

State authorization:

Unlined Produced Water Pit Estimated percolation:

Unlined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Unlined pit bond number:

Unlined pit bond amount:

Additional bond information attachment:

Section 4 - Injection

Would you like to utilize Injection PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Injection PWD discharge volume (bbl/day):

Injection well mineral owner:

Injection well type:

Injection well number:

Assigned injection well API number?

Injection well new surface disturbance (acres):

Minerals protection information:

Mineral protection attachment:

Underground Injection Control (UIC) Permit?

UIC Permit attachment:

Injection well name:

Injection well API number:

Section 5 - Surface Discharge

Would you like to utilize Surface Discharge PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Surface discharge PWD discharge volume (bbl/day):

Surface Discharge NPDES Permit?

Surface Discharge NPDES Permit attachment:

Surface Discharge site facilities information:

Surface discharge site facilities map:

Section 6 - Other

Would you like to utilize Other PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Other PWD discharge volume (bbl/day):

Other PWD type description:

Other PWD type attachment:

Have other regulatory requirements been met?

Other regulatory requirements attachment:



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Bond Information

Federal/Indian APD: FED

BLM Bond number: CO1104

BIA Bond number:

Do you have a reclamation bond? NO

Is the reclamation bond a rider under the BLM bond?

Is the reclamation bond BLM or Forest Service?

BLM reclamation bond number:

Forest Service reclamation bond number:

Forest Service reclamation bond attachment:

Reclamation bond number:

• Reclamation bond amount:

Reclamation bond rider amount:

• Additional reclamation bond information attachment: