

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

OCD Artesia

FORM APPROVED
OMB NO. 1004-0137
Expires: January 31, 2018**SUNDRY NOTICES AND REPORTS ON WELLS**
*Do not use this form for proposals to drill or to re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.*5. Lease Serial No.
NMNM108456

6. If Indian, Allottee or Tribe Name

SUBMIT IN TRIPLICATE - Other instructions on page 2

7. If Unit or CA/Agreement, Name and/or No.

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

8. Well Name and No.

KIAWAH BFQ FEDERAL 1

2. Name of Operator

EOG Y RESOURCES INC

Contact: TINA HUERTA

E-Mail: tina_huerta@eogresources.com

9. API Well No.

30-015-38095-00-S1

3a. Address

104 S 4TH STREET
ARTESIA, NM 88210

3b. Phone No. (include area code)

Ph: 575-748-4168

10. Field and Pool or Exploratory Area

UNDESIGNATED

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

Sec 34 T20S R25E NWSW 2310FSL 400FWL

GC 12-17-18
Accepted for record - NMOCD

11. County or Parish, State

EDDY COUNTY, NM

12. CHECK THE APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Hydraulic Fracturing	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input checked="" type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation: Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recompleat horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recompleat in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed and the operator has determined that the site is ready for final inspection.

EOG Y Resources, Inc. plans to plug and abandon this well as follows:

1. MIRU all safety equipment as needed. POOH with production equipment.
2. RIH with bit and scraper 2788 ft
3. Set a CIBP at 2788 ft with 25 sx of Class C cement on top. This will cover the top of Yeso. WOC. Tag TOC. *Tag 20 lower than 2608. Covers T/Yeso & T/Glorieta*
4. Set a CIBP at 1040 ft with 100 ft Class C cement on top. This will cover the top of San Andres. WOC. Tag TOC. *or spot 25 sx plug from 1040-940*
5. Perforate at 852 ft. Attempt to establish circulation between 9-5/8 inch and 7 inch casing.
6. If no circulation see step 7. If able to circulate see step 8.
7. Spot a 35 sx (188 ft) Class C cement plug from 940 ft ? 752 ft. This will cover the 9-5/8 inch casing shoe. *WOC Tag*

*Records indicate Both 9 5/8" & 7" Circ. to Surf. Perf/sec NO Required.***SEE ATTACHED FOR
CONDITIONS OF APPROVAL****NM OIL CONSERVATION**

14. I hereby certify that the foregoing is true and correct.

Electronic Submission #443768 verified by the BLM Well Information System

ARTESIA DISTRICT

For EOG Y RESOURCES INC, sent to the Carlsbad

Committed to AFMSS for processing by DEBORAH MCKINNEY on 11/13/2018 (19DLM0111SE) DEC 12 2018

Name (Printed/Typed) TINA HUERTA

Title REGULATORY SPECIALIST

Signature (Electronic Submission)

Date 11/12/2018

RECEIVED**THIS SPACE FOR FEDERAL OR STATE OFFICE USE**

Approved By <i>James R. Pons</i>	Title <i>SPET</i>	Date <i>11-29-18</i>
----------------------------------	-------------------	----------------------

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office *CHO*

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

**** BLM REVISED ** BLM REVISED ** BLM REVISED ** BLM REVISED ** BLM REVISED ******ENTERED**
[Signature]

Additional data for EC transaction #443768 that would not fit on the form

32. Additional remarks, continued

8. Spot a 150 sx Class C cement plug circulating cement back to surface between the 7 inch and 9-5/8 inch casing and a 188 ft cement plug inside the 7 inch casing from 940 ft ? 752 ft. This will cover the 9-5/8 inch casing shoe. WOC. Tag TOC.
9. Spot a 25 sx Class C cement plug from 150 ft up to surface.
10. Cut off wellhead and install dry hole marker. Clean location.

Wellbore schematics attached

WELL NAME: Kiawah BFQ Federal #1 FIELD: _____

LOCATION: 2310' FNL & 400' FWL Sec. 34-20S-25E

GL: 3370' ZERO: _____ KB: _____

COMMENTS: API No.: 30-015-38095

CASING PROGRAM

9-5/8" 36# K-55	802'
7" 26# J-55	3600'

Before

Formations

Tops	Depth (ft)
San Andres	990
Glorieta	2658
Yeso	2802

14-3/4" Hole

9-5/8" casing @ 802'. Cemented with 670sx circulated to surface.

8 3/4" Hole

Yeso Perforations @
2838' - 2890'

7" casing @ 3600'. Cemented w/ 555
sx circulated to surface.

TD: 3600'
PBTD: 3555'

Not to Scale
11/4/2018
SAA


WELL NAME: Kiawah BFQ Federal #1 FIELD: _____
 LOCATION: 2310' FNL & 400' FWL Sec. 34-20S-25E
 GL: 3370' ZERO: _____ KB: _____
 COMMENTS: API No.: 30-015-38095

CASING PROGRAM

9-5/8" 36# K-55	802'
7" 26# J-55	3600'

After

Formations	
Tops	Depth (ft)
San Andres	990
Glorieta	2658
Yes	2802



Not to Scale
 11/4/2018
 SAA

BUREAU OF LAND MANAGEMENT
Carlsbad Field Office
620 East Greene Street
Carlsbad, New Mexico 88220
575-234-5972

Permanent Abandonment of Federal Wells
Conditions of Approval

Failure to comply with the following Conditions of Approval may result in a Notice of Incidents of Noncompliance (INC) in accordance with 43 CFR 3163.1.

1. Plugging operations shall commence within **ninety (90)** days from the approval date of this Notice of Intent to Abandon.

If you are unable to plug the well by the 90th day provide this office, prior to the 90th day, with the reason for not meeting the deadline and a date when we can expect the well to be plugged. Failure to do so will result in enforcement action.

The rig used for the plugging procedure cannot be released and moved off without the prior approval of the authorized officer. Failure to do so may result in enforcement action.

2. **Notification:** Contact the appropriate BLM office at least 24 hours prior to the commencing of any plugging operations. For wells in Chaves and Roosevelt County, call 575-627-0272; Eddy County, call 575-361-2822; Lea County, call 575-393-3612.

3. **Blowout Preventers:** A blowout preventer (BOP), as appropriate, shall be installed before commencing any plugging operation. The BOP must be installed and maintained as per API and manufacturer recommendations. The minimum BOP requirement is a 2M system for a well not deeper than 9,090 feet; a 3M system for a well not deeper than 13,636 feet; and a 5M system for a well not deeper than 22,727 feet.

4. **Mud Requirement:** Mud shall be placed between all plugs. Minimum consistency of plugging mud shall be obtained by mixing at the rate of 25 sacks (50 pounds each) of gel per 100 barrels of brine water. Minimum nine (9) pounds per gallon.

5. **Cement Requirement:** Sufficient cement shall be used to bring any required plug to the specified depth and length. Any given cement volumes on the proposed plugging procedure are merely estimates and are not final. Unless specific approval is received, no plug except the surface plug shall be less than 25 sacks of cement. Any plug that requires a tag will have a minimum WOC time of 4 hours.

In lieu of a cement plug across perforations in a cased hole (not for any other plugs), a bridge plug set within 50 feet to 100 feet above the perforations shall be capped with 25 sacks of cement. If a bailer is used to cap this plug, 35 feet of cement shall be sufficient. **Before pumping or bailing cement on top of CIBP, tag will be required to verify depth. Based on depth, a tag of the cement may be deemed necessary.**

Unless otherwise specified in the approved procedure, the cement plug shall consist of either Neat Class "C", for up to 7,500 feet of depth or Neat Class "H", for deeper than 7,500 feet plugs.

6. Dry Hole Marker: All casing shall be cut-off at the base of the cellar or 3 feet below final restored ground level (whichever is deeper). **The BLM is to be notified a minimum of 4 hours prior to the wellhead being cut off to verify that cement is to surface in the casing and all annuluses. Wellhead cut off shall commence within ten (10) calendar days of the well being plugged. If the cut off cannot be done by the 10th day, the BLM is to be contacted with justification to receive an extension for completing the cut off.**

The well bore shall then be capped with a 4-inch pipe, 10-feet in length, 4 feet above ground and embedded in cement, unless otherwise noted in COA (requirements will be attached). The following information shall be permanently inscribed on the dry hole marker: well name and number, name of the operator, lease serial number, surveyed location (quarter-quarter section, section, township and range or other authorized survey designation acceptable to the authorized officer such as metes and bounds).

7. Subsequent Plugging Reporting: Within 30 days after plugging work is completed, file one original and three copies of the Subsequent Report of Abandonment, Form 3160-5 to BLM. The report should give in detail the manner in which the plugging work was carried out, the extent (by depths) of cement plugs placed, and the size and location (by depths) of casing left in the well. **Show date well was plugged.**

8. Trash: All trash, junk and other waste material shall be contained in trash cages or bins to prevent scattering and will be removed and deposited in an approved sanitary landfill. Burial on-site is not permitted.

Following the submission and approval of the Subsequent Report of Abandonment, surface restoration will be required. See attached reclamation objectives.