

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENTFORM APPROVED
OMB NO. 1004-0137
Expires: January 31, 2018**SUNDRY NOTICES AND REPORTS ON WELLS**
*Do not use this form for proposals to drill or to re-enter an abandoned well. Use form 3160-3 (APD) for such proposals.*5. Lease Serial No.
NMNM26870

6. If Indian, Allottee or Tribe Name

7. If Unit or CA/Agreement, Name and/or No.

SUBMIT IN TRIPLICATE - Other instructions on page 2

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

CIMAREX ENERGY COMPANY OF CO

Contact: FATIMA VASQUEZ

E-Mail: fvasquez@cimarex.com

3a. Address

600 N MARIENFELD STE 600
MIDLAND, TX 79703

3b. Phone No. (include area code)

Ph: 432.820.1933

BLM CONSERVATION
ARTESIA DISTRICT10. Field and Pool or Exploratory Area
WILDCAT

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

Sec 35 T25S R26E SESE 200FSL 1010FEL

MAR 11 2019

11. County or Parish, State

EDDY COUNTY, NM

RECEIVED

12. CHECK THE APPROPRIATE BOX(ES) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
<input checked="" type="checkbox"/> Notice of Intent	<input type="checkbox"/> Acidize	<input type="checkbox"/> Deepen	<input type="checkbox"/> Production (Start/Resume)	<input type="checkbox"/> Water Shut-Off
<input type="checkbox"/> Subsequent Report	<input type="checkbox"/> Alter Casing	<input type="checkbox"/> Hydraulic Fracturing	<input type="checkbox"/> Reclamation	<input type="checkbox"/> Well Integrity
<input type="checkbox"/> Final Abandonment Notice	<input type="checkbox"/> Casing Repair	<input type="checkbox"/> New Construction	<input type="checkbox"/> Recomplete	<input checked="" type="checkbox"/> Other
	<input type="checkbox"/> Change Plans	<input type="checkbox"/> Plug and Abandon	<input type="checkbox"/> Temporarily Abandon	Change to Original A PD
	<input type="checkbox"/> Convert to Injection	<input type="checkbox"/> Plug Back	<input type="checkbox"/> Water Disposal	

13. Describe Proposed or Completed Operation: Clearly state all pertinent details, including estimated starting date of any proposed work and approximate duration thereof. If the proposal is to deepen directionally or recomple horizontally, give subsurface locations and measured and true vertical depths of all pertinent markers and zones. Attach the Bond under which the work will be performed or provide the Bond No. on file with BLM/BIA. Required subsequent reports must be filed within 30 days following completion of the involved operations. If the operation results in a multiple completion or recomple in a new interval, a Form 3160-4 must be filed once testing has been completed. Final Abandonment Notices must be filed only after all requirements, including reclamation, have been completed and the operator has determined that the site is ready for final inspection.

Cimarex respectfully requests approval to change the SHL and BHL of the Bonnie 35 Federal Com 2H well. There is no additional surface disturbance.

Cimarex also requests approval to change the completion formation to Bone Spring.

Approved:

SHL: 200' FSL & 1010' FEL Sec. 35

BHL: 330' FNL & 660' FEL Sec. 26

Proposed:

SHL: 260' FSL & 1010' FEL Sec. 35

BHL: 100' FNL & 990' FEL Sec. 35

Surface good 2-28-19 BR

Engineering is Good. All previous COAs still apply 25. 2-26-19



14. I hereby certify that the foregoing is true and correct.

Electronic Submission #444128 verified by the BLM Well Information System
For CIMAREX ENERGY COMPANY OF CO, sent to the Carlsbad
Committed to AFMSS for processing by PRISCILLA PEREZ on 11/15/2018 (19PP0383SE).

Name (Printed/Typed) FATIMA VASQUEZ

Title REGULATORY ANALYST

Signature (Electronic Submission)

Date 11/14/2018

THIS SPACE FOR FEDERAL OR STATE OFFICE USE

Approved By

[Signature]

Title

AFM - L & M

Date

[Signature]

Conditions of approval, if any, are attached. Approval of this notice does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

Office

CFD

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

(Instructions on page 2)

**** BLM REVISED ** BLM REVISED ** BLM REVISED ** BLM REVISED ** BLM REVISED ****

RWP - 3-22-19

• **Additional data for EC transaction #444128 that would not fit on the form**

32. Additional remarks, continued

Please see attached C-102 plat, directional plan, and drilling plan for changes.

1. Geological Formations

TVD of target 7,817

Pilot Hole TD N/A

MD at TD 12,571

Deepest expected fresh water 50

Formation	Depth (TVD) from KB	Water/Mineral Bearing/Target Zone	Hazards
Quaternary fill	0	N/A	
Rustler	0	N/A	
Salado	1199	N/A	
Castille	1763	N/A	
Lamar	1956	N/A	
Bell Canyon	2007	Hydrocarbons	
Cherry Canyon	2969	Hydrocarbons	
Brushy Canyon	3959	Hydrocarbons	
Brushy Canyon Lower	3959	Hydrocarbons	
Bone Spring	5524	Hydrocarbons	
Bone Spring A Shale	5645	Hydrocarbons	
Bone Spring C Shale	6031	Hydrocarbons	
1st Bone Spring Ss	6496	Hydrocarbons	
2nd Bone Spring Ls	6761	N/A	
2nd Bone Spring Ss	7023	Hydrocarbons	
2nd BS Ss Lower	7833	Hydrocarbons	
3rd Bone spring Ss	8353	Hydrocarbons	

2. Casing Program

Hole Size	Casing Depth From	Casing Depth To	Setting Depth TVD	Casing Size	Weight (lb/ft)	Grade	Conn.	SF Collapse	SF Burst	SF Tension
17 1/2	0	450	450	13-3/8"	48.00	H-40/J-55 Hybrid	ST&C	3.59	8.40	14.91
12 1/4	0	1935	1935	9-5/8"	36.00	J-55	ST&C	1.97	3.43	8.10
8 3/4	0	7364	7364	5-1/2"	17.00	L-80	LT&C	1.83	2.25	2.54
8 3/4	7364	12571	7817	5-1/2"	17.00	L-80	BT&C	1.72	2.12	51.55
BLM Minimum Safety Factor								1.125	1	1.6 Dry 1.8 Wet

TVD was used on all calculations.

All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h

	Y or N:
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Does casing meet API specifications? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the intermediate pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	N
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	N
Is well within the designated 4 string boundary.	N
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3rd string cement tied back 500' into previous casing?	N
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	N
Is 2nd string set 100' to 600' below the base of salt?	N
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	N
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	N
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	N
Is AC Report included?	N

3. Cementing Program

Casing	# Skts	Wt. lb/gal	Yld ft ³ /sack	H ₂ O gal/sk	500# Comp. Strength (hours)	Slurry Description
Surface	117	14.80	1.34	6.32	9.5	Lead: Class C + LCM
	192	14.80	1.36	6.57	9.5	Tail: Class C + Retarder
Intermediate	365	12.90	1.88	9.65	12	Lead: 35:65 (Poz:C) + Salt + Bentonite
	113	14.80	1.34	6.32	9.5	Tail: Class C + LCM
Production	486	10.30	3.64	22.18		Lead: Tuned Light + LCM
	1114	14.20	1.30	5.86	14:30	Tail: 50:50 (Poz:H) + Salt + Bentonite + Fluid Loss + Dispersant + SMS

Casing String	TOC	% Excess
Surface	0	33
Intermediate	0	50
Production	1735	18

4. Pressure Control Equipment

A variance is requested for the use of a diverter on the surface casing. See attached for schematic.					
BOP Installed and tested before drilling which hole?	Size	Min. Required WP	Type		Tested To
12 1/4	13 5/8	2M	Annular	X	50% of working pressure
			Blind Ram	X	2M
			Pipe Ram		
			Double Ram	X	
			Other		
8 3/4	13 5/8	3M	Annular	X	50% of working pressure
			Blind Ram		3M
			Pipe Ram		
			Double Ram	X	
			Other		

BOP/BOPE will be tested by an independent service company to 250 psi low and the high pressure indicated above per Onshore Order 2 requirements. The System may be upgraded to a higher pressure but still tested to the working pressure listed in the table above. If the system is upgraded all the components installed will be functional and tested.

Pipe rams will be operationally checked each 24 hour period. Blind rams will be operationally checked on each trip out of the hole. These checks will be noted on the daily tour sheets. Other accessories to the BOP equipment will include a Kelly cock and floor safety valve (inside BOP) and choke lines and choke manifold. See attached schematics.

	Formation integrity test will be performed per Onshore Order #2. On Exploratory wells or on that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.i.				
X	A variance is requested for the use of a flexible choke line from the BOP to Choke Manifold. See attached for specs and hydrostatic test chart.				
N	Are anchors required by manufacturer?				

5. Mud Program

Depth	Type	Weight (ppg)	Viscosity	Water Loss
0' to 450'	FW Spud Mud	8.30 - 8.80	30-32	N/C
450' to 1935'	Brine Water	9.70 - 10.20	30-32	N/C
1935' to 12571'	FW/Cut Brine	8.50 - 9.00	30-32	N/C

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	PVT/Pason/Visual Monitoring
---	-----------------------------

6. Logging and Testing Procedures

Logging, Coring and Testing	
X	Will run GR/CNL from TD to surface (horizontal well – vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
	No logs are planned based on well control or offset log information.
	Drill stem test?
	Coring?

Additional Logs Planned	Interval
-------------------------	----------

7. Drilling Conditions

Condition	
BH Pressure at deepest TVD	3658 psi
Abnormal Temperature	No

Hydrogen Sulfide (H2S) monitors will be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.

X	H2S is present
X	H2S plan is attached

8. Other Facets of Operation**9. Wellhead**

A multi-bowl wellhead system will be utilized.

After running the 13-3/8" surface casing, a 13 5/8" BOP/BOPE system with a minimum working pressure of 3000 psi will be installed on the wellhead system and will be pressure tested to 250 psi low followed by a 3000 psi test. Annular will be tested to 50% of working pressure. The pressure test will be repeated at least every 30 days, as per Onshore Order No. 2.

The multi-bowl wellhead will be installed by vendor's representative. A copy of the installation instructions has been sent to the BLM field office.

The wellhead will be installed by a third-party welder while being monitored by the wellhead vendor representative.

All BOP equipment will be tested utilizing a conventional test plug. Not a cup or J-packer type.

A solid steel body pack-off will be utilized after running and cementing the intermediate casing. After installation the pack-off and lower flange will be pressure tested to 3000 psi.


The surface casing string will be tested as per Onshore Order No. 2 to at least 0.22 psi/ft or 1500 psi, whichever is greater.

The casing string utilizing steel body pack-off will be tested to 70% of casing burst.

If well conditions dictate conventional slips will be set and BOPE will be tested to appropriate pressures based on permitted pressure requirements.

Borehole:	Well:	Field:	Structure:
Original Borehole	Cimarex Bonnie 35 Federal Com 2H	NM Eddy County (NAD 83)	Cimarex Bonnie 35 Federal Com 2H

Gravity & Magnetic Parameters				Surface Location				Miscellaneous			
Model:	HOGM 2018	Dip:	59.718°	Date:	26-Oct-2018	Lat:	N 32 4 47.00	Northings:	392748.34FUS	Grid Conv:	0.0358°
MagDec:	7.347°	FS:	47823.421nT	Gravity FS:	985.420mg (9.80665 Based)	Lon:	W 104 16 30.40	Easting:	564532.38FUS	Scale Fact:	0.89040071
								Cimarex Bonnie 35 Federal Com 2H Rev3 RM 26Oct18			



Critical Points								
Critical Point	MD	INCL	AZIM	TVD	VSEC	N(+)/S(-)	E(+)/W(-)	DLS
SHL (260' FSL, 1010' FEL)	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
Salado (Top Salt)	1064.00	0.00	5.61	1064.00	0.00	0.00	0.00	0.00
Castilla (Base Salt)	1775.00	0.00	5.61	1775.00	0.00	0.00	0.00	0.00
Beli Canyon (Top Delaware)	1955.00	0.00	5.61	1955.00	0.00	0.00	0.00	0.00
Cherry Canyon	2963.00	0.00	5.61	2963.00	0.00	0.00	0.00	0.00
Brushy Canyon	3963.00	0.00	5.61	3963.00	0.00	0.00	0.00	0.00
Top Bone Spring	5520.00	0.00	5.61	5520.00	0.00	0.00	0.00	0.00
Top 1st BSPG SS	6490.00	0.00	5.61	6490.00	0.00	0.00	0.00	0.00
Top 2nd BSPG SS	7020.00	0.00	5.61	7020.00	0.00	0.00	0.00	0.00
KOP - Build 12°/100' DLS	7363.86	0.00	5.61	7363.86	0.00	0.00	0.00	0.00
Top 3rd BSPG Carb	7533.55	20.36	5.61	7530.00	29.72	29.69	2.62	12.00
Build & Turn 12°/100' DLS	7655.53	35.00	5.61	7637.72	86.01	85.93	8.44	12.00
Top Harkey SS	7853.09	58.62	2.70	7772.00	228.75	228.80	18.10	12.00
Harkey SS Target	8112.48	89.68	0.56	7842.00	475.17	474.97	24.75	12.00
Landing Point	8117.85	90.32	0.52	7842.00	480.55	480.35	24.80	12.00
Harkey SS Target	8117.86	90.32	0.52	7842.00	480.56	480.36	24.80	0.00
Cimarex Bonnie 35 Federal Com 2H - PBHL (100' FNL, 990' FEL)	12570.80	90.32	0.52	7817.00	4933.42	4933.04	65.22	0.00
Base Harkey SS Lobe	NaN			7854.00				

Cimarex Bonnie 35 Federal Com 2H Rev3 RM 26Oct18 Proposal Geodetic Report

(Non-Def Plan)



Report Date: October 26, 2018 - 03:51 PM
Client: Cimarex
Field: NM Eddy County (NAD 83)
Structure / Slot: Cimarex Bonnie 35 Federal Com 2H / Cimarex Bonnie 35 Federal Com 2H
Well: Cimarex Bonnie 35 Federal Com 2H
Borehole: Original Borehole
UWI / APH: Unknown / Unknown
Survey Name: Cimarex Bonnie 35 Federal Com 2H Rev3 RM 26Oct18
Survey Date: October 15, 2018
Tort / AHD / DDI / ERD Ratio: 90.479 * / 4934.077 ft / 5.855 / 0.629
Coordinate Reference System: NAD83 New Mexico State Plane, Eastern Zone, US Feet
Location Lat / Long: N 32° 4' 47.00175", W 104° 15' 30.39623"
Location Grid N/E Y/X: N 392748.340 ftUS, E 564532.380 ftUS
CRS Grid Convergence Angle: 0.0398 *
Grid Scale Factor: 0.99990971
Version / Patch: 2.10.740.0

Survey / DLS Computation: Minimum Curvature / Lubinski
Vertical Section Azimuth: 0.520 * (Grid North)
Vertical Section Origin: 0.000 ft, 0.000 ft
TVD Reference Datum: RKB
TVD Reference Elevation: 3385.200 ft above MSL
Seabed / Ground Elevation: 3339.200 ft above MSL
Magnetic Declination: 7.347 *
Total Gravity Field Strength: 998.4250mgm (0.80865 Based)
Gravity Model: GARM
Total Magnetic Field Strength: 47823.421 nT
Magnetic Dip Angle: 58.716 *
Declination Date: October 26, 2018
Magnetic Declination Model: HDGM 2018
North Reference: Grid North
Grid Convergence Used: 0.0398 *
Total Corr Mag North->Grid North: 7.3069 *
Local Coord Referenced To: Structure Reference Point

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (*100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")
SHL [280' FSL, 1010' FEL]	0.00	0.00	0.00	0.00	0.00	0.00	0.00	N/A	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	100.00	0.00	5.61	100.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	200.00	0.00	5.61	200.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	300.00	0.00	5.61	300.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	400.00	0.00	5.61	400.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	500.00	0.00	5.61	500.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	600.00	0.00	5.61	600.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	700.00	0.00	5.61	700.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	800.00	0.00	5.61	800.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	900.00	0.00	5.61	900.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	1000.00	0.00	5.61	1000.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
Salado (Top Salt)	1084.00	0.00	5.61	1084.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	1100.00	0.00	5.61	1100.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	1200.00	0.00	5.61	1200.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	1300.00	0.00	5.61	1300.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	1400.00	0.00	5.61	1400.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	1500.00	0.00	5.61	1500.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	1600.00	0.00	5.61	1600.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	1700.00	0.00	5.61	1700.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
Castilla (Base Salt)	1775.00	0.00	5.61	1775.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	1800.00	0.00	5.61	1800.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	1900.00	0.00	5.61	1900.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
Bell Canyon (Top Delaware)	1955.00	0.00	5.61	1955.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	2000.00	0.00	5.61	2000.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	2100.00	0.00	5.61	2100.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	2200.00	0.00	5.61	2200.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	2300.00	0.00	5.61	2300.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	2400.00	0.00	5.61	2400.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	2500.00	0.00	5.61	2500.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	2600.00	0.00	5.61	2600.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	2700.00	0.00	5.61	2700.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	2800.00	0.00	5.61	2800.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	2900.00	0.00	5.61	2900.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
Cherry Canyon	2963.00	0.00	5.61	2963.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	3000.00	0.00	5.61	3000.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	3100.00	0.00	5.61	3100.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	3200.00	0.00	5.61	3200.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	3300.00	0.00	5.61	3300.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	3400.00	0.00	5.61	3400.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	3500.00	0.00	5.61	3500.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	3600.00	0.00	5.61	3600.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	3700.00	0.00	5.61	3700.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	3800.00	0.00	5.61	3800.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	3900.00	0.00	5.61	3900.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
Brushy Canyon	3963.00	0.00	5.61	3963.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	4000.00	0.00	5.61	4000.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	4100.00	0.00	5.61	4100.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	4200.00	0.00	5.61	4200.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	4300.00	0.00	5.61	4300.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	4400.00	0.00	5.61	4400.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	4500.00	0.00	5.61	4500.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	4600.00	0.00	5.61	4600.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	4700.00	0.00	5.61	4700.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	4800.00	0.00	5.61	4800.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	4900.00	0.00	5.61	4900.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	5000.00	0.00	5.61	5000.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	5100.00	0.00	5.61	5100.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	5200.00	0.00	5.61	5200.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	5300.00	0.00	5.61	5300.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	5400.00	0.00	5.61	5400.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	5500.00	0.00	5.61	5500.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
Top Bone Spring	5520.00	0.00	5.61	5520.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	5600.00	0.00	5.61	5600.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
	5700.00	0.00	5.61	5700.00	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40

Comments	MD (ft)	Incl (°)	Adm Grid (°)	TYD (ft)	VREC (ft)	NS (ft)	EW (ft)	DL S (°100ft)	Northng	Eastng (ft)	Latitude (N S °.)	Longitude (E W °.)
Top 1st BSPG SS	6600.00	0.00	5.61	6600.00	0.00	0.00	0.00	0.00	392748.34	594532.38	N 32 44.70	W 104 15 30.40
	6800.00	0.00	5.61	6800.00	0.00	0.00	0.00	0.00	392748.34	594532.38	N 32 44.70	W 104 15 30.40
	6700.00	0.00	5.61	6700.00	0.00	0.00	0.00	0.00	392748.34	594532.38	N 32 44.70	W 104 15 30.40
	6200.00	0.00	5.61	6200.00	0.00	0.00	0.00	0.00	392748.34	594532.38	N 32 44.70	W 104 15 30.40
	6300.00	0.00	5.61	6300.00	0.00	0.00	0.00	0.00	392748.34	594532.38	N 32 44.70	W 104 15 30.40
	6400.00	0.00	5.61	6400.00	0.00	0.00	0.00	0.00	392748.34	594532.38	N 32 44.70	W 104 15 30.40
	6400.00	0.00	5.61	6400.00	0.00	0.00	0.00	0.00	392748.34	594532.38	N 32 44.70	W 104 15 30.40
Top 2nd BSPG SS	7020.00	0.00	5.61	7020.00	0.00	0.00	0.00	0.00	392748.34	594532.38	N 32 44.70	W 104 15 30.40
	7100.00	0.00	5.61	7100.00	0.00	0.00	0.00	0.00	392748.34	594532.38	N 32 44.70	W 104 15 30.40
	7200.00	0.00	5.61	7200.00	0.00	0.00	0.00	0.00	392748.34	594532.38	N 32 44.70	W 104 15 30.40
	7300.00	0.00	5.61	7300.00	0.00	0.00	0.00	0.00	392748.34	594532.38	N 32 44.70	W 104 15 30.40
KOP - Build 12/100' DLS	7363.88	0.00	5.61	7363.88	0.00	0.00	0.00	0.00	392748.34	594532.38	N 32 44.70	W 104 15 30.40
	7400.00	4.34	5.61	7399.87	1.38	1.36	0.13	12.00	392749.70	594532.51	N 32 44.70	W 104 15 30.39
	7500.00	16.34	5.61	7488.16	19.20	19.18	1.88	12.00	392778.52	594534.26	N 32 44.71	W 104 15 30.37
Top 3rd BSPG Cap	7533.55	20.36	5.61	7530.00	28.72	29.69	2.92	12.00	392778.03	594535.30	N 32 44.70	W 104 15 30.36
	7600.00	28.34	5.61	7580.49	56.98	56.94	5.59	12.00	392805.27	594537.87	N 32 44.57	W 104 15 30.33
Build & Turn 12/100' DLS	7655.53	35.00	5.61	7637.72	86.01	85.93	8.44	12.00	392834.27	594540.82	N 32 44.76	W 104 15 30.30
	7700.00	40.31	4.72	7672.82	113.08	112.98	10.88	12.00	392861.31	594543.26	N 32 44.82	W 104 15 30.27
	7800.00	52.26	3.29	7741.90	165.10	164.98	15.82	12.00	392933.28	594546.20	N 32 44.83	W 104 15 30.21
Top Harker SS	7853.09	59.62	2.70	7772.00	229.75	229.80	18.70	12.00	392978.67	594550.48	N 32 44.82	W 104 15 30.18
	7900.00	64.23	2.25	7794.53	289.91	289.74	19.87	12.00	393011.06	594552.25	N 32 44.87	W 104 15 30.16
	8000.00	78.21	1.41	7828.43	383.81	383.82	22.85	12.00	393111.03	594555.23	N 32 45.00	W 104 15 30.13
	8100.00	88.18	0.85	7841.77	462.70	462.50	24.82	12.00	393210.78	594557.00	N 32 45.15	W 104 15 30.11
Harker SS Target	8112.48	89.66	0.56	7842.00	475.17	474.97	24.75	12.00	393223.27	594557.13	N 32 45.17	W 104 15 30.10
Harker SS Target	8117.65	90.32	0.52	7842.00	480.55	480.35	24.80	12.00	393228.64	594557.18	N 32 45.17	W 104 15 30.10
Landing Point	8200.00	90.32	0.52	7841.54	562.70	562.49	25.55	0.00	393310.78	594557.83	N 32 45.27	W 104 15 30.08
	8300.00	90.32	0.52	7840.98	662.48	662.46	26.46	0.00	393410.76	594559.83	N 32 45.59	W 104 15 30.07
	8400.00	90.32	0.52	7840.42	762.69	762.48	27.36	0.00	393510.75	594559.74	N 32 45.55	W 104 15 30.07
	8500.00	90.32	0.52	7839.85	862.47	862.47	28.18	0.00	393610.73	594560.65	N 32 45.54	W 104 15 30.05
	8600.00	90.32	0.52	7839.29	962.69	962.47	29.18	0.00	393710.72	594561.56	N 32 45.53	W 104 15 30.05
	8700.00	90.32	0.52	7838.73	1062.68	1062.46	30.08	0.00	393810.70	594562.46	N 32 45.71	W 104 15 30.04
	8800.00	90.32	0.52	7838.17	1162.65	1162.45	30.99	0.00	393910.69	594563.37	N 32 45.80	W 104 15 30.02
	8900.00	90.32	0.52	7837.61	1262.69	1262.45	31.90	0.00	394010.67	594564.28	N 32 45.84	W 104 15 30.02
	9000.00	90.32	0.52	7837.05	1362.69	1362.44	32.81	0.00	394110.66	594565.09	N 32 5 1.47	W 104 15 29.99
	9100.00	90.32	0.52	7836.49	1462.68	1462.43	33.72	0.00	394210.64	594566.00	N 32 5 1.47	W 104 15 29.99
	9200.00	90.32	0.52	7835.92	1562.68	1562.43	34.62	0.00	394310.63	594567.00	N 32 5 2.48	W 104 15 29.98
	9300.00	90.32	0.52	7835.36	1662.68	1662.43	35.53	0.00	394410.61	594567.91	N 32 5 3.45	W 104 15 29.98
	9400.00	90.32	0.52	7834.80	1762.68	1762.42	36.44	0.00	394510.60	594568.82	N 32 5 4.44	W 104 15 29.96
	9500.00	90.32	0.52	7834.24	1862.68	1862.42	37.35	0.00	394610.58	594569.72	N 32 5 5.43	W 104 15 29.95
	9600.00	90.32	0.52	7833.68	1962.67	1962.41	38.26	0.00	394710.57	594570.63	N 32 5 6.42	W 104 15 29.94
	9700.00	90.32	0.52	7833.12	2062.67	2062.40	39.16	0.00	394810.55	594571.54	N 32 5 7.41	W 104 15 29.92
	9800.00	90.32	0.52	7832.56	2162.67	2162.40	40.07	0.00	394910.54	594572.45	N 32 5 8.40	W 104 15 29.91
	9900.00	90.32	0.52	7831.99	2262.67	2262.39	40.98	0.00	395010.52	594573.35	N 32 5 9.39	W 104 15 29.90
	10000.00	90.32	0.52	7831.43	2362.67	2362.38	41.88	0.00	395110.51	594574.26	N 32 5 10.38	W 104 15 29.78
	10100.00	90.32	0.52	7830.87	2462.67	2462.38	42.78	0.00	395210.49	594575.17	N 32 5 11.37	W 104 15 29.88
	10200.00	90.32	0.52	7830.31	2562.67	2562.37	43.70	0.00	395310.48	594576.08	N 32 5 12.36	W 104 15 29.87
	10300.00	90.32	0.52	7829.75	2662.66	2662.37	44.61	0.00	395410.46	594576.98	N 32 5 13.35	W 104 15 29.86
	10400.00	90.32	0.52	7829.19	2762.66	2762.36	45.51	0.00	395510.45	594577.89	N 32 5 14.34	W 104 15 29.84
	10500.00	90.32	0.52	7828.63	2862.66	2862.36	46.42	0.00	395610.43	594578.79	N 32 5 15.33	W 104 15 29.83
	10600.00	90.32	0.52	7828.06	2962.66	2962.35	47.33	0.00	395710.42	594579.71	N 32 5 16.31	W 104 15 29.82
	10700.00	90.32	0.52	7827.50	3062.66	3062.35	48.24	0.00	395810.40	594580.61	N 32 5 17.29	W 104 15 29.81
	10800.00	90.32	0.52	7826.94	3162.66	3162.34	49.15	0.00	395910.39	594581.52	N 32 5 18.28	W 104 15 29.80
	10900.00	90.32	0.52	7826.38	3262.66	3262.34	50.05	0.00	396010.37	594582.43	N 32 5 19.26	W 104 15 29.79
	11000.00	90.32	0.52	7825.82	3362.65	3362.33	50.96	0.00	396110.36	594583.34	N 32 5 20.27	W 104 15 29.78
	11100.00	90.32	0.52	7825.26	3462.65	3462.32	51.87	0.00	396210.34	594584.24	N 32 5 21.27	W 104 15 29.76
	11200.00	90.32	0.52	7824.70	3562.65	3562.32	52.78	0.00	396310.33	594585.15	N 32 5 22.25	W 104 15 29.75
	11300.00	90.32	0.52	7824.13	3662.65	3662.31	53.68	0.00	396410.31	594586.06	N 32 5 23.24	W 104 15 29.74
	11400.00	90.32	0.52	7823.57	3762.65	3762.31	54.59	0.00	396510.30	594586.97	N 32 5 24.23	W 104 15 29.73
	11500.00	90.32	0.52	7823.01	3862.65	3862.30	55.50	0.00	396610.28	594587.87	N 32 5 25.22	W 104 15 29.72
	11600.00	90.32	0.52	7822.45	3962.64	3962.29	56.41	0.00	396710.27	594588.78	N 32 5 26.21	W 104 15 29.71
	11700.00	90.32	0.52	7821.89	4062.64	4062.29	57.31	0.00	396810.25	594589.69	N 32 5 27.20	W 104 15 29.70
	11800.00	90.32	0.52	7821.33	4162.64	4162.28	58.22	0.00	396910.24	594590.60	N 32 5 28.19	W 104 15 29.69
	11900.00	90.32	0.52	7820.77	4262.64	4262.28	59.13	0.00	397010.22	594591.50	N 32 5 29.18	W 104 15 29.67
	12000.00	90.32	0.52	7820.20	4362.64	4362.27	60.04	0.00	397110.21	594592.41	N 32 5 30.17	W 104 15 29.66
	12100.00	90.32	0.52	7819.64	4462.64	4462.27	60.94	0.00	397210.20	594593.32	N 32 5 31.16	W 104 15 29.65
	12200.00	90.32	0.52	7819.08	4562.63	4562.26	61.85	0.00	397310.18	594594.23	N 32 5 32.15	W 104 15 29.64
	12300.00	90.32	0.52	7818.52	4662.63	4662.26	62.76	0.00	397410.17	594595.14	N 32 5 33.14	W 104 15 29.63
	12400.00	90.32	0.52	7817.96	4762.63	4762.25	63.67	0.00	397510.15	594596.04	N 32 5 34.13	W 104 15 29.62
	12500.00	90.32	0.52	7817.40	4862.63	4862.24	64.57	0.00	397610.14	594596.95	N 32 5 35.11	W 104 15 29.61
Cinmarex Bonnie 35 Federal Com 2H - FBHL (100' FHL, 960' FHL)	12570.80	90.32	0.52	7817.00	4933.42	4933.04	65.22	0.00	397680.92	594597.59	N 32 5 35.82	W 104 15 29.80

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS ("/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S " " " ")	Longitude (E/W " " " ")
		1	0.000	28.000	1/100.000	30.000	30.000		NAL_MWD_IFR1+MS-Depth Only		Original Borehole / Cimarex Bonnie 35 Federal Com 2H Rev3 RM 28Oct18	
		1	28.000	12570.795	1/100.000	30.000	30.000		NAL_MWD_IFR1+MS		Original Borehole / Cimarex Bonnie 35 Federal Com 2H Rev3	

Cimarex Bonnie 35 Federal Com 2H Rev3 RM 26Oct18 Proposal Geodetic Report

(Non-Def Plan)



Report Date: October 26, 2018 - 03:51 PM
Client: Cimarex
Field: NM Eddy County (NAD 83)
Structure / Slot: Cimarex Bonnie 35 Federal Com 2H / Cimarex Bonnie 35 Federal Com 2H
Well: Cimarex Bonnie 35 Federal Com 2H
Borehole: Original Borehole
UWI / API#: Unknown / Unknown
Survey Name: Cimarex Bonnie 35 Federal Com 2H Rev3 RM 26Oct18
Survey Date: October 15, 2018
Tort / AHD / DDI / ERD Ratio: 90.479° / 4934.077 ft / 5.855 / 0.829
Coordinate Reference System: NAD83 New Mexico State Plane, Eastern Zone, US Feet
Location Lat / Long: N 32° 4' 47.00175", W 104° 15' 30.39623"
Location Grid N/E Y/X: N 392748.340 ftUS, E 564532.380 ftUS
CRS Grid Convergence Angle: 0.0398°
Grid Scale Factor: 0.99990971
Version / Patch: 2.10.740.0

Survey / DLS Computation: Minimum Curvature / Lubinski
Vertical Section Azimuth: 0.520° (Grid North)
Vertical Section Origin: 0.000 ft, 0.000 ft
TVD Reference Datum: RKB
TVD Reference Elevation: 3385.200 ft above MSL
Seabed / Ground Elevation: 3330.200 ft above MSL
Magnetic Declination: 7.347°
Total Gravity Field Strength: 998.4259mgn (9.80665 Based)
Gravity Model: GARM
Total Magnetic Field Strength: 47823.421 nT
Magnetic Dip Angle: 59.716°
Declination Date: October 26, 2018
Magnetic Declination Model: HDGM 2018
North Reference: Grid North
Grid Convergence Used: 0.0398°
Total Corr Mag North->Grid North: 7.3069°
Local Coord Referenced To: Structure Reference Point

Comments	MD (ft)	Incl (°)	Azim Grid (°)	TVD (ft)	VSEC (ft)	NS (ft)	EW (ft)	DLS (°/100ft)	Northing (ftUS)	Easting (ftUS)	Latitude (N/S ° ' ")	Longitude (E/W ° ' ")
SHL [280' FSL, 1010' FEL]	0.00	0.00	0.00	0.00	0.00	0.00	0.00	N/A	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
KOP - Build 12"/100' DLS	7363.86	0.00	5.61	7363.86	0.00	0.00	0.00	0.00	392748.34	564532.38	N 32 4 47.00	W 104 15 30.40
Build & Turn 12"/100' DLS	7655.53	35.00	5.61	7637.72	86.01	85.93	8.44	12.00	392834.27	564540.82	N 32 4 47.85	W 104 15 30.30
Landing Point	8117.85	90.32	0.52	7842.00	480.55	480.35	24.80	12.00	393228.64	564557.18	N 32 4 51.75	W 104 15 30.10
Cimarex Bonnie 35 Federal Com 2H - FBHL [100' FNL, 990' FEL]	12570.80	90.32	0.52	7817.00	4933.42	4933.04	65.22	0.00	397680.92	564597.59	N 32 5 35.82	W 104 15 29.80

Survey Type: Non-Def Plan

Survey Error Model: ISCWSA Rev 0 *** 3-D 95.000% Confidence 2.7955 sigma
Survey Program:

Description	Part	MD From (ft)	MD To (ft)	EOU Freq (ft)	Hole Size (in)	Casing Diameter (in)	Expected Max Inclination (deg)	Survey Tool Type	Borehole / Survey
	1	0.000	26.000	1/100.000	30.000	30.000		NAL_MWD_IFR1+MS-Depth Only	Original Borehole / Cimarex Bonnie 35 Federal Com 2H Rev3 RM 26Oct18
	1	26.000	12570.795	1/100.000	30.000	30.000		NAL_MWD_IFR1+MS	Original Borehole / Cimarex Bonnie 35 Federal Com 2H Rev3

PECOS DISTRICT DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME:	CIMAREX ENERGY
LEASE NO.:	NMNM26870
WELL NAME & NO.:	BONNIE 35 FEDERAL COM 2H
SURFACE HOLE FOOTAGE:	260'/S & 1010'/E
BOTTOM HOLE FOOTAGE	100'/N & 990'/E
LOCATION:	Sec. 35, T. 25S; R26E
COUNTY:	EDDY, NEW MEXICO

COA

All previous COAs still apply expect the following:

H2S	<input checked="" type="radio"/> Yes	<input checked="" type="radio"/> No	
Potash	<input checked="" type="radio"/> None	<input checked="" type="radio"/> Secretary	<input checked="" type="radio"/> R-111-P
Cave/Karst Potential	<input checked="" type="radio"/> Low	<input checked="" type="radio"/> Medium	<input checked="" type="radio"/> High
Variance	<input checked="" type="radio"/> None	<input checked="" type="radio"/> Flex Hose	<input checked="" type="radio"/> Other
Wellhead	<input checked="" type="radio"/> Conventional	<input checked="" type="radio"/> Multibowl	<input checked="" type="radio"/> Both
Other	<input type="checkbox"/> 4 String Area	<input type="checkbox"/> Capitan Reef	<input type="checkbox"/> WIPP
Other	<input type="checkbox"/> Fluid Filled	<input type="checkbox"/> Cement Squeeze	<input type="checkbox"/> Pilot Hole
Special Requirements	<input type="checkbox"/> Water Disposal	<input type="checkbox"/> COM	<input type="checkbox"/> Unit

A. HYDROGEN SULFIDE

Hydrogen Sulfide (H2S) monitors shall be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the Hydrogen Sulfide area shall meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, provide measured values and formations to the BLM.

B. CASING

1. The 13-3/8 inch surface casing shall be set at approximately 450 feet (a minimum of 25 feet into the Rustler Anhydrite and above the salt) and cemented to the surface. **Additional cement maybe required. Excess calculates to 14%.**
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. Wait on cement (WOC) time for a primary cement job will be a minimum of 8 hours or 500 pounds compressive strength, whichever is greater. (This is to

- include the lead cement)
 - c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
 - d. If cement falls back, remedial cementing will be done prior to drilling out that string.
2. The minimum required fill of cement behind the 9-5/8 inch intermediate casing is:
Cement to surface. If cement does not circulate see B.1.a, c-d above.
Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst or potash.
- ❖ In High Cave/Karst Areas if cement does not circulate to surface on the first two casing strings, the cement on the 3rd casing string must come to surface.
3. The minimum required fill of cement behind the 5-1/2 inch production casing is:
- Cement should tie-back at least **200 feet** into previous casing string. Operator shall provide method of verification. **Additional cement maybe required. Excess calculates to 14%.**

C. PRESSURE CONTROL

1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).
2. Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **3000 (3M) psi.**
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
 - e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ Chaves and Roosevelt Counties

Call the Roswell Field Office, 2909 West Second St., Roswell NM 88201.

During office hours call (575) 627-0272.

After office hours call (575)

☒ Eddy County

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,

(575) 361-2822

☒ Lea County

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575)

393-3612

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
 - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
 - b. When the operator proposes to set surface casing with Spudder Rig
 - Notify the BLM when moving in and removing the Spudder Rig.
 - Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
 - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.

3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.

8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.
 - e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the

plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).

- b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time.
- c. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
- d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- e. The results of the test shall be reported to the appropriate BLM office.
- f. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- g. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- h. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

ZS 022619