

NM OIL CONSERVATION

ARTESIA DISTRICT

OCT 22 2019

FORM APPROVED
OMB No. 1004-0137
Expires: January 31, 2018

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

RECEIVED

APPLICATION FOR PERMIT TO DRILL OR REENTER

1a. Type of work: <input checked="" type="checkbox"/> DRILL <input type="checkbox"/> REENTER		5. Lease Serial No. NMNM0404441
1b. Type of Well: <input checked="" type="checkbox"/> Oil Well <input type="checkbox"/> Gas Well <input type="checkbox"/> Other		6. If Indian, Allottee or Tribe Name
1c. Type of Completion: <input type="checkbox"/> Hydraulic Fracturing <input checked="" type="checkbox"/> Single Zone <input type="checkbox"/> Multiple Zone		7. If Unit or CA Agreement, Name and No.
2. Name of Operator DEVON ENERGY PRODUCTION COMPANY LP		8. Lease Name and Well No. BELLOQ 11-2 FED STATE COM 524H 322487
3a. Address 333 West Sheridan Avenue Oklahoma City OK 73102	3b. Phone No. (include area code) (800)583-3866	9. API Well No. 30-015-46412
4. Location of Well (Report location clearly and in accordance with any State requirements. *) At surface SESE / 500 FSL / 910 FEL / LAT 32.3130828 / LONG -103.7429714 At proposed prod. zone LOT 1 / 20 FNL / 1040 FEL / LAT 32.3406719 / LONG -103.743422		10. Field and Pool, or Exploratory LIVINGSTON RIDGE / BONESPRING
11. Sec., T, R, M, or Blk. and Survey or Area SEC 11, T23S, R31E / NMP		
14. Distance in miles and direction from nearest town or post office*		12. County or Parish EDDY
13. State NM		
15. Distance from proposed* location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any) 500 feet	16. No of acres in lease 1440	17. Spacing Unit dedicated to this well 640
18. Distance from proposed location* to nearest well, drilling, completed, applied for, on this lease, ft. 1565 feet	19. Proposed Depth 9105 feet / 19356 feet	20. BLM/BIA Bond No. in file FED: CO1104
21. Elevations (Show whether DF, KDB, RT, GL, etc.) 3488 feet	22. Approximate date work will start* 12/31/2019	23. Estimated duration 45 days
24. Attachments		

The following, completed in accordance with the requirements of Onshore Oil and Gas Order No. 1, and the Hydraulic Fracturing rule per 43 CFR 3162.3-3 (as applicable)

- | | |
|--|---|
| 1. Well plat certified by a registered surveyor. | 4. Bond to cover the operations unless covered by an existing bond on file (see Item 20 above). |
| 2. A Drilling Plan. | 5. Operator certification. |
| 3. A Surface Use Plan (if the location is on National Forest System Lands, the SUPO must be filed with the appropriate Forest Service Office). | 6. Such other site specific information and/or plans as may be requested by the BLM. |

25. Signature (Electronic Submission)	Name (Printed/Typed) Jenny Harms / Ph: (405)524-4902	Date 01/31/2019
Title Regulatory Compliance Professional		
Approved by (Signature) (Electronic Submission)	Name (Printed/Typed) Christopher Walls / Ph: (575)234-2234	Date 10/18/2019
Title Petroleum Engineer		

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.
Conditions of approval, if any, are attached.

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

APPROVED WITH CONDITIONS
Approval Date: 10/18/2019

RIP 10-22-19

INSTRUCTIONS

GENERAL: This form is designed for submitting proposals to perform certain well operations, as indicated on Federal and Indian lands and leases for action by appropriate Federal agencies, pursuant to applicable Federal laws and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from local Federal offices.

ITEM 1: If the proposal is to redrill to the same reservoir at a different subsurface location or to a new reservoir, use this form with appropriate notations. Consult applicable Federal regulations concerning subsequent work proposals or reports on the well.

ITEM 4: Locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local Federal offices for specific instructions.

ITEM 14: Needed only when location of well cannot readily be found by road from the land or lease description. A plat, or plats, separate or on the reverse side, showing the roads to, and the surveyed location of, the well, and any other required information, should be furnished when required by Federal agency offices.

ITEMS 15 AND 18: If well is to be, or has been directionally drilled, give distances for subsurface location of hole in any present or objective productive zone.

ITEM 22: Consult applicable Federal regulations, or appropriate officials, concerning approval of the proposal before operations are started.

ITEM 24: If the proposal will involve hydraulic fracturing operations, you must comply with 43 CFR 3162.3-3, including providing information about the protection of usable water. Operators should provide the best available information about all formations containing water and their depths. This information could include data and interpretation of resistivity logs run on nearby wells. Information may also be obtained from state or tribal regulatory agencies and from local BLM offices.

NOTICES

The Privacy Act of 1974 and regulation in 43 CFR 2.48(d) provide that you be furnished the following information in connection with information required by this application.

AUTHORITY: 30 U.S.C. 181 et seq., 25 U.S.C. 396; 43 CFR 3160

PRINCIPAL PURPOSES: The information will be used to: (1) process and evaluate your application for a permit to drill a new oil, gas, or service well or to reenter a plugged and abandoned well; and (2) document, for administrative use, information for the management, disposal and use of National Resource Lands and resources including (a) analyzing your proposal to discover and extract the Federal or Indian resources encountered; (b) reviewing procedures and equipment and the projected impact on the land involved; and (c) evaluating the effects of the proposed operation on the surface and subsurface water and other environmental impacts.

ROUTINE USE: Information from the record and/or the record will be transferred to appropriate Federal, State, and local or foreign agencies, when relevant to civil, criminal or regulatory investigations or prosecution, in connection with congressional inquiries and for regulatory responsibilities.

EFFECT OF NOT PROVIDING INFORMATION: Filing of this application and disclosure of the information is mandatory only if you elect to initiate a drilling or reentry operation on an oil and gas lease.

The Paperwork Reduction Act of 1995 requires us to inform you that:

The BLM connects this information to an evaluation of the technical, safety, and environmental factors involved with drilling for oil and/or gas on Federal and Indian oil and gas leases. This information will be used to analyze and approve applications. Response to this request is mandatory only if the operator elects to initiate drilling or reentry operations on an oil and gas lease. The BLM would like you to know that you do not have to respond to this or any other Federal agency-sponsored information collection unless it displays a currently valid OMB control number.

BURDEN HOURS STATEMENT: Public reporting burden for this form is estimated to average 8 hours per response, including the time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding the burden estimate or any other aspect of this form to U.S. Department of the Interior, Bureau of Land Management (1004-0137), Bureau Information Connection Clearance Officer (WO-630), 1849 C Street, N.W., Mail Stop 401 LS, Washington, D.C. 20240.

Additional Operator Remarks

Location of Well

1. SHL: SESE / 500 FSL / 910 FEL / TWSP: 23S / RANGE: 31E / SECTION: 11 / LAT: 32.3130828 / LONG: -103.7429714 (TVD: 0 feet; MD: 0 feet)
PPP: SESE / 100 FSL / 1040 FEL / TWSP: 23S / RANGE: 31E / SECTION: 11 / LAT: 32.3119848 / LONG: -103.7433933 (TVD: 8769 feet; MD: 8774 feet)
BHL: LOT 1 / 20 FNL / 1040 FEL / TWSP: 23S / RANGE: 31E / SECTION: 2 / LAT: 32.3406719 / LONG: -103.743422 (TVD: 9105 feet; MD: 19356 feet)

BLM Point of Contact

Name: Tenille Ortiz

Title: Legal Instruments Examiner

Phone: 5752342224

Email: tortiz@blm.gov

CONFIDENTIAL

Review and Appeal Rights

A person contesting a decision shall request a State Director review. This request must be filed within 20 working days of receipt of the Notice with the appropriate State Director (see 43 CFR 3165.3). The State Director review decision may be appealed to the Interior Board of Land Appeals, 801 North Quincy Street, Suite 300, Arlington, VA 22203 (see 43 CFR 3165.4). Contact the above listed Bureau of Land Management office for further information.

Geologic Conditions of Approval

:

All APDs in Basin Areas need to consist of: Rustler Top of Salt Base of Salt Lamar Bell Canyon Cherry Canyon Brushy Canyon Bone Springs Lime 1st Bone Sand 2nd Bone Sand 3rd Bone Lime (if near or in Potash Area) 3rd Bone Sand Wolfcamp Strawn *All formation casing setting depths, TVD formations.

CONFIDENTIAL

PECOS DISTRICT

DRILLING CONDITIONS OF APPROVAL

OPERATOR'S NAME:	Devon Energy Production Company LP
LEASE NO.:	NMNM0404441
WELL NAME & NO.:	BELLOQ 11-2 FED STATE COM 524H
SURFACE HOLE FOOTAGE:	500'/S & 910'/E
BOTTOM HOLE FOOTAGE:	20'/N & 1040'/E
LOCATION:	Section 11, T.23 S., R.31 E., NMPM
COUNTY:	Eddy County, New Mexico

COA

H2S	<input checked="" type="radio"/> Yes	<input type="radio"/> No	
Potash	<input type="radio"/> None	<input type="radio"/> Secretary	<input checked="" type="radio"/> R-111-P
Cave/Karst Potential	<input checked="" type="radio"/> Low	<input type="radio"/> Medium	<input type="radio"/> High
Cave/Karst Potential	<input type="radio"/> Critical		
Variance	<input type="radio"/> None	<input checked="" type="radio"/> Flex Hose	<input type="radio"/> Other
Wellhead	<input type="radio"/> Conventional	<input type="radio"/> Multibowl	<input checked="" type="radio"/> Both
Other	<input type="checkbox"/> 4 String Area	<input type="checkbox"/> Capitan Reef	<input type="checkbox"/> WIPP
Other	<input checked="" type="checkbox"/> Fluid Filled	<input checked="" type="checkbox"/> Cement Squeeze	<input type="checkbox"/> Pilot Hole
Special Requirements	<input type="checkbox"/> Water Disposal	<input checked="" type="checkbox"/> COM	<input type="checkbox"/> Unit

A. HYDROGEN SULFIDE

A Hydrogen Sulfide (H2S) Drilling Plan shall be activated 500 feet prior to drilling into the **Triste Draw Sand Dunes, the Salad, Bone Springs** formation. As a result, the Hydrogen Sulfide area must meet Onshore Order 6 requirements, which includes equipment and personnel/public protection items. If Hydrogen Sulfide is encountered, please provide measured values and formations to the BLM.

B. CASING

1. The **13-3/8** inch surface casing shall be set at approximately **825 feet** (a minimum of **70 feet (Eddy County)** into the Rustler Anhydrite and above the salt) and cemented to the surface.
 - a. If cement does not circulate to the surface, the appropriate BLM office shall be notified and a temperature survey utilizing an electronic type temperature survey with surface log readout will be used or a cement bond log shall be run to verify the top of the cement. Temperature survey will be run a minimum of six hours after pumping cement and ideally between 8-10 hours after completing the cement job.
 - b. Wait on cement (WOC) time for a primary cement job will be a minimum of

24 hours in the Potash Area or 500 pounds compressive strength, whichever is greater. (This is to include the lead cement)

- c. Wait on cement (WOC) time for a remedial job will be a minimum of 4 hours after bringing cement to surface or 500 pounds compressive strength, whichever is greater.
- d. If cement falls back, remedial cementing will be done prior to drilling out that string.

Intermediate casing must be kept fluid filled to meet BLM minimum collapse requirement.

- 2. The minimum required fill of cement behind the 9-5/8 inch intermediate casing shall be set at approximately **4450 feet** is:

Option 1 (Single Stage):

- Cement to surface. If cement does not circulate see B.1.a, c-d above.
Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst or potash.

Option 2:

Operator has proposed a DV tool, the depth may be adjusted as long as the cement is changed proportionally. The DV tool may be cancelled if cement circulates to surface on the first stage.

- a. First stage to DV tool: Cement to circulate. If cement does not circulate off the DV tool, contact the appropriate BLM office before proceeding with second stage cement job.
 - b. Second stage above DV tool:
 - Cement to surface. If cement does not circulate, contact the appropriate BLM office.
Wait on cement (WOC) time for a primary cement job is to include the lead cement slurry due to cave/karst or potash.
- ❖ In R111 Potash Areas if cement does not circulate to surface on the first two casing strings, the cement on the 3rd casing string must come to surface.

Operator has proposed to pump down 13-3/8" X 9-5/8" annulus. Operator must run a CBL from TD of the 9-5/8" casing to surface. Submit results to BLM.

3. The minimum required fill of cement behind the **5-1/2** inch production casing is:

- Cement to surface. If cement does not circulate, contact the appropriate BLM office.

Cement excess is less than 25%, more cement might be required.

C. PRESSURE CONTROL

1. Variance approved to use flex line from BOP to choke manifold. Manufacturer's specification to be readily available. No external damage to flex line. Flex line to be installed as straight as possible (no hard bends).'

2.

Option 1:

- a. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **2000 (2M)** psi.
- b. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the intermediate casing shoe shall be **3000 (3M)** psi.

Option 2:

1. Operator has proposed a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be **3000 (3M)** psi.
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
 - e. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.

D. SPECIAL REQUIREMENT (S)

Communitization Agreement

- The operator will submit a Communitization Agreement to the Carlsbad Field Office, 620 E Greene St. Carlsbad, New Mexico 88220, at least 90 days before the anticipated date of first production from a well subject to a spacing order issued by the New Mexico Oil Conservation Division. The Communitization Agreement will include the signatures of all working interest owners in all Federal and Indian leases subject to the Communitization Agreement (i.e., operating rights owners and lessees of record), or certification that the operator has obtained the written signatures of all such owners and will make those signatures available to the BLM immediately upon request.
- If the operator does not comply with this condition of approval, the BLM may take enforcement actions that include, but are not limited to, those specified in 43 CFR 3163.1.
- In addition, the well sign shall include the surface and bottom hole lease numbers. When the Communitization Agreement number is known, it shall also be on the sign.

GENERAL REQUIREMENTS

The BLM is to be notified in advance for a representative to witness:

- a. Spudding well (minimum of 24 hours)
- b. Setting and/or Cementing of all casing strings (minimum of 4 hours)
- c. BOPE tests (minimum of 4 hours)

☒ Eddy County

Call the Carlsbad Field Office, 620 East Greene St., Carlsbad, NM 88220,
(575) 361-2822

☒ Lea County

Call the Hobbs Field Station, 414 West Taylor, Hobbs NM 88240, (575)
393-3612

1. Unless the production casing has been run and cemented or the well has been properly plugged, the drilling rig shall not be removed from over the hole without prior approval.
 - a. In the event the operator has proposed to drill multiple wells utilizing a skid/walking rig. Operator shall secure the wellbore on the current well, after installing and testing the wellhead, by installing a blind flange of like pressure rating to the wellhead and a pressure gauge that can be monitored while drilling is performed on the other well(s).
 - b. When the operator proposes to set surface casing with Spudder Rig
 - Notify the BLM when moving in and removing the Spudder Rig.
 - Notify the BLM when moving in the 2nd Rig. Rig to be moved in within 90 days of notification that Spudder Rig has left the location.
 - BOP/BOPE test to be conducted per Onshore Oil and Gas Order No. 2 as soon as 2nd Rig is rigged up on well.
2. Floor controls are required for 3M or Greater systems. These controls will be on the rig floor, unobstructed, readily accessible to the driller and will be operational at all times during drilling and/or completion activities. Rig floor is defined as the area immediately around the rotary table; the area immediately above the substructure on which the draw works are located, this does not include the dog house or stairway area.
3. The record of the drilling rate along with the GR/N well log run from TD to surface (horizontal well – vertical portion of hole) shall be submitted to the BLM office as well as all other logs run on the borehole 30 days from completion. If available, a digital copy of the logs is to be submitted in addition to the paper copies. The Rustler top and top and bottom of Salt are to be recorded on the Completion Report.

A. CASING

1. Changes to the approved APD casing program need prior approval if the items substituted are of lesser grade or different casing size or are Non-API. The Operator can exchange the components of the proposal with that of superior strength (i.e. changing from J-55 to N-80, or from 36# to 40#). Changes to the approved cement program need prior approval if the altered cement plan has less volume or strength or if the changes are substantial (i.e. Multistage tool, ECP, etc.). The initial wellhead installed on the well will remain on the well with spools used as needed.
2. Wait on cement (WOC) for Potash Areas: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi for all cement blends, 2) until cement has been in place at least 24 hours. WOC time will be recorded in the driller's log. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
3. Wait on cement (WOC) for Water Basin: After cementing but before commencing any tests, the casing string shall stand cemented under pressure until both of the following conditions have been met: 1) cement reaches a minimum compressive strength of 500 psi at the shoe, 2) until cement has been in place at least 8 hours. WOC time will be recorded in the driller's log. See individual casing strings for details regarding lead cement slurry requirements. The casing integrity test can be done (prior to the cement setting up) immediately after bumping the plug.
4. Provide compressive strengths including hours to reach required 500 pounds compressive strength prior to cementing each casing string. Have well specific cement details onsite prior to pumping the cement for each casing string.
5. No pea gravel permitted for remedial or fall back remedial without prior authorization from the BLM engineer.
6. On that portion of any well approved for a 5M BOPE system or greater, a pressure integrity test of each casing shoe shall be performed. Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole.
7. If hardband drill pipe is rotated inside casing, returns will be monitored for metal. If metal is found in samples, drill pipe will be pulled and rubber protectors which have a larger diameter than the tool joints of the drill pipe will be installed prior to continuing drilling operations.
8. Whenever a casing string is cemented in the R-111-P potash area, the NMOCD requirements shall be followed.

B. PRESSURE CONTROL

1. All blowout preventer (BOP) and related equipment (BOPE) shall comply with well control requirements as described in Onshore Oil and Gas Order No. 2 and API RP 53 Sec. 17.
2. If a variance is approved for a flexible hose to be installed from the BOP to the choke manifold, the following requirements apply: The flex line must meet the requirements of API 16C. Check condition of flexible line from BOP to choke manifold, replace if exterior is damaged or if line fails test. Line to be as straight as possible with no hard bends and is to be anchored according to Manufacturer's requirements. The flexible hose can be exchanged with a hose of equal size and equal or greater pressure rating. Anchor requirements, specification sheet and hydrostatic pressure test certification matching the hose in service, to be onsite for review. These documents shall be posted in the company man's trailer and on the rig floor.
3. 5M or higher system requires an HCR valve, remote kill line and annular to match. The remote kill line is to be installed prior to testing the system and tested to stack pressure.
4. If the operator has proposed a multi-bowl wellhead assembly in the APD. The following requirements must be met:
 - a. Wellhead shall be installed by manufacturer's representatives, submit documentation with subsequent sundry.
 - b. If the welding is performed by a third party, the manufacturer's representative shall monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
 - c. Manufacturer representative shall install the test plug for the initial BOP test.
 - d. Whenever any seal subject to test pressure is broken, all the tests in OOGO2.III.A.2.i must be followed.
 - e. If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head shall be cut off, cementing operations performed and another wellhead installed.
5. The appropriate BLM office shall be notified a minimum of 4 hours in advance for a representative to witness the tests.
 - a. In a water basin, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. The casing cut-off and BOP installation can be initiated four hours after installing the slips, which will be approximately six hours after bumping the plug. For those casing strings not using slips, the minimum wait time before cut-off is eight hours after bumping the plug. BOP/BOPE testing can begin after cut-off or once cement reaches 500 psi compressive strength (including lead when specified), whichever is greater. However, if the float does not

hold, cut-off cannot be initiated until cement reaches 500 psi compressive strength (including lead when specified).

- b. In potash areas, for all casing strings utilizing slips, these are to be set as soon as the crew and rig are ready and any fallback cement remediation has been done. For all casing strings, casing cut-off and BOP installation can be initiated at twelve hours after bumping the plug. However, **no tests** shall commence until the cement has had a minimum of 24 hours setup time, except the casing pressure test can be initiated immediately after bumping the plug (only applies to single stage cement jobs).
- c. The tests shall be done by an independent service company utilizing a test plug not a cup or J-packer. The operator also has the option of utilizing an independent tester to test without a plug (i.e. against the casing) pursuant to Onshore Order 2 with the pressure not to exceed 70% of the burst rating for the casing. Any test against the casing must meet the WOC time for water basin (8 hours) or potash (24 hours) or 500 pounds compressive strength, whichever is greater, prior to initiating the test (see casing segment as lead cement may be critical item).
- d. The test shall be run on a 5000 psi chart for a 2-3M BOP/BOP, on a 10000 psi chart for a 5M BOP/BOPE and on a 15000 psi chart for a 10M BOP/BOPE. If a linear chart is used, it shall be a one hour chart. A circular chart shall have a maximum 2 hour clock. If a twelve hour or twenty-four hour chart is used, tester shall make a notation that it is run with a two hour clock.
- e. The results of the test shall be reported to the appropriate BLM office.
- f. All tests are required to be recorded on a calibrated test chart. A copy of the BOP/BOPE test chart and a copy of independent service company test will be submitted to the appropriate BLM office.
- g. The BOP/BOPE test shall include a low pressure test from 250 to 300 psi. The test will be held for a minimum of 10 minutes if test is done with a test plug and 30 minutes without a test plug. This test shall be performed prior to the test at full stack pressure.
- h. BOP/BOPE must be tested by an independent service company within 500 feet of the top of the Wolfcamp formation if the time between the setting of the intermediate casing and reaching this depth exceeds 20 days. This test does not exclude the test prior to drilling out the casing shoe as per Onshore Order No. 2.

C. DRILLING MUD

Mud system monitoring equipment, with derrick floor indicators and visual and audio alarms, shall be operating before drilling into the Wolfcamp formation, and shall be used until production casing is run and cemented.

D. WASTE MATERIAL AND FLUIDS

All waste (i.e. drilling fluids, trash, salts, chemicals, sewage, gray water, etc.) created as a result of drilling operations and completion operations shall be safely contained and disposed of properly at a waste disposal facility. No waste material or fluid shall be disposed of on the well location or surrounding area.

Porto-johns and trash containers will be on-location during fracturing operations or any other crew-intensive operations.

**PECOS DISTRICT
SURFACE USE
CONDITIONS OF APPROVAL**

OPERATOR'S NAME:	Devon Energy Production Company L.P.
WELL NAME & NO.:	BELLOQ 11-2 FED STATE COM 524H
SURFACE HOLE FOOTAGE:	500'/S & 910'/E
BOTTOM HOLE FOOTAGE:	20'/N & 1040'/E
LOCATION:	Section 11, T.23 S., R.31 E., NMPM
COUNTY:	Eddy County, New Mexico

TABLE OF CONTENTS

Standard Conditions of Approval (COA) apply to this APD. If any deviations to these standards exist or special COAs are required, the section with the deviation or requirement will be checked below.

- ☐ **General Provisions**
- ☐ **Permit Expiration**
- ☐ **Archaeology, Paleontology, and Historical Sites**
- ☐ **Noxious Weeds**
- ☒ **Special Requirements**
 - Lesser Prairie-Chicken Timing Stipulations
 - Ground-level Abandoned Well Marker
 - Range
 - Potash
- ☐ **Construction**
 - Notification
 - Topsoil
 - Closed Loop System
 - Federal Mineral Material Pits
 - Well Pads
 - Roads
- ☐ **Road Section Diagram**
- ☒ **Production (Post Drilling)**
 - Well Structures & Facilities
 - Pipelines
 - Electric Lines
 - Oil and Gas Related sites
- ☐ **Interim Reclamation**
- ☐ **Final Abandonment & Reclamation**

I. GENERAL PROVISIONS

The approval of the Application For Permit To Drill (APD) is in compliance with all applicable laws and regulations: 43 Code of Federal Regulations 3160, the lease terms, Onshore Oil and Gas Orders, Notices To Lessees, New Mexico Oil Conservation Division (NMOCD) Rules, National Historical Preservation Act As Amended, and instructions and orders of the Authorized Officer. Any request for a variance shall be submitted to the Authorized Officer on Form 3160-5, Sundry Notices and Report on Wells.

II. PERMIT EXPIRATION

If the permit terminates prior to drilling and drilling cannot be commenced within 60 days after expiration, an operator is required to submit Form 3160-5, Sundry Notices and Reports on Wells, requesting surface reclamation requirements for any surface disturbance. However, if the operator will be able to initiate drilling within 60 days after the expiration of the permit, the operator must have set the conductor pipe in order to allow for an extension of 60 days beyond the expiration date of the APD. (Filing of a Sundry Notice is required for this 60 day extension.)

III. ARCHAEOLOGICAL, PALEONTOLOGY & HISTORICAL SITES

Any cultural and/or paleontological resource discovered by the operator or by any person working on the operator's behalf shall immediately report such findings to the Authorized Officer. The operator is fully accountable for the actions of their contractors and subcontractors. The operator shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery shall be made by the Authorized Officer to determine the appropriate actions that shall be required to prevent the loss of significant cultural or scientific values of the discovery. The operator shall be held responsible for the cost of the proper mitigation measures that the Authorized Officer assesses after consultation with the operator on the evaluation and decisions of the discovery. Any unauthorized collection or disturbance of cultural or paleontological resources may result in a shutdown order by the Authorized Officer.

IV. NOXIOUS WEEDS

The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

V. SPECIAL REQUIREMENT(S)

Timing Limitation Stipulation / Condition of Approval for lesser prairie-chicken:

Oil and gas activities including 3-D geophysical exploration, and drilling will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Additionally, no new drilling will be allowed within up to 200 meters of leks known at the time of permitting. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 feet from the source of the noise.

Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well. For more installation details, contact the Carlsbad Field Office at 575-234-5972.

Lessees must comply with the 2012 Secretarial Potash Order. The Order is designed to manage the efficient development of oil, gas, and potash resources. Section 6 of the Order provides general provisions which must be followed to minimize conflict between the industries and ensure the safety of operations.

To minimize impacts to potash resources, the proposed well is confined within the boundaries of the established Uber North Drill Island (See Potash Memo and Map in attached file for Drill Island description).

Livestock Watering Requirement

Any damage to structures that provide water to livestock throughout the life of the well, caused by operations from the well site, must be immediately corrected by the operator. The operator must notify the BLM office (575-234-5972) and the private surface landowner or the grazing allotment holder if any damage occurs to structures that provide water to livestock.

Fence Requirement

Where entry is granted across a fence line, the fence must be braced and tied off on both sides of the passageway with H-braces prior to cutting. Once the work is completed, the fence will be restored to its prior condition, or better. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fence(s).

The operator must contact the allotment holder prior to construction to identify the location of the pipeline. The operator must take measures to protect the pipeline from compression or other damages. If the pipeline is damaged or compromised in any way near the proposed project as a result of oil and gas activity, the operator is responsible for repairing the pipeline immediately. The operator must notify the BLM office (575-234-5972) and the private surface landowner or the grazing allotment holder if any damage occurs to structures that provide water to livestock.

During construction, the proponent shall minimize disturbance to existing fences, water lines, troughs, windmills, and other improvements on public lands. The proponent is required to promptly repair improvements to at least their former state. Functional use of these

improvements will be maintained at all times. The holder will contact the grazing permittee/allottee prior to disturbing any range improvement projects. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

VI. CONSTRUCTION

A. NOTIFICATION

The BLM shall administer compliance and monitor construction of the access road and well pad. Notify the Carlsbad Field Office at (575) 234-5909 at least 3 working days prior to commencing construction of the access road and/or well pad.

When construction operations are being conducted on this well, the operator shall have the approved APD and Conditions of Approval (COA) on the well site and they shall be made available upon request by the Authorized Officer.

B. TOPSOIL

The operator shall strip the top portion of the soil (root zone) from the entire well pad area and stockpile the topsoil along the edge of the well pad as depicted in the APD. The root zone is typically six (6) inches in depth. All the stockpiled topsoil will be redistributed over the interim reclamation areas. Topsoil shall not be used for berming the pad or facilities. For final reclamation, the topsoil shall be spread over the entire pad area for seeding preparation.

Other subsoil (below six inches) stockpiles must be completely segregated from the topsoil stockpile. Large rocks or subsoil clods (not evident in the surrounding terrain) must be buried within the approved area for interim and final reclamation.

C. CLOSED LOOP SYSTEM

Tanks are required for drilling operations: No Pits.

The operator shall properly dispose of drilling contents at an authorized disposal site.

D. FEDERAL MINERAL MATERIALS PIT

Payment shall be made to the BLM prior to removal of any federal mineral materials. Call the Carlsbad Field Office at (575) 234-5972.

E. WELL PAD SURFACING

Surfacing of the well pad is not required.

If the operator elects to surface the well pad, the surfacing material may be required to be removed at the time of reclamation. The well pad shall be constructed in a manner which creates the smallest possible surface disturbance, consistent with safety and operational needs.

F. EXCLOSURE FENCING (CELLARS & PITS)

Exclosure Fencing

The operator will install and maintain exclosure fencing for all open well cellars to prevent access to public, livestock, and large forms of wildlife before and after drilling operations until the pit is free of fluids and the operator initiates backfilling. (For examples of exclosure fencing design, refer to BLM's Oil and Gas Gold Book, Exclosure Fence Illustrations, Figure 1, Page 18.)

G. ON LEASE ACCESS ROADS**Road Width**

The access road shall have a driving surface that creates the smallest possible surface disturbance and does not exceed fourteen (14) feet in width. The maximum width of surface disturbance, when constructing the access road, shall not exceed twenty-five (25) feet.

Surfacing

Surfacing material is not required on the new access road driving surface. If the operator elects to surface the new access road or pad, the surfacing material may be required to be removed at the time of reclamation.

Where possible, no improvements should be made on the unsurfaced access road other than to remove vegetation as necessary, road irregularities, safety issues, or to fill low areas that may sustain standing water.

The Authorized Officer reserves the right to require surfacing of any portion of the access road at any time deemed necessary. Surfacing may be required in the event the road deteriorates, erodes, road traffic increases, or it is determined to be beneficial for future field development. The surfacing depth and type of material will be determined at the time of notification.

Crowning

Crowning shall be done on the access road driving surface. The road crown shall have a grade of approximately 2% (i.e., a 1" crown on a 14' wide road). The road shall conform to Figure 1; cross section and plans for typical road construction.

Ditching

Ditching shall be required on both sides of the road.

Turnouts


Vehicle turnouts shall be constructed on the road. Turnouts shall be intervisible with interval spacing distance less than 1000 feet. Turnouts shall conform to Figure 1; cross section and plans for typical road construction.

Drainage

Drainage control systems shall be constructed on the entire length of road (e.g. ditches, sidehill outslowing and insloping, lead-off ditches, culvert installation, and low water crossings).

A typical lead-off ditch has a minimum depth of 1 foot below and a berm of 6 inches above natural ground level. The berm shall be on the down-slope side of the lead-off ditch.

Cross Section of a Typical Lead-off Ditch



All lead-off ditches shall be graded to drain water with a 1 percent minimum to 3 percent maximum ditch slope. The spacing interval are variable for lead-off ditches and shall be determined according to the formula for spacing intervals of lead-off ditches, but may be amended depending upon existing soil types and centerline road slope (in %);

Formula for Spacing Interval of Lead-off Ditches

Example - On a 4% road slope that is 400 feet long, the water flow shall drain water into a lead-off ditch. Spacing interval shall be determined by the following formula:

$$400 \text{ foot road with } 4\% \text{ road slope: } \frac{400'}{4\%} + 100' = 200' \text{ lead-off ditch interval}$$

Cattle guards

An appropriately sized cattle guard sufficient to carry out the project shall be installed and maintained at fence/road crossings. Any existing cattle guards on the access road route shall be repaired or replaced if they are damaged or have deteriorated beyond practical use. The operator shall be responsible for the condition of the existing cattle guards that are in place and are utilized during lease operations.

Fence Requirement

Where entry is granted across a fence line, the fence shall be braced and tied off on both sides of the passageway prior to cutting. The operator shall notify the private surface landowner or the grazing allotment holder prior to crossing any fences.


Public Access

Public access on this road shall not be restricted by the operator without specific written approval granted by the Authorized Officer.


Construction Steps

1. Salvage topsoil
2. Construct road


3. Redistribute topsoil
4. Revegetate slopes




Typical Turnout Plan




Level Ground Section



Side Hill Section



Typical Outsloped Section



Typical Insloped Section

Figure 1. Cross-sections and plans for typical road sections representative of BLM resource or FS local and higher-class roads.

VII. PRODUCTION (POST DRILLING)

A. WELL STRUCTURES & FACILITIES

Placement of Production Facilities

Production facilities should be placed on the well pad to allow for maximum interim recontouring and revegetation of the well location.

Exclosure Netting (Open-top Tanks)

Immediately following active drilling or completion operations, the operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock, hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps.

Chemical and Fuel Secondary Containment and Exclosure Screening

The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock exclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

Open-Vent Exhaust Stack Exclosures

The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (*Recommended exclosure structures on open-vent exhaust stacks are in the shape of a cone.*) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

Containment Structures

Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

Painting Requirement

All above-ground structures including meter housing that are not subject to safety requirements shall be painted a flat non-reflective paint color, **Shale Green** from the BLM Standard Environmental Color Chart (CC-001: June 2008).

B. PIPELINES

BURIED PIPELINE STIPULATIONS

A copy of the application (Grant, APD, or Sundry Notice) and attachments, including conditions of approval, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The Holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. The Holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.
3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C.6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

4. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil or other pollutant, wherever found, shall be the responsibility of holder, regardless of fault. Upon failure of holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he deems necessary to control and clean up the discharge and restore the area, including where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve holder of any responsibility as provided herein.

5. All construction and maintenance activity will be confined to the authorized right-of-way.
6. The pipeline will be buried with a minimum cover of 36 inches between the top of the pipe and ground level.
7. The maximum allowable disturbance for construction in this right-of-way will be 30 feet:
- Blading of vegetation within the right-of-way will be allowed: maximum width of blading operations will not exceed 20 feet. The trench is included in this area. (*Blading is defined as the complete removal of brush and ground vegetation.*)
 - Clearing of brush species within the right-of-way will be allowed: maximum width of clearing operations will not exceed 30 feet. The trench and bladed area are included in this area. (*Clearing is defined as the removal of brush while leaving ground vegetation (grasses, weeds, etc.) intact. Clearing is best accomplished by holding the blade 4 to 6 inches above the ground surface.*)
 - The remaining area of the right-of-way (if any) shall only be disturbed by compressing the vegetation. (*Compressing can be caused by vehicle tires, placement of equipment, etc.*)
8. The holder shall stockpile an adequate amount of topsoil where blading is allowed. The topsoil to be stripped is approximately 6 inches in depth. The topsoil will be segregated from other spoil piles from trench construction. The topsoil will be evenly distributed over the bladed area for the preparation of seeding.
9. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.
10. Vegetation, soil, and rocks left as a result of construction or maintenance activity will be randomly scattered on this right-of-way and will not be left in rows, piles, or berms, unless otherwise approved by the Authorized Officer. The entire right-of-way shall be recontoured to match the surrounding landscape. The backfilled soil shall be compacted and a 6 inch berm will be left over the ditch line to allow for settling back to grade.
11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.

12. The holder will reseed all disturbed areas. Seeding will be done according to the attached seeding requirements, using the following seed mix.

- | | |
|--|--|
| <input type="checkbox"/> seed mixture 1 | <input type="checkbox"/> seed mixture 3 |
| <input type="checkbox"/> seed mixture 2 | <input type="checkbox"/> seed mixture 4 |
| <input checked="" type="checkbox"/> seed mixture 2/LPC | <input type="checkbox"/> Aplomado Falcon Mixture |

13. All above-ground structures not subject to safety requirements shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be color which simulates "Standard Environmental Colors" – **Shale Green**, Munsell Soil Color No. 5Y 4/2.

14. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. All signs and information thereon will be posted in a permanent, conspicuous manner, and will be maintained in a legible condition for the life of the pipeline.

15. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder before maintenance begins. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway. As determined necessary during the life of the pipeline, the Authorized Officer may ask the holder to construct temporary deterrence structures.

16. Any cultural and/or paleontological resources (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

17. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes associated roads, pipeline corridor and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

18. Escape Ramps - The operator will construct and maintain pipeline/utility trenches that are not otherwise fenced, screened, or netted to prevent livestock, wildlife, and humans from becoming entrapped. At a minimum, the operator will construct and maintain escape ramps, ladders, or

other methods of avian and terrestrial wildlife escape in the trenches according to the following criteria:

- a. Any trench left open for eight (8) hours or less is not required to have escape ramps; however, before the trench is backfilled, the contractor/operator shall inspect the trench for wildlife, remove all trapped wildlife, and release them at least 100 yards from the trench.
- b. For trenches left open for eight (8) hours or more, earthen escape ramps (built at no more than a 30 degree slope and spaced no more than 500 feet apart) shall be placed in the trench.

19. Special Stipulations:

Lesser Prairie-Chicken

Oil and gas activities will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, geophysical exploration other than 3-D operations, and pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 ft. from the source of the noise.

STANDARD STIPULATIONS FOR SURFACE INSTALLED PIPELINES

A copy of the application (Grant, Sundry Notice, APD) and attachments, including stipulations, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. The holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 *et seq.* (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR, Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the

authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.

3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to activity of the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.

4. The holder shall be liable for damage or injury to the United States to the extent provided by 43 CFR Sec. 2883.1-4. The holder shall be held to a standard of strict liability for damage or injury to the United States resulting from pipe rupture, fire, or spills caused or substantially aggravated by any of the following within the right-of-way or permit area:

- a. Activities of the holder including, but not limited to construction, operation, maintenance, and termination of the facility.
- b. Activities of other parties including, but not limited to:
 - (1) Land clearing.
 - (2) Earth-disturbing and earth-moving work.
 - (3) Blasting.
 - (4) Vandalism and sabotage.
- c. Acts of God.

The maximum limitation for such strict liability damages shall not exceed one million dollars (\$1,000,000) for any one event, and any liability in excess of such amount shall be determined by the ordinary rules of negligence of the jurisdiction in which the damage or injury occurred.

This section shall not impose strict liability for damage or injury resulting primarily from an act of war or from the negligent acts or omissions of the United States.

5. If, during any phase of the construction, operation, maintenance, or termination of the pipeline, any oil, salt water, or other pollutant should be discharged from the pipeline system, impacting Federal lands, the control and total removal, disposal, and cleaning up of such oil, salt water, or other pollutant, wherever found, shall be the responsibility of the holder, regardless of fault. Upon failure of the holder to control, dispose of, or clean up such discharge on or affecting Federal lands, or to repair all damages resulting therefrom, on the Federal lands, the Authorized Officer may take such measures as he deems necessary to control and clean up the discharge and restore the area, including, where appropriate, the aquatic environment and fish and wildlife habitats, at the full expense of the holder. Such action by the Authorized Officer shall not relieve the holder

of any responsibility as provided herein.

6. All construction and maintenance activity will be confined to the authorized right-of-way width of 20 feet. If the pipeline route follows an existing road or buried pipeline right-of-way, the surface pipeline must be installed no farther than 10 feet from the edge of the road or buried pipeline right-of-way. If existing surface pipelines prevent this distance, the proposed surface pipeline must be installed immediately adjacent to the outer surface pipeline. All construction and maintenance activity will be confined to existing roads or right-of-ways.

7. No blading or clearing of any vegetation will be allowed unless approved in writing by the Authorized Officer.

8. The holder shall install the pipeline on the surface in such a manner that will minimize suspension of the pipeline across low areas in the terrain. In hummocky or dune areas, the pipeline will be "snaked" around hummocks and dunes rather than suspended across these features.

9. The pipeline shall be buried with a minimum of 24 inches under all roads, "two-tracks," and trails. Burial of the pipe will continue for 20 feet on each side of each crossing. The condition of the road, upon completion of construction, shall be returned to at least its former state with no bumps or dips remaining in the road surface.

10. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting of the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

11. In those areas where erosion control structures are required to stabilize soil conditions, the holder will install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound resource management practices.

12. Excluding the pipe, all above-ground structures not subject to safety requirement shall be painted by the holder to blend with the natural color of the landscape. The paint used shall be a color which simulates "Standard Environmental Colors" – **Shale Green**, Munsell Soil Color No. 5Y 4/2; designated by the Rocky Mountain Five State Interagency Committee.

13. The pipeline will be identified by signs at the point of origin and completion of the right-of-way and at all road crossings. At a minimum, signs will state the holder's name, BLM serial number, and the product being transported. Signs will be maintained in a legible condition for the life of the pipeline.

14. The holder shall not use the pipeline route as a road for purposes other than routine maintenance as determined necessary by the Authorized Officer in consultation with the holder. The holder will take whatever steps are necessary to ensure that the pipeline route is not used as a roadway.

15. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the authorized officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the authorized officer. An evaluation of the discovery will be made by the authorized officer to determine appropriate cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the authorized officer after consulting with the holder.

16. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, powerline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

17. Surface pipelines must be less than or equal to 4 inches and a working pressure below 125 psi.

18. Special Stipulations:

- a. **Lesser Prairie-Chicken:** Oil and gas activities will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities and pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Normal vehicle use on existing roads will not be restricted.

C. ELECTRIC LINES

STANDARD STIPULATIONS FOR OVERHEAD ELECTRIC DISTRIBUTION LINES

A copy of the grant and attachments, including stipulations, survey plat and/or map, will be on location during construction. BLM personnel may request to you a copy of your permit during construction to ensure compliance with all stipulations.

Holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer:

1. The holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant.
2. The holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976 as amended, 15 USC 2601 et seq. (1982) with regards to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized under this right-of-way grant. (See 40 CFR, Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation, and Liability Act, section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the authorized officer concurrent with the filing of the reports to the involved Federal agency or State government.
3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et seq.) on the Right-of-Way (unless the release or threatened release is wholly unrelated to the Right-of-Way holder's activity on the Right-of-Way), or resulting from the activity of the Right-of-Way holder on the Right-of-Way. This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.
4. There will be no clearing or blading of the right-of-way unless otherwise agreed to in writing by the Authorized Officer.
5. Power lines shall be constructed and designed in accordance to standards outlined in "Suggested Practices for Avian Protection on Power lines: The State of the Art in 2006" Edison Electric Institute, APLIC, and the California Energy Commission 2006 . The holder shall assume the burden and expense of proving that pole designs not shown in the above publication deter raptor perching, roosting, and nesting. Such proof shall be provided by a raptor expert approved by the Authorized Officer. The BLM reserves the right to require modification or additions to all powerline structures placed on this right-of-way, should they be necessary to ensure the safety of large perching birds. Such modifications and/or additions shall be made by the holder without liability or expense to the United States.

Raptor deterrence will consist of but not limited to the following: triangle perch discouragers shall be placed on each side of the cross arms and a nonconductive perching deterrence shall be placed on all vertical poles that extend past the cross arms.

6. The holder shall minimize disturbance to existing fences and other improvements on public lands. The holder is required to promptly repair improvements to at least their former state. Functional use of these improvements will be maintained at all times. The holder will contact the owner of any improvements prior to disturbing them. When necessary to pass through a fence line, the fence shall be braced on both sides of the passageway prior to cutting the fence. No permanent gates will be allowed unless approved by the Authorized Officer.

7. The BLM serial number assigned to this authorization shall be posted in a permanent, conspicuous manner where the power line crosses roads and at all serviced facilities. Numbers will be at least two inches high and will be affixed to the pole nearest the road crossing and at the facilities served.

8. Upon cancellation, relinquishment, or expiration of this grant, the holder shall comply with those abandonment procedures as prescribed by the Authorized Officer.

9. All surface structures (poles, lines, transformers, etc.) shall be removed within 180 days of abandonment, relinquishment, or termination of use of the serviced facility or facilities or within 180 days of abandonment, relinquishment, cancellation, or expiration of this grant, whichever comes first. This will not apply where the power line extends service to an active, adjoining facility or facilities.

10. Any cultural and/or paleontological resource (historic or prehistoric site or object) discovered by the holder, or any person working on his behalf, on public or Federal land shall be immediately reported to the Authorized Officer. Holder shall suspend all operations in the immediate area of such discovery until written authorization to proceed is issued by the Authorized Officer. An evaluation of the discovery will be made by the Authorized Officer to determine appropriate actions to prevent the loss of significant cultural or scientific values. The holder will be responsible for the cost of evaluation and any decision as to proper mitigation measures will be made by the Authorized Officer after consulting with the holder.

11. Special Stipulations:

- For reclamation remove poles, lines, transformer, etc. and dispose of properly.
- Fill in any holes from the poles removed.

Timing Limitation Stipulation/Condition of Approval for Lesser Prairie-Chicken:

Oil and gas activities including 3-D geophysical exploration, and drilling will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, geophysical exploration other than 3-D operations, and pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Additionally, no new drilling will be

allowed within up to 200 meters of leaks known at the time of permitting. Normal vehicle use on existing roads will not be restricted. Exhaust noise from pump jack engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 ft. from the source of the noise.

STANDARD STIPULATIONS FOR OIL AND GAS RELATED SITES

A copy of the application (Grant/Sundry Notice) and attachments, including stipulations and map, will be on location during construction. BLM personnel may request to view a copy of your permit during construction to ensure compliance with all stipulations.

The holder agrees to comply with the following stipulations to the satisfaction of the Authorized Officer, BLM.

1. The holder shall indemnify the United States against any liability for damage to life or property arising from the occupancy or use of public lands under this grant and for all response costs, penalties, damages, claims, and other costs arising from the provisions of the Resource Conservation and Recovery Act (RCRA), 42 U.S.C. Chap. 82, Section 6901 et. seq., from the Comprehensive Environmental Response, Compensation and Liability Act (CERCLA), 42 U.S.C. Chap. 109, Section 9601 et. seq., and from other applicable environmental statutes.
2. The holder shall comply with all applicable Federal laws and regulations existing or hereafter enacted or promulgated. In any event, the holder shall comply with the Toxic Substances Control Act of 1976, as amended (15 U.S.C. 2601, et. seq.) with regard to any toxic substances that are used, generated by or stored on the right-of-way or on facilities authorized by this grant. (See 40 CFR, Part 702-799 and especially, provisions on polychlorinated biphenyls, 40 CFR 761.1-761.193.) Additionally, any release of toxic substances (leaks, spills, etc.) in excess of the reportable quantity established by 40 CFR, Part 117 shall be reported as required by the Comprehensive Environmental Response, Compensation and Liability Act, Section 102b. A copy of any report required or requested by any Federal agency or State government as a result of a reportable release or spill of any toxic substances shall be furnished to the Authorized Officer concurrent with the filing of the reports to the involved Federal agency or State government.
3. The holder agrees to indemnify the United States against any liability arising from the release of any hazardous substance or hazardous waste (as these terms are defined in the Comprehensive Environmental Response, Compensation and Liability Act of 1980, 42 U.S.C. 9601, et. seq. or the Resource Conservation and Recovery Act, 42 U.S.C. 6901, et. seq.) on the right-of-way (unless the release or threatened release is wholly unrelated to the right-of-way holder's activity on the right-of-way). This agreement applies without regard to whether a release is caused by the holder, its agent, or unrelated third parties.
4. If, during any phase of the construction, operation, maintenance, or termination of the site or related pipeline(s), any oil or other pollutant should be discharged from site

10. The operator shall be held responsible if noxious weeds become established within the areas of operations. Weed control shall be required on the disturbed land where noxious weeds exist, which includes the roads, pads, associated pipeline corridor, and adjacent land affected by the establishment of weeds due to this action. The operator shall consult with the Authorized Officer for acceptable weed control methods, which include following EPA and BLM requirements and policies.

11. Once the site is no longer in service or use, the site must undergo final abandonment. At final abandonment, the site and access roads must undergo "final" reclamation so that the character and productivity of the land are restored. Earthwork for final reclamation must be completed within six (6) months of the abandonment of the site. All pads and facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact. After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

12. The holder shall stockpile an adequate amount of topsoil where blading occurs. The topsoil to be stripped is approximately 6 inches in depth. The topsoil will be segregated from other spoil piles. The topsoil will be used for final reclamation.

13. The holder will reseed all disturbed areas. Seeding will be done according to the attached seeding requirements, using the following seed mix.

- | | |
|--|--|
| <input type="checkbox"/> seed mixture 1 | <input type="checkbox"/> seed mixture 3 |
| <input type="checkbox"/> seed mixture 2 | <input type="checkbox"/> seed mixture 4 |
| <input checked="" type="checkbox"/> seed mixture 2/LPC | <input type="checkbox"/> Aplomado Falcon Mixture |

14. In those areas where erosion control structures are required to stabilize soil conditions, the holder shall install such structures as are suitable for the specific soil conditions being encountered and which are in accordance with sound management practices. Any earth work will require prior approval by the Authorized Officer.

15. Open-topped Tanks - The operator will take actions necessary to prevent wildlife and livestock access, including avian wildlife, to all open-topped tanks that contain or have the potential to contain salinity sufficient to cause harm to wildlife or livestock,

hydrocarbons, or Resource Conservation and Recovery Act of 1976-exempt hazardous substances. At a minimum, the operator will net, screen, or cover open-topped tanks to exclude wildlife and livestock and prevent mortality. If the operator uses netting, the operator will cover and secure the open portion of the tank to prevent wildlife entry. The operator will net, screen, or cover the tanks until the operator removes the tanks from the location or the tanks no longer contain substances that could be harmful to wildlife or livestock. Use a maximum netting mesh size of 1 ½ inches. The netting must not be in contact with fluids and must not have holes or gaps

16. The operator will prevent all hazardous, poisonous, flammable, and toxic substances from coming into contact with soil and water. At a minimum, the operator will install and maintain an

impervious secondary containment system for any tank or barrel containing hazardous, poisonous, flammable, or toxic substances sufficient to contain the contents of the tank or barrel and any drips, leaks, and anticipated precipitation. The operator will dispose of fluids within the containment system that do not meet applicable state or U. S. Environmental Protection Agency livestock water standards in accordance with state law; the operator must not drain the fluids to the soil or ground. The operator will design, construct, and maintain all secondary containment systems to prevent wildlife and livestock exposure to harmful substances. At a minimum, the operator will install effective wildlife and livestock enclosure systems such as fencing, netting, expanded metal mesh, lids, and grate covers. Use a maximum netting mesh size of 1 ½ inches.

17. Open-Vent Exhaust Stack Enclosures – The operator will construct, modify, equip, and maintain all open-vent exhaust stacks on production equipment to prevent birds and bats from entering, and to discourage perching, roosting, and nesting. (Recommended enclosure structures on open-vent exhaust stacks are in the shape of a cone.) Production equipment includes, but may not be limited to, tanks, heater-treaters, separators, dehydrators, flare stacks, in-line units, and compressor mufflers.

18. Containment Structures - Proposed production facilities such as storage tanks and other vessels will have a secondary containment structure that is constructed to hold the capacity of 1.5 times the largest tank, plus freeboard to account for precipitation, unless more stringent protective requirements are deemed necessary.

19. Special Stipulations:

- The entire well pad will be bermed to prevent oil, salt, and other chemical contaminants from leaving the well pad. Topsoil shall not be used to construct the berm. No water flow from the uphill side(s) of the pad shall be allowed to enter the well pad. The berm shall be maintained through the life of the well and after interim reclamation has been completed.

- Any water erosion that may occur due to the construction of the well pad during the life of the well will be corrected within two weeks and proper measures will be taken to prevent future erosion.

Lesser Prairie-Chicken

Oil and gas activities will not be allowed in lesser prairie-chicken habitat during the period from March 1st through June 15th annually. During that period, other activities that produce noise or involve human activity, such as the maintenance of oil and gas facilities, geophysical exploration other than 3-D operations, and pipeline, road, and well pad construction, will be allowed except between 3:00 am and 9:00 am. The 3:00 am to 9:00 am restriction will not apply to normal, around-the-clock operations, such as venting, flaring, or pumping, which do not require a human presence during this period. Normal vehicle use on existing roads will not be restricted. Exhaust noise from permanent engines must be muffled or otherwise controlled so as not to exceed 75 db measured at 30 ft. from the source of the noise.

VIII. INTERIM RECLAMATION

During the life of the development, all disturbed areas not needed for active support of production operations should undergo interim reclamation in order to minimize the environmental impacts of development on other resources and uses.

Within six (6) months of well completion, operators should work with BLM surface management specialists (Jim Amos: 575-234-5909) to devise the best strategies to reduce the size of the location. Interim reclamation should allow for remedial well operations, as well as safe and efficient removal of oil and gas.

During reclamation, the removal of caliche is important to increasing the success of revegetating the site. Removed caliche that is free of contaminants may be used for road repairs, fire walls or for building other roads and locations. In order to operate the well or complete workover operations, it may be necessary to drive, park and operate on restored interim vegetation within the previously disturbed area. Disturbing revegetated areas for production or workover operations will be allowed. If there is significant disturbance and loss of vegetation, the area will need to be revegetated. Communicate with the appropriate BLM office for any exceptions/exemptions if needed.

All disturbed areas after they have been satisfactorily prepared need to be reseeded with the seed mixture provided below.

Upon completion of interim reclamation, the operator shall submit a Sundry Notices and Reports on Wells, Subsequent Report of Reclamation (Form 3160-5).

IX. FINAL ABANDONMENT & RECLAMATION

At final abandonment, well locations, production facilities, and access roads must undergo "final" reclamation so that the character and productivity of the land are restored.

Earthwork for final reclamation must be completed within six (6) months of well plugging. All pads, pits, facility locations and roads must be reclaimed to a satisfactory revegetated, safe, and stable condition, unless an agreement is made with the landowner or BLM to keep the road and/or pad intact.

After all disturbed areas have been satisfactorily prepared, these areas need to be revegetated with the seed mixture provided below. Seeding should be accomplished by drilling on the contour whenever practical or by other approved methods. Seeding may need to be repeated until revegetation is successful, as determined by the BLM.

Operators shall contact a BLM surface protection specialist prior to surface abandonment operations for site specific objectives (Jim Amos: 575-234-5909).

Ground-level Abandoned Well Marker to avoid raptor perching: Upon the plugging and subsequent abandonment of the well, the well marker will be installed at ground level on a plate containing the pertinent information for the plugged well.

Seed Mixture for LPC Sand/Shinnery Sites

Holder shall seed all disturbed areas with the seed mixture listed below. The seed mixture shall be planted in the amounts specified in pounds of pure live seed (PLS)* per acre. There shall be no primary or secondary noxious weeds in the seed mixture. Seed will be tested and the viability testing of seed shall be done in accordance with State law(s) and within nine (9) months prior to purchase. Commercial seed shall be either certified or registered seed. The seed container shall be tagged in accordance with State law(s) and available for inspection by the Authorized Officer.

Seed will be planted using a drill equipped with a depth regulator to ensure proper depth of planting where drilling is possible. The seed mixture will be evenly and uniformly planted over the disturbed area (smaller/heavier seeds have a tendency to drop the bottom of the drill and are planted first). Holder shall take appropriate measures to ensure this does not occur. Where drilling is not possible, seed will be broadcast and the area shall be raked or chained to cover the seed. When broadcasting the seed, the pounds per acre are to be doubled. Seeding shall be repeated until a satisfactory stand is established as determined by the Authorized Officer. Evaluation of growth may not be made before completion of at least one full growing season after seeding.

Species to be planted in pounds of pure live seed* per acre:

<u>Species</u>	<u>lb/acre</u>
Plains Bristlegrass	5lbs/A
Sand Bluestem	5lbs/A
Little Bluestem	3lbs/A
Big Bluestem	6lbs/A
Plains Coreopsis	2lbs/A
Sand Dropseed	1lbs/A

*Pounds of pure live seed:

Pounds of seed x percent purity x percent germination = pounds pure live seed



Application for Permit to Drill

APD Package Report

Date Printed: 10/20/2019 01:33 PM

APD ID: 10400038622

Well Status: AAPD

APD Received Date: 01/31/2019 09:29 AM

Well Name: BELLOQ 11-2 FED STATE COM

Operator: DEVON ENERGY PRODUCTION COMPANY LP

Well Number: 524H

APD Package Report Contents

- Form 3160-3 : Error Generating Form
- Operator Certification Report
- Application Report
- Application Attachments
 - Operator Letter of Designation: 1 file(s)
 - Well Plat: 1 file(s)
- Drilling Plan Report
- Drilling Plan Attachments
 - Blowout Prevention Choke Diagram Attachment: 2 file(s)
 - Blowout Prevention BOP Diagram Attachment: 2 file(s)
 - Casing Design Assumptions and Worksheet(s): 3 file(s)
 - Hydrogen sulfide drilling operations plan: 1 file(s)
 - Proposed horizontal/directional/multi-lateral plan submission: 2 file(s)
 - Other Facets: 8 file(s)
 - Other Variances: 1 file(s)
- SUPO Report
- SUPO Attachments
 - Existing Road Map: 1 file(s)
 - Attach Well map: 1 file(s)
 - Water source and transportation map: 1 file(s)
 - Construction Materials source location attachment: 1 file(s)
 - Well Site Layout Diagram: 1 file(s)
 - Recontouring attachment: 1 file(s)
 - Other SUPO Attachment: 4 file(s)
- PWD Report
- PWD Attachments
 - None

- Bond Report
- Bond Attachments
 - None



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Operator Certification Data Report

10/20/2019

Operator Certification

I hereby certify that I, or someone under my direct supervision, have inspected the drill site and access route proposed herein; that I am familiar with the conditions which currently exist; that I have full knowledge of state and Federal laws applicable to this operation; that the statements made in this APD package are, to the best of my knowledge, true and correct; and that the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for the operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

NAME: Jenny Harms

Signed on: 01/30/2019

Title: Regulatory Compliance Professional

Street Address:

City:

State:

Zip:

Phone: (405)524-4902

Email address: RAY.VAZ@DVN.COM

Field Representative

Representative Name: Ray Vaz

Street Address: 6488 Seven Rivers Hwy

City: Artesia

State: NM

Zip: 88210

Phone: (575)748-1871

Email address: ray.vaz@dvn.com



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Application Data Report

10/20/2019

APD ID: 10400038622

Submission Date: 01/31/2019

Highlighted data
reflects the most
recent changes

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11-2 FED STATE COM

Well Number: 524H

[Show Final Text](#)

Well Type: OIL WELL

Well Work Type: Drill

Section 1 - General

APD ID: 10400038622

Tie to previous NOS?

Submission Date: 01/31/2019

BLM Office: CARLSBAD

User: Jenny Harms

Title: Regulatory Compliance
Professional

Federal/Indian APD: FED

Is the first lease penetrated for production Federal or Indian? FED

Lease number: NMNM0404441

Lease Acres: 1440

Surface access agreement in place?

Allotted?

Reservation:

Agreement in place? NO

Federal or Indian agreement:

Agreement number:

Agreement name:

Keep application confidential? YES

Permitting Agent? NO

APD Operator: DEVON ENERGY PRODUCTION COMPANY LP

Operator letter of designation:

BELLOQ_11_2_FED_STATE_COM_524H_WL_P_R2_1_30_2019_20190130090026.pdf

Operator Info

Operator Organization Name: DEVON ENERGY PRODUCTION COMPANY LP

Operator Address: 333 West Sheridan Avenue

Zip: 73102

Operator PO Box:

Operator City: Oklahoma City

State: OK

Operator Phone: (800)583-3866

Operator Internet Address:

Section 2 - Well Information

Well in Master Development Plan? NO

Master Development Plan name:

Well in Master SUPO? NO

Master SUPO name:

Well in Master Drilling Plan? NO

Master Drilling Plan name:

Well Name: BELLOQ 11-2 FED STATE COM

Well Number: 524H

Well API Number:

Field/Pool or Exploratory? Field and Pool

Field Name: LIVINGSTON
RIDGE

Pool Name: BONESPRING

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11-2 FED STATE COM

Well Number: 524H

Is the proposed well in an area containing other mineral resources? NATURAL GAS,OIL

Is the proposed well in a Helium production area? N **Use Existing Well Pad?** YES **New surface disturbance?** Y

Type of Well Pad: MULTIPLE WELL

Multiple Well Pad Name: **Number:** 4

Well Class: HORIZONTAL

BELLOQ 11 PAD

Number of Legs: 1

Well Work Type: Drill

Well Type: OIL WELL

Describe Well Type:

Well sub-Type: INFILL

Describe sub-type:

Distance to town:

Distance to nearest well: 1565 FT

Distance to lease line: 500 FT

Reservoir well spacing assigned acres Measurement: 640 Acres

Well plat: BELLOQ_11_2_FED_STATE_COM_524H_WL_P_R2_signed_20190929192459.pdf

Well work start Date: 12/31/2019

Duration: 45 DAYS

Section 3 - Well Location Table

Survey Type: RECTANGULAR

Describe Survey Type:

Datum: NAD83

Vertical Datum: NAVD88

Survey number: 6186B

Reference Datum:

Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD	Will this well produce from this lease?
SHL Leg #1	500	FSL	910	FEL	23S	31E	11	Aliquot SESE	32.3130828	-103.7429714	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 040444 1	3488	0	0	
KOP Leg #1	50	FSL	1040	FEL	23S	31E	11	Aliquot SESE	32.31185	-103.7434	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 040444 1	-5024	8533	8512	
PPP Leg #1	100	FSL	1040	FEL	23S	31E	11	Aliquot SESE	32.3119848	-103.7433933	EDD Y	NEW MEXI CO	NEW MEXI CO	F	NMNM 040444 1	-5281	8774	8769	

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11-2 FED STATE COM

Well Number: 524H

Wellbore	NS-Foot	NS Indicator	EW-Foot	EW Indicator	Twsp	Range	Section	Aliquot/Lot/Tract	Latitude	Longitude	County	State	Meridian	Lease Type	Lease Number	Elevation	MD	TVD	Will this well produce from this lease?
EXIT Leg #1	100	FNL	104 0	FEL	23S	31E	2	Lot 1	32.34045 2	- 103.7434 214	EDD Y	NEW MEXI CO	NEW MEXI CO	S	STATE	- 561 6	192 74	910 4	
BHL Leg #1	20	FNL	104 0	FEL	23S	31E	2	Lot 1	32.34067 19	- 103.7434 22	EDD Y	NEW MEXI CO	NEW MEXI CO	S	STATE	- 561 7	193 56	910 5	

District I
1625 N. French Dr., Hobbs, NM 88240
Phone: (575) 393-6161 Fax: (575) 393-0720
District II
811 S. First St., Artesia, NM 88210
Phone: (575) 748-1283 Fax: (575) 748-9720
District III
1000 Rio Brazos Road, Aztec, NM 87410
Phone: (505) 334-6178 Fax: (505) 334-6170
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505
Phone: (505) 476-3460 Fax: (505) 476-3462

State of New Mexico
Energy, Minerals & Natural Resources Department
OIL CONSERVATION DIVISION
1220 South St. Francis Dr.
Santa Fe, NM 87505

Form C-102
Revised August 1, 2011
Submit one copy to appropriate
District Office
☐ AMENDED REPORT

WELL LOCATION AND ACREAGE DEDICATION PLAT

¹ API Number	² Pool Code 39350	³ Pool Name Livingston Ridge; Bonespring
⁴ Property Code	⁵ Property Name BELLOQ 11-2 FED STATE COM	⁶ Well Number 524H
⁷ OGRID No. 6137	⁸ Operator Name DEVON ENERGY PRODUCTION COMPANY, L.P.	⁹ Elevation 3488.9

¹⁰ Surface Location

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
P	11	23 S	31 E		500	SOUTH	910	EAST	EDDY

¹¹ Bottom Hole Location If Different From Surface

UL or lot no.	Section	Township	Range	Lot Idn	Feet from the	North/South line	Feet from the	East/West line	County
1	2	23 S	31 E		20	NORTH	1040	EAST	EDDY

¹² Dedicated Acres 640	¹³ Joint or Infill	¹⁴ Consolidation Code	¹⁵ Order No.
--------------------------------------	-------------------------------	----------------------------------	-------------------------

No allowable will be assigned to this completion until all interests have been consolidated or a non-standard unit has been approved by the division.

<p>NW CORNER SEC. 2 LAT. = 32.3407356°N LONG. = 103.7571603°W NMSP EAST (FT) N = 488170.26 E = 719281.88</p> <p>W/4 CORNER SEC. 2 LAT. = 32.3335234°N LONG. = 103.7571441°W NMSP EAST (FT) N = 485546.51 E = 719301.00</p> <p>SECTION CORNER LAT. = 32.3262643°N LONG. = 103.7571278°W NMSP EAST (FT) N = 482905.72 E = 719320.25</p> <p>W/4 CORNER SEC. 11 LAT. = 32.3190067°N LONG. = 103.7571257°W NMSP EAST (FT) N = 480265.44 E = 719335.09</p> <p>SW CORNER SEC. 11 LAT. = 32.3117463°N LONG. = 103.7571237°W NMSP EAST (FT) N = 477624.13 E = 719349.92</p>	<p>N89°43'53"E 2641.96 FT N/4 CORNER SEC. 2 SCALED LOT 4 LOT 3 LOT 2 LOT 1 39.93 AC.</p> <p>LAST TAKE POINT 100' FSL, 1040' FEL LAT. = 32.3404520°N LONG. = 103.7434214°W</p> <p>NOTE: LATITUDE AND LONGITUDE COORDINATES ARE SHOWN USING THE NORTH AMERICAN DATUM OF 1983 (NAD83). LISTED NEW MEXICO STATE PLANE EAST COORDINATES ARE GRID-(NAD83)- BASIS OF BEARING- AND DISTANCES USED ARE NEW MEXICO STATE PLANE EAST COORDINATES MODIFIED TO THE SURFACE. ELEVATION VALUES ARE NAVD83.</p> <p>QUARTER CORNER LAT. = 32.3262353°N LONG. = 103.7485656°W S89°55'23"W 2645.45 FT NMSP EAST (FT) N = 482909.48 E = 721965.08</p> <p>SEC 11 FIRST TAKE POINT 100' FSL, 1040' FEL LAT. = 32.3119848°N LONG. = 103.7433933°W LAT. = 32.3130828°N (NAD83) LONG. = 103.7429714°W NMSP EAST (FT) N = 478134.17 E = 723719.47</p> <p>S/4 CORNER SEC. 11 LAT. = 32.3117253°N LONG. = 103.7485813°W NMSP EAST (FT) N = 477630.81 E = 721989.05</p>	<p>N89°43'53"E 2641.96 FT NE CORNER SEC. 2 LAT. = 32.3407245°N LONG. = 103.7400556°W NMSP EAST (FT) N = 488195.03 E = 724564.59</p> <p>E/4 CORNER SEC. 2 LAT. = 32.3334649°N LONG. = 103.7400345°W NMSP EAST (FT) N = 485554.08 E = 724585.72</p> <p>SECTION CORNER LAT. = 32.3262057°N LONG. = 103.7400123°W NMSP EAST (FT) N = 482913.26 E = 724607.20</p> <p>E/4 CORNER SEC. 11 LAT. = 32.3116999°N LONG. = 103.7400280°W NMSP EAST (FT) N = 480274.75 E = 724619.44</p> <p>SE CORNER SEC. 11 LAT. = 32.3116999°N LONG. = 103.7400280°W NMSP EAST (FT) N = 477636.10 E = 724631.57</p>	<p>¹⁷ OPERATOR CERTIFICATION I hereby certify that the information contained herein is true and complete to the best of my knowledge and belief, and that this organization either owns a working interest or unleased mineral interest in the land including the proposed bottom hole location or has a right to drill this well at this location pursuant to a contract with an owner of such a mineral or working interest, or to a voluntary pooling agreement or a compulsory pooling order heretofore entered by the division. Signature: <u>Jenny Harms</u> Date: <u>1-14-2019</u> Printed Name: <u>Jenny Harms</u> E-mail Address: <u>Jenny.harms@dvn.com</u></p> <p>¹⁸ SURVEYOR CERTIFICATION I hereby certify that the well location shown on this plat was plotted from field notes of actual surveys made by me or under my supervision, and that the same is true and correct to the best of my belief. DECEMBER 2018 Date of Survey: <u>12/20/18</u> Signature and Seal of Professional Surveyor: <u>PHILIP MONTE JARAMILLO, PLS 12797</u> Certificate Number: <u>PHILIP MONTE JARAMILLO, PLS 12797</u> SURVEY NO. 61868</p>
--	--	---	--

Intent ☐ As Drilled ☐

API #

Operator Name: DEVON ENERGY PRODUCTION COMPANY, L.P.	Property Name: BELLOQ 11-2 FED STATE COM	Well Number 524H
--	---	---------------------

Kick Off Point (KOP)

UL	Section	Township	Range	Lot	Feet	From N/S	Feet	From E/W	County
P	11	23S	31E		50	ESI	1040	FEL	EDDY
Latitude					Longitude				NAD
32.31185					103.7434				83

First Take Point (FTP)

UL	Section	Township	Range	Lot	Feet	From N/S	Feet	From E/W	County
P	11	23S	31E		100	SOUTH	1040	EAST	EDDY
Latitude					Longitude				NAD
32.3119848					103.7433933				83

Last Take Point (LTP)

UL	Section	Township	Range	Lot	Feet	From N/S	Feet	From E/W	County
A	2	23S	31E	1	100	NORTH	1040	EAST	EDDY
Latitude					Longitude				NAD
32.3404520					103.7434214				83

Is this well the defining well for the Horizontal Spacing Unit? ☒ YES


Is this well an infill well? ☐ NO

If infill is yes please provide API if available, Operator Name and well number for Defining well for Horizontal Spacing Unit.

API #		
Operator Name:	Property Name:	Well Number

KZ 06/29/2018

**SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
SITE MAP**



020 100 200 400

SCALE 1" = 200'

DIRECTIONS TO LOCATION

FROM STATE HIGHWAY 128 AND CR 798 (RED ROAD)
GO NORTH ON CR 798 APPROX. 4.0 MILES TO A ROAD
LATH WITH RED & WHITE FLAGGING ON LEFT SIDE
(WEST) OF CR 798, TURN WEST FOLLOW ROAD LATH
APPROX. 0.2 OF A MILE, TURN LEFT (SOUTH) GO 455'
TO THE SOUTHWEST PAD CORNER FOR THIS LOCATION.


**DEVON ENERGY PRODUCTION COMPANY, L.P.
BELLOQ 11-2 FED STATE COM 524H
LOCATED 500 FT. FROM THE SOUTH LINE
AND 910 FT. FROM THE EAST LINE OF
SECTION 11, TOWNSHIP 23 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO**

DECEMBER 13, 2018

SURVEY NO. 6186B

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 **CARLSBAD, NEW MEXICO**

SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
INTERIM SITE RECLAMATION



020 100 200 400
SCALE 1" = 200'

1.995± ACRES INTERIM PAD RECLAMATION AREA
8.971± ACRES GRADING SITE RECLAMATION AREA
3.499± ACRES NON-RECLAIMED AREA
14.465± ACRES BELLOQ & GALAPAGOS WELL PAD


DEVON ENERGY PRODUCTION COMPANY, L.P.
BELLOQ 11-2 FED STATE COM 524H
LOCATED 500 FT. FROM THE SOUTH LINE
AND 910 FT. FROM THE EAST LINE OF
SECTION 11, TOWNSHIP 23 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

DECEMBER 13, 2018

SURVEY NO. 6186B

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO

SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
LOCATION VERIFICATION MAP



USGS QUAD MAP:
LOS MEDANOS
BOOTLEG RIDGE

NOT TO SCALE


DEVON ENERGY PRODUCTION COMPANY, L.P.
BELLOQ 11-2 FED STATE COM 524H
LOCATED 500 FT. FROM THE SOUTH LINE
AND 910 FT. FROM THE EAST LINE OF
SECTION 11, TOWNSHIP 23 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

DECEMBER 13, 2018

SURVEY NO. 6186B

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO

SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
VICINITY MAP



DISTANCES IN MILES

NOT TO SCALE

DIRECTIONS TO LOCATION

FROM STATE HIGHWAY 128 AND CR 798 (RED ROAD)
GO NORTH ON CR 798 APPROX. 4.0 MILES TO A ROAD
LATH WITH RED & WHITE FLAGGING ON LEFT SIDE
(WEST) OF CR 798, TURN WEST FOLLOW ROAD LATH
APPROX. 0.2 OF A MILE, TURN LEFT (SOUTH) GO 455'
TO THE SOUTHWEST PAD CORNER FOR THIS LOCATION.

DEVON ENERGY PRODUCTION COMPANY, L.P.

BELLOQ 11-2 FED STATE COM 524H

LOCATED 500 FT. FROM THE SOUTH LINE
AND 910 FT. FROM THE EAST LINE OF
SECTION 11, TOWNSHIP 23 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

DECEMBER 13, 2018

SURVEY NO. 6186B

MADRON SURVEYING, INC. 301 SOUTH CANAL

(575) 234-3341

CARLSBAD, NEW MEXICO

SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
AERIAL PHOTO



NOT TO SCALE
AERIAL PHOTO:
GOOGLE EARTH
NOV. 2017


DEVON ENERGY PRODUCTION COMPANY, L.P.
BELLOQ 11-2 FED STATE COM 524H
LOCATED 500 FT. FROM THE SOUTH LINE
AND 910 FT. FROM THE EAST LINE OF
SECTION 11, TOWNSHIP 23 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

DECEMBER 13, 2018

SURVEY NO. 6186B

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO

SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
AERIAL ACCESS ROUTE MAP




NOT TO SCALE
AERIAL PHOTO:
GOOGLE EARTH
NOV. 2017

DEVON ENERGY PRODUCTION COMPANY, L.P.
BELLOQ 11-2 FED STATE COM 524H
LOCATED 500 FT. FROM THE SOUTH LINE
AND 910 FT. FROM THE EAST LINE OF
SECTION 11, TOWNSHIP 23 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO




DECEMBER 13, 2018

SURVEY NO. 6186B

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO



CROSS SECTIONS



DEVON ENERGY PRODUCTION COMPANY, L.P.
PAD GRADING AND CROSS SECTIONS
FOR BELLOQ 11-2 FED STATE COM 524H
SECTION 11, TOWNSHIP 23 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

DECEMBER 13, 2018

012 60 120 240
SCALE 1" = 120' - 1" = 20' VER



EARTHWORK QUANTITIES		
CUT	FILL	NET
91716 CU. YD	22659 CU. YD	69058 CU. YD (CUT)

EARTHWORK QUANTITIES ARE ESTIMATED

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO

SHEET 2-3
SURVEY NO. 6186B

CROSS SECTIONS



DEVON ENERGY PRODUCTION COMPANY, L.P.
 PAD GRADING AND CROSS SECTIONS
 FOR BELLOQ 11-2 FED STATE COM 524H
 SECTION 11, TOWNSHIP 23 SOUTH,
 RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO

DECEMBER 13, 2018

012 60 120 240
 SCALE 1" = 120' - 1" = 20' VER

EARTHWORK QUANTITIES		
CUT	FILL	NET
91716 CU. YD	22659 CU. YD	69058 CU. YD (CUT)

EARTHWORK QUANTITIES ARE ESTIMATED


MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO

SHEET 3-3
 SURVEY NO. 6186B


ACCESS ROAD PLAT

ACCESS ROAD FOR BELLOQ 11-2 FED STATE COM 524H, 514H, 223H, & 234H

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 14, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
DECEMBER 13, 2018



SEE NEXT SHEET (2-4) FOR DESCRIPTION



GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SHEET: 1-4

MADRON SURVEYING, INC.

SURVEYOR CERTIFICATE

I, FILMON E. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 12TH DAY OF DECEMBER 2018

FILMON E. JARAMILLO, DES. 12797
MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SURVEY NO. 6186B

CARLSBAD, NEW MEXICO

ACCESS ROAD PLAT

ACCESS ROAD FOR BELLOQ 11-2 FED STATE COM 524H, 514H, 223H, & 234H

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 14, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
DECEMBER 13, 2018

DESCRIPTION

A STRIP OF LAND 30 FEET WIDE CROSSING BUREAU OF LAND MANAGEMENT LAND IN SECTION 14, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, STATE OF NEW MEXICO AND BEING 15 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

BEGINNING AT A POINT WITHIN THE NE/4 NE/4 OF SAID SECTION 14, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE NORTHEAST CORNER OF SAID SECTION 14, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS N54°37'54"E, A DISTANCE OF 693.03 FEET;
THENCE N00°08'43"W A DISTANCE OF 400.02 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE NORTHEAST CORNER OF SAID SECTION 14, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS N89°53'07"E, A DISTANCE OF 566.15 FEET;

SAID STRIP OF LAND BEING 400.02 FEET OR 24.24 RODS IN LENGTH, CONTAINING 0.275 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

NE/4 NE/4 400.02 L.F. 24.24 RODS 0.275 ACRES

GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SHEET: 2-4

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
(575) 234-3341

SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 12TH DAY OF DECEMBER, 2018

FILIMON F. JARAMILLO P.S. 12797


MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SURVEY NO. 6186B


ACCESS ROAD PLAT

ACCESS ROAD FOR BELLOQ 11-2 FED STATE COM 524H, 514H, 223H, & 234H

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
DECEMBER 13, 2018



SEE NEXT SHEET (4-4) FOR DESCRIPTION



GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 13 DAY OF DECEMBER 2018

FILIMON F. JARAMILLO, P.S. 12797
301 SOUTH CANAL
(575) 234-3341

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SURVEY NO. 6186B
CARLSBAD, NEW MEXICO

SHEET: 3-4

MADRON SURVEYING, INC.

ACCESS ROAD PLAT

ACCESS ROAD FOR BELLOQ 11-2 FED STATE COM 524H, 514H, 223H, & 234H

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
DECEMBER 13, 2018

DESCRIPTION

A STRIP OF LAND 30 FEET WIDE CROSSING BUREAU OF LAND MANAGEMENT LAND IN SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, STATE OF NEW MEXICO AND BEING 15 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

SOUTH ACCESS

BEGINNING AT A POINT WITHIN THE SE/4 SE/4 OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE SOUTHEAST CORNER OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS N89°53'07"E, A DISTANCE OF 566.15 FEET;
THENCE N00°08'43"W A DISTANCE OF 280.00 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE SOUTHEAST CORNER OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S63°48'18"E, A DISTANCE OF 631.74 FEET;

SAID STRIP OF LAND BEING 280.00 FEET OR 16.97 RODS IN LENGTH, CONTAINING 0.193 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

SE/4 SE/4 280.00 L.F. 16.97 RODS 0.193 ACRES

WEST ACCESS

BEGINNING AT A POINT WITHIN THE SE/4 SE/4 OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE SOUTHEAST CORNER OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S60°20'02"E, A DISTANCE OF 1308.80 FEET;
THENCE S00°06'49"E A DISTANCE OF 355.11 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;
THENCE N89°44'21"E A DISTANCE OF 25.20 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE SOUTHEAST CORNER OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S75°14'27"E, A DISTANCE OF 1149.27 FEET;

SAID STRIP OF LAND BEING 380.31 FEET OR 23.05 RODS IN LENGTH, CONTAINING 0.262 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

SE/4 SE/4 380.31 L.F. 23.05 RODS 0.262 ACRES

GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.


SHEET: 4-4

MADRON SURVEYING, INC.

SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 12TH DAY OF DECEMBER 2018




MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

FILIMON F. JARAMILLO DES 12797

SURVEY NO. 6186B

301 SOUTH CANAL
(575) 234-3341

CARLSBAD, NEW MEXICO



SCALE 1" = 200'

FROM STATE HIGHWAY 128 AND CR 798 (RED ROAD)
GO NORTH ON CR 798 APPROX. 4.0 MILES TO A ROAD
LATH WITH RED & WHITE FLAGGING ON LEFT SIDE
(WEST) OF CR 798, TURN WEST FOLLOW ROAD LATH
APPROX. 0.2 OF A MILE, TURN LEFT (SOUTH) GO 455'
TO THE SOUTHWEST PAD CORNER FOR THIS LOCATION.

DECEMBER 13, 2018


SURVEY NO. 6186B

MADRON SURVEYING, INC.

301 SOUTH CANAL
(575) 234-3341

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
(575) 234-3341

SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
INTERIM SITE RECLAMATION



0 20 100 200 400
SCALE 1" = 200'

1.995± ACRES INTERIM PAD RECLAMATION AREA
8.971± ACRES GRADING SITE RECLAMATION AREA
3.499± ACRES NON-RECLAIMED AREA
14.465± ACRES BELLOQ & GALAPAGOS WELL PAD


DEVON ENERGY PRODUCTION COMPANY, L.P.
BELLOQ 11-2 FED STATE COM 524H
LOCATED 500 FT. FROM THE SOUTH LINE
AND 910 FT. FROM THE EAST LINE OF
SECTION 11, TOWNSHIP 23 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

DECEMBER 13, 2018

SURVEY NO. 6186B

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO

SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
LOCATION VERIFICATION MAP



USGS QUAD MAP:
LOS MEDANOS
BOOTLEG RIDGE

NOT TO SCALE


DEVON ENERGY PRODUCTION COMPANY, L.P.
BELLOQ 11-2 FED STATE COM 524H
LOCATED 500 FT. FROM THE SOUTH LINE
AND 910 FT. FROM THE EAST LINE OF
SECTION 11, TOWNSHIP 23 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

DECEMBER 13, 2018

SURVEY NO. 6186B

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO

SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
VICINITY MAP



DISTANCES IN MILES

NOT TO SCALE

DIRECTIONS TO LOCATION

FROM STATE HIGHWAY 128 AND CR 798 (RED ROAD)
GO NORTH ON CR 798 APPROX. 4.0 MILES TO A ROAD
LATH WITH RED & WHITE FLAGGING ON LEFT SIDE
(WEST) OF CR 798, TURN WEST FOLLOW ROAD LATH
APPROX. 0.2 OF A MILE, TURN LEFT (SOUTH) GO 455'
TO THE SOUTHWEST PAD CORNER FOR THIS LOCATION.

DEVON ENERGY PRODUCTION COMPANY, L.P.

BELLOQ 11-2 FED STATE COM 524H

LOCATED 500 FT. FROM THE SOUTH LINE
AND 910 FT. FROM THE EAST LINE OF
SECTION 11, TOWNSHIP 23 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

DECEMBER 13, 2018


SURVEY NO. 6186B

MADRON SURVEYING, INC. 301 SOUTH CANAL

(575) 234-3341

CARLSBAD, NEW MEXICO

SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
AERIAL PHOTO



NOT TO SCALE
AERIAL PHOTO:
GOOGLE EARTH
NOV. 2017

DEVON ENERGY PRODUCTION COMPANY, L.P.
BELLOQ 11-2 FED STATE COM 524H
LOCATED 500 FT. FROM THE SOUTH LINE
AND 910 FT. FROM THE EAST LINE OF
SECTION 11, TOWNSHIP 23 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

DECEMBER 13, 2018

SURVEY NO. 6186B

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO

SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
AERIAL ACCESS ROUTE MAP



NOT TO SCALE
AERIAL PHOTO:
GOOGLE EARTH
NOV. 2017


DEVON ENERGY PRODUCTION COMPANY, L.P.
BELLOQ 11-2 FED STATE COM 524H
LOCATED 500 FT. FROM THE SOUTH LINE
AND 910 FT. FROM THE EAST LINE OF
SECTION 11, TOWNSHIP 23 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

DECEMBER 13, 2018

SURVEY NO. 6186B

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO

PLAN VIEW



DEVON ENERGY PRODUCTION COMPANY, L.P.
PAD GRADING AND CROSS SECTIONS
FOR BELLOQ 11-2 FED STATE COM 524H
SECTION 11, TOWNSHIP 23 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

DECEMBER 13, 2018

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO


EARTHWORK QUANTITIES

CUT	FILL	NET
91716 CU. YD	22659 CU. YD	69058 CU. YD (CUT)

EARTHWORK QUANTITIES ARE ESTIMATED

SHEET 1-3
SURVEY NO. 6186B

CROSS SECTIONS



DEVON ENERGY PRODUCTION COMPANY, L.P.
 PAD GRADING AND CROSS SECTIONS
 FOR BELLOQ 11-2 FED STATE COM 524H
 SECTION 11, TOWNSHIP 23 SOUTH,
 RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO

DECEMBER 13, 2018

012 60 120 240
 SCALE 1" = 120' - 1" = 20' VER



EARTHWORK QUANTITIES		
CUT	FILL	NET
91716 CU. YD	22659 CU. YD	69058 CU. YD (CUT)

EARTHWORK QUANTITIES ARE ESTIMATED

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO

SHEET 2-3
 SURVEY NO. 6186B

CROSS SECTIONS



DEVON ENERGY PRODUCTION COMPANY, L.P.
 PAD GRADING AND CROSS SECTIONS
 FOR BELLOQ 11-2 FED STATE COM 524H
 SECTION 11, TOWNSHIP 23 SOUTH,
 RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO

DECEMBER 13, 2018

012 60 120 240
 SCALE 1" = 120' - 1" = 20' VER

EARTHWORK QUANTITIES		
CUT	FILL	NET
91716 CU. YD	22659 CU. YD	69058 CU. YD (CUT)

EARTHWORK QUANTITIES ARE ESTIMATED


MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO

SHEET 3-3
 SURVEY NO. 6186B


ACCESS ROAD PLAT

ACCESS ROAD FOR BELLOQ 11-2 FED STATE COM 524H, 514H, 223H, & 234H

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 14, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
DECEMBER 13, 2018



SEE NEXT SHEET (2-4) FOR DESCRIPTION



GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SHEET: 1-4

MADRON SURVEYING, INC.

SURVEYOR CERTIFICATE

I, FILMON E. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 12TH DAY OF DECEMBER 2018

FILMON E. JARAMILLO, P.E.S. 12797

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SURVEY NO. 6186B

CARLSBAD, NEW MEXICO

ACCESS ROAD PLAT

ACCESS ROAD FOR BELLOQ 11-2 FED STATE COM 524H, 514H, 223H, & 234H

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 14, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
DECEMBER 13, 2018

DESCRIPTION

A STRIP OF LAND 30 FEET WIDE CROSSING BUREAU OF LAND MANAGEMENT LAND IN SECTION 14, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, STATE OF NEW MEXICO AND BEING 15 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

BEGINNING AT A POINT WITHIN THE NE/4 NE/4 OF SAID SECTION 14, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE NORTHEAST CORNER OF SAID SECTION 14, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS N54°37'54"E, A DISTANCE OF 693.03 FEET;

THENCE N00°08'43"W A DISTANCE OF 400.02 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE NORTHEAST CORNER OF SAID SECTION 14, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS N89°53'07"E, A DISTANCE OF 566.15 FEET;

SAID STRIP OF LAND BEING 400.02 FEET OR 24.24 RODS IN LENGTH, CONTAINING 0.275 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

NE/4 NE/4 400.02 L.F. 24.24 RODS 0.275 ACRES

SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 12TH DAY OF DECEMBER, 2018

FILIMON F. JARAMILLO P.S. 12797

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

GENERAL NOTES

1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.

2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SHEET: 2-4


MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
(575) 234-3341

SURVEY NO. 6186B


ACCESS ROAD PLAT

ACCESS ROAD FOR BELLOQ 11-2 FED STATE COM 524H, 514H, 223H, & 234H

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
DECEMBER 13, 2018



SEE NEXT SHEET (4-4) FOR DESCRIPTION



GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SURVEYOR CERTIFICATE

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 13 DAY OF DECEMBER 2018

FILMON F. JARAMILLO, P.S. 12797
301 SOUTH CANAL
(575) 234-3341

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SURVEY NO. 6186B

MADRON SURVEYING, INC. CARLSBAD, NEW MEXICO

SHEET: 3-4

ACCESS ROAD PLAT

ACCESS ROAD FOR BELLOQ 11-2 FED STATE COM 524H, 514H, 223H, & 234H

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
DECEMBER 13, 2018

DESCRIPTION

A STRIP OF LAND 30 FEET WIDE CROSSING BUREAU OF LAND MANAGEMENT LAND IN SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, STATE OF NEW MEXICO AND BEING 15 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

SOUTH ACCESS

BEGINNING AT A POINT WITHIN THE SE/4 SE/4 OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE SOUTHEAST CORNER OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS N89°53'07"E, A DISTANCE OF 566.15 FEET;
THENCE N00°08'43"W A DISTANCE OF 280.00 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE SOUTHEAST CORNER OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S63°48'18"E, A DISTANCE OF 631.74 FEET;

SAID STRIP OF LAND BEING 280.00 FEET OR 16.97 RODS IN LENGTH, CONTAINING 0.193 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

SE/4 SE/4 280.00 L.F. 16.97 RODS 0.193 ACRES

WEST ACCESS

BEGINNING AT A POINT WITHIN THE SE/4 SE/4 OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE SOUTHEAST CORNER OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S60°20'02"E, A DISTANCE OF 1308.80 FEET;
THENCE S00°06'49"E A DISTANCE OF 355.11 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;
THENCE N89°44'21"E A DISTANCE OF 25.20 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE SOUTHEAST CORNER OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S75°14'27"E, A DISTANCE OF 1149.27 FEET;

SAID STRIP OF LAND BEING 380.31 FEET OR 23.05 RODS IN LENGTH, CONTAINING 0.262 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

SE/4 SE/4 380.31 L.F. 23.05 RODS 0.262 ACRES

GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SHEET: 4-4

MADRON SURVEYING, INC. CARLSBAD, NEW MEXICO

SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 13TH DAY OF DECEMBER 2018

NEW MEXICO, 12797

REGISTERED PROFESSIONAL SURVEYOR

FILIMON F. JARAMILLO DLS 12797

301 SOUTH CANAL
(575) 234-3341

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SURVEY NO. 6186B



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Drilling Plan Data Report

10/20/2019

APD ID: 10400038622

Submission Date: 01/31/2019

Highlighted data
reflects the most
recent changes

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11-2 FED STATE COM

Well Number: 524H

[Show Final Text](#)

Well Type: OIL WELL

Well Work Type: Drill

Section 1 - Geologic Formations

Formation ID	Formation Name	Elevation	True Vertical Depth	Measured Depth	Lithologies	Mineral Resources	Producing Formation
1	UNKNOWN	3488	0	0	ALLUVIUM	NONE	N
2	RUSTLER	2749	739	739	SALT	NONE	N
3	BASE OF SALT	-982	4470	4470	SALT	NONE	N
4	DELAWARE	-1019	4507	4507	SANDSTONE	NATURAL GAS,OIL	N
5	BONE SPRING 1ST	-5974	9462	9462	SANDSTONE	NATURAL GAS,OIL	N
6	BONE SPRING 2ND	-6379	9867	9867	SANDSTONE	NATURAL GAS,OIL	Y

Section 2 - Blowout Prevention

Pressure Rating (PSI): 5M

Rating Depth: 6000

Equipment: BOP/BOPE will be installed per Onshore Oil & Gas Order #2 requirements prior to drilling below surface casing, a BOP/BOPE system with the minimum rating listed above will be installed on the wellhead system. BOP/BOPE will be tested by an independent service company per Onshore Oil & Gas Order #2 requirements and MASP (Maximum Anticipated Surface Pressure) calculations. If the system is upgraded, all the components installed will be functional and tested.

Requesting Variance? YES

Variance request: A variance is requested for the use of a flexible choke line from the BOP stack to the choke manifold. See attached for specs for hydrostatic test chart.

Testing Procedure: A multibowl wellhead may be used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested.

Choke Diagram Attachment:

5M_BOPE__CK_20190130083214.pdf

BOP Diagram Attachment:

5M_BOPE__CK_20190130083227.pdf

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11-2 FED STATE COM

Well Number: 524H

Pressure Rating (PSI): 5M

Rating Depth: 9104

Equipment: BOP/BOPE will be installed per Onshore Oil & Gas Order #2 requirements prior to drilling below surface casing, a BOP/BOPE system with the minimum rating listed above will be installed on the wellhead system. BOP/BOPE will be tested by an independent service company per Onshore Oil & Gas Order #2 requirements and MASP (Maximum Anticipated Surface Pressure) calculations. If the system is upgraded, all the components installed will be functional and tested.

Requesting Variance? YES

Variance request: A variance is requested for the use of a flexible choke line from the BOP stack to the choke manifold. See attached for specs for hydrostatic test chart.

Testing Procedure: A multibowl wellhead may be used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested.

Choke Diagram Attachment:

5M_BOPE__CK_20190130083236.pdf

BOP Diagram Attachment:

5M_BOPE__CK_20190130083243.pdf

Section 3 - Casing

Casing ID	String Type	Hole Size	Csg Size	Condition	Standard	Tapered String	Top Set MD	Bottom Set MD	Top Set TVD	Bottom Set TVD	Top Set MSL	Bottom Set MSL	Calculated casing length MD	Grade	Weight	Joint Type	Collapse SF	Burst SF	Joint SF Type	Joint SF	Body SF Type	Body SF
1	SURFACE	17.5	13.375	NEW	API	N	0	764	0	764	-6961	-7725	764	H-40	48	ST&C	1.125	1	BUOY	1.6	BUOY	1.6
2	INTERMEDIATE	12.25	9.625	NEW	API	N	0	6000	0	6000	-6961	-11211	6000	J-55	40	OTHER - BTC	1.125	1	BUOY	1.6	BUOY	1.6
3	PRODUCTION	8.75	5.5	NEW	API	N	0	19356	0	9104	-6961	-16961	19356	P-110	17	OTHER - BTC	1.125	1	BUOY	1.6	BUOY	1.6

Casing Attachments

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11-2 FED STATE COM

Well Number: 524H

Casing Attachments

Casing ID: 1 **String Type:** SURFACE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Surf_Csg_Ass_20190130083450.pdf

Casing ID: 2 **String Type:** INTERMEDIATE

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Int_Csg_Ass_20190130083503.pdf

Casing ID: 3 **String Type:** PRODUCTION

Inspection Document:

Spec Document:

Tapered String Spec:

Casing Design Assumptions and Worksheet(s):

Prod_Csg_Ass_20190130083515.pdf

Section 4 - Cement

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11-2 FED STATE COM

Well Number: 524H

String Type	Lead/Tail	Stage Tool Depth	Top MD	Bottom MD	Quantity(sx)	Yield	Density	Cu Ft	Excess%	Cement type	Additives
SURFACE	Lead		0	764	798	1.33	13.2	1061	100	C	Class C + adds

INTERMEDIATE	Lead		0	5500	1115	1.94	9	2164	50	C	Class C + adds
INTERMEDIATE	Tail		5500	6000	196	1.33	13.2	261	50	C	Class C + adds
PRODUCTION	Lead		5500	8518	740.2	3.27	9	2420.6	10	TUNED	Class C + adds
PRODUCTION	Tail		8533	19356	2264.2	1.33	13.2	3011.4	10	H	(50:50) Clas H Cement: Poz (Fly Ash) + 0.5% bwoc HALAD-344 + 0.4% bwoc CFR-3 + 0.2% BWOC HR-601 + 2% bwoc Bentonite

Section 5 - Circulating Medium

Mud System Type: Closed

Will an air or gas system be Used? NO

Description of the equipment for the circulating system in accordance with Onshore Order #2:

Diagram of the equipment for the circulating system in accordance with Onshore Order #2:

Describe what will be on location to control well or mitigate other conditions: Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

Describe the mud monitoring system utilized: PVT/Pason/Visual Monitoring

Circulating Medium Table

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
0	9105	OTHER : FRESH WATER	8.5	9				2			

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11-2 FED STATE COM

Well Number: 524H

Top Depth	Bottom Depth	Mud Type	Min Weight (lbs/gal)	Max Weight (lbs/gal)	Density (lbs/cu ft)	Gel Strength (lbs/100 sqft)	PH	Viscosity (CP)	Salinity (ppm)	Filtration (cc)	Additional Characteristics
764	9105	OTHER : BRINE	10	10.5				2			
6000	9105	WATER-BASED MUD	8.5	9							

Section 6 - Test, Logging, Coring

List of production tests including testing procedures, equipment and safety measures:

Will run GRMWD from TD to from KOP. Cement bond logs will be run in vertical to determine top of cement. Stated logs run will be in the completion report and submitted to the BLM.

List of open and cased hole logs run in the well:

CALIPER,CBL,DS,GR,MUDLOG

Coring operation description for the well:

N/A

Section 7 - Pressure

Anticipated Bottom Hole Pressure: 4261

Anticipated Surface Pressure: 2257.9

Anticipated Bottom Hole Temperature(F): 146

Anticipated abnormal pressures, temperatures, or potential geologic hazards? NO

Describe:

Contingency Plans geohazards description:

Contingency Plans geohazards attachment:

Hydrogen Sulfide drilling operations plan required? YES

Hydrogen sulfide drilling operations plan:

Belloq_11_2_Fed_State_Com_524H_H2S_20190130091507.pdf

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11-2 FED STATE COM

Well Number: 524H

Section 8 - Other Information

Proposed horizontal/directional/multi-lateral plan submission:

Devon___Belloq_11_2_Fed_State_Com_524H___p2_20190130091545.pdf

Belloq_11_2_Fed_State_Com_524H_APD_20190708074132.pdf

Other proposed operations facets description:

Multi-Bowl Verbiage

Multi-Bowl Wellhead

Closed-Loop Design Plan

Gas Capture Plan-BELLOQ 11 CTB 2

Drill Plan-SPEC SHEETS, drilling plan revised for prod cmt 7/8/2019

Other proposed operations facets attachment:

Clsd_Loop_20190130075305.pdf

Spudder_Rig_Info_20190130075304.pdf

9.625_40___J_55_SPEC_20190130075234.pdf

MB_Wellhd_5M_20190130075306.pdf

13.375_48___H40_SPEC_20190130075152.pdf

MB_Verb_5M_20190130075306.pdf


5_500in_17_00___P110RY_DWC_C_SPEC_20190130075235.pdf

BELLOQ_11_CTB_2_GasCapturePlan_20190130075320.pdf


Other Variance attachment:

Co_flex_20190130084111.pdf


13-5/8" 5M BOPE & Closed Loop Equipment Schematic




13-5/8" 5M BOPE & Closed Loop Equipment Schematic



13-5/8" 5M BOPE & Closed Loop Equipment Schematic



13-5/8" 5M BOPE & Closed Loop Equipment Schematic



Casing Assumptions and Load Cases

Surface

All casing design assumptions were ran in Stress Check to determine safety factor which meet or exceed both Devon Energy and BLM minimum requirements. All casing strings will be filled while running in hole in order to not exceed collapse rating of the pipe.

Surface Casing Burst Design		
Load Case	External Pressure	Internal Pressure
Pressure Test	Formation Pore Pressure	Max mud weight of next hole-section plus Test psi
Drill Ahead	Formation Pore Pressure	Max mud weight of next hole section
Displace to Gas	Formation Pore Pressure	Dry gas from next casing point

Surface Casing Collapse Design		
Load Case	External Pressure	Internal Pressure
Full Evacuation	Water gradient in cement, mud above TOC	None
Cementing	Wet cement weight	Water (8.33ppg)

Surface Casing Tension Design	
Load Case	Assumptions
Overpull	100kips
Runing in hole	3 ft/s
Service Loads	N/A

Casing Assumptions and Load Cases

Intermediate

All casing design assumptions were ran in Stress Check to determine safety factor which meet or exceed both Devon Energy and BLM minimum requirements. All casing strings will be filled while running in hole in order to not exceed collapse rating of the pipe.

Intermediate Casing Burst Design		
Load Case	External Pressure	Internal Pressure
Pressure Test	Formation Pore Pressure	Max mud weight of next hole-section plus Test psi
Drill Ahead	Formation Pore Pressure	Max mud weight of next hole section
Fracture @ Shoe	Formation Pore Pressure	Dry gas

Intermediate Casing Collapse Design		
Load Case	External Pressure	Internal Pressure
Full Evacuation	Water gradient in cement, mud above TOC	None
Cementing	Wet cement weight	Water (8.33ppg)

Intermediate Casing Tension Design	
Load Case	Assumptions
Overpull	100kips
Runing in hole	2 ft/s
Service Loads	N/A

Casing Assumptions and Load Cases

Production

All casing design assumptions were ran in Stress Check to determine safety factor which meet or exceed both Devon Energy and BLM minimum requirements. All casing strings will be filled while running in hole in order to not exceed collapse rating of the pipe.

Production Casing Burst Design		
Load Case	External Pressure	Internal Pressure
Pressure Test	Formation Pore Pressure	Fluid in hole (water or produced water) + test psi
Tubing Leak	Formation Pore Pressure	Packer @ KOP, leak below surface 8.6 ppg packer fluid
Stimulation	Formation Pore Pressure	Max frac pressure with heaviest frac fluid

Production Casing Collapse Design		
Load Case	External Pressure	Internal Pressure
Full Evacuation	Water gradient in cement, mud above TOC.	None
Cementing	Wet cement weight	Water (8.33ppg)

Production Casing Tension Design	
Load Case	Assumptions
Overpull	100kips
Runing in hole	2 ft/s
Service Loads	N/A



**Devon Energy Center
333 West Sheridan Avenue
Oklahoma City, Oklahoma 73102-5015**

Hydrogen Sulfide (H₂S) Contingency Plan

For



Belloq 11-2 Fed State Com 524H

**Sec-11 T-23S R-31E
500' FSL & 910' FEL
LAT. = 32.3130828' N (NAD83)
LONG = 103.7429714' W**

Eddy County NM

Belloq 11-2 Fed State Com 524H

This is an open drilling site. H₂S monitoring equipment and emergency response equipment will be used within 500' of zones known to contain H₂S, including warning signs, wind indicators and H₂S monitor.



Assumed 100 ppm ROE = 3000' (Radius of Exposure)
100 ppm H₂S concentration shall trigger activation of this plan.

Escape

Crews shall escape upwind of escaping gas in the event of an emergency release of gas. Escape can be facilitated from the location entrance road. Crews should then block the entrance to the location from the lease road so as not to allow anyone traversing into a hazardous area. The blockade should be at a safe distance outside of the ROE. There are no homes or buildings in or near the ROE.

Assumed 100 ppm ROE = 3000'

100 ppm H₂S concentration shall trigger activation of this plan.

Emergency Procedures

In the event of a release of gas containing H₂S, the first responder(s) must

- **Isolate the area and prevent entry by other persons into the 100 ppm ROE.**
- **Evacuate any public places encompassed by the 100 ppm ROE.**
- **Be equipped with H₂S monitors and air packs in order to control the release.**
- **Use the “buddy system” to ensure no injuries occur during the response**
- **Take precautions to avoid personal injury during this operation.**
- **Contact operator and/or local officials to aid in operation. See list of phone numbers attached.**
- **Have received training in the**
 - **Detection of H₂S, and**
 - **Measures for protection against the gas,**
 - **Equipment used for protection and emergency response.**

Ignition of Gas Source

Should control of the well be considered lost and ignition considered, take care to protect against exposure to Sulfur Dioxide (SO₂). Intentional ignition must be coordinated with the NMOCD and local officials. Additionally the NM State Police may become involved. NM State Police shall be the Incident Command on scene of any major release. Take care to protect downwind whenever there is an ignition of the gas

Characteristics of H₂S and SO₂

Common Name	Chemical Formula	Specific Gravity	Threshold Limit	Hazardous Limit	Lethal Concentration
Hydrogen Sulfide	H₂S	1.189 Air = 1	10 ppm	100 ppm/hr	600 ppm
Sulfur Dioxide	SO₂	2.21 Air = 1	2 ppm	N/A	1000 ppm

Contacting Authorities

Devon Energy Corp. personnel must liaison with local and state agencies to ensure a proper response to a major release. Additionally, the OCD must be notified of the release as soon as possible but no later than 4 hours. Agencies will ask for information such as type and volume of release, wind direction, location of release, etc. Be prepared with all information available. The following call list of essential and potential responders has been prepared for use during a release. Devon Energy Corp. Company response must be in coordination with the State of New Mexico's 'Hazardous Materials Emergency Response Plan' (HMER)

Hydrogen Sulfide Drilling Operation Plan

I. HYDROGEN SULFIDE (H₂S) TRAINING

All personnel, whether regularly assigned, contracted, or employed on an unscheduled basis, will receive training from a qualified instructor in the following areas prior to commencing drilling operations on this well:

1. The hazards and characteristics of hydrogen sulfide (H₂S)
2. The proper use and maintenance of personal protective equipment and life support systems.
3. The proper use of H₂S detectors, alarms, warning systems, briefing areas, evacuation procedures, and prevailing winds.
4. The proper techniques for first aid and rescue procedures.

In addition, supervisory personnel will be trained in the following areas:

1. The effects of H₂S metal components. If high tensile tubulars are to be used, personnel will be trained in their special maintenance requirements.
2. Corrective action and shut-in procedures when drilling or reworking a well and blowout prevention and well control procedures.
3. The contents and requirements of the H₂S Drilling Operations Plan and Public Protection Plan.

There will be an initial training session just prior to encountering a known or probable H₂S zone (within 3 days or 500 feet) and weekly H₂S and well control drills for all personnel in each crew. The initial training session shall include a review of the site specific H₂S Drilling Operations Plan and the Public Protection Plan.

II. HYDROGEN SULFIDE TRAINING

Note: All H₂S safety equipment and systems will be installed, tested, and operational when drilling reaches a depth of 500 feet above, or three days prior to penetrating the first zone containing or reasonably expected to contain H₂S.

1. Well Control Equipment

- A. Flare line
- B. Choke manifold – Remotely Operated
- C. Blind rams and pipe rams to accommodate all pipe sizes with properly sized closing unit
- D. Auxiliary equipment may include if applicable: annular preventer and rotating head.
- E. Mud/Gas Separator

2. Protective equipment for essential personnel:

30-minute SCBA units located at briefing areas, as indicated on well site diagram, with escape units available in the top doghouse. As it may be difficult to communicate audibly while wearing these units, hand signals shall be utilized.

3. H₂S detection and monitoring equipment:

Portable H₂S monitors positioned on location for best coverage and response. These units have warning lights which activate when H₂S levels reach 10 ppm and audible sirens which activate at 15 ppm. Sensor locations:

- Bell nipple
- Possum Belly/Shale shaker
- Rig floor
- Choke manifold
- Cellar

Visual warning systems:

- A. Wind direction indicators as shown on well site diagram
- B. Caution/ Danger signs shall be posted on roads providing direct access to locations. Signs will be painted a high visibility yellow with black lettering of sufficient size to be reasonable distance from the immediate location. Bilingual signs will be used when appropriate.

4. Mud program:

The mud program has been designed to minimize the volume of H₂S circulated to surface. Proper mud weight, safe drilling practices and the use of H₂S scavengers will minimize hazards when penetrating H₂S bearing zones.

5. Metallurgy:

- A. All drill strings, casings, tubing, wellhead, blowout preventer, drilling spool, kill lines, choke manifold lines, and valves shall be H₂S trim.
- B. All elastomers used for packing and seals shall be H₂S trim.

6. Communication:

- A. Company personnel have/use cellular telephones in the field.
- B. Land line (telephone) communications at Office

7. Well testing:

- A. Drill stem testing will be performed with a minimum number of personnel in the immediate vicinity, which are necessary to safety and adequately conduct the test. The drill stem testing will be conducted during daylight hours and formation fluids will not be flowed to the surface. All drill-stem-testing operations conducted in an H₂S environment will use the closed chamber method of testing.
- B. There will be no drill stem testing.

<u>Devon Energy Corp. Company Call List</u>		
Drilling Supervisor – Basin – Mark Kramer		405-823-4796
EHS Professional – Laura Wright		405-439-8129
<u>Agency Call List</u>		
<u>Lea County (575)</u>	Hobbs	
	Lea County Communication Authority	393-3981
	State Police	392-5588
	City Police	397-9265
	Sheriff's Office	393-2515
	Ambulance	911
	Fire Department	397-9308
	LEPC (Local Emergency Planning Committee)	393-2870
	NMOCD	393-6161
	US Bureau of Land Management	393-3612
<u>Eddy County (575)</u>	Carlsbad	
	State Police	885-3137
	City Police	885-2111
	Sheriff's Office	887-7551
	Ambulance	911
	Fire Department	885-3125
	LEPC (Local Emergency Planning Committee)	887-3798
	US Bureau of Land Management	887-6544
	NM Emergency Response Commission (Santa Fe)	(505) 476-9600
	24 HR	(505) 827-9126
	National Emergency Response Center	(800) 424-8802
	National Pollution Control Center: Direct	(703) 872-6000
	For Oil Spills	(800) 280-7118
	Emergency Services	
	Wild Well Control	(281) 784-4700
	Cudd Pressure Control	(915) 699-0139 (915) 563-3356
	Halliburton	(575) 746-2757
	B. J. Services	(575) 746-3569
	Native Air – Emergency Helicopter – Hobbs	(575) 392-6429
	Flight For Life - Lubbock, TX	(806) 743-9911
<u>Give GPS position:</u>	Aerocare - Lubbock, TX	(806) 747-8923
	Med Flight Air Amb - Albuquerque, NM	(575) 842-4433
	Lifeguard Air Med Svc. Albuquerque, NM	(800) 222-1222
	Poison Control (24/7)	(575) 272-3115
	Oil & Gas Pipeline 24 Hour Service	(800) 364-4366
	NOAA – Website - www.nhc.noaa.gov	

Prepared in conjunction with
Dave Small



Devon Energy

Project: Eddy County, NM (NAD-83)
 Site: Belloq 11-2 Fed State Com
 Well: Belloq 11-2 Fed State Com 524H
 Wellbore: OH
 Design: Plan #2



Azimuths to Grid North
 True North: -0.32°
 Magnetic North: 6.53°
 Magnetic Field
 Strength: 48019.5snT
 Dip Angle: 60.05°
 Date: 1/21/2019
 Model: HDGM



SECTION DETAILS




MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	Vsect
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
2500.00	0.00	0.00	2500.00	0.00	0.00	0.00	0.00	0.00
3034.26	5.34	195.76	3033.49	-23.96	-6.76	1.00	195.76	-23.91
7521.31	5.34	195.76	7501.04	-426.04	-120.24	0.00	0.00	-425.26
8055.57	0.00	0.00	8034.53	-450.00	-127.00	1.00	180.00	-449.17
8533.08	0.00	0.00	8512.04	-450.00	-127.00	0.00	0.00	-449.17
9431.94	89.89	359.63	9085.00	121.81	-130.65	10.00	359.63	122.65
14810.26	89.89	359.63	9095.70	5500.00	-165.00	0.00	0.00	5500.95
15191.96	89.89	352.00	9096.45	5880.40	-192.82	2.00	-89.98	5881.53
15491.96	89.89	352.00	9097.02	6177.48	-234.57	0.00	0.00	6178.87
15892.21	89.88	0.00	9097.83	6576.43	-262.45	2.00	90.08	6577.99
16392.21	89.88	0.00	9098.88	7076.43	-262.41	0.00	0.00	7077.98
16791.96	89.88	8.00	9099.71	7474.88	-234.53	2.00	90.01	7476.24
16970.96	89.88	8.00	9100.09	7652.14	-209.62	0.00	0.00	7653.33
17389.43	89.88	359.63	9100.96	8069.31	-181.80	2.00	-89.99	8070.32
19356.15	89.88	359.63	9105.00	10035.99	-194.48	0.00	0.00	10037.04

PROJECT DETAILS: Eddy County, NM (NAD-83)

Geodetic System: US State Plane 1983
 Datum: North American Datum 1983
 Ellipsoid: GRS 1980
 Zone: New Mexico Eastern Zone
 Datum: 3488.9' GE + 23.5 @ 3512.40usft

DESIGN TARGET DETAILS

Name	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
FTP (Belloq 524H)	8746.13	-400.00	-127.32	477734.17	723592.15	32° 18' 43.1471 N	103° 44' 36.2062 W
KOP (Belloq 524H)	8512.04	-450.00	-127.00	477684.17	723592.47	32° 18' 42.6523 N	103° 44' 36.2057 W
LTP (Belloq 524H)	9104.83	9953.99	-193.95	488088.16	723525.52	32° 20' 25.6073 N	103° 44' 36.3183 W
PBHL (Belloq 524H)	9105.00	10035.99	-194.48	488170.16	723524.99	32° 20' 26.4188 N	103° 44' 36.3192 W
SHL (Belloq 524H)	0.00	0.00	0.00	478134.17	723719.47	32° 18' 47.0983 N	103° 44' 34.6969 W



LEAM DRILLING SERVICES
 2010 East Davis, Conroe, Texas 77301
 Phone: 936/756-7618, Fax: 936/756-7595

Plan: Plan #2 (Belloq 11-2 Fed State Com 524H/OH)
 Belloq 11-2 Fed State Com
 Created By: Dustin Ault
 Date: 12/24, January 23 2019
 Approved: _____
 Date: _____

Project: Eddy County, NM (NAD-83)
Site: Belloq 11-2 Fed State Com
Well: Belloq 11-2 Fed State Com 524H
Wellbore: OH
Design: Plan #2



Azimuths to Grid North
True North: -0.32°
Magnetic North: 6.53°

**Magnetic Field
Strength: 48019.5nT
Dip Angle: 60.05°
Date: 1/21/2019
Model: HDGM**





PROJECT DETAILS: Eddy County, NM (NAD-83)
Geodetic System: US State Plane 1983
Datum: North American Datum 1983
Ellipsoid: GRS 1980
Zone: New Mexico Eastern Zone

DESIGN TARGET DETAILS

Name	TVD	+N/-S	+E/-W	Northing	Easting	Latitude	Longitude
FTP (Belloq 524H)	8746.13	-400.00	-127.32	477734.17	723592.15	32° 18' 43.1471 N	103° 44' 36.2062 W
KOP (Belloq 524H)	8512.04	-450.00	-127.00	477684.17	723592.47	32° 18' 42.6523 N	103° 44' 36.2057 W
LTP (Belloq 524H)	9104.83	9953.99	-193.95	488088.16	723525.52	32° 20' 25.6073 N	103° 44' 36.3183 W
PBHL (Belloq 524H)	9105.00	10035.99	-194.48	488170.16	723524.99	32° 20' 26.4188 N	103° 44' 36.3192 W
SHL (Belloq 524H)	0.00	0.00	0.00	478134.17	723719.47	32° 18' 47.0983 N	103° 44' 34.6969 W

SECTION DETAILS

MD	Inc	Azi	TVD	+N/-S	+E/-W	Dleg	TFace	V Sect	Annotation
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
2500.00	0.00	0.00	2500.00	0.00	0.00	0.00	0.00	0.00	
3034.26	5.34	195.76	3033.49	-23.96	-6.76	1.00	195.76	-23.91	
7521.31	5.34	195.76	7501.04	-426.04	-120.24	0.00	0.00	-425.26	
8055.57	0.00	0.00	8034.53	-450.00	-127.00	1.00	180.00	-449.17	
8533.08	0.00	0.00	8512.04	-450.00	-127.00	0.00	0.00	-449.17	
9431.94	89.89	359.63	9085.00	121.81	-130.65	10.00	359.63	122.65	
14810.26	89.89	359.63	9095.70	5500.00	-165.00	0.00	0.00	5500.95	
15191.96	89.89	352.00	9096.45	5880.40	-192.82	2.00	-89.98	5881.53	
15491.96	89.89	352.00	9097.02	6177.48	-234.57	0.00	0.00	6178.87	
15892.21	89.88	0.00	9097.83	6576.43	-262.45	2.00	90.08	6577.99	
16392.21	89.88	0.00	9098.88	7076.43	-262.41	0.00	0.00	7077.98	
16791.96	89.88	8.00	9099.71	7474.88	-234.53	2.00	90.01	7476.24	
16970.96	89.88	8.00	9100.09	7652.14	-209.62	0.00	0.00	7653.33	
17389.43	89.88	359.63	9100.96	8069.31	-181.80	2.00	-89.99	8070.32	
19356.15	89.88	359.63	9105.00	10035.99	-194.48	0.00	0.00	10037.04	



LEAM DRILLING SYSTEMS LLC
2010 East Davis, Conroe, Texas 77301
Phone: 936/756-7577, Fax: 936/756-7595

Plan: Plan #2 (Belloq 11-2 Fed State Com 524H/OH)
Belloq 11-2 Fed State Com
Created By: Dustin Ault Date: 12:25, January 23 2019
Date: _____
Approved: _____ Date: _____

Devon Energy

Eddy County, NM (NAD-83)

Belloq 11-2 Fed State Com

Belloq 11-2 Fed State Com 524H

OH

Plan: Plan #2

Standard Planning Report - Geographic

23 January, 2019

LEAM Drilling Services

Planning Report - Geographic

Database:	EDM 5000.1 Multi User Db	Local Co-ordinate Reference:	Well Belloq 11-2 Fed State Com 524H
Company:	Devon Energy	TVD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Project:	Eddy County, NM (NAD-83)	MD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Site:	Belloq 11-2 Fed State Com	North Reference:	Grid
Well:	Belloq 11-2 Fed State Com 524H	Survey Calculation Method:	Minimum Curvature
Wellbore:	OH		
Design:	Plan #2		

Project	Eddy County, NM (NAD-83)		
Map System:	US State Plane 1983	System Datum:	Mean Sea Level
Geo Datum:	North American Datum 1983		
Map Zone:	New Mexico Eastern Zone		

Site	Belloq 11-2 Fed State Com		
Site Position:	Map	Northing:	477,925.73 usft
From:		Easting:	720,008.09 usft
Position Uncertainty:	0.00 usft	Slot Radius:	13-3/16 "
		Latitude:	32° 18' 45.2359 N
		Longitude:	103° 45' 17.9570 W
		Grid Convergence:	0.31 °

Well	Belloq 11-2 Fed State Com 524H		
Well Position	+N/-S	0.00 usft	Northing:
	+E/-W	0.00 usft	Easting:
Position Uncertainty	0.00 usft	Wellhead Elevation:	0.00 usft
		Latitude:	32° 18' 47.0983 N
		Longitude:	103° 44' 34.6969 W
		Ground Level:	3,488.90 usft

Wellbore	OH		
Magnetics	Model Name	Sample Date	Declination
			(°)
	HDGM	1/21/2019	6.85
			Dip Angle
			(°)
			Field Strength
			(nT)
			60.05
			48,020

Design	Plan #2		
Audit Notes:			
Version:	Phase:	PLAN	Tie On Depth:
			0.00
Vertical Section:	Depth From (TVD)	+N/-S	+E/-W
	(usft)	(usft)	(usft)
	0.00	0.00	0.00
			Direction
			(°)
			359.63

Plan Sections										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
2,500.00	0.00	0.00	2,500.00	0.00	0.00	0.00	0.00	0.00	0.00	
3,034.26	5.34	195.76	3,033.49	-23.96	-6.76	1.00	1.00	0.00	195.76	
7,521.31	5.34	195.76	7,501.04	-426.04	-120.24	0.00	0.00	0.00	0.00	
8,055.57	0.00	0.00	8,034.53	-450.00	-127.00	1.00	-1.00	0.00	180.00	
8,533.08	0.00	0.00	8,512.04	-450.00	-127.00	0.00	0.00	0.00	0.00	
9,431.94	89.89	359.63	9,085.00	121.81	-130.65	10.00	10.00	-0.04	359.63	
14,810.26	89.89	359.63	9,095.70	5,500.00	-165.00	0.00	0.00	0.00	0.00	
15,191.96	89.89	352.00	9,096.45	5,880.40	-192.82	2.00	0.00	-2.00	-89.98	
15,491.96	89.89	352.00	9,097.02	6,177.48	-234.57	0.00	0.00	0.00	0.00	
15,892.21	89.88	0.01	9,097.83	6,576.43	-262.45	2.00	0.00	2.00	90.08	
16,392.21	89.88	0.01	9,098.88	7,076.43	-262.41	0.00	0.00	0.00	0.00	
16,791.96	89.88	8.00	9,099.71	7,474.88	-234.53	2.00	0.00	2.00	90.01	
16,970.96	89.88	8.00	9,100.09	7,652.14	-209.62	0.00	0.00	0.00	0.00	
17,389.43	89.88	359.63	9,100.96	8,069.31	-181.80	2.00	0.00	-2.00	-89.99	
19,356.15	89.88	359.63	9,105.00	10,035.99	-194.48	0.00	0.00	0.00	0.00	PBHL (Belloq 524H) -

LEAM Drilling Services

Planning Report - Geographic

Database:	EDM 5000.1 Multi User Db	Local Co-ordinate Reference:	Well Belloq 11-2 Fed State Com 524H
Company:	Devon Energy-	TVD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Project:	Eddy County, NM (NAD-83)	MD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Site:	Belloq 11-2 Fed State Com	North Reference:	Grid
Well:	Belloq 11-2 Fed State Com 524H	Survey Calculation Method:	Minimum Curvature
Wellbore:	OH		
Design:	Plan #2		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
0.00	0.00	0.00	0.00	0.00	0.00	478,134.17	723,719.47	32° 18' 47.0983 N	103° 44' 34.6969 W
SHL (Belloq 524H) - 500' FSL, 910' FEL S11									
100.00	0.00	0.00	100.00	0.00	0.00	478,134.17	723,719.47	32° 18' 47.0983 N	103° 44' 34.6969 W
200.00	0.00	0.00	200.00	0.00	0.00	478,134.17	723,719.47	32° 18' 47.0983 N	103° 44' 34.6969 W
300.00	0.00	0.00	300.00	0.00	0.00	478,134.17	723,719.47	32° 18' 47.0983 N	103° 44' 34.6969 W
400.00	0.00	0.00	400.00	0.00	0.00	478,134.17	723,719.47	32° 18' 47.0983 N	103° 44' 34.6969 W
500.00	0.00	0.00	500.00	0.00	0.00	478,134.17	723,719.47	32° 18' 47.0983 N	103° 44' 34.6969 W
600.00	0.00	0.00	600.00	0.00	0.00	478,134.17	723,719.47	32° 18' 47.0983 N	103° 44' 34.6969 W
700.00	0.00	0.00	700.00	0.00	0.00	478,134.17	723,719.47	32° 18' 47.0983 N	103° 44' 34.6969 W
800.00	0.00	0.00	800.00	0.00	0.00	478,134.17	723,719.47	32° 18' 47.0983 N	103° 44' 34.6969 W
900.00	0.00	0.00	900.00	0.00	0.00	478,134.17	723,719.47	32° 18' 47.0983 N	103° 44' 34.6969 W
1,000.00	0.00	0.00	1,000.00	0.00	0.00	478,134.17	723,719.47	32° 18' 47.0983 N	103° 44' 34.6969 W
1,100.00	0.00	0.00	1,100.00	0.00	0.00	478,134.17	723,719.47	32° 18' 47.0983 N	103° 44' 34.6969 W
1,200.00	0.00	0.00	1,200.00	0.00	0.00	478,134.17	723,719.47	32° 18' 47.0983 N	103° 44' 34.6969 W
1,300.00	0.00	0.00	1,300.00	0.00	0.00	478,134.17	723,719.47	32° 18' 47.0983 N	103° 44' 34.6969 W
1,400.00	0.00	0.00	1,400.00	0.00	0.00	478,134.17	723,719.47	32° 18' 47.0983 N	103° 44' 34.6969 W
1,500.00	0.00	0.00	1,500.00	0.00	0.00	478,134.17	723,719.47	32° 18' 47.0983 N	103° 44' 34.6969 W
1,600.00	0.00	0.00	1,600.00	0.00	0.00	478,134.17	723,719.47	32° 18' 47.0983 N	103° 44' 34.6969 W
1,700.00	0.00	0.00	1,700.00	0.00	0.00	478,134.17	723,719.47	32° 18' 47.0983 N	103° 44' 34.6969 W
1,800.00	0.00	0.00	1,800.00	0.00	0.00	478,134.17	723,719.47	32° 18' 47.0983 N	103° 44' 34.6969 W
1,900.00	0.00	0.00	1,900.00	0.00	0.00	478,134.17	723,719.47	32° 18' 47.0983 N	103° 44' 34.6969 W
2,000.00	0.00	0.00	2,000.00	0.00	0.00	478,134.17	723,719.47	32° 18' 47.0983 N	103° 44' 34.6969 W
2,100.00	0.00	0.00	2,100.00	0.00	0.00	478,134.17	723,719.47	32° 18' 47.0983 N	103° 44' 34.6969 W
2,200.00	0.00	0.00	2,200.00	0.00	0.00	478,134.17	723,719.47	32° 18' 47.0983 N	103° 44' 34.6969 W
2,300.00	0.00	0.00	2,300.00	0.00	0.00	478,134.17	723,719.47	32° 18' 47.0983 N	103° 44' 34.6969 W
2,400.00	0.00	0.00	2,400.00	0.00	0.00	478,134.17	723,719.47	32° 18' 47.0983 N	103° 44' 34.6969 W
2,500.00	0.00	0.00	2,500.00	0.00	0.00	478,134.17	723,719.47	32° 18' 47.0983 N	103° 44' 34.6969 W
2,600.00	1.00	195.76	2,599.99	-0.84	-0.24	478,133.33	723,719.23	32° 18' 47.0900 N	103° 44' 34.6998 W
2,700.00	2.00	195.76	2,699.96	-3.36	-0.95	478,130.81	723,718.52	32° 18' 47.0651 N	103° 44' 34.7082 W
2,800.00	3.00	195.76	2,799.86	-7.56	-2.13	478,126.61	723,717.33	32° 18' 47.0236 N	103° 44' 34.7223 W
2,900.00	4.00	195.76	2,899.68	-13.43	-3.79	478,120.74	723,715.68	32° 18' 46.9656 N	103° 44' 34.7420 W
3,000.00	5.00	195.76	2,999.37	-20.98	-5.92	478,113.19	723,713.54	32° 18' 46.8910 N	103° 44' 34.7673 W
3,034.26	5.34	195.76	3,033.49	-23.96	-6.76	478,110.22	723,712.71	32° 18' 46.8616 N	103° 44' 34.7773 W
3,100.00	5.34	195.76	3,098.94	-29.85	-8.42	478,104.32	723,711.04	32° 18' 46.8034 N	103° 44' 34.7970 W
3,200.00	5.34	195.76	3,198.51	-38.81	-10.95	478,095.36	723,708.51	32° 18' 46.7149 N	103° 44' 34.8271 W
3,300.00	5.34	195.76	3,298.07	-47.77	-13.48	478,086.40	723,705.98	32° 18' 46.6263 N	103° 44' 34.8571 W
3,400.00	5.34	195.76	3,397.64	-56.73	-16.01	478,077.44	723,703.46	32° 18' 46.5378 N	103° 44' 34.8871 W
3,500.00	5.34	195.76	3,497.20	-65.69	-18.54	478,068.48	723,700.93	32° 18' 46.4493 N	103° 44' 34.9172 W
3,600.00	5.34	195.76	3,596.77	-74.65	-21.07	478,059.52	723,698.40	32° 18' 46.3607 N	103° 44' 34.9472 W
3,700.00	5.34	195.76	3,696.33	-83.61	-23.60	478,050.56	723,695.87	32° 18' 46.2722 N	103° 44' 34.9773 W
3,800.00	5.34	195.76	3,795.90	-92.57	-26.13	478,041.60	723,693.34	32° 18' 46.1836 N	103° 44' 35.0073 W
3,900.00	5.34	195.76	3,895.47	-101.54	-28.66	478,032.64	723,690.81	32° 18' 46.0951 N	103° 44' 35.0374 W
4,000.00	5.34	195.76	3,995.03	-110.50	-31.18	478,023.67	723,688.28	32° 18' 46.0066 N	103° 44' 35.0674 W
4,100.00	5.34	195.76	4,094.60	-119.46	-33.71	478,014.71	723,685.75	32° 18' 45.9180 N	103° 44' 35.0975 W
4,200.00	5.34	195.76	4,194.16	-128.42	-36.24	478,005.75	723,683.22	32° 18' 45.8295 N	103° 44' 35.1275 W
4,300.00	5.34	195.76	4,293.73	-137.38	-38.77	477,996.79	723,680.69	32° 18' 45.7410 N	103° 44' 35.1575 W
4,400.00	5.34	195.76	4,393.29	-146.34	-41.30	477,987.83	723,678.17	32° 18' 45.6524 N	103° 44' 35.1876 W
4,500.00	5.34	195.76	4,492.86	-155.30	-43.83	477,978.87	723,675.64	32° 18' 45.5639 N	103° 44' 35.2176 W
4,600.00	5.34	195.76	4,592.42	-164.26	-46.36	477,969.91	723,673.11	32° 18' 45.4754 N	103° 44' 35.2477 W
4,700.00	5.34	195.76	4,691.99	-173.22	-48.89	477,960.95	723,670.58	32° 18' 45.3868 N	103° 44' 35.2777 W
4,800.00	5.34	195.76	4,791.56	-182.19	-51.42	477,951.99	723,668.05	32° 18' 45.2983 N	103° 44' 35.3078 W
4,900.00	5.34	195.76	4,891.12	-191.15	-53.95	477,943.02	723,665.52	32° 18' 45.2097 N	103° 44' 35.3378 W
5,000.00	5.34	195.76	4,990.69	-200.11	-56.47	477,934.06	723,662.99	32° 18' 45.1212 N	103° 44' 35.3679 W
5,100.00	5.34	195.76	5,090.25	-209.07	-59.00	477,925.10	723,660.46	32° 18' 45.0327 N	103° 44' 35.3979 W

LEAM Drilling Services

Planning Report - Geographic

Database:	EDM 5000.1 Multi User Db	Local Co-ordinate Reference:	Well Belloq 11-2 Fed State Com 524H
Company:	Devon Energy	TVD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Project:	Eddy County, NM (NAD-83)	MD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Site:	Belloq 11-2 Fed State Com	North Reference:	Grid
Well:	Belloq 11-2 Fed State Com 524H	Survey Calculation Method:	Minimum Curvature
Wellbore:	OH		
Design:	Plan #2		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
5,200.00	5.34	195.76	5,189.82	-218.03	-61.53	477,916.14	723,657.93	32° 18' 44.9441 N	103° 44' 35.4279 W
5,300.00	5.34	195.76	5,289.38	-226.99	-64.06	477,907.18	723,655.40	32° 18' 44.8556 N	103° 44' 35.4580 W
5,400.00	5.34	195.76	5,388.95	-235.95	-66.59	477,898.22	723,652.88	32° 18' 44.7671 N	103° 44' 35.4880 W
5,500.00	5.34	195.76	5,488.51	-244.91	-69.12	477,889.26	723,650.35	32° 18' 44.6785 N	103° 44' 35.5181 W
5,600.00	5.34	195.76	5,588.08	-253.87	-71.65	477,880.30	723,647.82	32° 18' 44.5900 N	103° 44' 35.5481 W
5,700.00	5.34	195.76	5,687.65	-262.84	-74.18	477,871.34	723,645.29	32° 18' 44.5015 N	103° 44' 35.5782 W
5,800.00	5.34	195.76	5,787.21	-271.80	-76.71	477,862.37	723,642.76	32° 18' 44.4129 N	103° 44' 35.6082 W
5,900.00	5.34	195.76	5,886.78	-280.76	-79.24	477,853.41	723,640.23	32° 18' 44.3244 N	103° 44' 35.6383 W
6,000.00	5.34	195.76	5,986.34	-289.72	-81.77	477,844.45	723,637.70	32° 18' 44.2359 N	103° 44' 35.6683 W
6,100.00	5.34	195.76	6,085.91	-298.68	-84.29	477,835.49	723,635.17	32° 18' 44.1473 N	103° 44' 35.6983 W
6,200.00	5.34	195.76	6,185.47	-307.64	-86.82	477,826.53	723,632.64	32° 18' 44.0588 N	103° 44' 35.7284 W
6,300.00	5.34	195.76	6,285.04	-316.60	-89.35	477,817.57	723,630.11	32° 18' 43.9702 N	103° 44' 35.7584 W
6,400.00	5.34	195.76	6,384.60	-325.56	-91.88	477,808.61	723,627.59	32° 18' 43.8817 N	103° 44' 35.7885 W
6,500.00	5.34	195.76	6,484.17	-334.52	-94.41	477,799.65	723,625.06	32° 18' 43.7932 N	103° 44' 35.8185 W
6,600.00	5.34	195.76	6,583.74	-343.49	-96.94	477,790.69	723,622.53	32° 18' 43.7046 N	103° 44' 35.8486 W
6,700.00	5.34	195.76	6,683.30	-352.45	-99.47	477,781.72	723,620.00	32° 18' 43.6161 N	103° 44' 35.8786 W
6,800.00	5.34	195.76	6,782.87	-361.41	-102.00	477,772.76	723,617.47	32° 18' 43.5276 N	103° 44' 35.9086 W
6,900.00	5.34	195.76	6,882.43	-370.37	-104.53	477,763.80	723,614.94	32° 18' 43.4390 N	103° 44' 35.9387 W
7,000.00	5.34	195.76	6,982.00	-379.33	-107.06	477,754.84	723,612.41	32° 18' 43.3505 N	103° 44' 35.9687 W
7,100.00	5.34	195.76	7,081.56	-388.29	-109.58	477,745.88	723,609.88	32° 18' 43.2620 N	103° 44' 35.9988 W
7,200.00	5.34	195.76	7,181.13	-397.25	-112.11	477,736.92	723,607.35	32° 18' 43.1734 N	103° 44' 36.0288 W
7,300.00	5.34	195.76	7,280.69	-406.21	-114.64	477,727.96	723,604.82	32° 18' 43.0849 N	103° 44' 36.0589 W
7,400.00	5.34	195.76	7,380.26	-415.17	-117.17	477,719.00	723,602.29	32° 18' 42.9963 N	103° 44' 36.0889 W
7,500.00	5.34	195.76	7,479.83	-424.14	-119.70	477,710.04	723,599.77	32° 18' 42.9078 N	103° 44' 36.1190 W
7,521.31	5.34	195.76	7,501.04	-426.04	-120.24	477,708.13	723,599.23	32° 18' 42.8889 N	103° 44' 36.1254 W
7,600.00	4.56	195.76	7,579.44	-432.58	-122.08	477,701.59	723,597.38	32° 18' 42.8244 N	103° 44' 36.1473 W
7,700.00	3.56	195.76	7,679.19	-439.39	-124.00	477,694.79	723,595.46	32° 18' 42.7571 N	103° 44' 36.1701 W
7,800.00	2.56	195.76	7,779.04	-444.52	-125.45	477,689.66	723,594.01	32° 18' 42.7065 N	103° 44' 36.1873 W
7,900.00	1.56	195.76	7,878.98	-447.97	-126.43	477,686.20	723,593.04	32° 18' 42.6723 N	103° 44' 36.1989 W
8,000.00	0.56	195.76	7,978.96	-449.74	-126.93	477,684.43	723,592.54	32° 18' 42.6548 N	103° 44' 36.2048 W
8,055.57	0.00	0.00	8,034.53	-450.00	-127.00	477,684.17	723,592.47	32° 18' 42.6523 N	103° 44' 36.2057 W
8,100.00	0.00	0.00	8,078.96	-450.00	-127.00	477,684.17	723,592.47	32° 18' 42.6523 N	103° 44' 36.2057 W
8,200.00	0.00	0.00	8,178.96	-450.00	-127.00	477,684.17	723,592.47	32° 18' 42.6523 N	103° 44' 36.2057 W
8,300.00	0.00	0.00	8,278.96	-450.00	-127.00	477,684.17	723,592.47	32° 18' 42.6523 N	103° 44' 36.2057 W
8,400.00	0.00	0.00	8,378.96	-450.00	-127.00	477,684.17	723,592.47	32° 18' 42.6523 N	103° 44' 36.2057 W
8,500.00	0.00	0.00	8,478.96	-450.00	-127.00	477,684.17	723,592.47	32° 18' 42.6523 N	103° 44' 36.2057 W
8,533.08	0.00	0.00	8,512.04	-450.00	-127.00	477,684.17	723,592.47	32° 18' 42.6523 N	103° 44' 36.2057 W
KOP (Belloq 524H) - 50' FSL, 1040' FEL S11									
8,550.00	1.69	359.63	8,528.96	-449.75	-127.00	477,684.42	723,592.46	32° 18' 42.6547 N	103° 44' 36.2057 W
8,600.00	6.69	359.63	8,578.81	-446.10	-127.02	477,688.07	723,592.44	32° 18' 42.6909 N	103° 44' 36.2057 W
8,650.00	11.69	359.63	8,628.15	-438.11	-127.08	477,696.06	723,592.39	32° 18' 42.7699 N	103° 44' 36.2058 W
8,700.00	16.69	359.63	8,676.61	-425.86	-127.15	477,708.31	723,592.31	32° 18' 42.8912 N	103° 44' 36.2059 W
8,750.00	21.69	359.63	8,723.81	-409.43	-127.26	477,724.74	723,592.21	32° 18' 43.0538 N	103° 44' 36.2061 W
8,774.23	24.11	359.63	8,746.13	-400.00	-127.32	477,734.17	723,592.15	32° 18' 43.1471 N	103° 44' 36.2062 W
FTP (Belloq 524H) - 100' FSL, 1040' FEL S11									
8,800.00	26.69	359.63	8,769.41	-388.94	-127.39	477,745.23	723,592.08	32° 18' 43.2565 N	103° 44' 36.2063 W
8,850.00	31.69	359.63	8,813.04	-364.57	-127.55	477,769.61	723,591.92	32° 18' 43.4977 N	103° 44' 36.2065 W
8,900.00	36.69	359.63	8,854.39	-336.48	-127.73	477,797.69	723,591.74	32° 18' 43.7757 N	103° 44' 36.2068 W
8,950.00	41.69	359.63	8,893.13	-304.89	-127.93	477,829.28	723,591.54	32° 18' 44.0882 N	103° 44' 36.2072 W
9,000.00	46.69	359.63	8,928.97	-270.05	-128.15	477,864.12	723,591.32	32° 18' 44.4330 N	103° 44' 36.2075 W
9,050.00	51.69	359.63	8,961.63	-232.22	-128.39	477,901.95	723,591.08	32° 18' 44.8074 N	103° 44' 36.2079 W
9,100.00	56.69	359.63	8,990.88	-191.68	-128.65	477,942.49	723,590.82	32° 18' 45.2085 N	103° 44' 36.2083 W
9,150.00	61.69	359.63	9,016.48	-148.75	-128.92	477,985.42	723,590.54	32° 18' 45.6333 N	103° 44' 36.2088 W
9,200.00	66.69	359.63	9,038.24	-103.75	-129.21	478,030.42	723,590.25	32° 18' 46.0786 N	103° 44' 36.2092 W

LEAM Drilling Services

Planning Report - Geographic

Database:	EDM 5000.1 Multi User Db	Local Co-ordinate Reference:	Well Belloq 11-2 Fed State Com 524H
Company:	Devon Energy	TVD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Project:	Eddy County, NM (NAD-83)	MD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Site:	Belloq 11-2 Fed State Com	North Reference:	Grid
Well:	Belloq 11-2 Fed State Com 524H	Survey Calculation Method:	Minimum Curvature
Wellbore:	OH		
Design:	Plan #2		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
9,250.00	71.69	359.63	9,056.00	-57.03	-129.51	478,077.14	723,589.96	32° 18' 46.5410 N	103° 44' 36.2097 W
9,300.00	76.69	359.63	9,069.61	-8.94	-129.82	478,125.23	723,589.65	32° 18' 47.0169 N	103° 44' 36.2102 W
9,350.00	81.69	359.63	9,078.99	40.16	-130.13	478,174.33	723,589.34	32° 18' 47.5027 N	103° 44' 36.2107 W
9,400.00	86.69	359.63	9,084.04	89.88	-130.45	478,224.05	723,589.02	32° 18' 47.9948 N	103° 44' 36.2112 W
9,431.94	89.89	359.63	9,085.00	121.81	-130.65	478,255.98	723,588.81	32° 18' 48.3107 N	103° 44' 36.2116 W
9,500.00	89.89	359.63	9,085.13	189.86	-131.09	478,324.03	723,588.38	32° 18' 48.9842 N	103° 44' 36.2122 W
9,600.00	89.89	359.63	9,085.33	289.86	-131.73	478,424.03	723,587.74	32° 18' 49.9737 N	103° 44' 36.2133 W
9,700.00	89.89	359.63	9,085.53	389.86	-132.36	478,524.03	723,587.10	32° 18' 50.9633 N	103° 44' 36.2143 W
9,800.00	89.89	359.63	9,085.73	489.86	-133.00	478,624.03	723,586.46	32° 18' 51.9529 N	103° 44' 36.2153 W
9,900.00	89.89	359.63	9,085.93	589.85	-133.64	478,724.03	723,585.83	32° 18' 52.9424 N	103° 44' 36.2164 W
10,000.00	89.89	359.63	9,086.13	689.85	-134.28	478,824.02	723,585.19	32° 18' 53.9320 N	103° 44' 36.2174 W
10,100.00	89.89	359.63	9,086.33	789.85	-134.92	478,924.02	723,584.55	32° 18' 54.9215 N	103° 44' 36.2184 W
10,200.00	89.89	359.63	9,086.53	889.85	-135.56	479,024.02	723,583.91	32° 18' 55.9111 N	103° 44' 36.2194 W
10,300.00	89.89	359.63	9,086.72	989.85	-136.20	479,124.02	723,583.27	32° 18' 56.9006 N	103° 44' 36.2205 W
10,400.00	89.89	359.63	9,086.92	1,089.84	-136.83	479,224.01	723,582.63	32° 18' 57.8902 N	103° 44' 36.2215 W
10,500.00	89.89	359.63	9,087.12	1,189.84	-137.47	479,324.01	723,581.99	32° 18' 58.8797 N	103° 44' 36.2225 W
10,600.00	89.89	359.63	9,087.32	1,289.84	-138.11	479,424.01	723,581.35	32° 18' 59.8693 N	103° 44' 36.2236 W
10,700.00	89.89	359.63	9,087.52	1,389.84	-138.75	479,524.01	723,580.72	32° 19' 0.8588 N	103° 44' 36.2246 W
10,800.00	89.89	359.63	9,087.72	1,489.83	-139.39	479,624.01	723,580.08	32° 19' 1.8484 N	103° 44' 36.2256 W
10,900.00	89.89	359.63	9,087.92	1,589.83	-140.03	479,724.00	723,579.44	32° 19' 2.8379 N	103° 44' 36.2266 W
11,000.00	89.89	359.63	9,088.12	1,689.83	-140.67	479,824.00	723,578.80	32° 19' 3.8275 N	103° 44' 36.2277 W
11,100.00	89.89	359.63	9,088.32	1,789.83	-141.30	479,924.00	723,578.16	32° 19' 4.8170 N	103° 44' 36.2287 W
11,200.00	89.89	359.63	9,088.52	1,889.83	-141.94	480,024.00	723,577.52	32° 19' 5.8066 N	103° 44' 36.2297 W
11,300.00	89.89	359.63	9,088.71	1,989.82	-142.58	480,123.99	723,576.88	32° 19' 6.7961 N	103° 44' 36.2308 W
11,400.00	89.89	359.63	9,088.91	2,089.82	-143.22	480,223.99	723,576.25	32° 19' 7.7857 N	103° 44' 36.2318 W
11,500.00	89.89	359.63	9,089.11	2,189.82	-143.86	480,323.99	723,575.61	32° 19' 8.7752 N	103° 44' 36.2328 W
11,600.00	89.89	359.63	9,089.31	2,289.82	-144.50	480,423.99	723,574.97	32° 19' 9.7648 N	103° 44' 36.2338 W
11,700.00	89.89	359.63	9,089.51	2,389.81	-145.14	480,523.99	723,574.33	32° 19' 10.7543 N	103° 44' 36.2349 W
11,800.00	89.89	359.63	9,089.71	2,489.81	-145.78	480,623.98	723,573.69	32° 19' 11.7439 N	103° 44' 36.2359 W
11,900.00	89.89	359.63	9,089.91	2,589.81	-146.41	480,723.98	723,573.05	32° 19' 12.7334 N	103° 44' 36.2369 W
12,000.00	89.89	359.63	9,090.11	2,689.81	-147.05	480,823.98	723,572.41	32° 19' 13.7230 N	103° 44' 36.2379 W
12,100.00	89.89	359.63	9,090.31	2,789.81	-147.69	480,923.98	723,571.77	32° 19' 14.7125 N	103° 44' 36.2390 W
12,200.00	89.89	359.63	9,090.51	2,889.80	-148.33	481,023.97	723,571.14	32° 19' 15.7021 N	103° 44' 36.2400 W
12,300.00	89.89	359.63	9,090.70	2,989.80	-148.97	481,123.97	723,570.50	32° 19' 16.6916 N	103° 44' 36.2410 W
12,400.00	89.89	359.63	9,090.90	3,089.80	-149.61	481,223.97	723,569.86	32° 19' 17.6812 N	103° 44' 36.2420 W
12,500.00	89.89	359.63	9,091.10	3,189.80	-150.25	481,323.97	723,569.22	32° 19' 18.6707 N	103° 44' 36.2431 W
12,600.00	89.89	359.63	9,091.30	3,289.79	-150.88	481,423.97	723,568.58	32° 19' 19.6603 N	103° 44' 36.2441 W
12,700.00	89.89	359.63	9,091.50	3,389.79	-151.52	481,523.96	723,567.94	32° 19' 20.6498 N	103° 44' 36.2451 W
12,800.00	89.89	359.63	9,091.70	3,489.79	-152.16	481,623.96	723,567.30	32° 19' 21.6394 N	103° 44' 36.2462 W
12,900.00	89.89	359.63	9,091.90	3,589.79	-152.80	481,723.96	723,566.67	32° 19' 22.6290 N	103° 44' 36.2472 W
13,000.00	89.89	359.63	9,092.10	3,689.79	-153.44	481,823.96	723,566.03	32° 19' 23.6185 N	103° 44' 36.2482 W
13,100.00	89.89	359.63	9,092.30	3,789.78	-154.08	481,923.95	723,565.39	32° 19' 24.6081 N	103° 44' 36.2492 W
13,200.00	89.89	359.63	9,092.50	3,889.78	-154.72	482,023.95	723,564.75	32° 19' 25.5976 N	103° 44' 36.2503 W
13,300.00	89.89	359.63	9,092.69	3,989.78	-155.35	482,123.95	723,564.11	32° 19' 26.5872 N	103° 44' 36.2513 W
13,400.00	89.89	359.63	9,092.89	4,089.78	-155.99	482,223.95	723,563.47	32° 19' 27.5767 N	103° 44' 36.2523 W
13,500.00	89.89	359.63	9,093.09	4,189.77	-156.63	482,323.94	723,562.83	32° 19' 28.5663 N	103° 44' 36.2533 W
13,600.00	89.89	359.63	9,093.29	4,289.77	-157.27	482,423.94	723,562.20	32° 19' 29.5558 N	103° 44' 36.2544 W
13,700.00	89.89	359.63	9,093.49	4,389.77	-157.91	482,523.94	723,561.56	32° 19' 30.5454 N	103° 44' 36.2554 W
13,800.00	89.89	359.63	9,093.69	4,489.77	-158.55	482,623.94	723,560.92	32° 19' 31.5349 N	103° 44' 36.2564 W
13,900.00	89.89	359.63	9,093.89	4,589.77	-159.19	482,723.94	723,560.28	32° 19' 32.5245 N	103° 44' 36.2574 W
14,000.00	89.89	359.63	9,094.09	4,689.76	-159.83	482,823.93	723,559.64	32° 19' 33.5140 N	103° 44' 36.2585 W
14,100.00	89.89	359.63	9,094.29	4,789.76	-160.46	482,923.93	723,559.00	32° 19' 34.5036 N	103° 44' 36.2595 W
14,200.00	89.89	359.63	9,094.49	4,889.76	-161.10	483,023.93	723,558.36	32° 19' 35.4931 N	103° 44' 36.2605 W
14,300.00	89.89	359.63	9,094.68	4,989.76	-161.74	483,123.93	723,557.72	32° 19' 36.4827 N	103° 44' 36.2616 W
14,400.00	89.89	359.63	9,094.88	5,089.75	-162.38	483,223.92	723,557.09	32° 19' 37.4722 N	103° 44' 36.2626 W

LEAM Drilling Services

Planning Report - Geographic

Database:	EDM 5000.1 Multi User Db	Local Co-ordinate Reference:	Well Belloq 11-2 Fed State Com 524H
Company:	Devon Energy	TVD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Project:	Eddy County, NM-(NAD-83)	MD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Site:	Belloq 11-2 Fed State Com	North Reference:	Grid
Well:	Belloq 11-2 Fed State Com 524H	Survey Calculation Method:	Minimum Curvature
Wellbore:	OH		
Design:	Plan #2		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
14,500.00	89.89	359.63	9,095.08	5,189.75	-163.02	483,323.92	723,556.45	32° 19' 38.4618 N	103° 44' 36.2636 W
14,600.00	89.89	359.63	9,095.28	5,289.75	-163.66	483,423.92	723,555.81	32° 19' 39.4513 N	103° 44' 36.2646 W
14,700.00	89.89	359.63	9,095.48	5,389.75	-164.30	483,523.92	723,555.17	32° 19' 40.4409 N	103° 44' 36.2657 W
14,800.00	89.89	359.63	9,095.68	5,489.75	-164.93	483,623.92	723,554.53	32° 19' 41.4304 N	103° 44' 36.2667 W
14,810.26	89.89	359.63	9,095.70	5,500.00	-165.00	483,634.17	723,554.47	32° 19' 41.5319 N	103° 44' 36.2668 W
14,900.00	89.89	357.84	9,095.88	5,589.72	-166.98	483,723.89	723,552.49	32° 19' 42.4198 N	103° 44' 36.2841 W
15,000.00	89.89	355.84	9,096.08	5,689.56	-172.49	483,823.73	723,546.97	32° 19' 43.4081 N	103° 44' 36.3419 W
15,100.00	89.89	353.84	9,096.27	5,789.15	-181.49	483,923.32	723,537.98	32° 19' 44.3941 N	103° 44' 36.4404 W
15,191.96	89.89	352.00	9,096.45	5,880.40	-192.82	484,014.58	723,526.64	32° 19' 45.2977 N	103° 44' 36.5666 W
15,200.00	89.89	352.00	9,096.46	5,888.37	-193.94	484,022.54	723,525.53	32° 19' 45.3765 N	103° 44' 36.5792 W
15,300.00	89.89	352.00	9,096.65	5,987.39	-207.86	484,121.56	723,511.61	32° 19' 46.3572 N	103° 44' 36.7350 W
15,400.00	89.89	352.00	9,096.85	6,086.42	-221.78	484,220.59	723,497.69	32° 19' 47.3378 N	103° 44' 36.8908 W
15,491.96	89.89	352.00	9,097.02	6,177.48	-234.57	484,311.66	723,484.89	32° 19' 48.2396 N	103° 44' 37.0342 W
15,500.00	89.89	352.16	9,097.04	6,185.45	-235.68	484,319.62	723,483.78	32° 19' 48.3185 N	103° 44' 37.0466 W
15,600.00	89.89	354.16	9,097.23	6,284.73	-247.59	484,418.90	723,471.88	32° 19' 49.3016 N	103° 44' 37.1790 W
15,700.00	89.88	356.16	9,097.43	6,384.37	-256.02	484,518.54	723,463.44	32° 19' 50.2880 N	103° 44' 37.2709 W
15,800.00	89.88	358.16	9,097.64	6,484.24	-260.98	484,618.41	723,458.49	32° 19' 51.2766 N	103° 44' 37.3222 W
15,892.21	89.88	0.01	9,097.83	6,576.43	-262.45	484,710.61	723,457.01	32° 19' 52.1889 N	103° 44' 37.3335 W
15,900.00	89.88	0.01	9,097.84	6,584.23	-262.45	484,718.40	723,457.01	32° 19' 52.2660 N	103° 44' 37.3330 W
16,000.00	89.88	0.01	9,098.05	6,684.23	-262.44	484,818.40	723,457.02	32° 19' 53.2556 N	103° 44' 37.3265 W
16,100.00	89.88	0.01	9,098.26	6,784.23	-262.43	484,918.40	723,457.03	32° 19' 54.2451 N	103° 44' 37.3200 W
16,200.00	89.88	0.01	9,098.47	6,884.23	-262.43	485,018.40	723,457.04	32° 19' 55.2346 N	103° 44' 37.3134 W
16,300.00	89.88	0.01	9,098.68	6,984.23	-262.42	485,118.40	723,457.05	32° 19' 56.2242 N	103° 44' 37.3069 W
16,392.21	89.88	0.01	9,098.88	7,076.43	-262.41	485,210.60	723,457.06	32° 19' 57.1366 N	103° 44' 37.3009 W
16,400.00	89.88	0.16	9,098.89	7,084.23	-262.40	485,218.40	723,457.07	32° 19' 57.2137 N	103° 44' 37.3003 W
16,500.00	89.88	2.16	9,099.10	7,184.20	-260.37	485,318.37	723,459.09	32° 19' 58.2029 N	103° 44' 37.2703 W
16,600.00	89.88	4.16	9,099.31	7,284.04	-254.86	485,418.21	723,464.61	32° 19' 59.1905 N	103° 44' 37.1996 W
16,700.00	89.88	6.16	9,099.52	7,383.63	-245.86	485,517.80	723,473.60	32° 20' 0.1755 N	103° 44' 37.0884 W
16,791.96	89.88	8.00	9,099.71	7,474.88	-234.53	485,609.05	723,484.94	32° 20' 1.0779 N	103° 44' 36.9504 W
16,800.00	89.88	8.00	9,099.73	7,482.85	-233.41	485,617.02	723,486.06	32° 20' 1.1566 N	103° 44' 36.9369 W
16,900.00	89.88	8.00	9,099.94	7,581.87	-219.49	485,716.05	723,499.97	32° 20' 2.1358 N	103° 44' 36.7683 W
16,970.96	89.88	8.00	9,100.09	7,652.14	-209.62	485,786.31	723,509.85	32° 20' 2.8306 N	103° 44' 36.6487 W
17,000.00	89.88	7.42	9,100.15	7,680.92	-205.72	485,815.09	723,513.74	32° 20' 3.1151 N	103° 44' 36.6014 W
17,100.00	89.88	5.42	9,100.36	7,780.29	-194.54	485,914.46	723,524.92	32° 20' 4.0978 N	103° 44' 36.4648 W
17,200.00	89.88	3.42	9,100.57	7,879.99	-186.84	486,014.16	723,532.63	32° 20' 5.0839 N	103° 44' 36.3686 W
17,300.00	89.88	1.42	9,100.77	7,979.89	-182.62	486,114.06	723,536.85	32° 20' 6.0723 N	103° 44' 36.3129 W
17,389.43	89.88	359.63	9,100.96	8,069.31	-181.80	486,203.49	723,537.67	32° 20' 6.9571 N	103° 44' 36.2977 W
17,400.00	89.88	359.63	9,100.98	8,079.88	-181.87	486,214.05	723,537.60	32° 20' 7.0617 N	103° 44' 36.2978 W
17,500.00	89.88	359.63	9,101.19	8,179.88	-182.51	486,314.05	723,536.96	32° 20' 8.0513 N	103° 44' 36.2989 W
17,600.00	89.88	359.63	9,101.39	8,279.88	-183.16	486,414.05	723,536.31	32° 20' 9.0408 N	103° 44' 36.3000 W
17,700.00	89.88	359.63	9,101.60	8,379.88	-183.80	486,514.05	723,535.67	32° 20' 10.0304 N	103° 44' 36.3011 W
17,800.00	89.88	359.63	9,101.80	8,479.87	-184.45	486,614.05	723,535.02	32° 20' 11.0199 N	103° 44' 36.3022 W
17,900.00	89.88	359.63	9,102.01	8,579.87	-185.09	486,714.04	723,534.38	32° 20' 12.0095 N	103° 44' 36.3033 W
18,000.00	89.88	359.63	9,102.21	8,679.87	-185.73	486,814.04	723,533.73	32° 20' 12.9990 N	103° 44' 36.3044 W
18,100.00	89.88	359.63	9,102.42	8,779.87	-186.38	486,914.04	723,533.09	32° 20' 13.9886 N	103° 44' 36.3055 W
18,200.00	89.88	359.63	9,102.62	8,879.87	-187.02	487,014.04	723,532.44	32° 20' 14.9781 N	103° 44' 36.3066 W
18,300.00	89.88	359.63	9,102.83	8,979.86	-187.67	487,114.03	723,531.80	32° 20' 15.9677 N	103° 44' 36.3077 W
18,400.00	89.88	359.63	9,103.04	9,079.86	-188.31	487,214.03	723,531.15	32° 20' 16.9572 N	103° 44' 36.3087 W
18,500.00	89.88	359.63	9,103.24	9,179.86	-188.96	487,314.03	723,530.51	32° 20' 17.9468 N	103° 44' 36.3098 W
18,600.00	89.88	359.63	9,103.45	9,279.86	-189.60	487,414.03	723,529.86	32° 20' 18.9363 N	103° 44' 36.3109 W
18,700.00	89.88	359.63	9,103.65	9,379.85	-190.25	487,514.03	723,529.22	32° 20' 19.9258 N	103° 44' 36.3120 W
18,800.00	89.88	359.63	9,103.86	9,479.85	-190.89	487,614.02	723,528.57	32° 20' 20.9154 N	103° 44' 36.3131 W
18,900.00	89.88	359.63	9,104.06	9,579.85	-191.54	487,714.02	723,527.93	32° 20' 21.9049 N	103° 44' 36.3142 W
19,000.00	89.88	359.63	9,104.27	9,679.85	-192.18	487,814.02	723,527.28	32° 20' 22.8945 N	103° 44' 36.3153 W
19,100.00	89.88	359.63	9,104.47	9,779.85	-192.83	487,914.02	723,526.64	32° 20' 23.8840 N	103° 44' 36.3164 W

LEAM Drilling Services
Planning Report - Geographic

Database:	EDM 5000.1 Multi User Db	Local Co-ordinate Reference:	Well Belloq 11-2 Fed State Com 524H
Company:	Devon Energy	TVD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Project:	Eddy County, NM (NAD-83)	MD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Site:	Belloq 11-2 Fed State Com	North Reference:	Grid
Well:	Belloq 11-2 Fed State Com 524H	Survey Calculation Method:	Minimum Curvature
Wellbore:	OH		
Design:	Plan #2		

Planned Survey									
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	+N/-S (usft)	+E/-W (usft)	Map Northing (usft)	Map Easting (usft)	Latitude	Longitude
19,200.00	89.88	359.63	9,104.68	9,879.84	-193.47	488,014.01	723,525.99	32° 20' 24.8736 N	103° 44' 36.3175 W
19,274.15	89.88	359.63	9,104.83	9,953.99	-193.95	488,088.16	723,525.51	32° 20' 25.6073 N	103° 44' 36.3183 W
LTP (Belloq 524H) - 100' FNL, 1040' FEL S2									
19,300.00	89.88	359.63	9,104.88	9,979.84	-194.12	488,114.01	723,525.35	32° 20' 25.8631 N	103° 44' 36.3186 W
19,356.15	89.88	359.63	9,105.00	10,035.99	-194.48	488,170.16	723,524.99	32° 20' 26.4188 N	103° 44' 36.3192 W
PBHL (Belloq 524H) - 20' FNL, 1040' FEL S2									

Design Targets									
Target Name	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
- hit/miss target									
- Shape									
SHL (Belloq 524H) - 500 - plan hits target center - Point	0.00	0.00	0.00	0.00	0.00	478,134.17	723,719.47	32° 18' 47.0983 N	103° 44' 34.6969 W
KOP (Belloq 524H) - 50' - plan hits target center - Point	0.00	0.01	8,512.04	-450.00	-127.00	477,684.17	723,592.47	32° 18' 42.6523 N	103° 44' 36.2057 W
FTP (Belloq 524H) - 100 - plan hits target center - Point	0.00	0.01	8,746.13	-400.00	-127.32	477,734.17	723,592.15	32° 18' 43.1471 N	103° 44' 36.2062 W
LTP (Belloq 524H) - 100' - plan hits target center - Point	0.00	0.01	9,104.83	9,953.99	-193.95	488,088.16	723,525.52	32° 20' 25.6073 N	103° 44' 36.3183 W
PBHL (Belloq 524H) - 20' - plan hits target center - Point	0.00	0.00	9,105.00	10,035.99	-194.48	488,170.16	723,524.99	32° 20' 26.4188 N	103° 44' 36.3192 W

Devon Energy

Eddy County, NM (NAD-83)

Belloq 11-2 Fed State Com

Belloq 11-2 Fed State Com 524H

OH

Plan #2

Anticollision Report

23 January, 2019

LEAM Drilling Services

Anticollision Report

Company:	Devon Energy	Local Co-ordinate Reference:	Well Belloq 11-2 Fed State Com 524H
Project:	Eddy County, NM (NAD-83)	TVD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Reference Site:	Belloq 11-2 Fed State Com	MD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Belloq 11-2 Fed State Com 524H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	EDM 5000.1 Multi User Db
Reference Design:	Plan #2	Offset TVD Reference:	Offset Datum

Reference	Plan #2		
Filter type:	NO GLOBAL FILTER: Using user defined selection & filtering criteria		
Interpolation Method:	MD Interval 100.00usft	Error Model:	ISCWSA
Depth Range:	Unlimited	Scan Method:	Closest Approach 3D
Results Limited by:	Maximum center-center distance of 2,000.00 usft	Error Surface:	Elliptical Conic
Warning Levels Evaluated at:	2.00 Sigma	Casing Method:	Not applied

Survey Tool Program		Date	1/23/2019		
From (usft)	To (usft)	Survey (Wellbore)	Tool Name	Description	
0.00	19,356.11	Plan #2 (OH)	LEAM MWD+HDGM	MWD+HDGM	

Site Name	Reference Measured Depth (usft)	Offset Measured Depth (usft)	Distance Between Centres (usft)	Distance Between Ellipses (usft)	Separation Factor	Warning
Offset Well - Wellbore - Design						
Belloq 11-2 Fed State Com						
Barclay 11H Federal 1 (Offset) - OH - OH	11,867.07	9,089.54	371.92	244.67	2.923	CC, ES, SF
Barclay 11M Federal 13 (Offset) - OH - OH						Out of range
Barclay State 1 (Offset) - OH - OH	16,035.60	9,098.78	462.82	174.30	1.604	CC, ES, SF
Belloq 11 Fed 222H (Offset) - OH - Plan #1						Out of range
Belloq 11-2 Fed State Com 223H (Offset) - OH - Plan #1	4,783.41	4,803.79	80.54	59.67	3.859	CC
Belloq 11-2 Fed State Com 223H (Offset) - OH - Plan #1	4,800.00	4,820.16	80.59	59.60	3.840	ES
Belloq 11-2 Fed State Com 223H (Offset) - OH - Plan #1	4,900.00	4,918.80	82.79	61.09	3.816	SF
Belloq 11-2 Fed State Com 231H (Offset) - OH - Plan #1						Out of range
Belloq 11-2 Fed State Com 234H (Offset) - OH - Plan #1	2,500.00	2,499.70	209.94	198.98	19.158	CC
Belloq 11-2 Fed State Com 234H (Offset) - OH - Plan #1	2,600.00	2,599.69	210.18	198.80	18.471	ES
Belloq 11-2 Fed State Com 234H (Offset) - OH - Plan #1	19,100.00	19,983.89	1,396.68	1,230.11	8.385	SF
Belloq 11-2 Fed State Com 511H - OH - Plan #1						Out of range
Belloq 11-2 Fed State Com 512H - OH - Plan #1	15,878.19	15,666.27	1,852.96	1,630.69	8.336	CC
Belloq 11-2 Fed State Com 512H - OH - Plan #1	19,356.15	19,139.32	1,944.09	1,611.63	5.848	ES, SF
Belloq 11-2 Fed State Com 513H - OH - Plan #2	15,874.69	15,577.08	582.93	372.79	2.774	CC
Belloq 11-2 Fed State Com 513H - OH - Plan #2	19,356.15	19,053.62	672.79	354.62	2.115	ES, SF
Belloq 11-2 Fed State Com 514H - OH - Plan #2	2,500.00	2,499.90	29.99	19.03	2.736	CC, ES
Belloq 11-2 Fed State Com 514H - OH - Plan #2	19,356.15	19,224.84	670.36	353.77	2.117	SF
Belloq 11-2 Fed State Com 521H - OH - Plan #2						Out of range
Belloq 11-2 Fed State Com 522H - OH - Plan #2						Out of range
Belloq 11-2 Fed State Com 523H - OH - Plan #1	15,879.44	15,854.47	1,179.36	957.95	5.326	CC
Belloq 11-2 Fed State Com 523H - OH - Plan #1	19,356.15	19,326.30	1,269.75	937.71	3.824	ES, SF
Belloq 2 State						
2H - OH - OH						Out of range
5H - OH - OH						Out of range
6H - OH - OH						Out of range

Offset Design												Belloq 11-2 Fed State Com - Barclay 11H Federal 1 (Offset) - OH - OH		Offset Site Error:		0.00 usft	
Survey Program:												9104-INC-ONLY		Offset Well Error:		0.00 usft	
Reference		Offset		Semi Major Axis		Distance						Warning					
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	Offset Wellbore Centre +E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning				
10,000.00	9,086.13	9,085.83	9,085.83	23.73	79.07	89.43	2,559.25	225.71	1,903.75	1,805.33	98.41	19.345					

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

LEAM Drilling Services

Anticollision Report

Company:	Devon Energy	Local Co-ordinate Reference:	Well Belloq 11-2 Fed State Com 524H
Project:	Eddy County, NM (NAD-83)	TVD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Reference Site:	Belloq 11-2 Fed State Com	MD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Belloq 11-2 Fed State Com 524H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore:	OH	Database:	EDM 5000.1 Multi User Db
Reference Design:	Plan #2	Offset TVD Reference:	Offset Datum

Offset Design													Offset Site Error:		0.00 usft
Survey Program: 9104-INC-ONLY													Offset Well Error:		0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Distance			Minimum Separation (usft)	Separation Factor	Warning			
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)				Between Ellipses (usft)		
10,100.00	9,086.33	9,086.03	9,086.03	24.70	79.07	89.46	2,559.25	225.71	1,805.78	1,707.25	98.53	18.327			
10,200.00	9,086.53	9,086.23	9,086.23	25.73	79.07	89.49	2,559.25	225.71	1,708.05	1,609.37	98.68	17.310			
10,300.00	9,086.72	9,086.42	9,086.42	26.82	79.08	89.52	2,559.25	225.71	1,610.59	1,511.74	98.85	16.293			
10,400.00	9,086.92	9,086.62	9,086.62	27.97	79.08	89.55	2,559.25	225.71	1,513.47	1,414.40	99.07	15.276			
10,500.00	9,087.12	9,086.82	9,086.82	29.16	79.08	89.58	2,559.25	225.71	1,416.75	1,317.41	99.34	14.261			
10,600.00	9,087.32	9,087.02	9,087.02	30.39	79.08	89.61	2,559.25	225.71	1,320.52	1,220.84	99.68	13.247			
10,700.00	9,087.52	9,087.22	9,087.22	31.66	79.08	89.64	2,559.25	225.71	1,224.89	1,124.79	100.11	12.236			
10,800.00	9,087.72	9,087.42	9,087.42	32.97	79.08	89.67	2,559.25	225.71	1,130.02	1,029.38	100.65	11.228			
10,900.00	9,087.92	9,087.62	9,087.62	34.30	79.09	89.70	2,559.25	225.71	1,036.12	934.78	101.34	10.224			
11,000.00	9,088.12	9,087.82	9,087.82	35.66	79.09	89.73	2,559.25	225.71	943.46	841.23	102.24	9.228			
11,100.00	9,088.32	9,088.02	9,088.02	37.04	79.09	89.76	2,559.25	225.71	852.47	749.07	103.41	8.244			
11,200.00	9,088.52	9,088.22	9,088.22	38.44	79.09	89.80	2,559.25	225.71	763.74	658.79	104.95	7.277			
11,300.00	9,088.71	9,088.41	9,088.41	39.86	79.09	89.83	2,559.25	225.71	678.15	571.17	106.98	6.339			
11,400.00	9,088.91	9,088.61	9,088.61	41.29	79.10	89.86	2,559.25	225.71	597.06	487.39	109.67	5.444			
11,500.00	9,089.11	9,088.81	9,088.81	42.74	79.10	89.89	2,559.25	225.71	522.55	409.43	113.12	4.619			
11,600.00	9,089.31	9,089.01	9,089.01	44.20	79.10	89.92	2,559.25	225.71	457.87	340.51	117.36	3.901			
11,700.00	9,089.51	9,089.21	9,089.21	45.68	79.10	89.95	2,559.25	225.71	407.72	285.75	121.97	3.343			
11,800.00	9,089.71	9,089.41	9,089.41	47.17	79.10	89.98	2,559.25	225.71	377.92	252.08	125.84	3.003			
11,867.07	9,089.84	9,089.54	9,089.54	48.17	79.10	90.00	2,559.25	225.71	371.92	244.67	127.26	2.923	CC, ES, SF		
11,900.00	9,089.91	9,089.61	9,089.61	48.66	79.10	90.01	2,559.25	225.71	373.38	245.89	127.49	2.929			
12,000.00	9,090.11	9,089.81	9,089.81	50.17	79.11	90.04	2,559.25	225.71	394.96	268.57	126.40	3.125			
12,100.00	9,090.31	9,090.01	9,090.01	51.68	79.11	90.07	2,559.25	225.71	438.84	315.34	123.50	3.553			
12,200.00	9,090.51	9,090.21	9,090.21	53.20	79.11	90.10	2,559.25	225.71	499.17	379.07	120.10	4.156			
12,300.00	9,090.70	9,090.40	9,090.40	54.73	79.11	90.13	2,559.25	225.71	570.75	453.82	116.94	4.881			
12,400.00	9,090.90	9,090.60	9,090.60	56.26	79.11	90.16	2,559.25	225.71	649.88	535.61	114.27	5.687			
12,500.00	9,091.10	9,090.80	9,090.80	57.80	79.11	90.19	2,559.25	225.71	734.12	622.01	112.11	6.548			
12,600.00	9,091.30	9,091.00	9,091.00	59.35	79.12	90.22	2,559.25	225.71	821.90	711.51	110.38	7.446			
12,700.00	9,091.50	9,091.20	9,091.20	60.90	79.12	90.26	2,559.25	225.71	912.20	803.20	109.00	8.369			
12,800.00	9,091.70	9,091.40	9,091.40	62.45	79.12	90.29	2,559.25	225.71	1,004.33	896.45	107.89	9.309			
12,900.00	9,091.90	9,091.60	9,091.60	64.01	79.12	90.32	2,559.25	225.71	1,097.85	990.86	106.99	10.261			
13,000.00	9,092.10	9,091.80	9,091.80	65.57	79.12	90.35	2,559.25	225.71	1,192.42	1,086.16	106.25	11.222			
13,100.00	9,092.30	9,092.00	9,092.00	67.14	79.12	90.38	2,559.25	225.71	1,287.81	1,182.16	105.65	12.189			
13,200.00	9,092.50	9,092.20	9,092.20	68.71	79.13	90.41	2,559.25	225.71	1,383.85	1,278.69	105.15	13.160			
13,300.00	9,092.69	9,092.39	9,092.39	70.28	79.13	90.44	2,559.25	225.71	1,480.41	1,375.67	104.74	14.134			
13,400.00	9,092.89	9,092.59	9,092.59	71.86	79.13	90.47	2,559.25	225.71	1,577.40	1,473.01	104.40	15.110			
13,500.00	9,093.09	9,092.79	9,092.79	73.44	79.13	90.50	2,559.25	225.71	1,674.75	1,570.64	104.11	16.087			
13,600.00	9,093.29	9,092.99	9,092.99	75.02	79.13	90.53	2,559.25	225.71	1,772.39	1,668.53	103.87	17.064			
13,700.00	9,093.49	9,093.19	9,093.19	76.60	79.14	90.56	2,559.25	225.71	1,870.28	1,766.62	103.66	18.042			
13,800.00	9,093.69	9,093.39	9,093.39	78.19	79.14	90.59	2,559.25	225.71	1,968.39	1,864.89	103.49	19.019			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

LEAM Drilling Services

Anticollision Report

Company:	Devon Energy	Local Co-ordinate Reference:	Well Belloq 11-2 Fed State Com 524H
Project:	Eddy County, NM (NAD-83)	TVD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Reference Site:	Belloq 11-2 Fed State Com	MD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Belloq 11-2 Fed State Com 524H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	EDM 5000.1 Multi User Db
Reference Design:	Plan #2	Offset TVD Reference:	Offset Datum

Offset Design													Offset Site Error:	0.00 usft
Survey Program: 142-INC-ONLY													Offset Well Error:	0.00 usft
Reference														
Offset														
Semi Major Axis														
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning	
14,100.00	9,094.29	9,094.94	9,093.99	82.96	175.87	89.41	6,719.78	200.38	1,963.46	1,760.95	202.52	9.695		
14,200.00	9,094.49	9,095.14	9,094.19	84.55	175.87	89.44	6,719.78	200.38	1,865.38	1,662.09	203.29	9.176		
14,300.00	9,094.68	9,095.34	9,094.38	86.15	175.88	89.47	6,719.78	200.38	1,767.52	1,563.34	204.18	8.657		
14,400.00	9,094.88	9,095.54	9,094.58	87.75	175.88	89.50	6,719.78	200.38	1,669.91	1,464.72	205.19	8.138		
14,500.00	9,095.08	9,095.73	9,094.78	89.35	175.88	89.53	6,719.78	200.38	1,572.59	1,366.24	206.35	7.621		
14,600.00	9,095.28	9,095.93	9,094.98	90.95	175.89	89.56	6,719.78	200.38	1,475.64	1,267.94	207.70	7.105		
14,700.00	9,095.48	9,096.13	9,095.18	92.55	175.89	89.59	6,719.78	200.38	1,379.12	1,169.85	209.27	6.590		
14,800.00	9,095.68	9,096.33	9,095.38	94.15	175.90	89.62	6,719.78	200.38	1,283.14	1,072.02	211.12	6.078		
14,900.00	9,095.88	9,096.53	9,095.58	95.65	175.90	89.69	6,719.78	200.38	1,188.27	974.90	213.37	5.569		
15,000.00	9,096.08	9,096.73	9,095.78	97.04	175.90	89.75	6,719.78	200.38	1,095.62	879.33	216.29	5.066		
15,100.00	9,096.27	9,096.92	9,095.97	98.44	175.91	89.80	6,719.78	200.38	1,005.93	785.86	220.07	4.571		
15,200.00	9,096.46	9,097.11	9,096.16	99.87	175.91	89.83	6,719.78	200.38	920.18	695.26	224.93	4.091		
15,300.00	9,096.65	9,097.31	9,096.35	101.51	175.92	89.85	6,719.78	200.38	838.48	607.50	230.98	3.630		
15,400.00	9,096.85	9,097.50	9,096.55	103.16	175.92	89.88	6,719.78	200.38	761.16	522.98	238.18	3.196		
15,500.00	9,097.04	9,097.69	9,096.74	104.79	175.92	89.90	6,719.78	200.38	689.68	443.09	246.59	2.797		
15,600.00	9,097.23	9,097.89	9,096.93	106.21	175.93	89.91	6,719.78	200.38	624.45	368.64	255.82	2.441		
15,700.00	9,097.43	9,098.08	9,097.13	107.62	175.93	89.93	6,719.78	200.38	566.40	300.84	265.56	2.133		
15,800.00	9,097.64	9,098.29	9,097.34	109.03	175.94	89.94	6,719.78	200.38	518.00	242.94	275.07	1.883		
15,900.00	9,097.84	9,098.50	9,097.54	110.44	175.94	89.96	6,719.78	200.38	482.27	199.24	283.03	1.704		
16,000.00	9,098.05	9,098.71	9,097.75	112.05	175.94	89.99	6,719.78	200.38	464.18	176.30	287.89	1.612		
16,035.60	9,098.13	9,098.78	9,097.83	112.63	175.95	90.00	6,719.78	200.38	462.82	174.30	288.52	1.604 CC, ES, SF		
16,100.00	9,098.26	9,098.91	9,097.96	113.67	175.95	90.02	6,719.78	200.38	467.28	179.24	288.04	1.622		
16,200.00	9,098.47	9,099.12	9,098.17	115.28	175.95	90.04	6,719.78	200.38	491.15	207.51	283.64	1.732		
16,300.00	9,098.68	9,099.33	9,098.38	116.89	175.96	90.07	6,719.78	200.38	533.02	256.69	276.33	1.929		
16,400.00	9,098.89	9,099.54	9,098.59	118.50	175.96	90.09	6,719.78	200.38	589.05	321.07	267.98	2.198		
16,500.00	9,099.10	9,099.75	9,098.80	119.89	175.97	90.11	6,719.78	200.38	654.20	394.66	259.54	2.521		
16,600.00	9,099.31	9,099.96	9,099.01	121.28	175.97	90.13	6,719.78	200.38	725.00	473.37	251.63	2.881		
16,700.00	9,099.52	9,100.17	9,099.22	122.65	175.97	90.14	6,719.78	200.38	799.89	555.46	244.43	3.272		
16,800.00	9,099.73	9,100.38	9,099.43	124.02	175.98	90.16	6,719.78	200.38	877.75	639.79	237.96	3.689		
16,900.00	9,099.94	9,100.59	9,099.64	125.56	175.98	90.18	6,719.78	200.38	958.90	726.48	232.42	4.126		
17,000.00	9,100.15	9,100.80	9,099.85	127.07	175.99	90.21	6,719.78	200.38	1,043.41	815.69	227.72	4.582		
17,100.00	9,100.36	9,101.01	9,100.06	128.42	175.99	90.25	6,719.78	200.38	1,131.65	907.81	223.84	5.056		
17,200.00	9,100.57	9,101.22	9,100.27	129.79	176.00	90.30	6,719.78	200.38	1,223.11	1,002.30	220.82	5.539		
17,300.00	9,100.77	9,101.43	9,100.47	131.18	176.00	90.36	6,719.78	200.38	1,317.03	1,098.54	218.49	6.028		
17,400.00	9,100.98	9,101.63	9,100.68	132.60	176.00	90.43	6,719.78	200.38	1,412.79	1,196.07	216.73	6.519		
17,500.00	9,101.19	9,101.84	9,100.89	134.22	176.01	90.46	6,719.78	200.38	1,509.47	1,294.12	215.35	7.010		
17,600.00	9,101.39	9,102.04	9,101.09	135.85	176.01	90.49	6,719.78	200.38	1,606.55	1,392.38	214.17	7.501		
17,700.00	9,101.60	9,102.25	9,101.30	137.47	176.02	90.52	6,719.78	200.38	1,703.97	1,490.82	213.15	7.994		
17,800.00	9,101.80	9,102.45	9,101.50	139.09	176.02	90.56	6,719.78	200.38	1,801.67	1,589.39	212.28	8.487		
17,900.00	9,102.01	9,102.66	9,101.71	140.72	176.02	90.59	6,719.78	200.38	1,899.61	1,688.09	211.52	8.981		
18,000.00	9,102.21	9,102.86	9,101.91	142.34	176.03	90.62	6,719.78	200.38	1,997.76	1,786.90	210.86	9.474		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

LEAM Drilling Services

Anticollision Report

Company:	Devon Energy	Local Co-ordinate Reference:	Well Belloq 11-2.Fed State Com 524H
Project:	Eddy County, NM (NAD-83)	TVD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Reference Site:	Belloq 11-2 Fed State Com	MD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Belloq 11-2 Fed State Com 524H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore:	OH	Database:	EDM 5000.1 Multi User Db
Reference Design:	Plan #2	Offset TVD Reference:	Offset Datum

Offset Design													Belloq 11-2 Fed State Com - Belloq 11-2 Fed State Com 223H (Offset) - OH - Plan #1		Offset Site Error: 0.00 usft	
Survey Program: 0-LEAM MWD+HDGM														Offset Well Error: 0.00 usft		
Reference		Offset		Semi Major Axis		Distance							Warning			
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor				
0.00	0.00	0.00	0.00	0.00	0.00	89.88	0.37	179.96	179.96							
100.00	100.00	99.70	99.70	0.09	0.08	89.88	0.37	179.96	179.96	179.79	0.17	1,058.543				
200.00	200.00	199.70	199.70	0.31	0.31	89.88	0.37	179.96	179.96	179.34	0.62	290.672				
300.00	300.00	299.70	299.70	0.54	0.53	89.88	0.37	179.96	179.96	178.89	1.07	168.400				
400.00	400.00	399.70	399.70	0.76	0.76	89.88	0.37	179.96	179.96	178.44	1.52	118.537				
500.00	500.00	499.70	499.70	0.99	0.98	89.88	0.37	179.96	179.96	177.99	1.97	91.457				
600.00	600.00	599.70	599.70	1.21	1.21	89.88	0.37	179.96	179.96	177.54	2.42	74.449				
700.00	700.00	699.70	699.70	1.43	1.43	89.88	0.37	179.96	179.96	177.09	2.87	62.774				
800.00	800.00	799.70	799.70	1.66	1.66	89.88	0.37	179.96	179.96	176.64	3.32	54.265				
900.00	900.00	899.70	899.70	1.88	1.88	89.88	0.37	179.96	179.96	176.19	3.77	47.788				
1,000.00	1,000.00	999.70	999.70	2.11	2.11	89.88	0.37	179.96	179.96	175.75	4.22	42.691				
1,100.00	1,100.00	1,099.70	1,099.70	2.33	2.33	89.88	0.37	179.96	179.96	175.30	4.66	38.577				
1,200.00	1,200.00	1,199.70	1,199.70	2.56	2.56	89.88	0.37	179.96	179.96	174.85	5.11	35.187				
1,300.00	1,300.00	1,299.70	1,299.70	2.78	2.78	89.88	0.37	179.96	179.96	174.40	5.56	32.344				
1,400.00	1,400.00	1,399.70	1,399.70	3.01	3.01	89.88	0.37	179.96	179.96	173.95	6.01	29.926				
1,500.00	1,500.00	1,499.70	1,499.70	3.23	3.23	89.88	0.37	179.96	179.96	173.50	6.46	27.845				
1,600.00	1,600.00	1,599.70	1,599.70	3.46	3.46	89.88	0.37	179.96	179.96	173.05	6.91	26.034				
1,700.00	1,700.00	1,699.70	1,699.70	3.68	3.68	89.88	0.37	179.96	179.96	172.60	7.36	24.444				
1,800.00	1,800.00	1,799.70	1,799.70	3.91	3.90	89.88	0.37	179.96	179.96	172.15	7.81	23.037				
1,900.00	1,900.00	1,899.70	1,899.70	4.13	4.13	89.88	0.37	179.96	179.96	171.70	8.26	21.784				
2,000.00	2,000.00	1,999.70	1,999.70	4.36	4.35	89.88	0.37	179.96	179.96	171.25	8.71	20.660				
2,100.00	2,100.00	2,099.70	2,099.70	4.58	4.58	89.88	0.37	179.96	179.96	170.80	9.16	19.646				
2,200.00	2,200.00	2,199.70	2,199.70	4.81	4.80	89.88	0.37	179.96	179.96	170.35	9.61	18.727				
2,300.00	2,300.00	2,299.70	2,299.70	5.03	5.03	89.88	0.37	179.96	179.96	169.90	10.06	17.890				
2,400.00	2,400.00	2,399.70	2,399.70	5.26	5.25	89.88	0.37	179.96	179.96	169.45	10.51	17.125				
2,500.00	2,500.00	2,499.70	2,499.70	5.48	5.48	89.88	0.37	179.96	179.96	169.00	10.96	16.422				
2,600.00	2,599.99	2,599.69	2,599.69	5.68	5.70	-106.14	0.37	179.96	180.20	168.82	11.38	15.836				
2,700.00	2,699.96	2,699.66	2,699.66	5.85	5.93	-106.93	0.37	179.96	180.95	169.17	11.77	15.369				
2,800.00	2,799.86	2,799.56	2,799.56	6.02	6.15	-108.23	0.37	179.96	182.27	170.09	12.17	14.975				
2,900.00	2,899.68	2,899.38	2,899.38	6.20	6.38	-110.01	0.37	179.96	184.27	171.70	12.57	14.656				
3,000.00	2,999.37	2,999.07	2,999.07	6.38	6.60	-112.24	0.37	179.96	187.10	174.12	12.98	14.415				
3,100.00	3,098.94	3,101.91	3,101.91	6.57	6.81	-114.79	0.00	179.13	189.94	176.57	13.38	14.201				
3,200.00	3,198.51	3,204.93	3,204.89	6.77	7.00	-117.19	-1.11	176.61	191.43	177.67	13.75	13.918				
3,300.00	3,298.07	3,308.04	3,307.90	6.97	7.20	-119.45	-2.97	172.39	191.46	177.32	14.14	13.545				
3,400.00	3,397.64	3,411.18	3,410.82	7.17	7.40	-121.63	-5.58	166.47	189.99	175.47	14.52	13.087				
3,500.00	3,497.20	3,514.26	3,513.57	7.38	7.61	-123.78	-8.94	158.86	187.00	172.10	14.90	12.550				
3,600.00	3,596.77	3,617.24	3,616.04	7.60	7.82	-125.96	-13.04	149.57	182.48	167.19	15.28	11.939				
3,700.00	3,696.33	3,720.03	3,718.14	7.81	8.04	-128.23	-17.87	138.62	176.42	160.76	15.67	11.262				
3,800.00	3,795.90	3,822.58	3,819.76	8.03	8.26	-130.66	-23.42	126.03	168.87	152.82	16.05	10.524				
3,900.00	3,895.47	3,924.82	3,920.81	8.26	8.50	-133.35	-29.69	111.82	159.85	143.43	16.43	9.731				
4,000.00	3,995.03	4,026.70	4,021.21	8.49	8.75	-136.43	-36.66	96.02	149.45	132.64	16.81	8.893				
4,100.00	4,094.60	4,128.13	4,120.86	8.72	9.01	-140.08	-44.31	78.67	137.78	120.59	17.19	8.017				
4,200.00	4,194.16	4,228.30	4,218.94	8.95	9.28	-144.52	-52.53	60.06	125.15	107.56	17.59	7.115				
4,300.00	4,293.73	4,326.94	4,315.45	9.18	9.57	-149.88	-60.75	41.42	113.08	95.04	18.04	6.268				
4,400.00	4,393.29	4,425.58	4,411.96	9.42	9.86	-156.44	-68.98	22.77	102.23	83.71	18.52	5.520				
4,500.00	4,492.86	4,524.23	4,508.48	9.66	10.15	-164.39	-77.20	4.13	93.02	73.98	19.04	4.885				
4,600.00	4,592.42	4,622.87	4,604.99	9.90	10.46	-173.83	-85.43	-14.52	85.99	66.36	19.63	4.381				
4,700.00	4,691.99	4,721.51	4,701.51	10.14	10.77	-175.45	-93.66	-33.16	81.70	61.41	20.29	4.028				
4,783.41	4,775.04	4,803.79	4,782.01	10.34	11.04	165.93	-100.52	-48.72	80.54	59.67	20.87	3.859 CC				
4,800.00	4,791.56	4,820.16	4,798.02	10.39	11.09	164.02	-101.88	-51.81	80.59	59.60	20.99	3.840 ES				
4,900.00	4,891.12	4,918.80	4,894.54	10.63	11.41	152.73	-110.11	-70.46	82.79	61.09	21.69	3.816 SF				
5,000.00	4,990.69	5,017.44	4,991.05	10.88	11.74	142.39	-118.33	-89.10	88.04	65.69	22.36	3.938				

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

LEAM Drilling Services

Anticollision Report

Company:	Devon Energy	Local Co-ordinate Reference:	Well Belloq 11-2 Fed State Com 524H
Project:	Eddy County, NM (NAD-83)	TVD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Reference Site:	Belloq 11-2 Fed State Com	MD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Belloq 11-2 Fed State Com 524H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	EDM 5000.1 Multi User Db
Reference Design:	Plan #2	Offset TVD Reference:	Offset Datum

Offset Design													Belloq 11-2 Fed State Com - Belloq 11-2 Fed State Com 223H (Offset) - OH - Plan #1		Offset Site Error: 0.00 usft	
Survey Program: O-LEAM MWD+HDGM													Offset Well Error: 0.00 usft			
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning			
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)						
5,100.00	5,090.25	5,116.08	5,087.57	11.13	12.08	133.45	-126.56	-107.75	95.86	72.90	22.96	4.174				
5,200.00	5,189.82	5,214.73	5,184.08	11.37	12.42	125.97	-134.79	-126.39	105.67	82.15	23.52	4.492				
5,300.00	5,289.38	5,313.37	5,280.60	11.62	12.76	119.84	-143.01	-145.04	116.97	92.92	24.05	4.863				
5,400.00	5,388.95	5,412.01	5,377.11	11.88	13.11	114.81	-151.24	-163.68	129.37	104.81	24.56	5.268				
5,500.00	5,488.51	5,510.66	5,473.63	12.13	13.46	110.69	-159.46	-182.33	142.59	117.53	25.06	5.690				
5,600.00	5,588.08	5,609.30	5,570.14	12.38	13.81	107.27	-167.69	-200.97	156.41	130.85	25.56	6.120				
5,700.00	5,687.65	5,707.94	5,666.66	12.64	14.17	104.41	-175.92	-219.62	170.69	144.64	26.06	6.551				
5,800.00	5,787.21	5,806.58	5,763.17	12.89	14.53	101.99	-184.14	-238.27	185.33	158.78	26.55	6.979				
5,900.00	5,886.78	5,905.23	5,859.69	13.15	14.89	99.93	-192.37	-256.91	200.25	173.19	27.06	7.401				
6,000.00	5,986.34	6,003.87	5,956.20	13.40	15.26	98.16	-200.59	-275.56	215.38	187.82	27.56	7.814				
6,100.00	6,085.91	6,102.51	6,052.71	13.66	15.62	96.62	-208.82	-294.20	230.69	202.62	28.07	8.218				
6,200.00	6,185.47	6,201.16	6,149.23	13.92	15.99	95.27	-217.05	-312.85	246.14	217.56	28.58	8.612				
6,300.00	6,285.04	6,299.80	6,245.74	14.17	16.36	94.08	-225.27	-331.49	261.71	232.62	29.10	8.995				
6,400.00	6,384.60	6,398.44	6,342.26	14.43	16.74	93.03	-233.50	-350.14	277.38	247.77	29.61	9.366				
6,500.00	6,484.17	6,497.08	6,438.77	14.69	17.11	92.08	-241.72	-368.78	293.13	263.00	30.13	9.727				
6,600.00	6,583.74	6,595.73	6,535.29	14.95	17.49	91.24	-249.95	-387.43	308.95	278.30	30.66	10.078				
6,700.00	6,683.30	6,694.37	6,631.80	15.21	17.86	90.47	-258.18	-406.08	324.83	293.65	31.18	10.417				
6,800.00	6,782.87	6,793.01	6,728.32	15.47	18.24	89.78	-266.40	-424.72	340.76	309.05	31.71	10.747				
6,900.00	6,882.43	6,891.66	6,824.83	15.74	18.62	89.15	-274.63	-443.37	356.74	324.50	32.24	11.066				
7,000.00	6,982.00	6,990.30	6,921.35	16.00	19.00	88.57	-282.85	-462.01	372.75	339.98	32.77	11.375				
7,100.00	7,081.56	7,088.94	7,017.86	16.26	19.38	88.04	-291.08	-480.66	388.80	355.50	33.30	11.675				
7,200.00	7,181.13	7,187.58	7,114.38	16.52	19.77	87.56	-299.31	-499.30	404.88	371.04	33.84	11.966				
7,300.00	7,280.69	7,286.23	7,210.89	16.78	20.15	87.11	-307.53	-517.95	420.98	386.61	34.37	12.248				
7,400.00	7,380.26	7,384.87	7,307.41	17.05	20.54	86.69	-315.76	-536.59	437.11	402.20	34.91	12.522				
7,500.00	7,479.83	7,483.51	7,403.92	17.31	20.92	86.30	-323.98	-555.24	453.26	417.81	35.45	12.787				
7,600.00	7,579.44	7,582.13	7,500.41	17.55	21.31	86.00	-332.21	-573.88	469.46	433.50	35.96	13.055				
7,700.00	7,679.19	7,680.66	7,596.81	17.76	21.70	85.57	-340.42	-592.51	485.82	449.40	36.43	13.338				
7,800.00	7,779.04	7,779.06	7,693.09	17.97	22.09	84.97	-348.63	-611.11	502.38	465.52	36.87	13.627				
7,900.00	7,878.98	7,877.31	7,789.22	18.16	22.47	84.24	-356.82	-629.68	519.20	481.92	37.28	13.926				
8,000.00	7,978.96	7,975.38	7,885.18	18.35	22.86	83.38	-365.00	-648.21	536.34	498.66	37.68	14.234				
8,100.00	8,078.96	8,073.26	7,980.94	18.54	23.25	-81.90	-373.16	-666.71	553.85	515.78	38.06	14.550				
8,200.00	8,178.96	8,171.10	8,076.67	18.72	23.64	-82.99	-381.32	-685.21	571.59	533.15	38.44	14.870				
8,300.00	8,278.96	8,268.94	8,172.40	18.90	24.03	-84.01	-389.48	-703.70	589.52	550.70	38.82	15.186				
8,400.00	8,378.96	8,366.78	8,268.14	19.08	24.42	-84.97	-397.64	-722.20	607.63	568.43	39.20	15.500				
8,500.00	8,478.96	8,464.63	8,363.87	19.27	24.81	-85.88	-405.80	-740.69	625.90	586.31	39.59	15.810				
8,600.00	8,578.81	8,562.00	8,459.14	19.43	25.20	-85.49	-413.92	-759.10	644.05	604.12	39.92	16.132				
8,700.00	8,676.61	8,668.21	8,563.21	19.53	25.54	-86.51	-422.47	-778.48	661.08	620.97	40.11	16.480				
8,800.00	8,769.41	8,774.30	8,667.70	19.56	25.84	-88.90	-429.89	-795.29	676.80	636.66	40.13	16.863				
8,900.00	8,854.39	8,871.98	8,764.31	19.55	26.09	-91.88	-435.68	-808.42	693.72	653.69	40.03	17.332				
9,000.00	8,928.97	8,958.25	8,849.92	19.53	26.30	-94.65	-439.96	-818.13	714.94	675.05	39.89	17.923				
9,100.00	8,990.88	9,030.27	8,921.57	19.51	26.45	-96.37	-442.94	-824.88	743.39	703.55	39.84	18.660				
9,200.00	9,038.24	9,085.45	8,976.54	19.55	26.57	-96.24	-444.85	-829.21	781.10	741.16	39.95	19.554				
9,300.00	9,069.61	9,121.50	9,012.50	19.67	26.64	-93.59	-445.93	-831.65	828.71	788.48	40.23	20.601				
9,400.00	9,084.04	9,136.57	9,027.53	19.91	26.67	-87.94	-446.34	-832.58	885.26	844.62	40.63	21.787				
9,500.00	9,085.13	9,134.60	9,025.56	20.26	26.67	-85.30	-446.29	-832.46	948.75	907.64	41.11	23.080				
9,600.00	9,085.33	9,131.39	9,022.36	20.74	26.66	-85.04	-446.20	-832.27	1,018.07	976.45	41.62	24.459				
9,700.00	9,085.53	9,128.09	9,019.06	21.34	26.65	-84.77	-446.11	-832.06	1,092.16	1,050.02	42.14	25.918				
9,800.00	9,085.73	9,124.69	9,015.68	22.05	26.65	-84.50	-446.02	-831.85	1,170.09	1,127.46	42.63	27.446				
9,900.00	9,085.93	9,121.20	9,012.20	22.85	26.64	-84.22	-445.92	-831.63	1,251.17	1,208.08	43.09	29.036				
10,000.00	9,086.13	11,198.44	10,200.00	23.73	29.16	-147.39	685.49	-846.99	1,322.63	1,289.21	33.42	39.574				
10,100.00	9,086.33	11,298.44	10,200.00	24.70	29.84	-147.39	785.49	-847.60	1,322.45	1,287.88	34.57	38.254				
10,200.00	9,086.53	11,398.44	10,200.00	25.73	30.61	-147.39	885.49	-848.21	1,322.26	1,286.45	35.81	36.922				

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

LEAM Drilling Services

Anticollision Report

Company:	Devon Energy	Local Co-ordinate Reference:	Well Belloq 11-2 Fed State Com 524H
Project:	Eddy County, NM (NAD-83)	TVD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Reference Site:	Belloq 11-2 Fed State Com	MD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Belloq 11-2 Fed State Com 524H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	EDM 5000.1 Multi User Db
Reference Design:	Plan #2	Offset TVD Reference:	Offset Datum

Offset Design Belloq 11-2 Fed State Com - Belloq 11-2 Fed State Com 223H (Offset) - OH - Plan #1														Offset Site Error:	0.00 usft
Survey Program: O-LEAM MWD-HDGM														Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning		
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference	Offset		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)					
10,300.00	9,086.72	11,498.44	10,200.00	26.82	31.46	-147.38	985.48	-848.82	1,322.08	1,284.95	37.14	35.600			
10,400.00	9,086.92	11,598.44	10,200.00	27.97	32.38	-147.38	1,085.48	-849.43	1,321.90	1,283.36	38.54	34.301			
10,500.00	9,087.12	11,698.44	10,200.00	29.16	33.37	-147.38	1,185.48	-850.05	1,321.72	1,281.71	40.01	33.038			
10,600.00	9,087.32	11,798.44	10,200.00	30.39	34.41	-147.37	1,285.48	-850.66	1,321.54	1,280.00	41.53	31.818			
10,700.00	9,087.52	11,898.44	10,200.00	31.66	35.49	-147.37	1,385.48	-851.27	1,321.35	1,278.24	43.12	30.647			
10,800.00	9,087.72	11,998.44	10,200.00	32.97	36.62	-147.36	1,485.47	-851.88	1,321.17	1,276.43	44.75	29.526			
10,900.00	9,087.92	12,098.44	10,200.00	34.30	37.79	-147.36	1,585.47	-852.49	1,320.99	1,274.57	46.42	28.457			
11,000.00	9,088.12	12,198.44	10,200.00	35.66	39.00	-147.36	1,685.47	-853.11	1,320.81	1,272.68	48.13	27.441			
11,100.00	9,088.32	12,298.44	10,200.00	37.04	40.23	-147.35	1,785.47	-853.72	1,320.63	1,270.75	49.88	26.476			
11,200.00	9,088.52	12,398.44	10,200.00	38.44	41.49	-147.35	1,885.47	-854.33	1,320.45	1,268.79	51.66	25.561			
11,300.00	9,088.71	12,498.44	10,200.00	39.86	42.78	-147.35	1,985.46	-854.94	1,320.26	1,266.80	53.47	24.694			
11,400.00	9,088.91	12,598.44	10,200.00	41.29	44.09	-147.34	2,085.46	-855.55	1,320.08	1,264.78	55.30	23.872			
11,500.00	9,089.11	12,698.44	10,200.00	42.74	45.43	-147.34	2,185.46	-856.17	1,319.90	1,262.75	57.15	23.094			
11,600.00	9,089.31	12,798.44	10,200.00	44.20	46.78	-147.33	2,285.46	-856.78	1,319.72	1,260.69	59.03	22.356			
11,700.00	9,089.51	12,898.44	10,200.00	45.68	48.15	-147.33	2,385.46	-857.39	1,319.54	1,258.61	60.93	21.658			
11,800.00	9,089.71	12,998.44	10,200.00	47.17	49.54	-147.33	2,485.45	-858.00	1,319.35	1,256.51	62.84	20.995			
11,900.00	9,089.91	13,098.44	10,200.00	48.66	50.94	-147.32	2,585.45	-858.61	1,319.17	1,254.40	64.77	20.367			
12,000.00	9,090.11	13,198.44	10,200.00	50.17	52.35	-147.32	2,685.45	-859.23	1,318.99	1,252.28	66.71	19.771			
12,100.00	9,090.31	13,298.44	10,200.00	51.68	53.78	-147.32	2,785.45	-859.84	1,318.81	1,250.14	68.67	19.205			
12,200.00	9,090.51	13,398.44	10,200.00	53.20	55.22	-147.31	2,885.45	-860.45	1,318.63	1,247.99	70.64	18.667			
12,300.00	9,090.70	13,498.44	10,200.00	54.73	56.67	-147.31	2,985.44	-861.06	1,318.44	1,245.82	72.62	18.156			
12,400.00	9,090.90	13,598.44	10,200.00	56.26	58.13	-147.31	3,085.44	-861.67	1,318.26	1,243.65	74.61	17.669			
12,500.00	9,091.10	13,698.44	10,200.00	57.80	59.60	-147.30	3,185.44	-862.29	1,318.08	1,241.47	76.61	17.205			
12,600.00	9,091.30	13,798.44	10,200.00	59.35	61.08	-147.30	3,285.44	-862.90	1,317.90	1,239.28	78.62	16.763			
12,700.00	9,091.50	13,898.44	10,200.00	60.90	62.56	-147.29	3,385.43	-863.51	1,317.72	1,237.08	80.64	16.341			
12,800.00	9,091.70	13,998.44	10,200.00	62.45	64.06	-147.29	3,485.43	-864.12	1,317.53	1,234.87	82.66	15.939			
12,900.00	9,091.90	14,098.44	10,200.00	64.01	65.56	-147.29	3,585.43	-864.73	1,317.35	1,232.66	84.70	15.554			
13,000.00	9,092.10	14,198.44	10,200.00	65.57	67.06	-147.28	3,685.43	-865.35	1,317.17	1,230.44	86.73	15.186			
13,100.00	9,092.30	14,298.44	10,200.00	67.14	68.58	-147.28	3,785.43	-865.96	1,316.99	1,228.21	88.78	14.834			
13,200.00	9,092.50	14,398.44	10,200.00	68.71	70.09	-147.28	3,885.42	-866.57	1,316.81	1,225.98	90.83	14.497			
13,300.00	9,092.69	14,498.44	10,200.00	70.28	71.62	-147.27	3,985.42	-867.18	1,316.63	1,223.74	92.89	14.175			
13,400.00	9,092.89	14,598.43	10,200.00	71.86	73.15	-147.27	4,085.42	-867.79	1,316.44	1,221.50	94.95	13.865			
13,500.00	9,093.09	14,698.43	10,200.00	73.44	74.68	-147.26	4,185.42	-868.41	1,316.26	1,219.25	97.01	13.568			
13,600.00	9,093.29	14,798.43	10,200.00	75.02	76.22	-147.26	4,285.42	-869.02	1,316.08	1,217.00	99.09	13.282			
13,700.00	9,093.49	14,898.43	10,200.00	76.60	77.76	-147.26	4,385.41	-869.63	1,315.90	1,214.74	101.16	13.008			
13,800.00	9,093.69	14,998.43	10,200.00	78.19	79.30	-147.25	4,485.41	-870.24	1,315.72	1,212.48	103.24	12.744			
13,900.00	9,093.89	15,098.43	10,200.00	79.78	80.85	-147.25	4,585.41	-870.85	1,315.53	1,210.21	105.32	12.491			
14,000.00	9,094.09	15,198.43	10,200.00	81.37	82.41	-147.25	4,685.41	-871.47	1,315.35	1,207.94	107.41	12.246			
14,100.00	9,094.29	15,298.43	10,200.00	82.96	83.96	-147.24	4,785.41	-872.08	1,315.17	1,205.67	109.50	12.011			
14,200.00	9,094.49	15,398.43	10,200.00	84.55	85.52	-147.24	4,885.40	-872.69	1,314.99	1,203.40	111.59	11.784			
14,300.00	9,094.68	15,498.43	10,200.00	86.15	87.08	-147.23	4,985.40	-873.30	1,314.81	1,201.12	113.69	11.565			
14,400.00	9,094.88	15,598.43	10,200.00	87.75	88.65	-147.23	5,085.40	-873.91	1,314.63	1,198.84	115.79	11.354			
14,500.00	9,095.08	15,698.43	10,200.00	89.35	90.21	-147.23	5,185.40	-874.53	1,314.44	1,196.56	117.89	11.150			
14,600.00	9,095.28	15,798.43	10,200.00	90.95	91.78	-147.22	5,285.40	-875.14	1,314.26	1,194.27	119.99	10.953			
14,700.00	9,095.48	15,898.43	10,200.00	92.55	93.36	-147.22	5,385.39	-875.75	1,314.08	1,191.98	122.10	10.762			
14,800.00	9,095.68	15,998.43	10,200.00	94.15	94.93	-147.22	5,485.39	-876.36	1,313.90	1,189.69	124.21	10.578			
14,900.00	9,095.88	16,098.42	10,200.00	95.65	96.51	-147.28	5,585.37	-876.97	1,313.72	1,187.77	126.18	10.405			
15,000.00	9,096.08	16,198.29	10,200.00	97.04	98.08	-147.49	5,685.25	-877.58	1,313.53	1,185.26	127.88	10.245			
15,100.00	9,096.27	16,297.93	10,200.00	98.44	99.66	-147.87	5,784.89	-878.19	1,313.35	1,182.14	129.35	10.093			
15,200.00	9,096.46	16,397.22	10,200.00	99.87	101.23	-148.41	5,884.18	-878.80	1,299.04	1,168.47	130.57	9.949			
15,300.00	9,096.65	16,496.33	10,200.00	101.51	102.80	-148.90	5,983.28	-879.41	1,291.91	1,160.16	131.75	9.806			
15,400.00	9,096.85	16,595.44	10,200.00	103.16	104.37	-149.40	6,082.39	-880.01	1,284.87	1,151.98	132.89	9.669			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

LEAM Drilling Services

Anticollision Report

Company:	Devon Energy	Local Co-ordinate Reference:	Well Belloq 11-2 Fed State Com 524H
Project:	Eddy County, NM (NAD-83)	TVD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Reference Site:	Belloq 11-2 Fed State Com	MD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Belloq 11-2 Fed State Com 524H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore:	OH	Database:	EDM 5000.1 Multi User Db
Reference Design:	Plan #2	Offset TVD Reference:	Offset Datum

Offset Design													Offset Site Error:	0.00 usft
Belloq 11-2 Fed State Com - Belloq 11-2 Fed State Com 223H (Offset) - OH - Plan #1													Offset Well Error:	0.00 usft
Survey Program: O-LEAM MWD+HDGM														
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)				
15,500.00	9,097.04	16,694.56	10,200.00	104.79	105.95	-149.90	6,181.50	-880.62	1,277.95	1,143.96	133.99	9.538		
15,600.00	9,097.23	16,793.91	10,200.00	106.21	107.52	-150.24	6,280.85	-881.23	1,272.11	1,136.99	135.12	9.415		
15,700.00	9,097.43	16,893.60	10,200.00	107.62	109.11	-150.47	6,380.54	-881.84	1,268.06	1,131.57	136.48	9.291		
15,800.00	9,097.64	16,993.50	10,200.00	109.03	110.70	-150.60	6,480.44	-882.45	1,265.74	1,127.64	138.10	9.165		
15,892.26	9,097.83	17,085.75	10,200.00	110.33	112.17	-150.63	6,572.69	-883.01	1,265.07	1,125.26	139.82	9.048		
15,900.00	9,097.84	17,093.49	10,200.00	110.44	112.29	-150.62	6,580.43	-883.06	1,265.14	1,125.16	139.98	9.038		
16,000.00	9,098.05	17,193.49	10,200.00	112.05	113.89	-150.59	6,680.42	-883.67	1,265.26	1,123.21	142.05	8.907		
16,100.00	9,098.26	17,293.49	10,200.00	113.67	115.48	-150.57	6,780.42	-884.29	1,265.38	1,121.25	144.13	8.780		
16,200.00	9,098.47	17,393.48	10,200.00	115.28	117.08	-150.54	6,880.42	-884.90	1,265.51	1,119.30	146.21	8.656		
16,300.00	9,098.68	17,493.48	10,200.00	116.89	118.68	-150.51	6,980.41	-885.51	1,265.63	1,117.34	148.29	8.535		
16,400.00	9,098.89	17,593.48	10,200.00	118.50	120.28	-150.48	7,080.41	-886.12	1,265.76	1,115.39	150.37	8.417		
16,500.00	9,099.10	17,693.44	10,200.00	119.89	121.88	-150.39	7,180.37	-886.73	1,266.88	1,114.33	152.55	8.305		
16,600.00	9,099.31	17,793.25	10,200.00	121.28	123.48	-150.20	7,280.17	-887.34	1,269.74	1,114.72	155.02	8.191		
16,700.00	9,099.52	17,892.78	10,200.00	122.65	125.07	-149.91	7,379.70	-887.95	1,274.37	1,116.57	157.80	8.076		
16,800.00	9,099.73	17,991.92	10,200.00	124.02	126.66	-149.51	7,478.84	-888.56	1,280.82	1,119.93	160.89	7.961		
16,900.00	9,099.94	18,090.86	10,200.00	125.56	128.25	-148.95	7,577.78	-889.17	1,288.13	1,123.93	164.19	7.845		
17,000.00	9,100.15	18,189.82	10,200.00	127.07	129.84	-148.37	7,676.73	-889.77	1,295.48	1,127.98	167.50	7.734		
17,100.00	9,100.36	18,289.11	10,200.00	128.42	131.43	-147.82	7,776.03	-890.38	1,301.57	1,131.04	170.53	7.633		
17,200.00	9,100.57	18,388.76	10,200.00	129.79	133.03	-147.43	7,875.68	-890.99	1,305.86	1,132.57	173.28	7.536		
17,300.00	9,100.77	18,488.64	10,200.00	131.18	134.64	-147.20	7,975.55	-891.60	1,308.29	1,132.54	175.75	7.444		
17,400.00	9,100.98	18,588.63	10,200.00	132.60	136.24	-147.13	8,075.54	-892.21	1,308.86	1,130.92	177.94	7.356		
17,500.00	9,101.19	18,688.63	10,200.00	134.22	137.85	-147.13	8,175.53	-892.82	1,308.67	1,128.59	180.08	7.267		
17,600.00	9,101.39	18,788.63	10,200.00	135.85	139.46	-147.12	8,275.53	-893.44	1,308.48	1,126.25	182.23	7.180		
17,700.00	9,101.60	18,888.63	10,200.00	137.47	141.07	-147.12	8,375.53	-894.05	1,308.29	1,123.91	184.38	7.096		
17,800.00	9,101.80	18,988.63	10,200.00	139.09	142.68	-147.12	8,475.53	-894.66	1,308.10	1,121.57	186.53	7.013		
17,900.00	9,102.01	19,088.62	10,200.00	140.72	144.30	-147.11	8,575.53	-895.27	1,307.91	1,119.23	188.68	6.932		
18,000.00	9,102.21	19,188.62	10,200.00	142.34	145.91	-147.11	8,675.52	-895.88	1,307.72	1,116.89	190.83	6.853		
18,100.00	9,102.42	19,288.62	10,200.00	143.96	147.52	-147.10	8,775.52	-896.50	1,307.53	1,114.55	192.98	6.775		
18,200.00	9,102.62	19,388.62	10,200.00	145.59	149.13	-147.10	8,875.52	-897.11	1,307.34	1,112.20	195.13	6.700		
18,300.00	9,102.83	19,488.62	10,200.00	147.22	150.75	-147.10	8,975.52	-897.72	1,307.15	1,109.86	197.29	6.626		
18,400.00	9,103.04	19,588.62	10,200.00	148.84	152.36	-147.09	9,075.52	-898.33	1,306.96	1,107.52	199.44	6.553		
18,500.00	9,103.24	19,688.62	10,200.00	150.47	153.98	-147.09	9,175.51	-898.94	1,306.77	1,105.17	201.60	6.482		
18,600.00	9,103.45	19,788.62	10,200.00	152.09	155.59	-147.09	9,275.51	-899.56	1,306.58	1,102.82	203.75	6.413		
18,700.00	9,103.65	19,888.62	10,200.00	153.72	157.21	-147.08	9,375.51	-900.17	1,306.38	1,100.48	205.91	6.345		
18,800.00	9,103.86	19,988.62	10,200.00	155.35	158.83	-147.08	9,475.51	-900.78	1,306.19	1,098.13	208.06	6.278		
18,900.00	9,104.06	20,088.62	10,200.00	156.97	160.44	-147.07	9,575.51	-901.39	1,306.00	1,095.78	210.22	6.213		
19,000.00	9,104.27	20,188.62	10,200.00	158.60	162.06	-147.07	9,675.50	-902.00	1,305.81	1,093.43	212.38	6.148		
19,100.00	9,104.47	20,288.62	10,200.00	160.23	163.68	-147.07	9,775.50	-902.62	1,305.62	1,091.09	214.54	6.086		
19,200.00	9,104.68	20,388.62	10,200.00	161.86	165.30	-147.06	9,875.50	-903.23	1,305.43	1,088.74	216.70	6.024		
19,279.73	9,104.84	20,465.86	10,200.00	163.15	166.55	-147.06	9,952.74	-903.70	1,305.28	1,086.88	218.41	5.976		
19,300.00	9,104.88	20,465.86	10,200.00	163.48	166.55	-147.06	9,952.74	-903.70	1,305.44	1,086.73	218.71	5.969		
19,356.15	9,105.00	20,465.86	10,200.00	164.40	166.55	-147.06	9,952.74	-903.70	1,307.52	1,088.22	219.30	5.962		

LEAM Drilling Services

Anticollision Report

Company:	Devon Energy	Local Co-ordinate Reference:	Well Belloq 11-2 Fed State Com 524H
Project:	Eddy County, NM (NAD-83)	TVD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Reference Site:	Belloq 11-2 Fed State Com	MD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Belloq 11-2 Fed State Com 524H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	EDM 5000.1 Multi User Db
Reference Design:	Plan #2	Offset TVD Reference:	Offset Datum

Offset Design Belloq 11-2 Fed State Com - Belloq 11-2 Fed State Com 234H (Offset) - OH - Plan #1														Offset Site Error:	0.00 usft
Survey Program: O-LEAM MWD+HDGM														Offset Well Error:	0.00 usft
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning		
Reference	Offset	Reference	Offset	Reference	Offset		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)					
0.00	0.00	0.00	0.00	0.00	0.00	89.88	0.44	209.94	209.94						
100.00	100.00	99.70	99.70	0.09	0.08	89.88	0.44	209.94	209.94	209.77	0.17	1,234.888			
200.00	200.00	199.70	199.70	0.31	0.31	89.88	0.44	209.94	209.94	209.32	0.62	339.096			
300.00	300.00	299.70	299.70	0.54	0.53	89.88	0.44	209.94	209.94	208.87	1.07	196.454			
400.00	400.00	399.70	399.70	0.76	0.76	89.88	0.44	209.94	209.94	208.42	1.52	138.284			
500.00	500.00	499.70	499.70	0.99	0.98	89.88	0.44	209.94	209.94	207.97	1.97	106.693			
600.00	600.00	599.70	599.70	1.21	1.21	89.88	0.44	209.94	209.94	207.52	2.42	86.851			
700.00	700.00	699.70	699.70	1.43	1.43	89.88	0.44	209.94	209.94	207.07	2.87	73.232			
800.00	800.00	799.70	799.70	1.66	1.66	89.88	0.44	209.94	209.94	206.62	3.32	63.305			
900.00	900.00	899.70	899.70	1.88	1.88	89.88	0.44	209.94	209.94	206.17	3.77	55.749			
1,000.00	1,000.00	999.70	999.70	2.11	2.11	89.88	0.44	209.94	209.94	205.73	4.22	49.804			
1,100.00	1,100.00	1,099.70	1,099.70	2.33	2.33	89.88	0.44	209.94	209.94	205.28	4.66	45.004			
1,200.00	1,200.00	1,199.70	1,199.70	2.56	2.56	89.88	0.44	209.94	209.94	204.83	5.11	41.049			
1,300.00	1,300.00	1,299.70	1,299.70	2.78	2.78	89.88	0.44	209.94	209.94	204.38	5.56	37.732			
1,400.00	1,400.00	1,399.70	1,399.70	3.01	3.01	89.88	0.44	209.94	209.94	203.93	6.01	34.912			
1,500.00	1,500.00	1,499.70	1,499.70	3.23	3.23	89.88	0.44	209.94	209.94	203.48	6.46	32.483			
1,600.00	1,600.00	1,599.70	1,599.70	3.46	3.46	89.88	0.44	209.94	209.94	203.03	6.91	30.371			
1,700.00	1,700.00	1,699.70	1,699.70	3.68	3.68	89.88	0.44	209.94	209.94	202.58	7.36	28.516			
1,800.00	1,800.00	1,799.70	1,799.70	3.91	3.90	89.88	0.44	209.94	209.94	202.13	7.81	26.875			
1,900.00	1,900.00	1,899.70	1,899.70	4.13	4.13	89.88	0.44	209.94	209.94	201.68	8.26	25.413			
2,000.00	2,000.00	1,999.70	1,999.70	4.36	4.35	89.88	0.44	209.94	209.94	201.23	8.71	24.101			
2,100.00	2,100.00	2,099.70	2,099.70	4.58	4.58	89.88	0.44	209.94	209.94	200.78	9.16	22.919			
2,200.00	2,200.00	2,199.70	2,199.70	4.81	4.80	89.88	0.44	209.94	209.94	200.33	9.61	21.847			
2,300.00	2,300.00	2,299.70	2,299.70	5.03	5.03	89.88	0.44	209.94	209.94	199.88	10.06	20.870			
2,400.00	2,400.00	2,399.70	2,399.70	5.26	5.25	89.88	0.44	209.94	209.94	199.43	10.51	19.978			
2,500.00	2,500.00	2,499.70	2,499.70	5.48	5.48	89.88	0.44	209.94	209.94	198.98	10.96	19.158 CC			
2,600.00	2,599.99	2,599.69	2,599.69	5.68	5.70	-106.11	0.44	209.94	210.18	198.80	11.38	18.471 ES			
2,700.00	2,699.96	2,699.66	2,699.66	5.85	5.93	-106.78	0.44	209.94	210.92	199.15	11.77	17.915			
2,800.00	2,799.86	2,799.56	2,799.56	6.02	6.15	-107.90	0.44	209.94	212.22	200.05	12.17	17.437			
2,900.00	2,899.68	2,899.38	2,899.38	6.20	6.38	-109.43	0.44	209.94	214.18	201.61	12.57	17.035			
3,000.00	2,999.37	2,999.07	2,999.07	6.38	6.60	-111.35	0.44	209.94	216.92	203.94	12.98	16.712			
3,100.00	3,098.94	3,098.64	3,098.64	6.57	6.82	-113.57	0.44	209.94	220.45	207.06	13.39	16.462			
3,200.00	3,198.51	3,198.21	3,198.21	6.77	7.05	-115.74	0.44	209.94	224.35	210.54	13.81	16.248			
3,300.00	3,298.07	3,297.77	3,297.77	6.97	7.27	-117.83	0.44	209.94	228.56	214.33	14.23	16.063			
3,400.00	3,397.64	3,397.34	3,397.34	7.17	7.50	-119.85	0.44	209.94	233.07	218.42	14.65	15.905			
3,500.00	3,497.20	3,496.90	3,496.90	7.38	7.72	-121.79	0.44	209.94	237.86	222.78	15.08	15.771			
3,600.00	3,596.77	3,596.47	3,596.47	7.60	7.94	-123.65	0.44	209.94	242.91	227.39	15.51	15.659			
3,700.00	3,696.33	3,696.03	3,696.03	7.81	8.17	-125.44	0.44	209.94	248.20	232.26	15.94	15.566			
3,800.00	3,795.90	3,795.60	3,795.60	8.03	8.39	-127.15	0.44	209.94	253.73	237.35	16.38	15.491			
3,900.00	3,895.47	3,895.17	3,895.17	8.26	8.61	-128.78	0.44	209.94	259.47	242.66	16.82	15.431			
4,000.00	3,995.03	3,994.73	3,994.73	8.49	8.84	-130.34	0.44	209.94	265.42	248.17	17.25	15.384			
4,100.00	4,094.60	4,094.30	4,094.30	8.72	9.06	-131.84	0.44	209.94	271.56	253.86	17.69	15.349			
4,200.00	4,194.16	4,193.86	4,193.86	8.95	9.29	-133.26	0.44	209.94	277.87	259.74	18.13	15.325			
4,300.00	4,293.73	4,293.43	4,293.43	9.18	9.51	-134.63	0.44	209.94	284.34	265.77	18.57	15.311			
4,400.00	4,393.29	4,392.99	4,392.99	9.42	9.73	-135.93	0.44	209.94	290.97	271.96	19.01	15.304			
4,500.00	4,492.86	4,492.56	4,492.56	9.66	9.96	-137.17	0.44	209.94	297.75	278.29	19.45	15.305			
4,600.00	4,592.42	4,592.12	4,592.12	9.90	10.18	-138.36	0.44	209.94	304.66	284.76	19.90	15.312			
4,700.00	4,691.99	4,691.69	4,691.69	10.14	10.40	-139.50	0.44	209.94	311.69	291.35	20.34	15.324			
4,800.00	4,791.56	4,791.26	4,791.26	10.39	10.63	-140.58	0.44	209.94	318.84	298.06	20.78	15.341			
4,900.00	4,891.12	4,890.82	4,890.82	10.63	10.85	-141.62	0.44	209.94	326.10	304.87	21.23	15.362			
5,000.00	4,990.69	4,990.39	4,990.39	10.88	11.08	-142.61	0.44	209.94	333.46	311.79	21.67	15.387			
5,100.00	5,090.25	5,089.95	5,089.95	11.13	11.30	-143.56	0.44	209.94	340.92	318.80	22.12	15.415			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

LEAM Drilling Services

Anticollision Report

Company:	Devon Energy	Local Co-ordinate Reference:	Well Belloq 11-2 Fed State Com 524H
Project:	Eddy County, NM (NAD-83)	TVD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Reference Site:	Belloq 11-2 Fed State Com	MD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Belloq 11-2 Fed State Com 524H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	EDM 5000.1 Multi User Db
Reference Design:	Plan #2	Offset TVD Reference:	Offset Datum

Offset Design Belloq 11-2 Fed State Com - Belloq 11-2 Fed State Com 234H (Offset) - OH - Plan #1													Offset Site Error:	0.00 usft
Survey Program: O-LEAM MWD+HDGM													Offset Well Error:	0.00 usft
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference - (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	Offset Wellbore Centre +E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning	
5,200.00	5,189.82	5,189.52	5,189.52	11.37	11.52	-144.47	0.44	209.94	348.46	325.90	22.56	15.446		
5,300.00	5,289.38	5,289.08	5,289.08	11.62	11.75	-145.34	0.44	209.94	356.09	333.09	23.01	15.479		
5,400.00	5,388.95	5,388.65	5,388.65	11.88	11.97	-146.17	0.44	209.94	363.80	340.35	23.45	15.513		
5,500.00	5,488.51	5,488.21	5,488.21	12.13	12.20	-146.97	0.44	209.94	371.58	347.68	23.90	15.550		
5,600.00	5,588.08	5,587.78	5,587.78	12.38	12.42	-147.73	0.44	209.94	379.43	355.09	24.34	15.587		
5,700.00	5,687.65	5,687.35	5,687.35	12.64	12.64	-148.47	0.44	209.94	387.35	362.56	24.79	15.626		
5,800.00	5,787.21	5,786.91	5,786.91	12.89	12.87	-149.17	0.44	209.94	395.32	370.09	25.23	15.666		
5,900.00	5,886.78	5,886.48	5,886.48	13.15	13.09	-149.85	0.44	209.94	403.35	377.67	25.68	15.706		
6,000.00	5,986.34	5,986.04	5,986.04	13.40	13.31	-150.50	0.44	209.94	411.44	385.31	26.13	15.747		
6,100.00	6,085.91	6,085.61	6,085.61	13.66	13.54	-151.13	0.44	209.94	419.58	393.00	26.58	15.788		
6,200.00	6,185.47	6,185.17	6,185.17	13.92	13.76	-151.73	0.44	209.94	427.76	400.74	27.02	15.830		
6,300.00	6,285.04	6,284.74	6,284.74	14.17	13.99	-152.31	0.44	209.94	435.99	408.52	27.47	15.872		
6,400.00	6,384.60	6,384.30	6,384.30	14.43	14.21	-152.86	0.44	209.94	444.27	416.35	27.92	15.914		
6,500.00	6,484.17	6,483.87	6,483.87	14.69	14.43	-153.40	0.44	209.94	452.58	424.22	28.37	15.955		
6,600.00	6,583.74	6,583.44	6,583.44	14.95	14.66	-153.92	0.44	209.94	460.93	432.12	28.81	15.997		
6,700.00	6,683.30	6,683.00	6,683.00	15.21	14.88	-154.42	0.44	209.94	469.32	440.06	29.26	16.039		
6,800.00	6,782.87	6,782.57	6,782.57	15.47	15.10	-154.90	0.44	209.94	477.74	448.03	29.71	16.080		
6,900.00	6,882.43	6,882.13	6,882.13	15.74	15.33	-155.37	0.44	209.94	486.20	456.04	30.16	16.121		
7,000.00	6,982.00	6,981.70	6,981.70	16.00	15.55	-155.82	0.44	209.94	494.68	464.07	30.61	16.162		
7,100.00	7,081.56	7,081.26	7,081.26	16.26	15.78	-156.25	0.44	209.94	503.20	472.14	31.06	16.202		
7,200.00	7,181.13	7,180.83	7,180.83	16.52	16.00	-156.67	0.44	209.94	511.74	480.23	31.51	16.242		
7,300.00	7,280.69	7,280.39	7,280.39	16.78	16.22	-157.07	0.44	209.94	520.31	488.35	31.96	16.282		
7,400.00	7,380.26	7,379.96	7,379.96	17.05	16.45	-157.47	0.44	209.94	528.90	496.50	32.41	16.321		
7,500.00	7,479.83	7,479.53	7,479.53	17.31	16.67	-157.85	0.44	209.94	537.52	504.66	32.86	16.360		
7,600.00	7,579.44	7,579.14	7,579.14	17.55	16.89	-158.22	0.44	209.94	545.66	512.36	33.29	16.398		
7,700.00	7,679.19	7,678.89	7,678.89	17.76	17.12	-158.51	0.44	209.94	552.24	518.52	33.72	16.378		
7,800.00	7,779.04	7,778.74	7,778.74	17.97	17.34	-158.73	0.44	209.94	557.20	523.06	34.14	16.321		
7,900.00	7,878.98	7,878.68	7,878.68	18.16	17.57	-158.88	0.44	209.94	560.55	525.98	34.56	16.219		
8,000.00	7,978.96	7,978.66	7,978.66	18.35	17.79	-158.95	0.44	209.94	562.26	527.28	34.98	16.073		
8,100.00	8,078.96	8,078.66	8,078.66	18.54	18.02	36.80	0.44	209.94	562.52	527.11	35.41	15.887		
8,200.00	8,178.96	8,178.66	8,178.66	18.72	18.24	36.80	0.44	209.94	562.52	526.69	35.83	15.701		
8,300.00	8,278.96	8,278.66	8,278.66	18.90	18.47	36.80	0.44	209.94	562.52	526.27	36.25	15.519		
8,400.00	8,378.96	8,378.66	8,378.66	19.08	18.69	36.80	0.44	209.94	562.52	525.85	36.67	15.341		
8,500.00	8,478.96	8,478.66	8,478.66	19.27	18.92	36.80	0.44	209.94	562.52	525.43	37.09	15.167		
8,600.00	8,578.81	8,578.51	8,578.51	19.43	19.14	37.59	0.44	209.94	559.41	521.91	37.50	14.916		
8,700.00	8,676.61	8,676.31	8,676.31	19.53	19.36	39.91	0.44	209.94	543.47	505.58	37.90	14.341		
8,800.00	8,769.41	8,769.11	8,769.11	19.56	19.57	44.49	0.44	209.94	515.18	476.92	38.26	13.467		
8,900.00	8,854.39	8,854.09	8,854.09	19.55	19.76	51.69	0.44	209.94	477.00	438.42	38.58	12.363		
9,000.00	8,928.97	8,928.67	8,928.67	19.53	19.93	61.56	0.44	209.94	432.98	394.09	38.89	11.133		
9,100.00	8,990.88	8,990.58	8,990.58	19.51	20.07	72.93	0.44	209.94	389.30	350.10	39.20	9.931		
9,200.00	9,038.24	9,037.94	9,037.94	19.55	20.17	83.23	0.44	209.94	354.80	315.25	39.54	8.972		
9,300.00	9,069.61	9,069.31	9,069.31	19.67	20.24	89.72	0.44	209.94	339.89	299.99	39.90	8.519		
9,307.40	9,071.27	9,070.97	9,070.97	19.69	20.25	90.00	0.44	209.94	339.81	299.89	39.92	8.512		
9,400.00	9,084.04	9,083.74	9,083.74	19.91	20.28	90.89	0.44	209.94	351.94	311.80	40.15	8.766		
9,500.00	9,085.13	9,084.83	9,084.83	20.26	20.28	90.06	0.44	209.94	390.10	349.87	40.23	9.696		
9,600.00	9,085.33	9,085.03	9,085.03	20.74	20.28	90.10	0.44	209.94	447.77	407.55	40.23	11.131		
9,700.00	9,085.53	9,085.23	9,085.23	21.34	20.28	90.13	0.44	209.94	518.48	478.29	40.19	12.902		
9,800.00	9,085.73	9,085.43	9,085.43	22.05	20.28	90.16	0.44	209.94	597.61	557.47	40.14	14.889		
9,900.00	9,085.93	9,085.63	9,085.63	22.85	20.28	90.20	0.44	209.94	682.24	642.15	40.10	17.016		
10,000.00	9,086.13	9,085.83	9,085.83	23.73	20.28	90.23	0.44	209.94	770.57	730.51	40.06	19.234		
10,100.00	9,086.33	9,086.03	9,086.03	24.70	20.28	90.27	0.44	209.94	861.45	821.41	40.04	21.516		
10,200.00	9,086.53	9,086.23	9,086.23	25.73	20.28	90.30	0.44	209.94	954.16	914.14	40.02	23.841		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

LEAM Drilling Services

Anticollision Report

Company:	Devon Energy	Local Co-ordinate Reference:	Well Belloq 11-2 Fed State Com 524H
Project:	Eddy County, NM (NAD-83)	TVD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Reference Site:	Belloq 11-2 Fed State Com	MD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Belloq 11-2 Fed State Com 524H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	EDM 5000.1 Multi User Db
Reference Design:	Plan #2	Offset TVD Reference:	Offset Datum

Offset Design													Belloq 11-2 Fed State Com - Belloq 11-2 Fed State Com 234H (Offset) - OH - Plan #1		Offset Site Error: 0.00 usft	
Survey Program: O-LEAM MWD+HDGM													Offset Well Error: 0.00 usft			
Reference		Offset		Semi Major Axis				Distance								
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning			
10,300.00	9,086.72	9,086.42	9,086.42	26.82	20.28	90.33	0.44	209.94	1,048.20	1,008.19	40.01	26.198				
10,400.00	9,086.92	9,086.62	9,086.62	27.97	20.28	90.37	0.44	209.94	1,143.26	1,103.26	40.01	28.576				
10,500.00	9,087.12	9,086.82	9,086.82	29.16	20.28	90.40	0.44	209.94	1,239.10	1,199.09	40.01	30.971				
10,600.00	9,087.32	9,087.02	9,087.02	30.39	20.28	90.43	0.44	209.94	1,335.55	1,295.53	40.01	33.377				
10,700.00	9,087.52	11,607.98	10,460.75	31.66	31.98	166.63	1,391.93	187.58	1,411.77	1,376.58	35.19	40.118				
10,800.00	9,087.72	11,707.98	10,460.60	32.97	33.13	166.61	1,491.93	187.58	1,411.57	1,375.24	36.34	38.846				
10,900.00	9,087.92	11,807.97	10,460.45	34.30	34.32	166.58	1,591.92	187.58	1,411.38	1,373.86	37.52	37.616				
11,000.00	9,088.12	11,907.97	10,460.30	35.66	35.55	166.55	1,691.92	187.58	1,411.19	1,372.45	38.74	36.430				
11,100.00	9,088.32	12,007.97	10,460.14	37.04	36.81	166.52	1,791.92	187.58	1,410.99	1,371.01	39.98	35.290				
11,200.00	9,088.52	12,107.97	10,459.99	38.44	38.09	166.49	1,891.91	187.58	1,410.80	1,369.55	41.26	34.197				
11,300.00	9,088.71	12,207.96	10,459.84	39.86	39.41	166.46	1,991.91	187.58	1,410.61	1,368.06	42.55	33.149				
11,400.00	9,088.91	12,307.96	10,459.69	41.29	40.74	166.44	2,091.91	187.58	1,410.42	1,366.54	43.87	32.147				
11,500.00	9,089.11	12,407.96	10,459.53	42.74	42.10	166.41	2,191.91	187.58	1,410.23	1,365.01	45.22	31.188				
11,600.00	9,089.31	12,507.96	10,459.38	44.20	43.48	166.38	2,291.90	187.58	1,410.03	1,363.46	46.58	30.272				
11,700.00	9,089.51	12,607.95	10,459.23	45.68	44.87	166.35	2,391.90	187.58	1,409.84	1,361.89	47.96	29.398				
11,800.00	9,089.71	12,707.95	10,459.08	47.17	46.28	166.32	2,491.90	187.58	1,409.65	1,360.30	49.35	28.562				
11,900.00	9,089.91	12,807.95	10,458.93	48.66	47.71	166.29	2,591.89	187.58	1,409.46	1,358.70	50.77	27.764				
12,000.00	9,090.11	12,907.95	10,458.77	50.17	49.15	166.26	2,691.89	187.58	1,409.27	1,357.08	52.19	27.002				
12,100.00	9,090.31	13,007.94	10,458.62	51.68	50.60	166.23	2,791.89	187.58	1,409.08	1,355.45	53.63	26.274				
12,200.00	9,090.51	13,107.94	10,458.47	53.20	52.06	166.21	2,891.89	187.58	1,408.89	1,353.81	55.08	25.578				
12,300.00	9,090.70	13,207.94	10,458.32	54.73	53.53	166.18	2,991.88	187.58	1,408.71	1,352.16	56.55	24.913				
12,400.00	9,090.90	13,307.94	10,458.16	56.26	55.01	166.15	3,091.88	187.58	1,408.52	1,350.50	58.02	24.277				
12,500.00	9,091.10	13,407.93	10,458.01	57.80	56.50	166.12	3,191.88	187.58	1,408.33	1,348.83	59.50	23.668				
12,600.00	9,091.30	13,507.93	10,457.86	59.35	58.00	166.09	3,291.88	187.58	1,408.14	1,347.14	61.00	23.085				
12,700.00	9,091.50	13,607.93	10,457.71	60.90	59.51	166.06	3,391.87	187.58	1,407.95	1,345.46	62.50	22.528				
12,800.00	9,091.70	13,707.92	10,457.56	62.45	61.02	166.03	3,491.87	187.58	1,407.77	1,343.76	64.01	21.993				
12,900.00	9,091.90	13,807.92	10,457.40	64.01	62.54	166.01	3,591.87	187.58	1,407.58	1,342.05	65.53	21.480				
13,000.00	9,092.10	13,907.92	10,457.25	65.57	64.06	165.98	3,691.86	187.58	1,407.40	1,340.34	67.05	20.989				
13,100.00	9,092.30	14,007.92	10,457.10	67.14	65.59	165.95	3,791.86	187.58	1,407.21	1,338.62	68.59	20.517				
13,200.00	9,092.50	14,107.91	10,456.95	68.71	67.13	165.92	3,891.86	187.58	1,407.02	1,336.90	70.13	20.064				
13,300.00	9,092.69	14,207.91	10,456.79	70.28	68.67	165.89	3,991.86	187.58	1,406.84	1,335.17	71.67	19.629				
13,400.00	9,092.89	14,307.91	10,456.64	71.86	70.21	165.86	4,091.85	187.58	1,406.65	1,333.43	73.22	19.210				
13,500.00	9,093.09	14,407.91	10,456.49	73.44	71.76	165.83	4,191.85	187.58	1,406.47	1,331.69	74.78	18.808				
13,600.00	9,093.29	14,507.90	10,456.34	75.02	73.31	165.80	4,291.85	187.58	1,406.29	1,329.94	76.35	18.420				
13,700.00	9,093.49	14,607.90	10,456.19	76.60	74.87	165.78	4,391.84	187.58	1,406.10	1,328.19	77.91	18.047				
13,800.00	9,093.69	14,707.90	10,456.03	78.19	76.42	165.75	4,491.84	187.58	1,405.92	1,326.43	79.49	17.687				
13,900.00	9,093.89	14,807.90	10,455.88	79.78	77.99	165.72	4,591.84	187.58	1,405.73	1,324.67	81.07	17.341				
14,000.00	9,094.09	14,907.89	10,455.73	81.37	79.55	165.69	4,691.84	187.58	1,405.55	1,322.90	82.65	17.007				
14,100.00	9,094.29	15,007.89	10,455.58	82.96	81.12	165.66	4,791.83	187.58	1,405.37	1,321.14	84.23	16.684				
14,200.00	9,094.49	15,107.89	10,455.42	84.55	82.69	165.63	4,891.83	187.58	1,405.19	1,319.36	85.83	16.372				
14,300.00	9,094.68	15,207.88	10,455.27	86.15	84.27	165.60	4,991.83	187.58	1,405.01	1,317.58	87.42	16.072				
14,400.00	9,094.88	15,307.88	10,455.12	87.75	85.84	165.57	5,091.83	187.58	1,404.83	1,315.80	89.02	15.781				
14,500.00	9,095.08	15,407.88	10,454.97	89.35	87.42	165.55	5,191.82	187.58	1,404.64	1,314.02	90.62	15.500				
14,600.00	9,095.28	15,507.88	10,454.81	90.95	89.00	165.52	5,291.82	187.58	1,404.46	1,312.23	92.23	15.228				
14,700.00	9,095.48	15,607.87	10,454.66	92.55	90.58	165.49	5,391.82	187.58	1,404.28	1,310.44	93.84	14.964				
14,800.00	9,095.68	15,707.87	10,454.51	94.15	92.17	165.46	5,491.81	187.58	1,404.10	1,308.65	95.46	14.710				
14,823.10	9,095.73	15,730.97	10,454.48	94.50	92.53	165.45	5,514.91	187.58	1,404.08	1,308.25	95.83	14.652				
14,900.00	9,095.88	15,807.85	10,454.36	95.65	93.75	165.38	5,591.79	187.58	1,404.28	1,307.15	97.13	14.458				
15,000.00	9,096.08	15,907.69	10,454.21	97.04	95.34	165.19	5,691.63	187.58	1,405.34	1,306.38	98.97	14.200				
15,100.00	9,096.27	16,007.28	10,454.05	98.44	96.92	164.87	5,791.22	187.58	1,407.34	1,306.34	101.00	13.934				
15,200.00	9,096.46	16,106.49	10,453.90	99.87	98.50	164.44	5,890.43	187.58	1,410.33	1,307.09	103.24	13.661				
15,300.00	9,096.65	16,205.52	10,453.75	101.51	100.08	163.90	5,989.46	187.58	1,413.83	1,308.20	105.62	13.385				

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

LEAM Drilling Services

Anticollision Report

Company:	Devon Energy	Local Co-ordinate Reference:	Well Belloq 11-2 Fed State Com 524H
Project:	Eddy County, NM (NAD-83)	TVD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Reference Site:	Belloq 11-2 Fed State Com	MD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Belloq 11-2 Fed State Com 524H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	EDM 5000.1 Multi User Db
Reference Design:	Plan #2	Offset TVD Reference:	Offset Datum

Offset Design													Belloq 11-2 Fed State Com - Belloq 11-2 Fed State Com 234H (Offset) - OH - Plan #1		Offset Site Error: 0.00 usft	
Survey Program: 0-LEAM MWD+HDGM													Offset Well Error: 0.00 usft			
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Distance		Minimum Separation (usft)	Separation Factor	Warning					
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)				Between Centres (usft)	Between Ellipses (usft)			
15,400.00	9,096.85	16,304.54	10,453.60	103.16	101.65	163.36	6,088.49	187.58	1,417.45	1,309.40	108.05	13.119				
15,500.00	9,097.04	16,403.57	10,453.45	104.79	103.23	162.82	6,187.51	187.58	1,421.20	1,310.69	110.51	12.860				
15,600.00	9,097.23	16,502.86	10,453.30	106.21	104.82	162.29	6,286.80	187.58	1,424.47	1,311.61	112.86	12.622				
15,700.00	9,097.43	16,602.49	10,453.15	107.62	106.41	161.92	6,386.44	187.58	1,426.73	1,311.71	115.02	12.404				
15,800.00	9,097.64	16,702.36	10,453.00	109.03	108.01	161.70	6,486.31	187.58	1,427.94	1,310.96	116.99	12.206				
15,900.00	9,097.84	16,802.35	10,452.84	110.44	109.61	161.63	6,586.29	187.58	1,428.07	1,309.33	118.74	12.027				
16,000.00	9,098.05	16,902.35	10,452.69	112.05	111.21	161.63	6,686.29	187.58	1,427.72	1,307.29	120.43	11.855				
16,100.00	9,098.26	17,002.35	10,452.54	113.67	112.81	161.62	6,786.29	187.58	1,427.37	1,305.24	122.13	11.687				
16,200.00	9,098.47	17,102.35	10,452.39	115.28	114.42	161.62	6,886.29	187.58	1,427.03	1,303.20	123.83	11.524				
16,300.00	9,098.68	17,202.35	10,452.24	116.89	116.02	161.61	6,986.29	187.58	1,426.68	1,301.15	125.53	11.365				
16,400.00	9,098.89	17,302.34	10,452.08	118.50	117.63	161.61	7,086.29	187.58	1,426.33	1,299.10	127.23	11.210				
16,500.00	9,099.10	17,402.32	10,451.93	119.89	119.23	161.70	7,186.26	187.58	1,425.35	1,296.60	128.75	11.070				
16,600.00	9,099.31	17,502.16	10,451.78	121.28	120.84	161.94	7,286.10	187.58	1,423.28	1,293.26	130.03	10.946				
16,700.00	9,099.52	17,601.75	10,451.63	122.65	122.44	162.33	7,385.69	187.58	1,420.17	1,289.13	131.04	10.838				
16,800.00	9,099.73	17,700.97	10,451.48	124.02	124.03	162.87	7,484.91	187.58	1,416.07	1,284.28	131.80	10.744				
16,900.00	9,099.94	17,799.99	10,451.33	125.56	125.63	163.40	7,583.93	187.58	1,411.65	1,279.19	132.47	10.657				
17,000.00	9,100.15	17,899.04	10,451.17	127.07	127.22	163.91	7,682.98	187.58	1,407.40	1,274.27	133.13	10.572				
17,100.00	9,100.36	17,998.41	10,451.02	128.42	128.82	164.28	7,782.35	187.58	1,403.97	1,270.02	133.95	10.481				
17,200.00	9,100.57	18,098.10	10,450.87	129.79	130.43	164.54	7,882.04	187.58	1,401.54	1,266.53	135.01	10.381				
17,300.00	9,100.77	18,198.01	10,450.72	131.18	132.04	164.67	7,981.95	187.58	1,400.08	1,263.76	136.32	10.271				
17,400.00	9,100.98	18,298.00	10,450.57	132.60	133.65	164.69	8,081.94	187.58	1,399.53	1,261.66	137.87	10.151				
17,500.00	9,101.19	18,398.00	10,450.41	134.22	135.27	164.66	8,181.94	187.58	1,399.36	1,259.80	139.56	10.027				
17,600.00	9,101.39	18,497.99	10,450.26	135.85	136.88	164.63	8,281.93	187.58	1,399.18	1,257.94	141.24	9.906				
17,700.00	9,101.60	18,597.99	10,450.11	137.47	138.49	164.61	8,381.93	187.58	1,399.01	1,256.08	142.93	9.788				
17,800.00	9,101.80	18,697.99	10,449.96	139.09	140.11	164.58	8,481.93	187.58	1,398.84	1,254.22	144.62	9.673				
17,900.00	9,102.01	18,797.99	10,449.81	140.72	141.72	164.55	8,581.93	187.58	1,398.66	1,252.35	146.31	9.560				
18,000.00	9,102.21	18,897.98	10,449.65	142.34	143.34	164.52	8,681.92	187.58	1,398.49	1,250.49	148.00	9.449				
18,100.00	9,102.42	18,997.98	10,449.50	143.96	144.96	164.49	8,781.92	187.58	1,398.32	1,248.62	149.70	9.341				
18,200.00	9,102.62	19,097.98	10,449.35	145.59	146.57	164.46	8,881.92	187.58	1,398.14	1,246.75	151.39	9.235				
18,300.00	9,102.83	19,197.97	10,449.20	147.22	148.19	164.43	8,981.91	187.58	1,397.97	1,244.88	153.09	9.132				
18,400.00	9,103.04	19,297.97	10,449.04	148.84	149.81	164.40	9,081.91	187.58	1,397.80	1,243.01	154.79	9.030				
18,500.00	9,103.24	19,397.97	10,448.89	150.47	151.43	164.37	9,181.91	187.58	1,397.63	1,241.13	156.50	8.931				
18,600.00	9,103.45	19,497.97	10,448.74	152.09	153.05	164.34	9,281.91	187.58	1,397.46	1,239.26	158.20	8.833				
18,700.00	9,103.65	19,597.96	10,448.59	153.72	154.66	164.31	9,381.90	187.58	1,397.29	1,237.38	159.91	8.738				
18,800.00	9,103.86	19,697.96	10,448.44	155.35	156.28	164.28	9,481.90	187.58	1,397.12	1,235.50	161.62	8.645				
18,900.00	9,104.06	19,797.96	10,448.28	156.97	157.90	164.25	9,581.90	187.58	1,396.95	1,233.62	163.33	8.553				
19,000.00	9,104.27	19,897.96	10,448.13	158.60	159.52	164.22	9,681.89	187.58	1,396.78	1,231.74	165.04	8.463				
19,088.29	9,104.45	19,983.89	10,448.00	160.04	160.92	164.20	9,767.83	187.58	1,396.63	1,230.11	166.52	8.387				
19,100.00	9,104.47	19,983.89	10,448.00	160.23	160.92	164.20	9,767.83	187.58	1,396.68	1,230.11	166.58	8.385 SF				
19,200.00	9,104.68	19,983.89	10,448.00	161.86	160.92	164.20	9,767.83	187.58	1,401.09	1,234.50	166.60	8.410				
19,300.00	9,104.88	19,983.89	10,448.00	163.48	160.92	164.20	9,767.83	187.58	1,412.59	1,246.71	165.88	8.516				
19,356.15	9,105.00	19,983.89	10,448.00	164.40	160.92	164.20	9,767.83	187.58	1,422.09	1,256.92	165.17	8.610				

LEAM Drilling Services

Anticollision Report

Company:	Devon Energy	Local Co-ordinate Reference:	Well Belloq 11-2 Fed State Com 524H
Project:	Eddy County, NM (NAD-83)	TVD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Reference Site:	Belloq 11-2 Fed State Com	MD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Belloq 11-2 Fed State Com 524H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	EDM 5000.1 Multi User Db
Reference Design:	Plan #2	Offset TVD Reference:	Offset Datum

Offset Design Belloq 11-2 Fed State Com - Belloq 11-2 Fed State Com 512H - OH - Plan #1														Offset Site Error:	0.00 usft
Survey Program: 0-LEAM MWD+HDGM														Offset Well Error:	0.00 usft
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference	Offset	Semi Major Axis	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning	
7,200.00	7,181.13	7,326.10	7,306.27	16.52	17.15	73.71		-432.12	-2,097.78	1,992.21	1,959.59	32.62	61.064		
7,300.00	7,280.69	7,425.46	7,405.20	16.78	17.41	73.82		-437.07	-2,089.84	1,981.66	1,948.54	33.12	59.828		
7,400.00	7,380.26	7,520.68	7,499.99	17.05	17.66	73.93		-441.81	-2,082.24	1,971.13	1,937.51	33.61	58.640		
7,500.00	7,479.83	7,600.00	7,579.01	17.31	17.85	74.03		-445.47	-2,076.37	1,961.20	1,927.14	34.06	57.575		
7,600.00	7,579.44	7,678.26	7,657.06	17.55	18.01	74.07		-448.51	-2,071.49	1,952.57	1,918.10	34.47	56.643		
7,700.00	7,679.19	7,755.69	7,734.34	17.76	18.17	74.08		-450.97	-2,067.55	1,945.55	1,910.71	34.84	55.842		
7,800.00	7,779.04	7,833.25	7,811.82	17.97	18.32	74.09		-452.87	-2,064.49	1,940.15	1,904.95	35.20	55.121		
7,900.00	7,878.98	7,900.00	7,878.54	18.16	18.44	74.09		-454.07	-2,062.57	1,936.42	1,900.90	35.52	54.510		
8,000.00	7,978.96	7,988.65	7,967.17	18.35	18.60	74.09		-455.02	-2,061.04	1,934.23	1,898.36	35.88	53.913		
8,100.00	8,078.96	8,068.04	8,046.56	18.54	18.75	-90.16		-455.26	-2,060.66	1,933.67	1,897.45	36.22	53.391		
8,200.00	8,178.96	8,168.04	8,146.56	18.72	18.94	-90.16		-455.26	-2,060.66	1,933.67	1,897.07	36.60	52.839		
8,300.00	8,278.96	8,268.04	8,246.56	18.90	19.13	-90.16		-455.26	-2,060.66	1,933.67	1,896.69	36.98	52.296		
8,300.70	8,279.66	8,268.75	8,247.26	18.90	19.13	-90.16		-455.26	-2,060.66	1,933.67	1,896.69	36.98	52.292		
8,400.00	8,378.96	8,367.58	8,346.07	19.08	19.31	-90.13		-454.25	-2,060.67	1,933.67	1,896.32	37.35	51.770		
8,500.00	8,478.96	8,464.08	8,441.47	19.27	19.46	-89.72		-440.45	-2,060.76	1,933.79	1,896.10	37.68	51.318		
8,600.00	8,578.81	8,554.86	8,527.91	19.43	19.57	-88.60		-413.04	-2,060.93	1,934.28	1,896.33	37.95	50.973		
8,700.00	8,676.61	8,642.09	8,605.90	19.53	19.64	-87.86		-374.16	-2,061.18	1,935.10	1,896.98	38.11	50.771		
8,800.00	8,769.41	8,726.61	8,675.00	19.56	19.68	-87.17		-325.63	-2,061.49	1,936.13	1,897.92	38.21	50.672		
8,900.00	8,854.39	8,808.95	8,734.76	19.55	19.71	-86.56		-269.08	-2,061.86	1,937.27	1,899.00	38.27	50.620		
9,000.00	8,928.97	8,889.58	8,784.82	19.53	19.72	-86.04		-205.97	-2,062.26	1,938.40	1,900.05	38.35	50.546		
9,100.00	8,990.88	8,968.89	8,824.96	19.51	19.73	-85.62		-137.64	-2,062.70	1,939.41	1,900.91	38.49	50.383		
9,200.00	9,038.24	9,050.00	8,855.86	19.55	19.76	-85.30		-62.71	-2,063.18	1,940.21	1,901.46	38.76	50.063		
9,300.00	9,069.61	9,124.98	8,874.75	19.67	19.89	-85.12		9.79	-2,063.65	1,940.73	1,901.58	39.15	49.572		
9,400.00	9,084.04	9,200.00	8,884.02	19.91	20.19	-85.04		84.18	-2,064.12	1,940.94	1,901.24	39.70	48.889		
9,500.00	9,085.13	9,293.03	8,884.91	20.26	20.69	-85.04		177.19	-2,064.72	1,940.95	1,900.42	40.53	47.891		
9,600.00	9,085.33	9,393.03	8,884.76	20.74	21.34	-85.03		277.19	-2,065.36	1,940.98	1,899.35	41.62	46.631		
9,700.00	9,085.53	9,493.03	8,884.61	21.34	22.09	-85.02		377.19	-2,066.01	1,941.01	1,898.07	42.94	45.203		
9,800.00	9,085.73	9,593.03	8,884.45	22.05	22.92	-85.01		477.18	-2,066.65	1,941.05	1,896.59	44.46	43.661		
9,900.00	9,085.93	9,693.03	8,884.30	22.85	23.84	-85.00		577.18	-2,067.29	1,941.08	1,894.93	46.16	42.055		
10,000.00	9,086.13	9,793.03	8,884.15	23.73	24.82	-84.99		677.18	-2,067.93	1,941.11	1,893.10	48.02	40.425		
10,100.00	9,086.33	9,893.03	8,884.00	24.70	25.88	-84.98		777.18	-2,068.57	1,941.15	1,891.13	50.02	38.805		
10,200.00	9,086.53	9,993.03	8,883.85	25.73	26.98	-84.97		877.17	-2,069.22	1,941.18	1,889.03	52.16	37.218		
10,300.00	9,086.72	10,093.03	8,883.70	26.82	28.14	-84.96		977.17	-2,069.86	1,941.22	1,886.81	54.40	35.682		
10,400.00	9,086.92	10,193.03	8,883.55	27.97	29.35	-84.95		1,077.17	-2,070.50	1,941.25	1,884.50	56.75	34.207		
10,500.00	9,087.12	10,293.03	8,883.40	29.16	30.59	-84.94		1,177.17	-2,071.14	1,941.29	1,882.10	59.18	32.801		
10,600.00	9,087.32	10,393.03	8,883.24	30.39	31.87	-84.93		1,277.16	-2,071.78	1,941.32	1,879.63	61.69	31.467		
10,700.00	9,087.52	10,493.03	8,883.09	31.66	33.18	-84.92		1,377.16	-2,072.43	1,941.35	1,877.08	64.27	30.205		
10,800.00	9,087.72	10,593.03	8,882.94	32.97	34.52	-84.91		1,477.16	-2,073.07	1,941.39	1,874.48	66.91	29.014		
10,900.00	9,087.92	10,693.03	8,882.79	34.30	35.88	-84.90		1,577.15	-2,073.71	1,941.42	1,871.82	69.60	27.892		
11,000.00	9,088.12	10,793.02	8,882.64	35.66	37.27	-84.89		1,677.15	-2,074.35	1,941.46	1,869.11	72.34	26.836		
11,100.00	9,088.32	10,893.02	8,882.49	37.04	38.67	-84.88		1,777.15	-2,075.00	1,941.49	1,866.37	75.13	25.843		
11,200.00	9,088.52	10,993.02	8,882.34	38.44	40.10	-84.86		1,877.15	-2,075.64	1,941.53	1,863.58	77.95	24.908		
11,300.00	9,088.71	11,093.02	8,882.18	39.86	41.54	-84.85		1,977.14	-2,076.28	1,941.56	1,860.76	80.80	24.029		
11,400.00	9,088.91	11,193.02	8,882.03	41.29	42.99	-84.84		2,077.14	-2,076.92	1,941.60	1,857.91	83.68	23.201		
11,500.00	9,089.11	11,293.02	8,881.88	42.74	44.45	-84.83		2,177.14	-2,077.56	1,941.63	1,855.04	86.60	22.422		
11,600.00	9,089.31	11,393.02	8,881.73	44.20	45.93	-84.82		2,277.13	-2,078.21	1,941.67	1,852.14	89.53	21.687		
11,700.00	9,089.51	11,493.02	8,881.58	45.68	47.42	-84.81		2,377.13	-2,078.85	1,941.70	1,849.21	92.49	20.994		
11,800.00	9,089.71	11,593.02	8,881.43	47.17	48.92	-84.80		2,477.13	-2,079.49	1,941.74	1,846.27	95.47	20.339		
11,900.00	9,089.91	11,693.02	8,881.28	48.66	50.42	-84.79		2,577.13	-2,080.13	1,941.77	1,843.31	98.46	19.721		
12,000.00	9,090.11	11,793.02	8,881.12	50.17	51.94	-84.78		2,677.12	-2,080.77	1,941.81	1,840.33	101.48	19.136		
12,100.00	9,090.31	11,893.02	8,880.97	51.68	53.46	-84.77		2,777.12	-2,081.42	1,941.84	1,837.34	104.50	18.581		
12,200.00	9,090.51	11,993.02	8,880.82	53.20	54.99	-84.76		2,877.12	-2,082.06	1,941.88	1,834.33	107.55	18.056		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

LEAM Drilling Services

Anticollision Report

Company:	Devon Energy	Local Co-ordinate Reference:	Well Belloq 11-2 Fed State Com 524H
Project:	Eddy County, NM (NAD-83)	TVD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Reference Site:	Belloq 11-2 Fed State Com	MD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Belloq 11-2 Fed State Com 524H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	EDM 5000.1 Multi User Db
Reference Design:	Plan #2	Offset TVD Reference:	Offset Datum

Offset Design													Offset Site Error: 0.00 usft	
Belloq 11-2 Fed State Com - Belloq 11-2 Fed State Com 512H - OH - Plan #1													Offset Well Error: 0.00 usft	
Survey Program: O-LEAM MWD+HDGM														
Reference		Offset		Semi Major Axis		Distance							Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor		
12,300.00	9,090.70	12,093.02	8,880.67	54.73	56.52	-84.75	2,977.11	-2,082.70	1,941.92	1,831.31	110.60	17.558		
12,400.00	9,090.90	12,193.02	8,880.52	56.26	58.06	-84.74	3,077.11	-2,083.34	1,941.95	1,828.28	113.67	17.084		
12,500.00	9,091.10	12,293.02	8,880.37	57.80	59.61	-84.73	3,177.11	-2,083.98	1,941.99	1,825.24	116.75	16.634		
12,600.00	9,091.30	12,393.02	8,880.22	59.35	61.16	-84.72	3,277.11	-2,084.63	1,942.02	1,822.19	119.83	16.206		
12,700.00	9,091.50	12,493.01	8,880.07	60.90	62.71	-84.71	3,377.10	-2,085.27	1,942.06	1,819.13	122.93	15.798		
12,800.00	9,091.70	12,593.01	8,879.91	62.45	64.27	-84.70	3,477.10	-2,085.91	1,942.09	1,816.06	126.03	15.409		
12,900.00	9,091.90	12,693.01	8,879.76	64.01	65.84	-84.69	3,577.10	-2,086.55	1,942.13	1,812.98	129.15	15.038		
13,000.00	9,092.10	12,793.01	8,879.61	65.57	67.40	-84.68	3,677.10	-2,087.20	1,942.17	1,809.90	132.27	14.684		
13,100.00	9,092.30	12,893.01	8,879.46	67.14	68.97	-84.67	3,777.09	-2,087.84	1,942.20	1,806.81	135.39	14.345		
13,200.00	9,092.50	12,993.01	8,879.31	68.71	70.55	-84.66	3,877.09	-2,088.48	1,942.24	1,803.71	138.53	14.021		
13,300.00	9,092.69	13,093.01	8,879.16	70.28	72.12	-84.65	3,977.09	-2,089.12	1,942.27	1,800.61	141.67	13.710		
13,400.00	9,092.89	13,193.01	8,879.01	71.86	73.70	-84.64	4,077.08	-2,089.76	1,942.31	1,797.50	144.81	13.413		
13,500.00	9,093.09	13,293.01	8,878.85	73.44	75.28	-84.63	4,177.08	-2,090.41	1,942.35	1,794.38	147.96	13.127		
13,600.00	9,093.29	13,393.01	8,878.70	75.02	76.87	-84.62	4,277.08	-2,091.05	1,942.38	1,791.26	151.12	12.853		
13,700.00	9,093.49	13,493.01	8,878.55	76.60	78.45	-84.61	4,377.08	-2,091.69	1,942.42	1,788.14	154.28	12.590		
13,800.00	9,093.69	13,593.01	8,878.40	78.19	80.04	-84.60	4,477.07	-2,092.33	1,942.45	1,785.01	157.44	12.338		
13,900.00	9,093.89	13,693.01	8,878.25	79.78	81.63	-84.59	4,577.07	-2,092.97	1,942.49	1,781.88	160.61	12.095		
14,000.00	9,094.09	13,793.01	8,878.10	81.37	83.23	-84.58	4,677.07	-2,093.62	1,942.53	1,778.75	163.78	11.861		
14,100.00	9,094.29	13,893.01	8,877.95	82.96	84.82	-84.57	4,777.06	-2,094.26	1,942.56	1,775.61	166.95	11.635		
14,200.00	9,094.49	13,993.01	8,877.79	84.55	86.42	-84.56	4,877.06	-2,094.90	1,942.60	1,772.47	170.13	11.418		
14,300.00	9,094.68	14,093.00	8,877.64	86.15	88.01	-84.55	4,977.06	-2,095.54	1,942.64	1,769.32	173.31	11.209		
14,400.00	9,094.88	14,193.00	8,877.49	87.75	89.61	-84.54	5,077.06	-2,096.19	1,942.67	1,766.18	176.50	11.007		
14,500.00	9,095.08	14,293.00	8,877.34	89.35	91.21	-84.53	5,177.05	-2,096.83	1,942.71	1,763.03	179.69	10.812		
14,600.00	9,095.28	14,393.00	8,877.19	90.95	92.81	-84.52	5,277.05	-2,097.47	1,942.75	1,759.87	182.88	10.623		
14,700.00	9,095.48	14,493.00	8,877.04	92.55	94.42	-84.50	5,377.05	-2,098.11	1,942.79	1,756.72	186.07	10.441		
14,800.00	9,095.68	14,593.00	8,876.89	94.15	96.02	-84.49	5,477.05	-2,098.75	1,942.82	1,753.56	189.26	10.265		
14,900.00	9,095.88	14,692.99	8,876.74	95.65	97.63	-84.47	5,577.03	-2,099.40	1,941.46	1,749.11	192.35	10.093		
15,000.00	9,096.08	14,792.86	8,876.58	97.04	99.23	-84.44	5,676.90	-2,100.04	1,936.64	1,741.32	195.33	9.915		
15,100.00	9,096.27	14,892.51	8,876.43	98.44	100.83	-84.38	5,776.54	-2,100.68	1,928.36	1,730.05	198.31	9.724		
15,200.00	9,096.46	14,991.80	8,876.28	99.87	102.43	-84.31	5,875.84	-2,101.31	1,916.64	1,715.32	201.31	9.521		
15,300.00	9,096.65	15,090.91	8,876.13	101.51	104.03	-84.26	5,974.95	-2,101.95	1,903.45	1,698.93	204.52	9.307		
15,400.00	9,096.85	15,190.03	8,875.98	103.16	105.62	-84.21	6,074.06	-2,102.59	1,890.27	1,682.54	207.73	9.100		
15,500.00	9,097.04	15,289.14	8,875.83	104.79	107.22	-84.16	6,173.17	-2,103.22	1,877.10	1,666.17	210.93	8.899		
15,600.00	9,097.23	15,388.50	8,875.68	106.21	108.82	-84.14	6,272.53	-2,103.86	1,865.92	1,652.00	213.92	8.722		
15,700.00	9,097.43	15,488.19	8,875.53	107.62	110.43	-84.13	6,372.21	-2,104.50	1,858.21	1,641.29	216.92	8.566		
15,800.00	9,097.64	15,588.09	8,875.38	109.03	112.04	-84.12	6,472.11	-2,105.14	1,853.95	1,634.03	219.92	8.430		
15,878.19	9,097.80	15,666.27	8,875.26	110.13	113.30	-84.11	6,550.29	-2,105.65	1,852.96	1,630.69	222.27	8.336 CC		
15,900.00	9,097.84	15,688.08	8,875.23	110.44	113.66	-84.11	6,572.10	-2,105.79	1,853.16	1,630.23	222.93	8.313		
16,000.00	9,098.05	15,788.08	8,875.08	112.05	115.27	-84.10	6,672.10	-2,106.43	1,853.85	1,627.70	226.14	8.198		
16,100.00	9,098.26	15,888.08	8,874.93	113.67	116.89	-84.09	6,772.09	-2,107.07	1,854.53	1,625.18	229.35	8.086		
16,200.00	9,098.47	15,988.07	8,874.78	115.28	118.51	-84.08	6,872.09	-2,107.71	1,855.21	1,622.65	232.57	7.977		
16,300.00	9,098.68	16,088.07	8,874.62	116.89	120.12	-84.07	6,972.08	-2,108.35	1,855.90	1,620.11	235.79	7.871		
16,400.00	9,098.89	16,188.07	8,874.47	118.50	121.74	-84.06	7,072.08	-2,109.00	1,856.59	1,617.60	238.99	7.768		
16,500.00	9,099.10	16,288.03	8,874.32	119.89	123.36	-84.06	7,172.03	-2,109.64	1,859.28	1,617.29	242.00	7.683		
16,600.00	9,099.31	16,387.83	8,874.17	121.28	124.97	-84.06	7,271.84	-2,110.28	1,865.44	1,620.45	244.99	7.614		
16,700.00	9,099.52	16,487.36	8,874.02	122.65	126.59	-84.06	7,371.36	-2,110.92	1,875.06	1,627.09	247.97	7.562		
16,800.00	9,099.73	16,586.49	8,873.87	124.02	128.19	-84.07	7,470.49	-2,111.55	1,888.12	1,637.17	250.95	7.524		
16,900.00	9,099.94	16,685.43	8,873.72	125.56	129.80	-84.11	7,569.43	-2,112.19	1,902.64	1,648.53	254.10	7.488		
17,000.00	9,100.15	16,784.39	8,873.57	127.07	131.40	-84.15	7,668.38	-2,112.82	1,917.00	1,659.78	257.22	7.453		
17,100.00	9,100.36	16,883.68	8,873.42	128.42	133.01	-84.19	7,767.67	-2,113.46	1,928.80	1,668.62	260.18	7.413		
17,200.00	9,100.57	16,983.32	8,873.27	129.79	134.63	-84.22	7,867.32	-2,114.10	1,937.14	1,673.97	263.16	7.361		
17,300.00	9,100.77	17,083.20	8,873.12	131.18	136.25	-84.23	7,967.19	-2,114.74	1,942.01	1,675.85	266.16	7.296		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

LEAM Drilling Services

Anticollision Report

Company:	Devon Energy	Local Co-ordinate Reference:	Well Belloq 11-2 Fed State Com 524H
Project:	Eddy County, NM (NAD-83)	TVD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Reference Site:	Belloq 11-2 Fed State Com	MD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Belloq 11-2 Fed State Com 524H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	EDM 5000.1 Multi User Db
Reference Design:	Plan #2	Offset TVD Reference:	Offset Datum

Offset Design													Offset Site Error: 0.00 usft	
Survey Program: O-LEAM MWD+HDGM													Offset Well Error: 0.00 usft	
Reference		Offset		Semi Major Axis			Distance							
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning	
17,400.00	9,100.98	17,183.18	8,872.97	132.60	137.87	-84.22	8,067.17	-2,115.39	1,943.43	1,674.24	269.20	7.219		
17,500.00	9,101.19	17,283.18	8,872.82	134.22	139.49	-84.21	8,167.17	-2,116.03	1,943.46	1,671.04	272.42	7.134		
17,600.00	9,101.39	17,383.18	8,872.66	135.85	141.12	-84.20	8,267.17	-2,116.67	1,943.50	1,667.84	275.65	7.050		
17,700.00	9,101.60	17,483.18	8,872.51	137.47	142.74	-84.19	8,367.16	-2,117.31	1,943.53	1,664.65	278.88	6.969		
17,800.00	9,101.80	17,583.18	8,872.36	139.09	144.36	-84.18	8,467.16	-2,117.95	1,943.56	1,661.45	282.12	6.889		
17,900.00	9,102.01	17,683.18	8,872.21	140.72	145.99	-84.17	8,567.16	-2,118.60	1,943.60	1,658.25	285.35	6.811		
18,000.00	9,102.21	17,783.18	8,872.06	142.34	147.61	-84.16	8,667.16	-2,119.24	1,943.63	1,655.05	288.58	6.735		
18,100.00	9,102.42	17,883.18	8,871.91	143.96	149.24	-84.15	8,767.15	-2,119.88	1,943.67	1,651.85	291.81	6.661		
18,200.00	9,102.62	17,983.18	8,871.76	145.59	150.86	-84.14	8,867.15	-2,120.52	1,943.70	1,648.65	295.05	6.588		
18,300.00	9,102.83	18,083.18	8,871.60	147.22	152.49	-84.13	8,967.15	-2,121.16	1,943.73	1,645.45	298.28	6.516		
18,400.00	9,103.04	18,183.18	8,871.45	148.84	154.12	-84.12	9,067.14	-2,121.81	1,943.77	1,642.25	301.51	6.447		
18,500.00	9,103.24	18,283.18	8,871.30	150.47	155.74	-84.11	9,167.14	-2,122.45	1,943.80	1,639.05	304.75	6.378		
18,600.00	9,103.45	18,383.18	8,871.15	152.09	157.37	-84.10	9,267.14	-2,123.09	1,943.83	1,635.85	307.98	6.311		
18,700.00	9,103.65	18,483.18	8,871.00	153.72	159.00	-84.09	9,367.14	-2,123.73	1,943.87	1,632.65	311.22	6.246		
18,800.00	9,103.86	18,583.18	8,870.85	155.35	160.62	-84.08	9,467.13	-2,124.38	1,943.90	1,629.45	314.45	6.182		
18,900.00	9,104.06	18,683.18	8,870.70	156.97	162.25	-84.07	9,567.13	-2,125.02	1,943.94	1,626.25	317.69	6.119		
19,000.00	9,104.27	18,783.17	8,870.54	158.60	163.88	-84.06	9,667.13	-2,125.66	1,943.97	1,623.04	320.93	6.057		
19,100.00	9,104.47	18,883.17	8,870.39	160.23	165.51	-84.05	9,767.12	-2,126.30	1,944.01	1,619.84	324.16	5.997		
19,200.00	9,104.68	18,983.17	8,870.24	161.86	167.14	-84.03	9,867.12	-2,126.94	1,944.04	1,616.64	327.40	5.938		
19,300.00	9,104.88	19,083.17	8,870.09	163.48	168.76	-84.02	9,967.12	-2,127.59	1,944.07	1,613.43	330.64	5.880		
19,356.15	9,105.00	19,139.32	8,870.01	164.40	169.68	-84.02	10,023.27	-2,127.95	1,944.09	1,611.63	332.46	5.848 ES, SF		

LEAM Drilling Services

Anticollision Report

Company:	Devon Energy	Local Co-ordinate Reference:	Well: Belloq 11-2 Fed State Com 524H
Project:	Eddy County, NM (NAD-83)	TVD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Reference Site:	Belloq 11-2 Fed State Com	MD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Belloq 11-2 Fed State Com 524H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	EDM 5000.1 Multi User Db
Reference Design:	Plan #2	Offset TVD Reference:	Offset Datum

Offset Design Belloq 11-2 Fed State Com - Belloq 11-2 Fed State Com 513H - OH - Plan #2													Offset Site Error:	0.00 usft
Survey Program: 0-LEAM MWD+HDGM													Offset Well Error:	0.00 usft
Reference	Offset	Semi Major Axis		Distance		Minimum		Separation		Warning				
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor		
0.00	0.00	0.00	0.00	0.00	0.00	-90.11	-2.41	-1,219.77	1,219.83					
100.00	100.00	87.90	87.90	0.09	0.08	-90.11	-2.41	-1,219.77	1,219.77	1,219.61	0.16	7,550.737		
200.00	200.00	187.90	187.90	0.31	0.28	-90.11	-2.41	-1,219.77	1,219.77	1,219.18	0.59	2,052.516		
300.00	300.00	287.90	287.90	0.54	0.51	-90.11	-2.41	-1,219.77	1,219.77	1,218.73	1.04	1,168.573		
400.00	400.00	387.90	387.90	0.76	0.73	-90.11	-2.41	-1,219.77	1,219.77	1,218.28	1.49	816.805		
500.00	500.00	487.90	487.90	0.99	0.96	-90.11	-2.41	-1,219.77	1,219.77	1,217.83	1.94	627.817		
600.00	600.00	587.90	587.90	1.21	1.18	-90.11	-2.41	-1,219.77	1,219.77	1,217.38	2.39	509.851		
700.00	700.00	687.90	687.90	1.43	1.41	-90.11	-2.41	-1,219.77	1,219.77	1,216.93	2.84	429.204		
800.00	800.00	787.90	787.90	1.66	1.63	-90.11	-2.41	-1,219.77	1,219.77	1,216.48	3.29	370.585		
900.00	900.00	887.90	887.90	1.88	1.86	-90.11	-2.41	-1,219.77	1,219.77	1,216.03	3.74	326.055		
1,000.00	1,000.00	987.90	987.90	2.11	2.08	-90.11	-2.41	-1,219.77	1,219.77	1,215.58	4.19	291.078		
1,100.00	1,100.00	1,087.90	1,087.90	2.33	2.31	-90.11	-2.41	-1,219.77	1,219.77	1,215.13	4.64	262.878		
1,200.00	1,200.00	1,187.90	1,187.90	2.56	2.53	-90.11	-2.41	-1,219.77	1,219.77	1,214.68	5.09	239.660		
1,300.00	1,300.00	1,287.90	1,287.90	2.78	2.76	-90.11	-2.41	-1,219.77	1,219.77	1,214.23	5.54	220.210		
1,400.00	1,400.00	1,387.90	1,387.90	3.01	2.98	-90.11	-2.41	-1,219.77	1,219.77	1,213.78	5.99	203.680		
1,500.00	1,500.00	1,487.90	1,487.90	3.23	3.21	-90.11	-2.41	-1,219.77	1,219.77	1,213.33	6.44	189.459		
1,600.00	1,600.00	1,587.90	1,587.90	3.46	3.43	-90.11	-2.41	-1,219.77	1,219.77	1,212.88	6.89	177.094		
1,700.00	1,700.00	1,687.90	1,687.90	3.68	3.66	-90.11	-2.41	-1,219.77	1,219.77	1,212.44	7.34	166.244		
1,800.00	1,800.00	1,787.90	1,787.90	3.91	3.88	-90.11	-2.41	-1,219.77	1,219.77	1,211.99	7.79	156.646		
1,900.00	1,900.00	1,887.90	1,887.90	4.13	4.10	-90.11	-2.41	-1,219.77	1,219.77	1,211.54	8.24	148.097		
2,000.00	2,000.00	1,987.90	1,987.90	4.36	4.33	-90.11	-2.41	-1,219.77	1,219.77	1,211.09	8.69	140.432		
2,100.00	2,100.00	2,087.90	2,087.90	4.58	4.55	-90.11	-2.41	-1,219.77	1,219.77	1,210.64	9.14	133.522		
2,200.00	2,200.00	2,187.90	2,187.90	4.81	4.78	-90.11	-2.41	-1,219.77	1,219.77	1,210.19	9.58	127.259		
2,300.00	2,300.00	2,287.90	2,287.90	5.03	5.00	-90.11	-2.41	-1,219.77	1,219.77	1,209.74	10.03	121.558		
2,400.00	2,400.00	2,387.90	2,387.90	5.26	5.23	-90.11	-2.41	-1,219.77	1,219.77	1,209.29	10.48	116.346		
2,500.00	2,500.00	2,487.90	2,487.90	5.48	5.45	-90.11	-2.41	-1,219.77	1,219.77	1,208.84	10.93	111.563		
2,600.00	2,599.99	2,606.01	2,606.00	5.68	5.69	74.16	-2.99	-1,218.98	1,218.88	1,207.51	11.37	107.222		
2,700.00	2,699.96	2,726.53	2,726.47	5.85	5.91	74.23	-5.07	-1,216.17	1,215.84	1,204.08	11.75	103.458		
2,800.00	2,799.86	2,846.87	2,846.65	6.02	6.14	74.35	-8.65	-1,211.33	1,210.63	1,198.49	12.14	99.716		
2,900.00	2,899.68	2,966.93	2,966.41	6.20	6.37	74.52	-13.72	-1,204.48	1,203.28	1,190.74	12.53	95.996		
3,000.00	2,999.37	3,086.62	3,085.59	6.38	6.61	74.73	-20.25	-1,195.65	1,193.78	1,180.85	12.93	92.294		
3,100.00	3,098.94	3,195.79	3,194.10	6.57	6.84	74.89	-27.37	-1,186.02	1,182.48	1,169.14	13.33	88.703		
3,200.00	3,198.51	3,295.09	3,292.78	6.77	7.05	75.01	-34.00	-1,177.05	1,170.95	1,157.22	13.73	85.313		
3,300.00	3,298.07	3,394.40	3,391.46	6.97	7.27	75.13	-40.64	-1,168.07	1,159.42	1,145.29	14.13	82.062		
3,400.00	3,397.64	3,493.70	3,490.13	7.17	7.50	75.25	-47.28	-1,159.10	1,147.90	1,133.36	14.54	78.948		
3,500.00	3,497.20	3,593.01	3,588.81	7.38	7.73	75.37	-53.91	-1,150.12	1,136.39	1,121.43	14.96	75.969		
3,600.00	3,596.77	3,692.31	3,687.48	7.60	7.96	75.50	-60.55	-1,141.15	1,124.88	1,109.50	15.38	73.121		
3,700.00	3,696.33	3,791.62	3,786.16	7.81	8.20	75.63	-67.19	-1,132.18	1,113.38	1,097.56	15.82	70.398		
3,800.00	3,795.90	3,890.92	3,884.83	8.03	8.44	75.76	-73.82	-1,123.20	1,101.88	1,085.63	16.25	67.797		
3,900.00	3,895.47	3,990.23	3,983.51	8.26	8.68	75.89	-80.46	-1,114.23	1,090.39	1,073.69	16.69	65.312		
4,000.00	3,995.03	4,089.53	4,082.19	8.49	8.93	76.03	-87.10	-1,105.25	1,078.90	1,061.76	17.14	62.939		
4,100.00	4,094.60	4,188.84	4,180.86	8.72	9.17	76.17	-93.73	-1,096.28	1,067.42	1,049.83	17.59	60.671		
4,200.00	4,194.16	4,288.14	4,279.54	8.95	9.42	76.31	-100.37	-1,087.31	1,055.95	1,037.90	18.05	58.504		
4,300.00	4,293.73	4,387.45	4,378.21	9.18	9.68	76.45	-107.01	-1,078.33	1,044.48	1,025.97	18.51	56.433		
4,400.00	4,393.29	4,486.75	4,476.89	9.42	9.93	76.60	-113.64	-1,069.36	1,033.02	1,014.05	18.97	54.452		
4,500.00	4,492.86	4,586.06	4,575.56	9.66	10.19	76.75	-120.28	-1,060.38	1,021.57	1,002.13	19.44	52.558		
4,600.00	4,592.42	4,685.36	4,674.24	9.90	10.45	76.91	-126.92	-1,051.41	1,010.12	990.21	19.91	50.745		
4,700.00	4,691.99	4,784.67	4,772.92	10.14	10.71	77.07	-133.55	-1,042.44	998.68	978.30	20.38	49.010		
4,800.00	4,791.56	4,883.97	4,871.59	10.39	10.97	77.23	-140.19	-1,033.46	987.25	966.40	20.85	47.347		
4,900.00	4,891.12	4,983.28	4,970.27	10.63	11.23	77.40	-146.82	-1,024.49	975.83	954.50	21.33	45.754		
5,000.00	4,990.69	5,082.58	5,068.94	10.88	11.50	77.57	-153.46	-1,015.51	964.41	942.61	21.81	44.227		
5,100.00	5,090.25	5,181.89	5,167.62	11.13	11.76	77.74	-160.10	-1,006.54	953.01	930.72	22.29	42.762		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

LEAM Drilling Services

Anticollision Report

Company:	Devon Energy	Local Co-ordinate Reference:	Well Belloq 11-2 Fed State Com 524H
Project:	Eddy County, NM (NAD-83)	TVD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Reference Site:	Belloq 11-2 Fed State Com	MD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Belloq 11-2 Fed State Com 524H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	EDM 5000.1 Multi User Db
Reference Design:	Plan #2	Offset TVD Reference:	Offset Datum

Offset Design Belloq 11-2 Fed State Com - Belloq 11-2 Fed State Com 513H - OH - Plan #2														Offset Site Error:	0.00 usft
Survey Program: O-LEAM MWD+HDGM														Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning		
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)					
5,200.00	5,189.82	5,281.19	5,266.30	11.37	12.03	77.92	-166.73	-997.56	941.61	918.84	22.77	41.356			
5,300.00	5,289.38	5,380.50	5,364.97	11.62	12.30	78.11	-173.37	-988.59	930.22	906.97	23.25	40.006			
5,400.00	5,388.95	5,479.80	5,463.65	11.88	12.57	78.29	-180.01	-979.62	918.85	895.11	23.74	38.708			
5,500.00	5,488.51	5,579.11	5,562.32	12.13	12.84	78.49	-186.64	-970.64	907.48	883.25	24.22	37.461			
5,600.00	5,588.08	5,678.41	5,661.00	12.38	13.11	78.68	-193.28	-961.67	896.12	871.41	24.71	36.262			
5,700.00	5,687.65	5,777.72	5,759.67	12.64	13.38	78.89	-199.92	-952.69	884.78	859.57	25.20	35.107			
5,800.00	5,787.21	5,877.02	5,858.35	12.89	13.65	79.09	-206.55	-943.72	873.44	847.75	25.69	33.996			
5,900.00	5,886.78	5,976.33	5,957.03	13.15	13.93	79.31	-213.19	-934.75	862.12	835.93	26.18	32.925			
6,000.00	5,986.34	6,075.63	6,055.70	13.40	14.20	79.53	-219.83	-925.77	850.80	824.13	26.68	31.894			
6,100.00	6,085.91	6,174.94	6,154.38	13.66	14.48	79.75	-226.46	-916.80	839.51	812.34	27.17	30.899			
6,200.00	6,185.47	6,274.24	6,253.05	13.92	14.75	79.98	-233.10	-907.82	828.22	800.56	27.66	29.939			
6,300.00	6,285.04	6,373.55	6,351.73	14.17	15.03	80.22	-239.74	-898.85	816.95	788.79	28.16	29.013			
6,400.00	6,384.60	6,472.85	6,450.40	14.43	15.30	80.46	-246.37	-889.88	805.69	777.04	28.65	28.118			
6,500.00	6,484.17	6,572.16	6,549.08	14.69	15.58	80.71	-253.01	-880.90	794.45	765.30	29.15	27.254			
6,600.00	6,583.74	6,671.46	6,647.78	14.95	15.86	80.97	-259.64	-871.93	783.22	753.57	29.65	26.419			
6,700.00	6,683.30	6,770.77	6,746.43	15.21	16.13	81.23	-266.28	-862.95	772.01	741.86	30.14	25.612			
6,800.00	6,782.87	6,870.07	6,845.11	15.47	16.41	81.51	-272.92	-853.98	760.81	730.17	30.64	24.831			
6,900.00	6,882.43	6,969.38	6,943.78	15.74	16.69	81.79	-279.55	-845.01	749.63	718.50	31.14	24.076			
7,000.00	6,982.00	7,068.68	7,042.46	16.00	16.97	82.08	-286.19	-836.03	738.48	706.84	31.63	23.344			
7,100.00	7,081.56	7,167.99	7,141.13	16.26	17.25	82.38	-292.83	-827.06	727.34	695.20	32.13	22.636			
7,200.00	7,181.13	7,267.29	7,239.81	16.52	17.53	82.69	-299.46	-818.08	716.22	683.59	32.63	21.950			
7,300.00	7,280.69	7,366.60	7,338.49	16.78	17.81	83.00	-306.10	-809.11	705.12	671.99	33.13	21.285			
7,400.00	7,380.26	7,465.90	7,437.16	17.05	18.09	83.33	-312.74	-800.13	694.04	660.42	33.63	20.641			
7,500.00	7,479.83	7,560.13	7,530.81	17.31	18.34	83.66	-318.91	-791.78	683.19	649.07	34.11	20.026			
7,600.00	7,579.44	7,650.11	7,620.37	17.55	18.55	83.92	-324.06	-784.82	673.65	639.09	34.56	19.491			
7,700.00	7,679.19	7,740.33	7,710.30	17.76	18.74	84.10	-328.39	-778.97	665.71	630.75	34.96	19.040			
7,800.00	7,779.04	7,830.76	7,800.54	17.97	18.92	84.22	-331.87	-774.26	659.37	624.01	35.35	18.652			
7,900.00	7,878.98	7,921.35	7,891.02	18.16	19.10	84.29	-334.52	-770.68	654.61	618.89	35.73	18.323			
8,000.00	7,978.96	8,012.04	7,981.66	18.35	19.27	84.28	-336.31	-768.25	651.45	615.36	36.09	18.052			
8,100.00	8,078.96	8,102.80	8,072.41	18.54	19.43	-80.01	-337.26	-766.98	649.86	613.41	36.45	17.831			
8,183.71	8,162.67	8,180.96	8,150.57	18.69	19.57	-80.02	-337.41	-766.77	649.60	612.86	36.74	17.680			
8,200.00	8,178.96	8,197.26	8,166.86	18.72	19.60	-80.02	-337.41	-766.77	649.60	612.80	36.80	17.650			
8,300.00	8,278.96	8,297.26	8,266.86	18.90	19.78	-80.02	-337.41	-766.77	649.60	612.42	37.18	17.471			
8,304.75	8,283.71	8,302.01	8,271.61	18.91	19.79	-80.02	-337.41	-766.77	649.60	612.40	37.20	17.463			
8,400.00	8,378.96	8,390.48	8,360.06	19.08	19.95	-79.94	-336.46	-766.78	649.81	612.28	37.53	17.314			
8,500.00	8,478.96	8,472.03	8,440.87	19.27	20.06	-79.03	-325.99	-766.84	652.27	614.49	37.78	17.266			
8,600.00	8,578.81	8,550.00	8,516.00	19.43	20.14	-76.81	-305.36	-766.98	657.21	619.29	37.91	17.334			
8,700.00	8,676.61	8,626.30	8,586.15	19.53	20.18	-75.06	-275.48	-767.17	662.10	624.19	37.91	17.463			
8,800.00	8,769.41	8,700.00	8,649.56	19.56	20.20	-73.70	-238.02	-767.42	666.35	628.56	37.79	17.632			
8,900.00	8,854.39	8,775.48	8,708.97	19.55	20.20	-72.69	-191.55	-767.72	669.61	631.98	37.62	17.797			
9,000.00	8,928.97	8,850.00	8,761.13	19.53	20.18	-72.10	-138.41	-768.07	671.62	634.17	37.45	17.932			
9,100.00	8,990.88	8,922.43	8,804.82	19.51	20.16	-71.93	-80.70	-768.44	672.25	634.90	37.35	17.998			
9,200.00	9,038.24	9,000.00	8,843.13	19.55	20.12	-72.18	-13.32	-768.88	671.45	634.02	37.43	17.939			
9,300.00	9,069.61	9,069.46	8,869.44	19.67	20.08	-72.81	50.91	-769.30	669.25	631.58	37.67	17.766			
9,400.00	9,084.04	9,143.72	8,888.75	19.91	20.06	-73.86	122.56	-769.77	665.85	627.67	38.18	17.441			
9,500.00	9,085.13	9,219.22	8,898.72	20.26	20.12	-74.74	197.34	-770.25	662.55	623.66	38.89	17.036			
9,548.00	9,085.23	9,256.02	8,900.00	20.49	20.25	-74.84	234.12	-770.49	662.15	622.88	39.27	16.862			
9,600.00	9,085.33	9,307.33	8,899.92	20.74	20.49	-74.83	285.43	-770.83	662.20	622.47	39.73	16.668			
9,700.00	9,085.53	9,407.33	8,899.77	21.34	21.06	-74.80	385.43	-771.48	662.30	621.49	40.81	16.228			
9,800.00	9,085.73	9,507.33	8,899.62	22.05	21.75	-74.77	485.43	-772.13	662.41	620.30	42.11	15.731			
9,900.00	9,085.93	9,607.33	8,899.46	22.85	22.52	-74.74	585.42	-772.78	662.51	618.91	43.60	15.195			
10,000.00	9,086.13	9,707.33	8,899.31	23.73	23.38	-74.71	685.42	-773.43	662.62	617.35	45.27	14.638			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

LEAM Drilling Services

Anticollision Report

Company:	Devon Energy	Local Co-ordinate Reference:	Well Belloq 11-2 Fed State Com 524H
Project:	Eddy County, NM (NAD-83)	TVD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Reference Site:	Belloq 11-2 Fed State Com	MD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Belloq 11-2 Fed State Com 524H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	EDM 5000.1 Multi User Db
Reference Design:	Plan #2	Offset TVD Reference:	Offset Datum

Offset Design: Belloq 11-2 Fed State Com - Belloq 11-2 Fed State Com 513H - OH - Plan #2												Offset Site Error:	0.00 usft
Survey Program: O-LEAM MWD+HDGM												Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference	Offset		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)			
10,100.00	9,086.33	9,807.33	8,899.16	24.70	24.32	-74.68	785.42	-774.09	662.72	615.64	47.09	14.074	
10,200.00	9,086.53	9,907.33	8,899.00	25.73	25.32	-74.65	885.41	-774.74	662.83	613.78	49.05	13.513	
10,300.00	9,086.72	10,007.33	8,898.85	26.82	26.39	-74.62	985.41	-775.39	662.94	611.80	51.14	12.964	
10,400.00	9,086.92	10,107.33	8,898.70	27.97	27.51	-74.60	1,085.41	-776.04	663.04	609.71	53.33	12.433	
10,500.00	9,087.12	10,207.33	8,898.54	29.16	28.68	-74.57	1,185.41	-776.69	663.15	607.53	55.62	11.924	
10,600.00	9,087.32	10,307.33	8,898.39	30.39	29.89	-74.54	1,285.40	-777.34	663.25	605.27	57.99	11.438	
10,700.00	9,087.52	10,407.33	8,898.24	31.66	31.14	-74.51	1,385.40	-778.00	663.36	602.93	60.43	10.977	
10,800.00	9,087.72	10,507.33	8,898.09	32.97	32.42	-74.48	1,485.40	-778.65	663.47	600.52	62.94	10.541	
10,900.00	9,087.92	10,607.33	8,897.93	34.30	33.74	-74.45	1,585.39	-779.30	663.57	598.06	65.51	10.129	
11,000.00	9,088.12	10,707.33	8,897.78	35.66	35.08	-74.42	1,685.39	-779.95	663.68	595.55	68.13	9.741	
11,100.00	9,088.32	10,807.33	8,897.63	37.04	36.44	-74.39	1,785.39	-780.60	663.79	592.99	70.79	9.376	
11,200.00	9,088.52	10,907.32	8,897.47	38.44	37.83	-74.36	1,885.39	-781.25	663.90	590.40	73.50	9.033	
11,300.00	9,088.71	11,007.32	8,897.32	39.86	39.24	-74.33	1,985.38	-781.90	664.00	587.76	76.24	8.710	
11,400.00	9,088.91	11,107.32	8,897.17	41.29	40.66	-74.31	2,085.38	-782.56	664.11	585.10	79.01	8.405	
11,500.00	9,089.11	11,207.32	8,897.01	42.74	42.10	-74.28	2,185.38	-783.21	664.22	582.41	81.81	8.119	
11,600.00	9,089.31	11,307.32	8,896.86	44.20	43.55	-74.25	2,285.37	-783.86	664.33	579.69	84.64	7.849	
11,700.00	9,089.51	11,407.32	8,896.71	45.68	45.02	-74.22	2,385.37	-784.51	664.43	576.95	87.49	7.595	
11,800.00	9,089.71	11,507.32	8,896.55	47.17	46.49	-74.19	2,485.37	-785.16	664.54	574.19	90.36	7.355	
11,900.00	9,089.91	11,607.32	8,896.40	48.66	47.98	-74.16	2,585.37	-785.81	664.65	571.41	93.25	7.128	
12,000.00	9,090.11	11,707.32	8,896.25	50.17	49.48	-74.13	2,685.36	-786.47	664.76	568.61	96.15	6.914	
12,100.00	9,090.31	11,807.32	8,896.10	51.68	50.98	-74.10	2,785.36	-787.12	664.87	565.80	99.07	6.711	
12,200.00	9,090.51	11,907.32	8,895.94	53.20	52.50	-74.07	2,885.36	-787.77	664.98	562.97	102.01	6.519	
12,300.00	9,090.70	12,007.32	8,895.79	54.73	54.02	-74.05	2,985.35	-788.42	665.09	560.13	104.96	6.337	
12,400.00	9,090.90	12,107.32	8,895.64	56.26	55.54	-74.02	3,085.35	-789.07	665.20	557.28	107.92	6.164	
12,500.00	9,091.10	12,207.32	8,895.48	57.80	57.08	-73.99	3,185.35	-789.72	665.30	554.42	110.89	6.000	
12,600.00	9,091.30	12,307.32	8,895.33	59.35	58.62	-73.96	3,285.35	-790.37	665.41	551.55	113.87	5.844	
12,700.00	9,091.50	12,407.32	8,895.18	60.90	60.16	-73.93	3,385.34	-791.03	665.52	548.67	116.86	5.695	
12,800.00	9,091.70	12,507.31	8,895.02	62.45	61.71	-73.90	3,485.34	-791.68	665.63	545.78	119.86	5.554	
12,900.00	9,091.90	12,607.31	8,894.87	64.01	63.27	-73.87	3,585.34	-792.33	665.74	542.88	122.86	5.419	
13,000.00	9,092.10	12,707.31	8,894.72	65.57	64.82	-73.84	3,685.33	-792.98	665.85	539.98	125.88	5.290	
13,100.00	9,092.30	12,807.31	8,894.56	67.14	66.39	-73.81	3,785.33	-793.63	665.97	537.07	128.90	5.167	
13,200.00	9,092.50	12,907.31	8,894.41	68.71	67.95	-73.79	3,885.33	-794.28	666.08	534.16	131.92	5.049	
13,300.00	9,092.69	13,007.31	8,894.26	70.28	69.52	-73.76	3,985.33	-794.94	666.19	531.24	134.95	4.937	
13,400.00	9,092.89	13,107.31	8,894.11	71.86	71.09	-73.73	4,085.32	-795.59	666.30	528.31	137.99	4.829	
13,500.00	9,093.09	13,207.31	8,893.95	73.44	72.67	-73.70	4,185.32	-796.24	666.41	525.38	141.03	4.725	
13,600.00	9,093.29	13,307.31	8,893.80	75.02	74.25	-73.67	4,285.32	-796.89	666.52	522.45	144.07	4.626	
13,700.00	9,093.49	13,407.31	8,893.65	76.60	75.83	-73.64	4,385.31	-797.54	666.63	519.51	147.12	4.531	
13,800.00	9,093.69	13,507.31	8,893.49	78.19	77.41	-73.61	4,485.31	-798.19	666.74	516.57	150.17	4.440	
13,900.00	9,093.89	13,607.31	8,893.34	79.78	79.00	-73.59	4,585.31	-798.84	666.85	513.63	153.23	4.352	
14,000.00	9,094.09	13,707.31	8,893.19	81.37	80.58	-73.56	4,685.31	-799.50	666.97	510.68	156.29	4.268	
14,100.00	9,094.29	13,807.31	8,893.03	82.96	82.17	-73.53	4,785.30	-800.15	667.08	507.73	159.35	4.186	
14,200.00	9,094.49	13,907.31	8,892.88	84.55	83.76	-73.50	4,885.30	-800.80	667.19	504.78	162.42	4.108	
14,300.00	9,094.68	14,007.31	8,892.73	86.15	85.36	-73.47	4,985.30	-801.45	667.30	501.82	165.48	4.032	
14,400.00	9,094.88	14,107.30	8,892.57	87.75	86.95	-73.44	5,085.29	-802.10	667.42	498.86	168.55	3.960	
14,500.00	9,095.08	14,207.30	8,892.42	89.35	88.55	-73.41	5,185.29	-802.75	667.53	495.90	171.63	3.889	
14,600.00	9,095.28	14,307.30	8,892.27	90.95	90.15	-73.38	5,285.29	-803.41	667.64	492.94	174.70	3.822	
14,700.00	9,095.48	14,407.30	8,892.12	92.55	91.75	-73.36	5,385.29	-804.06	667.76	489.98	177.78	3.756	
14,800.00	9,095.68	14,507.30	8,891.96	94.15	93.35	-73.33	5,485.28	-804.71	667.87	487.01	180.85	3.693	
14,900.00	9,095.88	14,607.29	8,891.81	95.65	94.95	-73.25	5,585.27	-805.36	666.64	482.83	183.81	3.627	
15,000.00	9,096.08	14,707.16	8,891.66	97.04	96.55	-73.07	5,685.14	-806.01	662.08	475.50	186.58	3.548	
15,100.00	9,096.27	14,806.81	8,891.50	98.44	98.15	-72.78	5,784.78	-806.66	654.20	464.91	189.29	3.456	
15,200.00	9,096.46	14,906.10	8,891.35	99.87	99.75	-72.37	5,884.08	-807.31	643.03	451.10	191.93	3.350	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

LEAM Drilling Services

Anticollision Report

Company:	Devon Energy	Local Co-ordinate Reference:	Well Belloq 11-2 Fed State Com 524H
Project:	Eddy County, NM (NAD-83)	TVD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Reference Site:	Belloq 11-2 Fed State Com	MD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Belloq 11-2 Fed State Com 524H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	EDM 5000.1 Multi User Db
Reference Design:	Plan #2	Offset TVD Reference:	Offset Datum

Offset Design														Offset Site Error: 0.00 usft	
Belloq 11-2 Fed State Com - Belloq 11-2 Fed State Com 513H - OH - Plan #2														Offset Well Error: 0.00 usft	
Survey Program: O-LEAM MWD+HDGM															
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Distance		Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning		
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)							
15,300.00	9,096.65	15,005.22	8,891.20	101.51	101.34	-71.98	5,983.19	-807.95	630.49	435.78	194.71	3.238			
15,400.00	9,096.85	15,104.33	8,891.05	103.16	102.93	-71.57	6,082.30	-808.60	617.98	420.52	197.46	3.130			
15,500.00	9,097.04	15,203.45	8,890.90	104.79	104.53	-71.15	6,181.41	-809.24	605.51	405.34	200.17	3.025			
15,600.00	9,097.23	15,302.81	8,890.74	106.21	106.13	-70.84	6,280.77	-809.89	594.97	392.26	202.70	2.935			
15,700.00	9,097.43	15,402.50	8,890.59	107.62	107.73	-70.61	6,380.46	-810.54	587.73	382.41	205.32	2.862			
15,800.00	9,097.64	15,502.40	8,890.44	109.03	109.34	-70.47	6,480.36	-811.19	583.79	375.76	208.04	2.806			
15,874.69	9,097.79	15,577.08	8,890.32	110.08	110.55	-70.42	6,555.04	-811.68	582.93	372.79	210.14	2.774 CC			
15,900.00	9,097.84	15,602.39	8,890.29	110.44	110.96	-70.42	6,580.35	-811.84	583.14	372.27	210.87	2.765			
16,000.00	9,098.05	15,702.39	8,890.13	112.05	112.57	-70.40	6,680.34	-812.50	583.88	369.95	213.93	2.729			
16,100.00	9,098.26	15,802.39	8,889.98	113.67	114.18	-70.39	6,780.34	-813.15	584.63	367.63	217.00	2.694			
16,200.00	9,098.47	15,902.38	8,889.83	115.28	115.80	-70.38	6,880.33	-813.80	585.37	365.30	220.07	2.660			
16,300.00	9,098.68	16,002.38	8,889.67	116.89	117.41	-70.37	6,980.33	-814.45	586.11	362.97	223.14	2.627			
16,400.00	9,098.89	16,102.38	8,889.52	118.50	119.03	-70.36	7,080.32	-815.10	586.87	360.66	226.20	2.594			
16,500.00	9,099.10	16,202.34	8,889.37	119.89	120.65	-70.40	7,180.28	-815.75	589.51	360.37	229.14	2.573			
16,600.00	9,099.31	16,302.14	8,889.21	121.28	122.26	-70.53	7,280.08	-816.40	595.44	363.24	232.20	2.564			
16,700.00	9,099.52	16,401.67	8,889.06	122.65	123.87	-70.74	7,379.61	-817.05	604.66	369.30	235.36	2.569			
16,800.00	9,099.73	16,500.80	8,888.91	124.02	125.48	-71.04	7,478.74	-817.70	617.17	378.55	238.62	2.586			
16,900.00	9,099.94	16,599.73	8,888.76	125.56	127.08	-71.44	7,577.67	-818.34	631.09	389.01	242.08	2.607			
17,000.00	9,100.15	16,698.69	8,888.61	127.07	128.68	-71.84	7,676.62	-818.99	644.90	399.41	245.48	2.627			
17,100.00	9,100.36	16,797.98	8,888.46	128.42	130.29	-72.20	7,775.91	-819.63	656.26	407.61	248.65	2.639			
17,200.00	9,100.57	16,897.63	8,888.30	129.79	131.90	-72.43	7,875.55	-820.28	664.33	412.60	251.73	2.639			
17,300.00	9,100.77	16,997.50	8,888.15	131.18	133.52	-72.56	7,975.43	-820.93	669.09	414.34	254.74	2.627			
17,400.00	9,100.98	17,097.49	8,888.00	132.60	135.14	-72.57	8,075.41	-821.59	670.53	412.85	257.69	2.602			
17,500.00	9,101.19	17,197.48	8,887.84	134.22	136.77	-72.54	8,175.41	-822.24	670.65	409.87	260.78	2.572			
17,600.00	9,101.39	17,297.48	8,887.69	135.85	138.39	-72.51	8,275.40	-822.89	670.76	406.89	263.88	2.542			
17,700.00	9,101.60	17,397.48	8,887.54	137.47	140.01	-72.48	8,375.40	-823.54	670.88	403.91	266.97	2.513			
17,800.00	9,101.80	17,497.48	8,887.38	139.09	141.63	-72.45	8,475.40	-824.19	670.99	400.93	270.06	2.485			
17,900.00	9,102.01	17,597.48	8,887.23	140.72	143.26	-72.42	8,575.39	-824.84	671.10	397.95	273.16	2.457			
18,000.00	9,102.21	17,697.48	8,887.08	142.34	144.88	-72.39	8,675.39	-825.49	671.22	394.97	276.25	2.430			
18,100.00	9,102.42	17,797.48	8,886.93	143.96	146.51	-72.36	8,775.39	-826.15	671.33	391.99	279.34	2.403			
18,200.00	9,102.62	17,897.48	8,886.77	145.59	148.13	-72.34	8,875.39	-826.80	671.45	389.01	282.44	2.377			
18,300.00	9,102.83	17,997.48	8,886.62	147.22	149.75	-72.31	8,975.38	-827.45	671.56	386.04	285.53	2.352			
18,400.00	9,103.04	18,097.48	8,886.47	148.84	151.38	-72.28	9,075.38	-828.10	671.68	383.06	288.62	2.327			
18,500.00	9,103.24	18,197.48	8,886.31	150.47	153.01	-72.25	9,175.38	-828.75	671.80	380.08	291.71	2.303			
18,600.00	9,103.45	18,297.48	8,886.16	152.09	154.63	-72.22	9,275.37	-829.40	671.91	377.11	294.81	2.279			
18,700.00	9,103.65	18,397.48	8,886.01	153.72	156.26	-72.19	9,375.37	-830.06	672.03	374.13	297.90	2.256			
18,800.00	9,103.86	18,497.48	8,885.85	155.35	157.88	-72.16	9,475.37	-830.71	672.14	371.15	300.99	2.233			
18,900.00	9,104.06	18,597.48	8,885.70	156.97	159.51	-72.13	9,575.37	-831.36	672.26	368.18	304.08	2.211			
19,000.00	9,104.27	18,697.48	8,885.55	158.60	161.14	-72.10	9,675.36	-832.01	672.38	365.21	307.17	2.189			
19,100.00	9,104.47	18,797.47	8,885.39	160.23	162.77	-72.07	9,775.36	-832.66	672.49	362.23	310.26	2.168			
19,200.00	9,104.68	18,897.47	8,885.24	161.86	164.39	-72.05	9,875.36	-833.31	672.61	359.26	313.35	2.147			
19,300.00	9,104.88	18,997.47	8,885.09	163.48	166.02	-72.02	9,975.35	-833.96	672.73	356.29	316.44	2.126			
19,356.15	9,105.00	19,053.62	8,885.00	164.40	166.93	-72.00	10,031.50	-834.33	672.79	354.62	318.18	2.115 ES, SF			

LEAM Drilling Services

Anticollision Report

Company:	Devon Energy	Local Co-ordinate Reference:	Well Belloq 11-2 Fed State Com 524H
Project:	Eddy County, NM (NAD-83)	TVD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Reference Site:	Belloq 11-2 Fed State Com	MD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Belloq 11-2 Fed State Com 524H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	EDM 5000.1 Multi User Db
Reference Design:	Plan #2	Offset TVD Reference:	Offset Datum

Offset Design													Belloq 11-2 Fed State Com - Belloq 11-2 Fed State Com 514H - OH - Plan #2		Offset Site Error: 0.00 usft	
Survey Program: O-LEAM MWD+HDGM													Offset Well Error: 0.00 usft			
Reference		Offset		Semi Major Axis		Distance							Warning			
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor				
0.00	0.00	0.00	0.00	0.00	0.00	89.89	0.06	29.99	29.99							
100.00	100.00	99.90	99.90	0.09	0.09	89.89	0.06	29.99	29.99	29.82	0.17	174.503				
200.00	200.00	199.90	199.90	0.31	0.31	89.89	0.06	29.99	29.99	29.37	0.62	48.273				
300.00	300.00	299.90	299.90	0.54	0.54	89.89	0.06	29.99	29.99	28.92	1.07	28.008				
400.00	400.00	399.90	399.90	0.76	0.76	89.89	0.06	29.99	29.99	28.47	1.52	19.726				
500.00	500.00	499.90	499.90	0.99	0.98	89.89	0.06	29.99	29.99	28.02	1.97	15.225				
600.00	600.00	599.90	599.90	1.21	1.21	89.89	0.06	29.99	29.99	27.57	2.42	12.396				
700.00	700.00	699.90	699.90	1.43	1.43	89.89	0.06	29.99	29.99	27.12	2.87	10.453				
800.00	800.00	799.90	799.90	1.66	1.66	89.89	0.06	29.99	29.99	26.67	3.32	9.037				
900.00	900.00	899.90	899.90	1.88	1.88	89.89	0.06	29.99	29.99	26.22	3.77	7.959				
1,000.00	1,000.00	999.90	999.90	2.11	2.11	89.89	0.06	29.99	29.99	25.77	4.22	7.111				
1,100.00	1,100.00	1,099.90	1,099.90	2.33	2.33	89.89	0.06	29.99	29.99	25.32	4.67	6.426				
1,200.00	1,200.00	1,199.90	1,199.90	2.56	2.56	89.89	0.06	29.99	29.99	24.87	5.12	5.861				
1,300.00	1,300.00	1,299.90	1,299.90	2.78	2.78	89.89	0.06	29.99	29.99	24.42	5.57	5.388				
1,400.00	1,400.00	1,399.90	1,399.90	3.01	3.01	89.89	0.06	29.99	29.99	23.97	6.02	4.985				
1,500.00	1,500.00	1,499.90	1,499.90	3.23	3.23	89.89	0.06	29.99	29.99	23.52	6.47	4.639				
1,600.00	1,600.00	1,599.90	1,599.90	3.46	3.46	89.89	0.06	29.99	29.99	23.08	6.91	4.337				
1,700.00	1,700.00	1,699.90	1,699.90	3.68	3.68	89.89	0.06	29.99	29.99	22.63	7.36	4.072				
1,800.00	1,800.00	1,799.90	1,799.90	3.91	3.91	89.89	0.06	29.99	29.99	22.18	7.81	3.838				
1,900.00	1,900.00	1,899.90	1,899.90	4.13	4.13	89.89	0.06	29.99	29.99	21.73	8.26	3.629				
2,000.00	2,000.00	1,999.90	1,999.90	4.36	4.36	89.89	0.06	29.99	29.99	21.28	8.71	3.442				
2,100.00	2,100.00	2,099.90	2,099.90	4.58	4.58	89.89	0.06	29.99	29.99	20.83	9.16	3.273				
2,200.00	2,200.00	2,199.90	2,199.90	4.81	4.81	89.89	0.06	29.99	29.99	20.38	9.61	3.120				
2,300.00	2,300.00	2,299.90	2,299.90	5.03	5.03	89.89	0.06	29.99	29.99	19.93	10.06	2.981				
2,400.00	2,400.00	2,399.90	2,399.90	5.26	5.26	89.89	0.06	29.99	29.99	19.48	10.51	2.853				
2,500.00	2,500.00	2,499.90	2,499.90	5.48	5.48	89.89	0.06	29.99	29.99	19.03	10.96	2.736 CC, ES				
2,600.00	2,599.99	2,599.51	2,599.51	5.68	5.68	-106.32	-0.53	30.62	30.86	19.51	11.35	2.718				
2,700.00	2,699.96	2,699.07	2,699.03	5.85	5.86	-107.52	-2.29	32.52	33.50	21.80	11.70	2.863				
2,800.00	2,799.86	2,798.54	2,798.40	6.02	6.04	-109.15	-5.23	35.68	37.91	25.86	12.05	3.146				
2,900.00	2,899.68	2,897.85	2,897.53	6.20	6.23	-110.86	-9.34	40.10	44.13	31.72	12.41	3.557				
3,000.00	2,999.37	2,996.97	2,996.35	6.38	6.42	-112.46	-14.61	45.76	52.16	39.39	12.77	4.084				
3,100.00	3,098.94	3,095.87	3,094.80	6.57	6.62	-113.57	-21.02	52.66	61.85	48.71	13.15	4.705				
3,200.00	3,198.51	3,194.56	3,192.86	6.77	6.82	-113.41	-28.57	60.78	72.67	59.15	13.53	5.373				
3,300.00	3,298.07	3,293.16	3,290.63	6.97	7.04	-112.42	-37.24	70.11	84.57	70.65	13.92	6.077				
3,400.00	3,397.64	3,392.39	3,388.96	7.17	7.26	-111.42	-46.33	79.88	96.84	82.51	14.33	6.759				
3,500.00	3,497.20	3,491.62	3,487.29	7.38	7.49	-110.65	-55.42	89.66	109.13	94.38	14.75	7.400				
3,600.00	3,596.77	3,590.86	3,585.62	7.60	7.72	-110.03	-64.51	99.44	121.44	106.26	15.18	8.002				
3,700.00	3,696.33	3,690.09	3,683.95	7.81	7.97	-109.53	-73.60	109.22	133.75	118.14	15.61	8.567				
3,800.00	3,795.90	3,789.32	3,782.28	8.03	8.21	-109.11	-82.69	118.99	146.08	130.03	16.06	9.098				
3,900.00	3,895.47	3,888.55	3,880.61	8.26	8.46	-108.76	-91.78	128.77	158.41	141.91	16.51	9.597				
4,000.00	3,995.03	3,987.79	3,978.94	8.49	8.72	-108.45	-100.87	138.55	170.75	153.79	16.96	10.067				
4,100.00	4,094.60	4,087.02	4,077.27	8.72	8.98	-108.19	-109.96	148.32	183.10	165.67	17.42	10.508				
4,200.00	4,194.16	4,186.25	4,175.60	8.95	9.24	-107.96	-119.05	158.10	195.44	177.55	17.89	10.924				
4,300.00	4,293.73	4,285.48	4,273.93	9.18	9.51	-107.76	-128.14	167.88	207.79	189.43	18.36	11.317				
4,400.00	4,393.29	4,384.71	4,372.26	9.42	9.78	-107.58	-137.23	177.65	220.14	201.30	18.84	11.687				
4,500.00	4,492.86	4,483.95	4,470.59	9.66	10.05	-107.42	-146.32	187.43	232.49	213.18	19.32	12.036				
4,600.00	4,592.42	4,583.18	4,568.92	9.90	10.32	-107.28	-155.41	197.21	244.85	225.05	19.80	12.366				
4,700.00	4,691.99	4,682.41	4,667.25	10.14	10.60	-107.15	-164.50	206.99	257.20	236.92	20.29	12.679				
4,800.00	4,791.56	4,781.64	4,765.58	10.39	10.88	-107.03	-173.59	216.76	269.56	248.78	20.78	12.974				
4,900.00	4,891.12	4,880.87	4,863.91	10.63	11.16	-106.92	-182.68	226.54	281.92	260.65	21.27	13.255				
5,000.00	4,990.69	4,980.11	4,962.24	10.88	11.44	-106.83	-191.77	236.32	294.28	272.51	21.76	13.521				
5,100.00	5,090.25	5,079.34	5,060.57	11.13	11.72	-106.73	-200.86	246.09	306.64	284.37	22.26	13.774				

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

LEAM Drilling Services

Anticollision Report

Company:	Devon Energy	Local Co-ordinate Reference:	Well Belloq 11-2 Fed State Com 524H
Project:	Eddy County, NM (NAD-83)	TVD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Reference Site:	Belloq 11-2 Fed State Com	MD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Belloq 11-2 Fed State Com 524H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	EDM 5000.1 Multi User Db
Reference Design:	Plan #2	Offset TVD Reference:	Offset Datum

Offset Design Belloq 11-2 Fed State Com - Belloq 11-2 Fed State Com 514H - OH - Plan #2														Offset Site Error:	0.00 usft
Survey Program: O-LEAM MWD+HDGM														Offset Well Error:	0.00 usft
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Distance		Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning		
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)							
5,200.00	5,189.82	5,178.57	5,158.90	11.37	12.01	-106.65	-209.95	255.87	319.00	296.23	22.76	14.014			
5,300.00	5,289.38	5,277.80	5,257.23	11.62	12.30	-106.57	-219.04	265.65	331.36	308.09	23.27	14.242			
5,400.00	5,388.95	5,377.04	5,355.56	11.88	12.58	-106.50	-228.13	275.42	343.72	319.95	23.77	14.460			
5,500.00	5,488.51	5,476.27	5,453.89	12.13	12.87	-106.44	-237.22	285.20	356.08	331.80	24.28	14.667			
5,600.00	5,588.08	5,575.50	5,552.22	12.38	13.16	-106.37	-246.31	294.98	368.44	343.66	24.79	14.865			
5,700.00	5,687.65	5,674.73	5,650.55	12.64	13.46	-106.31	-255.40	304.76	380.81	355.51	25.30	15.053			
5,800.00	5,787.21	5,773.96	5,748.88	12.89	13.75	-106.26	-264.49	314.53	393.17	367.36	25.81	15.234			
5,900.00	5,886.78	5,873.20	5,847.21	13.15	14.04	-106.21	-273.58	324.31	405.53	379.21	26.32	15.406			
6,000.00	5,986.34	5,972.43	5,945.54	13.40	14.34	-106.16	-282.67	334.09	417.90	391.06	26.84	15.571			
6,100.00	6,085.91	6,071.66	6,043.87	13.66	14.63	-106.11	-291.77	343.86	430.26	402.91	27.35	15.729			
6,200.00	6,185.47	6,170.89	6,142.20	13.92	14.93	-106.07	-300.86	353.64	442.63	414.75	27.87	15.880			
6,300.00	6,285.04	6,270.12	6,240.53	14.17	15.23	-106.03	-309.95	363.42	454.99	426.60	28.39	16.025			
6,400.00	6,384.60	6,369.36	6,338.86	14.43	15.53	-105.99	-319.04	373.20	467.36	438.44	28.91	16.165			
6,500.00	6,484.17	6,468.59	6,437.19	14.69	15.83	-105.96	-328.13	382.97	479.72	450.29	29.43	16.299			
6,600.00	6,583.74	6,567.82	6,535.52	14.95	16.12	-105.92	-337.22	392.75	492.09	462.13	29.96	16.427			
6,700.00	6,683.30	6,667.05	6,633.85	15.21	16.42	-105.89	-346.31	402.53	504.45	473.97	30.48	16.551			
6,800.00	6,782.87	6,766.28	6,732.19	15.47	16.73	-105.86	-355.40	412.30	516.82	485.81	31.00	16.670			
6,900.00	6,882.43	6,865.52	6,830.52	15.74	17.03	-105.83	-364.49	422.08	529.18	497.65	31.53	16.784			
7,000.00	6,982.00	6,964.75	6,928.85	16.00	17.33	-105.80	-373.58	431.86	541.55	509.49	32.06	16.894			
7,100.00	7,081.56	7,063.98	7,027.18	16.26	17.63	-105.77	-382.67	441.63	553.91	521.33	32.58	17.001			
7,200.00	7,181.13	7,163.21	7,125.51	16.52	17.93	-105.75	-391.76	451.41	566.28	533.17	33.11	17.103			
7,300.00	7,280.69	7,262.45	7,223.84	16.78	18.24	-105.72	-400.85	461.19	578.65	545.01	33.64	17.202			
7,400.00	7,380.26	7,361.68	7,322.17	17.05	18.54	-105.70	-409.94	470.97	591.01	556.85	34.17	17.298			
7,500.00	7,479.83	7,460.55	7,424.63	17.31	18.84	-105.69	-419.24	480.97	603.21	568.50	34.71	17.379			
7,600.00	7,579.44	7,572.80	7,531.66	17.55	19.10	-105.82	-427.74	490.11	614.07	578.85	35.22	17.436			
7,700.00	7,679.19	7,680.90	7,639.24	17.76	19.34	-105.93	-434.89	497.80	623.10	587.42	35.67	17.466			
7,800.00	7,779.04	7,789.28	7,747.29	17.97	19.57	-105.97	-440.67	504.02	630.28	594.17	36.11	17.454			
7,900.00	7,878.98	7,897.89	7,855.70	18.16	19.78	-105.96	-445.07	508.75	635.60	599.08	36.53	17.401			
8,000.00	7,978.96	8,006.66	7,964.38	18.35	19.99	-105.90	-448.06	511.97	639.07	602.14	36.92	17.308			
8,100.00	8,078.96	8,115.53	8,073.23	18.54	20.18	89.97	-449.66	513.69	640.71	603.40	37.31	17.173			
8,200.00	8,178.96	8,221.17	8,178.86	18.72	20.37	89.99	-449.94	513.99	640.99	603.31	37.68	17.011			
8,300.00	8,278.96	8,321.17	8,278.86	18.90	20.54	89.99	-449.94	513.99	640.99	602.94	38.05	16.847			
8,400.00	8,378.96	8,421.38	8,379.04	19.08	20.71	89.89	-448.74	513.98	640.98	602.57	38.41	16.687			
8,431.24	8,410.20	8,452.57	8,410.10	19.14	20.75	89.63	-445.88	513.96	640.98	602.45	38.52	16.638			
8,500.00	8,478.96	8,519.57	8,476.01	19.27	20.82	88.57	-434.06	513.89	641.09	602.34	38.75	16.544			
8,600.00	8,578.81	8,611.63	8,563.41	19.43	20.86	86.60	-405.45	513.70	642.20	603.18	39.02	16.457			
8,700.00	8,676.61	8,700.00	8,641.97	19.53	20.85	84.29	-365.17	513.45	644.39	605.26	39.13	16.466			
8,800.00	8,769.41	8,785.10	8,710.91	19.56	20.81	82.16	-315.41	513.13	647.36	608.27	39.09	16.559			
8,900.00	8,854.39	8,867.98	8,770.26	19.55	20.74	80.25	-257.66	512.76	650.76	611.81	38.95	16.708			
9,000.00	8,928.97	8,950.00	8,820.18	19.53	20.66	78.59	-192.68	512.34	654.23	615.47	38.77	16.875			
9,100.00	8,990.88	9,028.52	8,858.83	19.51	20.57	77.26	-124.40	511.90	657.45	618.83	38.62	17.023			
9,200.00	9,038.24	9,106.98	8,887.76	19.55	20.47	76.22	-51.54	511.43	660.12	621.53	38.59	17.104			
9,300.00	9,069.61	9,184.68	8,906.35	19.67	20.38	75.53	23.85	510.95	662.02	623.27	38.76	17.081			
9,400.00	9,084.04	9,261.96	8,914.56	19.91	20.29	75.19	100.62	510.45	662.99	623.85	39.14	16.938			
9,500.00	9,085.13	9,355.13	8,914.92	20.26	20.29	75.14	193.79	509.86	663.14	623.31	39.83	16.649			
9,600.00	9,085.33	9,455.13	8,914.81	20.74	20.87	75.11	293.79	509.21	663.22	622.46	40.76	16.270			
9,700.00	9,085.53	9,555.13	8,914.70	21.34	21.51	75.08	393.79	508.57	663.30	621.38	41.92	15.824			
9,800.00	9,085.73	9,655.13	8,914.59	22.05	22.24	75.06	493.78	507.93	663.37	620.10	43.28	15.329			
9,900.00	9,085.93	9,755.13	8,914.48	22.85	23.06	75.03	593.78	507.29	663.45	618.63	44.82	14.802			
10,000.00	9,086.13	9,855.13	8,914.36	23.73	23.95	75.01	693.78	506.65	663.53	616.99	46.53	14.259			
10,100.00	9,086.33	9,955.13	8,914.25	24.70	24.91	74.98	793.78	506.00	663.60	615.21	48.40	13.712			
10,200.00	9,086.53	10,055.13	8,914.14	25.73	25.94	74.95	893.77	505.36	663.68	613.29	50.39	13.170			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

LEAM Drilling Services

Anticollision Report

Company:	Devon Energy	Local Co-ordinate Reference:	Well Belloq 11-2 Fed State Com 524H
Project:	Eddy County, NM (NAD-83)	TVD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Reference Site:	Belloq 11-2 Fed State Com	MD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Belloq 11-2 Fed State Com 524H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	EDM 5000.1 Multi User Db
Reference Design:	Plan #2	Offset TVD Reference:	Offset Datum

Offset Design Belloq 11-2 Fed State Com - Belloq 11-2 Fed State Com 514H - OH - Plan #2													Offset Site Error:	0.00 usft
Survey Program: O-LEAM MWD+HDGM													Offset Well Error:	0.00 usft
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning	
10,300.00	9,086.72	10,155.13	8,914.03	26.82	27.02	74.93	993.77	504.72	663.76	611.25	52.50	12.642		
10,400.00	9,086.92	10,255.13	8,913.92	27.97	28.16	74.90	1,093.77	504.08	663.84	609.11	54.72	12.131		
10,500.00	9,087.12	10,355.13	8,913.81	29.16	29.34	74.88	1,193.76	503.43	663.91	606.88	57.03	11.642		
10,600.00	9,087.32	10,455.13	8,913.70	30.39	30.56	74.85	1,293.76	502.79	663.99	604.57	59.42	11.175		
10,700.00	9,087.52	10,555.13	8,913.59	31.66	31.82	74.82	1,393.76	502.15	664.07	602.19	61.88	10.732		
10,800.00	9,087.72	10,655.13	8,913.48	32.97	33.11	74.80	1,493.76	501.51	664.15	599.74	64.40	10.313		
10,900.00	9,087.92	10,755.13	8,913.36	34.30	34.43	74.77	1,593.75	500.87	664.22	597.24	66.98	9.917		
11,000.00	9,088.12	10,855.13	8,913.25	35.66	35.78	74.75	1,693.75	500.22	664.30	594.69	69.61	9.543		
11,100.00	9,088.32	10,955.13	8,913.14	37.04	37.14	74.72	1,793.75	499.58	664.38	592.10	72.28	9.191		
11,200.00	9,088.52	11,055.13	8,913.03	38.44	38.53	74.70	1,893.75	498.94	664.46	589.46	75.00	8.860		
11,300.00	9,088.71	11,155.12	8,912.92	39.86	39.94	74.67	1,993.74	498.30	664.54	586.79	77.74	8.548		
11,400.00	9,088.91	11,255.12	8,912.81	41.29	41.37	74.64	2,093.74	497.65	664.62	584.09	80.52	8.254		
11,500.00	9,089.11	11,355.12	8,912.70	42.74	42.81	74.62	2,193.74	497.01	664.69	581.37	83.33	7.977		
11,600.00	9,089.31	11,455.12	8,912.59	44.20	44.26	74.59	2,293.74	496.37	664.77	578.61	86.16	7.715		
11,700.00	9,089.51	11,555.12	8,912.48	45.68	45.73	74.57	2,393.73	495.73	664.85	575.84	89.02	7.469		
11,800.00	9,089.71	11,655.12	8,912.36	47.17	47.20	74.54	2,493.73	495.09	664.93	573.04	91.89	7.236		
11,900.00	9,089.91	11,755.12	8,912.25	48.66	48.69	74.51	2,593.73	494.44	665.01	570.22	94.79	7.016		
12,000.00	9,090.11	11,855.12	8,912.14	50.17	50.19	74.49	2,693.73	493.80	665.09	567.39	97.70	6.807		
12,100.00	9,090.31	11,955.12	8,912.03	51.68	51.69	74.46	2,793.72	493.16	665.17	564.54	100.63	6.610		
12,200.00	9,090.51	12,055.12	8,911.92	53.20	53.21	74.44	2,893.72	492.52	665.25	561.68	103.57	6.423		
12,300.00	9,090.70	12,155.12	8,911.81	54.73	54.73	74.41	2,993.72	491.87	665.33	558.81	106.52	6.246		
12,400.00	9,090.90	12,255.12	8,911.70	56.26	56.25	74.39	3,093.72	491.23	665.41	555.92	109.49	6.077		
12,500.00	9,091.10	12,355.12	8,911.59	57.80	57.79	74.36	3,193.71	490.59	665.49	553.02	112.47	5.917		
12,600.00	9,091.30	12,455.12	8,911.48	59.35	59.33	74.33	3,293.71	489.95	665.57	550.12	115.45	5.765		
12,700.00	9,091.50	12,555.12	8,911.36	60.90	60.87	74.31	3,393.71	489.31	665.65	547.20	118.45	5.620		
12,800.00	9,091.70	12,655.12	8,911.25	62.45	62.42	74.28	3,493.70	488.66	665.73	544.28	121.45	5.481		
12,900.00	9,091.90	12,755.12	8,911.14	64.01	63.97	74.26	3,593.70	488.02	665.81	541.35	124.47	5.349		
13,000.00	9,092.10	12,855.12	8,911.03	65.57	65.53	74.23	3,693.70	487.38	665.89	538.41	127.48	5.223		
13,100.00	9,092.30	12,955.12	8,910.92	67.14	67.09	74.20	3,793.70	486.74	665.97	535.46	130.51	5.103		
13,200.00	9,092.50	13,055.12	8,910.81	68.71	68.66	74.18	3,893.69	486.10	666.05	532.51	133.54	4.988		
13,300.00	9,092.69	13,155.12	8,910.70	70.28	70.22	74.15	3,993.69	485.45	666.14	529.56	136.58	4.877		
13,400.00	9,092.89	13,255.11	8,910.59	71.86	71.80	74.13	4,093.69	484.81	666.22	526.59	139.62	4.772		
13,500.00	9,093.09	13,355.11	8,910.48	73.44	73.37	74.10	4,193.69	484.17	666.30	523.63	142.67	4.670		
13,600.00	9,093.29	13,455.11	8,910.36	75.02	74.95	74.08	4,293.68	483.53	666.38	520.66	145.72	4.573		
13,700.00	9,093.49	13,555.11	8,910.25	76.60	76.53	74.05	4,393.68	482.88	666.46	517.68	148.78	4.480		
13,800.00	9,093.69	13,655.11	8,910.14	78.19	78.11	74.02	4,493.68	482.24	666.54	514.71	151.84	4.390		
13,900.00	9,093.89	13,755.11	8,910.03	79.78	79.69	74.00	4,593.68	481.60	666.63	511.72	154.90	4.304		
14,000.00	9,094.09	13,855.11	8,909.92	81.37	81.28	73.97	4,693.67	480.96	666.71	508.74	157.97	4.221		
14,100.00	9,094.29	13,955.11	8,909.81	82.96	82.87	73.95	4,793.67	480.32	666.79	505.75	161.04	4.141		
14,200.00	9,094.49	14,055.11	8,909.70	84.55	84.46	73.92	4,893.67	479.67	666.87	502.76	164.11	4.064		
14,300.00	9,094.68	14,155.11	8,909.59	86.15	86.05	73.90	4,993.67	479.03	666.95	499.77	167.19	3.989		
14,400.00	9,094.88	14,237.99	8,909.50	87.75	87.23	73.90	5,076.54	479.52	668.24	498.29	169.95	3.932		
14,500.00	9,095.08	14,319.57	8,909.41	89.35	88.32	73.96	5,158.07	482.33	672.25	499.70	172.55	3.896		
14,600.00	9,095.28	14,400.00	8,909.33	90.95	89.40	74.07	5,238.34	487.38	679.00	503.96	175.04	3.879		
14,700.00	9,095.48	14,481.84	8,909.25	92.55	90.49	74.23	5,319.84	494.83	688.46	510.99	177.47	3.879		
14,800.00	9,095.68	14,562.28	8,909.17	94.15	91.56	74.44	5,399.70	504.41	700.63	520.86	179.77	3.897		
14,900.00	9,095.88	14,641.88	8,909.10	95.65	92.61	74.64	5,478.43	516.10	716.82	534.94	181.88	3.941		
15,000.00	9,096.08	14,730.06	8,909.02	97.04	93.86	74.92	5,565.32	531.16	738.59	554.24	184.36	4.006		
15,100.00	9,096.27	14,826.58	8,908.94	98.44	95.34	75.28	5,660.37	547.92	763.99	576.57	187.42	4.076		
15,200.00	9,096.46	14,922.13	8,908.85	99.87	96.81	75.67	5,754.47	564.51	792.68	602.18	190.50	4.161		
15,300.00	9,096.65	15,017.23	8,908.77	101.51	98.27	76.19	5,848.13	581.03	822.80	629.04	193.76	4.247		
15,400.00	9,096.85	15,125.61	8,908.68	103.16	99.86	76.72	5,954.92	599.49	852.73	655.17	197.55	4.316		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

LEAM Drilling Services

Anticollision Report

Company:	Devon Energy	Local Co-ordinate Reference:	Well Belloq 11-2 Fed State Com 524H
Project:	Eddy County, NM (NAD-83)	TVD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Reference Site:	Belloq 11-2 Fed State Com	MD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Belloq 11-2 Fed State Com 524H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	EDM 5000.1 Multi User Db
Reference Design:	Plan #2	Offset TVD Reference:	Offset Datum

Offset Design													Offset Site Error:	0.00 usft
Belloq 11-2 Fed State Com - Belloq 11-2 Fed State Com 514H - OH - Plan #2													Offset Well Error:	0.00 usft
Survey Program: 0-LEAM MWD+HDGM														
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)				
15,500.00	9,097.04	15,262.17	8,908.56	104.79	101.71	77.28	6,090.23	617.83	879.23	677.10	202.13	4.350		
15,600.00	9,097.23	15,402.69	8,908.43	106.21	103.64	77.75	6,230.21	629.96	899.26	693.12	206.14	4.362		
15,700.00	9,097.43	15,546.36	8,908.31	107.62	105.65	78.00	6,373.77	635.24	911.15	701.44	209.71	4.345		
15,800.00	9,097.64	15,656.67	8,908.21	109.03	107.34	78.07	6,484.08	635.44	916.19	703.44	212.75	4.306		
15,900.00	9,097.84	15,756.65	8,908.12	110.44	108.95	78.08	6,584.06	635.44	917.69	701.97	215.72	4.254		
16,000.00	9,098.05	15,856.65	8,908.04	112.05	110.55	78.06	6,684.06	635.44	917.74	698.87	218.88	4.193		
16,100.00	9,098.26	15,956.65	8,907.95	113.67	112.16	78.04	6,784.06	635.44	917.80	695.76	222.04	4.134		
16,200.00	9,098.47	16,056.65	8,907.86	115.28	113.77	78.02	6,884.06	635.44	917.85	692.65	225.20	4.076		
16,300.00	9,098.68	16,156.65	8,907.77	116.89	115.38	78.00	6,984.06	635.44	917.90	689.55	228.36	4.020		
16,400.00	9,098.89	16,291.63	8,907.66	118.50	117.37	77.95	7,119.01	633.26	916.48	684.95	231.53	3.958		
16,500.00	9,099.10	16,436.34	8,907.53	119.89	119.46	77.72	7,263.40	623.97	908.29	674.34	233.95	3.882		
16,600.00	9,099.31	16,578.57	8,907.41	121.28	121.52	77.28	7,404.69	607.74	891.87	656.16	235.71	3.784		
16,700.00	9,099.52	16,705.91	8,907.29	122.65	123.41	76.67	7,530.39	587.40	867.63	630.36	237.26	3.657		
16,800.00	9,099.73	16,801.46	8,907.21	124.02	124.96	76.05	7,624.48	570.81	838.96	599.17	239.79	3.499		
16,900.00	9,099.94	16,896.56	8,907.13	125.56	126.51	75.50	7,718.14	554.29	808.98	566.58	242.40	3.337		
17,000.00	9,100.15	16,991.71	8,907.04	127.07	128.06	74.97	7,811.85	537.77	779.21	534.27	244.94	3.181		
17,100.00	9,100.36	17,087.63	8,906.96	128.42	129.63	74.54	7,906.31	521.11	751.93	504.62	247.32	3.040		
17,200.00	9,100.57	17,184.47	8,906.88	129.79	131.21	74.14	8,001.68	504.30	727.98	478.24	249.73	2.915		
17,300.00	9,100.77	17,269.60	8,906.80	131.18	132.55	73.84	8,085.60	489.99	707.93	455.17	252.75	2.801		
17,400.00	9,100.98	17,349.66	8,906.73	132.60	133.72	73.62	8,164.85	478.65	693.68	437.68	256.00	2.710		
17,500.00	9,101.19	17,430.46	8,906.66	134.22	134.88	73.39	8,245.11	469.45	683.45	424.15	259.30	2.636		
17,600.00	9,101.39	17,511.68	8,906.59	135.85	136.05	73.22	8,326.03	462.49	675.94	413.47	262.47	2.575		
17,700.00	9,101.60	17,600.00	8,906.51	137.47	137.31	73.09	8,414.21	457.53	671.19	405.74	265.45	2.529		
17,800.00	9,101.80	17,674.90	8,906.44	139.09	138.38	73.03	8,489.08	455.45	669.09	400.67	268.42	2.493		
17,828.23	9,101.86	17,698.45	8,906.41	139.55	138.71	73.02	8,512.63	455.20	669.00	399.78	269.22	2.485		
17,900.00	9,102.01	17,769.63	8,906.35	140.72	139.86	73.01	8,583.81	454.74	669.06	397.62	271.44	2.465		
18,000.00	9,102.21	17,869.63	8,906.28	142.34	141.48	72.98	8,663.81	454.10	669.15	394.60	274.55	2.437		
18,100.00	9,102.42	17,969.63	8,906.16	143.96	143.10	72.96	8,743.81	453.45	669.24	391.58	277.66	2.410		
18,200.00	9,102.62	18,069.63	8,906.07	145.59	144.73	72.93	8,823.80	452.81	669.33	388.56	280.76	2.384		
18,300.00	9,102.83	18,169.63	8,905.98	147.22	146.35	72.91	8,903.80	452.17	669.41	385.54	283.87	2.358		
18,400.00	9,103.04	18,269.63	8,905.89	148.84	147.97	72.88	9,083.80	451.52	669.50	382.52	286.98	2.333		
18,500.00	9,103.24	18,369.63	8,905.79	150.47	149.59	72.86	9,163.80	450.88	669.59	379.51	290.09	2.308		
18,600.00	9,103.45	18,469.63	8,905.70	152.09	151.22	72.83	9,243.79	450.23	669.68	376.49	293.19	2.284		
18,700.00	9,103.65	18,569.63	8,905.61	153.72	152.84	72.81	9,323.79	449.59	669.77	373.47	296.30	2.260		
18,800.00	9,103.86	18,669.63	8,905.51	155.35	154.46	72.79	9,403.79	448.95	669.86	370.45	299.41	2.237		
18,900.00	9,104.06	18,769.63	8,905.42	156.97	156.09	72.76	9,483.79	448.30	669.95	367.43	302.51	2.215		
19,000.00	9,104.27	18,869.63	8,905.33	158.60	157.71	72.74	9,563.78	447.66	670.04	364.42	305.62	2.192		
19,100.00	9,104.47	18,969.63	8,905.24	160.23	159.34	72.71	9,643.78	447.01	670.13	361.40	308.73	2.171		
19,200.00	9,104.68	19,069.63	8,905.14	161.86	160.96	72.69	9,723.78	446.37	670.22	358.38	311.83	2.149		
19,300.00	9,104.88	19,169.63	8,905.05	163.48	162.59	72.66	9,803.78	445.73	670.30	355.37	314.94	2.128		
19,356.15	9,105.00	19,224.84	8,905.00	164.40	163.40	72.65	10,038.99	445.37	670.36	353.77	316.58	2.117 SF		

LEAM Drilling Services

Anticollision Report

Company:	Devon Energy	Local Co-ordinate Reference:	Well Belloq 11-2 Fed State Com 524H
Project:	Eddy County, NM (NAD-83)	TVD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Reference Site:	Belloq 11-2 Fed State Com	MD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Belloq 11-2 Fed State Com 524H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore:	OH	Database:	EDM 5000.1 Multi User Db
Reference Design:	Plan #2	Offset TVD Reference:	Offset Datum

Offset Design													Offset Site Error: 0.00 usft	
Survey Program: O-LEAM MWD+HDGM													Offset Well Error: 0.00 usft	
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning	
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)				
0.00	0.00	0.00	0.00	0.00	0.00	-90.11	-2.49	-1,249.73	1,249.80					
100.00	100.00	86.80	86.80	0.09	0.07	-90.11	-2.49	-1,249.73	1,249.73	1,249.57	0.16	7,781.754		
200.00	200.00	186.80	186.80	0.31	0.28	-90.11	-2.49	-1,249.73	1,249.73	1,249.14	0.59	2,111.715		
300.00	300.00	286.80	286.80	0.54	0.51	-90.11	-2.49	-1,249.73	1,249.73	1,248.69	1.04	1,200.118		
400.00	400.00	386.80	386.80	0.76	0.73	-90.11	-2.49	-1,249.73	1,249.73	1,248.24	1.49	838.255		
500.00	500.00	486.80	486.80	0.99	0.96	-90.11	-2.49	-1,249.73	1,249.73	1,247.79	1.94	644.057		
600.00	600.00	586.80	586.80	1.21	1.18	-90.11	-2.49	-1,249.73	1,249.73	1,247.34	2.39	522.914		
700.00	700.00	686.80	686.80	1.43	1.40	-90.11	-2.49	-1,249.73	1,249.73	1,246.89	2.84	440.129		
800.00	800.00	786.80	786.80	1.66	1.63	-90.11	-2.49	-1,249.73	1,249.73	1,246.44	3.29	379.973		
900.00	900.00	886.80	886.80	1.88	1.85	-90.11	-2.49	-1,249.73	1,249.73	1,245.99	3.74	334.284		
1,000.00	1,000.00	986.80	986.80	2.11	2.08	-90.11	-2.49	-1,249.73	1,249.73	1,245.54	4.19	298.403		
1,100.00	1,100.00	1,086.80	1,086.80	2.33	2.30	-90.11	-2.49	-1,249.73	1,249.73	1,245.09	4.64	269.478		
1,200.00	1,200.00	1,186.80	1,186.80	2.56	2.53	-90.11	-2.49	-1,249.73	1,249.73	1,244.65	5.09	245.666		
1,300.00	1,300.00	1,286.80	1,286.80	2.78	2.75	-90.11	-2.49	-1,249.73	1,249.73	1,244.20	5.54	225.719		
1,400.00	1,400.00	1,386.80	1,386.80	3.01	2.98	-90.11	-2.49	-1,249.73	1,249.73	1,243.75	5.99	208.769		
1,500.00	1,500.00	1,486.80	1,486.80	3.23	3.20	-90.11	-2.49	-1,249.73	1,249.73	1,243.30	6.44	194.187		
1,600.00	1,600.00	1,586.80	1,586.80	3.46	3.43	-90.11	-2.49	-1,249.73	1,249.73	1,242.85	6.89	181.508		
1,700.00	1,700.00	1,686.80	1,686.80	3.68	3.65	-90.11	-2.49	-1,249.73	1,249.73	1,242.40	7.33	170.384		
1,800.00	1,800.00	1,786.80	1,786.80	3.91	3.88	-90.11	-2.49	-1,249.73	1,249.73	1,241.95	7.78	160.545		
1,900.00	1,900.00	1,886.80	1,886.80	4.13	4.10	-90.11	-2.49	-1,249.73	1,249.73	1,241.50	8.23	151.780		
2,000.00	2,000.00	1,986.80	1,986.80	4.36	4.33	-90.11	-2.49	-1,249.73	1,249.73	1,241.05	8.68	143.922		
2,100.00	2,100.00	2,086.80	2,086.80	4.58	4.55	-90.11	-2.49	-1,249.73	1,249.73	1,240.60	9.13	136.838		
2,200.00	2,200.00	2,186.80	2,186.80	4.81	4.78	-90.11	-2.49	-1,249.73	1,249.73	1,240.15	9.58	130.419		
2,300.00	2,300.00	2,286.80	2,286.80	5.03	5.00	-90.11	-2.49	-1,249.73	1,249.73	1,239.70	10.03	124.575		
2,400.00	2,400.00	2,386.80	2,386.80	5.26	5.23	-90.11	-2.49	-1,249.73	1,249.73	1,239.25	10.48	119.232		
2,500.00	2,500.00	2,486.80	2,486.80	5.48	5.45	-90.11	-2.49	-1,249.73	1,249.73	1,238.80	10.93	114.329		
2,600.00	2,599.99	2,581.26	2,581.26	5.68	5.64	74.14	-3.04	-1,249.91	1,249.69	1,238.37	11.32	110.438		
2,700.00	2,699.96	2,674.89	2,674.86	5.85	5.81	74.15	-5.03	-1,250.56	1,249.67	1,238.02	11.65	107.278		
2,702.94	2,702.89	2,677.64	2,677.61	5.85	5.81	74.15	-5.11	-1,250.59	1,249.67	1,238.01	11.66	107.188		
2,800.00	2,799.86	2,768.52	2,768.42	6.02	5.97	74.18	-8.47	-1,251.68	1,249.68	1,237.70	11.98	104.287		
2,900.00	2,899.68	2,862.16	2,861.92	6.20	6.13	74.20	-13.37	-1,253.28	1,249.73	1,237.41	12.32	101.398		
3,000.00	2,999.37	2,955.81	2,955.33	6.38	6.30	74.24	-19.72	-1,255.36	1,249.82	1,237.14	12.68	98.598		
3,100.00	3,098.94	3,049.85	3,049.01	6.57	6.48	74.26	-27.55	-1,257.92	1,250.03	1,237.00	13.04	95.878		
3,200.00	3,198.51	3,149.85	3,148.56	6.77	6.67	74.26	-36.56	-1,260.86	1,250.45	1,237.02	13.42	93.145		
3,300.00	3,298.07	3,249.85	3,248.11	6.97	6.87	74.25	-45.57	-1,263.80	1,250.86	1,237.04	13.82	90.500		
3,400.00	3,397.64	3,349.85	3,347.66	7.17	7.07	74.25	-54.57	-1,266.74	1,251.28	1,237.05	14.23	87.943		
3,500.00	3,497.20	3,449.85	3,447.21	7.38	7.28	74.25	-63.58	-1,269.69	1,251.69	1,237.05	14.64	85.476		
3,600.00	3,596.77	3,549.85	3,546.76	7.60	7.49	74.25	-72.59	-1,272.63	1,252.10	1,237.04	15.07	83.100		
3,700.00	3,696.33	3,649.85	3,646.31	7.81	7.71	74.25	-81.60	-1,275.57	1,252.52	1,237.02	15.50	80.815		
3,800.00	3,795.90	3,749.85	3,745.85	8.03	7.93	74.24	-90.61	-1,278.52	1,252.93	1,237.00	15.94	78.620		
3,900.00	3,895.47	3,849.85	3,845.40	8.26	8.16	74.24	-99.62	-1,281.46	1,253.35	1,236.97	16.38	76.513		
4,000.00	3,995.03	3,949.85	3,944.95	8.49	8.38	74.24	-108.63	-1,284.40	1,253.76	1,236.93	16.83	74.492		
4,100.00	4,094.60	4,049.85	4,044.50	8.72	8.61	74.24	-117.64	-1,287.34	1,254.17	1,236.89	17.29	72.553		
4,200.00	4,194.16	4,149.84	4,144.05	8.95	8.84	74.23	-126.64	-1,290.29	1,254.59	1,236.84	17.75	70.694		
4,300.00	4,293.73	4,249.84	4,243.60	9.18	9.08	74.23	-135.65	-1,293.23	1,255.00	1,236.79	18.21	68.912		
4,400.00	4,393.29	4,349.84	4,343.15	9.42	9.32	74.23	-144.66	-1,296.17	1,255.42	1,236.74	18.68	67.203		
4,500.00	4,492.86	4,449.84	4,442.70	9.66	9.55	74.23	-153.67	-1,299.12	1,255.83	1,236.68	19.15	65.565		
4,600.00	4,592.42	4,549.84	4,542.25	9.90	9.80	74.23	-162.68	-1,302.06	1,256.25	1,236.61	19.63	63.994		
4,700.00	4,691.99	4,649.84	4,641.80	10.14	10.04	74.22	-171.69	-1,305.00	1,256.66	1,236.55	20.11	62.487		
4,800.00	4,791.56	4,749.84	4,741.34	10.39	10.28	74.22	-180.70	-1,307.94	1,257.07	1,236.48	20.59	61.040		
4,900.00	4,891.12	4,849.84	4,840.89	10.63	10.53	74.22	-189.71	-1,310.89	1,257.49	1,236.41	21.08	59.652		
5,000.00	4,990.69	4,949.84	4,940.44	10.88	10.78	74.22	-198.71	-1,313.83	1,257.90	1,236.33	21.57	58.319		

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

LEAM Drilling Services

Anticollision Report

Company:	Devon Energy	Local Co-ordinate Reference:	Well Belloq 11-2 Fed State Com 524H
Project:	Eddy County, NM (NAD-83)	TVD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Reference Site:	Belloq 11-2 Fed State Com	MD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Belloq 11-2 Fed State Com 524H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	EDM 5000.1 Multi User Db
Reference Design:	Plan #2	Offset TVD Reference:	Offset Datum

Offset Design														Offset Site Error:	0.00 usft
Belloq 11-2 Fed State Com - Belloq 11-2 Fed State Com 523H - OH - Plan #1														Offset Well Error:	0.00 usft
Survey Program: O-LEAM MWD+HDGM															
Reference		Offset		Semi Major Axis		Highside Toolface (°)	Offset Wellbore Centre		Distance		Minimum Separation (usft)	Separation Factor	Warning		
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference (usft)	Offset (usft)		+N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)					
5,100.00	5,090.25	5,049.84	5,039.99	11.13	11.02	74.21	-207.72	-1,316.77	1,258.32	1,236.26	22.06	57.039			
5,200.00	5,189.82	5,149.84	5,139.54	11.37	11.27	74.21	-216.73	-1,319.72	1,258.73	1,236.18	22.55	55.809			
5,300.00	5,289.38	5,249.84	5,239.09	11.62	11.53	74.21	-225.74	-1,322.66	1,259.14	1,236.09	23.05	54.625			
5,400.00	5,388.95	5,349.83	5,338.64	11.88	11.78	74.21	-234.75	-1,325.60	1,259.56	1,236.01	23.55	53.488			
5,500.00	5,488.51	5,449.83	5,438.19	12.13	12.03	74.21	-243.76	-1,328.54	1,259.97	1,235.92	24.05	52.393			
5,600.00	5,588.08	5,549.83	5,537.74	12.38	12.28	74.20	-252.77	-1,331.49	1,260.39	1,235.84	24.55	51.338			
5,700.00	5,687.65	5,649.83	5,637.29	12.64	12.54	74.20	-261.78	-1,334.43	1,260.80	1,235.75	25.05	50.323			
5,800.00	5,787.21	5,749.83	5,736.83	12.89	12.80	74.20	-270.79	-1,337.37	1,261.21	1,235.66	25.56	49.344			
5,900.00	5,886.78	5,849.83	5,836.38	13.15	13.05	74.20	-279.79	-1,340.32	1,261.63	1,235.56	26.07	48.401			
6,000.00	5,986.34	5,949.83	5,935.93	13.40	13.31	74.19	-288.80	-1,343.26	1,262.04	1,235.47	26.57	47.491			
6,100.00	6,085.91	6,049.83	6,035.48	13.66	13.57	74.19	-297.81	-1,346.20	1,262.46	1,235.37	27.08	46.613			
6,200.00	6,185.47	6,149.83	6,135.03	13.92	13.83	74.19	-306.82	-1,349.14	1,262.87	1,235.28	27.59	45.765			
6,300.00	6,285.04	6,249.83	6,234.58	14.17	14.09	74.19	-315.83	-1,352.09	1,263.29	1,235.18	28.11	44.946			
6,400.00	6,384.60	6,349.83	6,334.13	14.43	14.35	74.19	-324.84	-1,355.03	1,263.70	1,235.08	28.62	44.154			
6,500.00	6,484.17	6,449.82	6,433.68	14.69	14.61	74.18	-333.85	-1,357.97	1,264.11	1,234.98	29.13	43.389			
6,600.00	6,583.74	6,549.82	6,533.23	14.95	14.87	74.18	-342.86	-1,360.92	1,264.53	1,234.88	29.65	42.649			
6,700.00	6,683.30	6,649.82	6,632.78	15.21	15.13	74.18	-351.86	-1,363.86	1,264.94	1,234.78	30.17	41.933			
6,800.00	6,782.87	6,749.82	6,732.32	15.47	15.39	74.18	-360.87	-1,366.80	1,265.36	1,234.67	30.68	41.239			
6,900.00	6,882.43	6,849.82	6,831.87	15.74	15.65	74.18	-369.88	-1,369.74	1,265.77	1,234.57	31.20	40.568			
7,000.00	6,982.00	6,949.82	6,931.42	16.00	15.92	74.17	-378.89	-1,372.69	1,266.18	1,234.46	31.72	39.917			
7,100.00	7,081.56	7,049.82	7,030.97	16.26	16.18	74.17	-387.90	-1,375.63	1,266.60	1,234.36	32.24	39.286			
7,200.00	7,181.13	7,149.82	7,130.52	16.52	16.44	74.17	-396.91	-1,378.57	1,267.01	1,234.25	32.76	38.675			
7,300.00	7,280.69	7,249.82	7,230.07	16.78	16.71	74.17	-405.92	-1,381.52	1,267.43	1,234.14	33.28	38.082			
7,400.00	7,380.26	7,349.82	7,329.62	17.05	16.97	74.16	-414.93	-1,384.46	1,267.84	1,234.04	33.80	37.506			
7,500.00	7,479.83	7,449.82	7,429.17	17.31	17.24	74.16	-423.93	-1,387.40	1,268.25	1,233.93	34.33	36.947			
7,600.00	7,579.44	7,553.90	7,532.81	17.55	17.49	74.15	-433.02	-1,390.37	1,268.73	1,233.91	34.81	36.443			
7,700.00	7,679.19	7,661.32	7,639.93	17.76	17.71	74.14	-440.69	-1,392.88	1,269.14	1,233.89	35.25	36.005			
7,800.00	7,779.04	7,768.75	7,747.19	17.97	17.93	74.13	-446.46	-1,394.76	1,269.45	1,233.78	35.67	35.590			
7,900.00	7,878.98	7,876.19	7,854.54	18.16	18.14	74.13	-450.30	-1,396.02	1,269.64	1,233.57	36.07	35.196			
8,000.00	7,978.96	7,983.63	7,961.96	18.35	18.34	74.13	-452.24	-1,396.65	1,269.73	1,233.27	36.46	34.823			
8,100.00	8,078.96	8,087.43	8,065.76	18.54	18.54	-90.11	-452.49	-1,396.73	1,269.73	1,232.88	36.85	34.457			
8,200.00	8,178.96	8,187.43	8,165.76	18.72	18.72	-90.11	-452.49	-1,396.73	1,269.73	1,232.52	37.22	34.119			
8,300.00	8,278.96	8,287.43	8,265.76	18.90	18.90	-90.11	-452.49	-1,396.73	1,269.73	1,232.15	37.58	33.786			
8,400.00	8,378.96	8,387.43	8,365.76	19.08	19.09	-90.11	-452.49	-1,396.73	1,269.73	1,231.78	37.95	33.459			
8,500.00	8,478.96	8,487.43	8,465.76	19.27	19.27	-90.11	-452.49	-1,396.73	1,269.73	1,231.41	38.32	33.136			
8,600.00	8,578.81	8,586.74	8,564.91	19.43	19.44	-89.74	-448.46	-1,396.76	1,269.73	1,231.08	38.65	32.851			
8,700.00	8,676.61	8,685.72	8,661.70	19.53	19.53	-89.73	-428.32	-1,396.89	1,269.73	1,230.89	38.84	32.689			
8,800.00	8,769.41	8,784.69	8,753.57	19.56	19.56	-89.74	-391.85	-1,397.12	1,269.74	1,230.83	38.91	32.635			
8,900.00	8,854.39	8,883.69	8,837.84	19.55	19.55	-89.75	-340.12	-1,397.45	1,269.74	1,230.85	38.89	32.651			
9,000.00	8,928.97	8,982.75	8,911.99	19.53	19.52	-89.77	-274.63	-1,397.87	1,269.74	1,230.89	38.85	32.686			
9,100.00	8,990.88	9,081.90	8,973.82	19.51	19.50	-89.79	-197.28	-1,398.37	1,269.74	1,230.89	38.85	32.681			
9,200.00	9,038.24	9,181.15	9,021.45	19.55	19.52	-89.82	-110.35	-1,398.93	1,269.74	1,230.77	38.97	32.579			
9,300.00	9,069.61	9,280.54	9,053.42	19.67	19.63	-89.86	-16.38	-1,399.54	1,269.75	1,230.48	39.27	32.337			
9,400.00	9,084.04	9,380.08	9,068.70	19.91	19.85	-89.90	81.86	-1,400.17	1,269.75	1,229.99	39.76	31.939			
9,500.00	9,085.13	9,479.95	9,070.09	20.26	20.20	-89.92	181.69	-1,400.81	1,269.75	1,229.29	40.46	31.380			
9,600.00	9,085.33	9,579.95	9,070.24	20.74	20.68	-89.91	281.69	-1,401.46	1,269.76	1,228.34	41.42	30.659			
9,700.00	9,085.53	9,679.95	9,070.39	21.34	21.27	-89.91	381.69	-1,402.10	1,269.76	1,227.17	42.60	29.809			
9,800.00	9,085.73	9,779.95	9,070.55	22.05	21.96	-89.91	481.69	-1,402.74	1,269.77	1,225.78	43.99	28.865			
9,900.00	9,085.93	9,879.95	9,070.70	22.85	22.76	-89.91	581.69	-1,403.39	1,269.77	1,224.20	45.58	27.859			
10,000.00	9,086.13	9,979.95	9,070.85	23.73	23.64	-89.91	681.68	-1,404.03	1,269.78	1,222.44	47.34	26.822			
10,100.00	9,086.33	10,079.95	9,071.00	24.70	24.60	-89.90	781.68	-1,404.67	1,269.78	1,220.53	49.26	25.778			
10,200.00	9,086.53	10,179.95	9,071.15	25.73	25.63	-89.90	881.68	-1,405.32	1,269.79	1,218.47	51.31	24.746			

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

LEAM Drilling Services

Anticollision Report

Company:	Devon Energy	Local Co-ordinate Reference:	Well Belloq 11-2 Fed.State.Com 524H
Project:	Eddy County, NM (NAD-83)	TVD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Reference Site:	Belloq 11-2 Fed State Com	MD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Belloq 11-2 Fed State Com 524H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2:00 sigma
Reference Wellbore	OH	Database:	EDM 5000.1 Multi User Db
Reference Design:	Plan #2	Offset TVD Reference:	Offset Datum

Offset Design Belloq 11-2 Fed State Com - Belloq 11-2 Fed State Com 523H - OH - Plan #1														Offset Site Error: 0.00 usft
Survey Program: O-LEAM MWD+HDGM														Offset Well Error: 0.00 usft
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Reference	Offset	Semi Major Axis	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	+E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning
10,300.00	9,086.72	10,279.95	9,071.30	26.82	26.71	-89.90	-89.90	981.68	-1,405.96	1,269.79	1,216.30	53.49	23.738	
10,400.00	9,086.92	10,379.95	9,071.45	27.97	27.86	-89.90	-89.90	1,081.67	-1,406.60	1,269.80	1,214.02	55.78	22.765	
10,500.00	9,087.12	10,479.95	9,071.61	29.16	29.05	-89.90	-89.90	1,181.67	-1,407.25	1,269.80	1,211.64	58.16	21.833	
10,600.00	9,087.32	10,579.95	9,071.76	30.39	30.28	-89.89	-89.89	1,281.67	-1,407.89	1,269.81	1,209.18	60.62	20.946	
10,700.00	9,087.52	10,679.95	9,071.91	31.66	31.55	-89.89	-89.89	1,381.67	-1,408.54	1,269.81	1,206.65	63.16	20.104	
10,800.00	9,087.72	10,779.95	9,072.06	32.97	32.85	-89.89	-89.89	1,481.67	-1,409.18	1,269.82	1,204.05	65.77	19.308	
10,900.00	9,087.92	10,879.95	9,072.21	34.30	34.18	-89.89	-89.89	1,581.66	-1,409.82	1,269.82	1,201.39	68.43	18.556	
11,000.00	9,088.12	10,979.95	9,072.36	35.66	35.53	-89.88	-89.88	1,681.66	-1,410.47	1,269.83	1,198.68	71.15	17.848	
11,100.00	9,088.32	11,079.95	9,072.51	37.04	36.91	-89.88	-89.88	1,781.66	-1,411.11	1,269.83	1,195.93	73.91	17.182	
11,200.00	9,088.52	11,179.95	9,072.66	38.44	38.31	-89.88	-89.88	1,881.66	-1,411.75	1,269.84	1,193.13	76.71	16.554	
11,300.00	9,088.71	11,279.95	9,072.82	39.86	39.73	-89.88	-89.88	1,981.65	-1,412.40	1,269.84	1,190.30	79.54	15.964	
11,400.00	9,088.91	11,379.95	9,072.97	41.29	41.17	-89.88	-89.88	2,081.65	-1,413.04	1,269.85	1,187.43	82.42	15.408	
11,500.00	9,089.11	11,479.95	9,073.12	42.74	42.61	-89.87	-89.87	2,181.65	-1,413.68	1,269.85	1,184.54	85.32	14.884	
11,600.00	9,089.31	11,579.95	9,073.27	44.20	44.08	-89.87	-89.87	2,281.65	-1,414.33	1,269.86	1,181.62	88.24	14.391	
11,700.00	9,089.51	11,679.95	9,073.42	45.68	45.55	-89.87	-89.87	2,381.65	-1,414.97	1,269.86	1,178.67	91.19	13.925	
11,800.00	9,089.71	11,779.95	9,073.57	47.17	47.04	-89.87	-89.87	2,481.64	-1,415.62	1,269.87	1,175.70	94.17	13.485	
11,900.00	9,089.91	11,879.95	9,073.72	48.66	48.53	-89.87	-89.87	2,581.64	-1,416.26	1,269.87	1,172.72	97.16	13.070	
12,000.00	9,090.11	11,979.95	9,073.88	50.17	50.04	-89.86	-89.86	2,681.64	-1,416.90	1,269.88	1,169.71	100.17	12.677	
12,100.00	9,090.31	12,079.95	9,074.03	51.68	51.55	-89.86	-89.86	2,781.64	-1,417.55	1,269.89	1,166.69	103.19	12.306	
12,200.00	9,090.51	12,179.95	9,074.18	53.20	53.07	-89.86	-89.86	2,881.63	-1,418.19	1,269.89	1,163.65	106.24	11.953	
12,300.00	9,090.70	12,279.95	9,074.33	54.73	54.60	-89.86	-89.86	2,981.63	-1,418.83	1,269.90	1,160.60	109.29	11.619	
12,400.00	9,090.90	12,379.95	9,074.48	56.26	56.13	-89.85	-89.85	3,081.63	-1,419.48	1,269.90	1,157.54	112.36	11.302	
12,500.00	9,091.10	12,479.95	9,074.63	57.80	57.67	-89.85	-89.85	3,181.63	-1,420.12	1,269.91	1,154.47	115.44	11.001	
12,600.00	9,091.30	12,579.95	9,074.78	59.35	59.22	-89.85	-89.85	3,281.63	-1,420.76	1,269.91	1,151.38	118.53	10.714	
12,700.00	9,091.50	12,679.95	9,074.94	60.90	60.77	-89.85	-89.85	3,381.62	-1,421.41	1,269.92	1,148.28	121.63	10.441	
12,800.00	9,091.70	12,779.95	9,075.09	62.45	62.32	-89.85	-89.85	3,481.62	-1,422.05	1,269.92	1,145.18	124.74	10.181	
12,900.00	9,091.90	12,879.95	9,075.24	64.01	63.88	-89.84	-89.84	3,581.62	-1,422.70	1,269.93	1,142.07	127.86	9.932	
13,000.00	9,092.10	12,979.95	9,075.39	65.57	65.44	-89.84	-89.84	3,681.62	-1,423.34	1,269.93	1,138.95	130.98	9.695	
13,100.00	9,092.30	13,079.95	9,075.54	67.14	67.01	-89.84	-89.84	3,781.61	-1,423.98	1,269.94	1,135.82	134.12	9.469	
13,200.00	9,092.50	13,179.95	9,075.69	68.71	68.58	-89.84	-89.84	3,881.61	-1,424.63	1,269.94	1,132.68	137.26	9.252	
13,300.00	9,092.69	13,279.95	9,075.84	70.28	70.15	-89.84	-89.84	3,981.61	-1,425.27	1,269.95	1,129.54	140.40	9.045	
13,400.00	9,092.89	13,379.95	9,076.00	71.86	71.73	-89.83	-89.83	4,081.61	-1,425.91	1,269.95	1,126.39	143.56	8.846	
13,500.00	9,093.09	13,479.95	9,076.15	73.44	73.30	-89.83	-89.83	4,181.61	-1,426.56	1,269.96	1,123.24	146.71	8.656	
13,600.00	9,093.29	13,579.95	9,076.30	75.02	74.89	-89.83	-89.83	4,281.60	-1,427.20	1,269.96	1,120.08	149.88	8.473	
13,700.00	9,093.49	13,679.95	9,076.45	76.60	76.47	-89.83	-89.83	4,381.60	-1,427.84	1,269.97	1,116.92	153.05	8.298	
13,800.00	9,093.69	13,779.95	9,076.60	78.19	78.06	-89.82	-89.82	4,481.60	-1,428.49	1,269.97	1,113.75	156.22	8.129	
13,900.00	9,093.89	13,879.95	9,076.75	79.78	79.64	-89.82	-89.82	4,581.60	-1,429.13	1,269.98	1,110.58	159.40	7.967	
14,000.00	9,094.09	13,979.95	9,076.90	81.37	81.23	-89.82	-89.82	4,681.60	-1,429.78	1,269.98	1,107.40	162.58	7.812	
14,100.00	9,094.29	14,079.95	9,077.05	82.96	82.83	-89.82	-89.82	4,781.59	-1,430.42	1,269.99	1,104.23	165.76	7.661	
14,200.00	9,094.49	14,179.95	9,077.21	84.55	84.42	-89.82	-89.82	4,881.59	-1,431.06	1,269.99	1,101.04	168.95	7.517	
14,300.00	9,094.68	14,279.95	9,077.36	86.15	86.02	-89.81	-89.81	4,981.59	-1,431.71	1,270.00	1,097.85	172.14	7.378	
14,400.00	9,094.88	14,379.95	9,077.51	87.75	87.61	-89.81	-89.81	5,081.59	-1,432.35	1,270.00	1,094.66	175.34	7.243	
14,500.00	9,095.08	14,479.95	9,077.66	89.35	89.21	-89.81	-89.81	5,181.58	-1,432.99	1,270.01	1,091.47	178.54	7.113	
14,600.00	9,095.28	14,579.95	9,077.81	90.95	90.81	-89.81	-89.81	5,281.58	-1,433.64	1,270.01	1,088.28	181.74	6.988	
14,700.00	9,095.48	14,679.95	9,077.96	92.55	92.42	-89.81	-89.81	5,381.58	-1,434.28	1,270.02	1,085.08	184.94	6.867	
14,800.00	9,095.68	14,779.95	9,078.11	94.15	94.02	-89.80	-89.80	5,481.58	-1,434.92	1,270.02	1,081.88	188.15	6.750	
14,900.00	9,095.88	14,879.93	9,078.27	95.65	95.62	-89.80	-89.80	5,581.56	-1,435.57	1,268.62	1,077.37	191.25	6.633	
15,000.00	9,096.08	14,979.81	9,078.42	97.04	97.23	-89.79	-89.79	5,681.43	-1,436.21	1,263.75	1,069.51	194.24	6.506	
15,100.00	9,096.27	15,079.45	9,078.57	98.44	98.83	-89.78	-89.78	5,781.08	-1,436.85	1,255.40	1,058.16	197.24	6.385	
15,200.00	9,096.46	15,178.75	9,078.72	99.87	100.42	-89.77	-89.77	5,880.37	-1,437.49	1,243.58	1,043.32	200.27	6.210	
15,300.00	9,096.65	15,277.86	9,078.87	101.51	102.02	-89.77	-89.77	5,979.48	-1,438.13	1,230.31	1,026.81	203.50	6.046	
15,400.00	9,096.85	15,376.98	9,079.02	103.16	103.61	-89.77	-89.77	6,078.59	-1,438.77	1,217.03	1,010.29	206.74	5.887	

CC - Min centre to center distance or convergent point, SF - min separation factor, ES - min ellipse separation

LEAM Drilling Services

Anticollision Report

Company:	Devon Energy	Local Co-ordinate Reference:	Well Belloq 11-2 Fed State Com 524H
Project:	Eddy County, NM (NAD-83)	TVD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Reference Site:	Belloq 11-2 Fed State Com	MD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Belloq 11-2 Fed State Com 524H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	EDM 5000.1 Multi User Db
Reference Design:	Plan #2	Offset TVD Reference:	Offset Datum

Offset Design Belloq 11-2 Fed State Com - Belloq 11-2 Fed State Com 523H - OH - Plan #1													Offset Site Error: 0.00 usft
Survey Program: 0-LEAM MWD+HDMG													Offset Well Error: 0.00 usft
Measured Depth (usft)	Vertical Depth (usft)	Measured Depth (usft)	Vertical Depth (usft)	Semi Major Axis Reference (usft)	Semi Major Axis Offset (usft)	Highside Toolface (°)	Offset Wellbore Centre +N/-S (usft)	Offset Wellbore Centre +E/-W (usft)	Between Centres (usft)	Between Ellipses (usft)	Minimum Separation (usft)	Separation Factor	Warning
15,500.00	9,097.04	15,476.09	9,079.17	104.79	105.21	-89.76	6,177.71	-1,439.40	1,203.76	993.79	209.97	5.733	
15,600.00	9,097.23	15,575.45	9,079.32	106.21	106.81	-89.76	6,277.06	-1,440.04	1,192.49	979.51	212.98	5.599	
15,700.00	9,097.43	15,675.14	9,079.47	107.62	108.42	-89.76	6,376.75	-1,440.69	1,184.70	968.70	216.00	5.485	
15,800.00	9,097.64	15,775.04	9,079.62	109.03	110.03	-89.76	6,476.65	-1,441.33	1,180.39	961.37	219.02	5.390	
15,879.44	9,097.80	15,854.47	9,079.74	110.15	111.31	-89.76	6,556.08	-1,441.84	1,179.36	957.95	221.42	5.326 CC	
15,900.00	9,097.84	15,875.03	9,079.77	110.44	111.64	-89.76	6,576.64	-1,441.97	1,179.55	957.52	222.04	5.312	
16,000.00	9,098.05	15,975.03	9,079.92	112.05	113.26	-89.76	6,676.64	-1,442.62	1,180.21	954.94	225.27	5.239	
16,100.00	9,098.26	16,075.03	9,080.08	113.67	114.87	-89.76	6,776.63	-1,443.26	1,180.86	952.36	228.50	5.168	
16,200.00	9,098.47	16,175.03	9,080.23	115.28	116.49	-89.76	6,876.63	-1,443.90	1,181.51	949.79	231.73	5.099	
16,300.00	9,098.68	16,275.03	9,080.38	116.89	118.11	-89.75	6,976.62	-1,444.55	1,182.16	947.21	234.96	5.031	
16,400.00	9,098.89	16,375.02	9,080.53	118.50	119.72	-89.75	7,076.62	-1,445.19	1,182.83	944.65	238.18	4.966	
16,500.00	9,099.10	16,474.98	9,080.68	119.89	121.34	-89.75	7,176.58	-1,445.83	1,185.50	944.30	241.20	4.915	
16,600.00	9,099.31	16,574.79	9,080.83	121.28	122.96	-89.75	7,276.38	-1,446.48	1,191.65	947.46	244.20	4.880	
16,700.00	9,099.52	16,674.32	9,080.98	122.65	124.57	-89.76	7,375.91	-1,447.12	1,201.29	954.11	247.18	4.860	
16,800.00	9,099.73	16,773.45	9,081.13	124.02	126.17	-89.76	7,475.04	-1,447.75	1,214.38	964.22	250.16	4.854	
16,900.00	9,099.94	16,872.39	9,081.28	125.56	127.78	-89.76	7,573.97	-1,448.39	1,228.94	975.63	253.31	4.852	
17,000.00	9,100.15	16,971.34	9,081.43	127.07	129.38	-89.76	7,672.93	-1,449.03	1,243.34	986.91	256.43	4.849	
17,100.00	9,100.36	17,070.64	9,081.58	128.42	130.99	-89.76	7,772.22	-1,449.67	1,255.16	995.78	259.39	4.839	
17,200.00	9,100.57	17,170.28	9,081.73	129.79	132.61	-89.75	7,871.86	-1,450.31	1,263.51	1,001.14	262.37	4.816	
17,300.00	9,100.77	17,270.16	9,081.88	131.18	134.23	-89.75	7,971.74	-1,450.95	1,268.37	1,002.99	265.39	4.779	
17,400.00	9,100.98	17,370.14	9,082.04	132.60	135.85	-89.74	8,071.72	-1,451.60	1,269.77	1,001.34	268.43	4.730	
17,500.00	9,101.19	17,470.14	9,082.19	134.22	137.47	-89.74	8,171.72	-1,452.24	1,269.77	998.09	271.68	4.674	
17,600.00	9,101.39	17,570.14	9,082.34	135.85	139.09	-89.74	8,271.72	-1,452.88	1,269.77	994.84	274.92	4.619	
17,700.00	9,101.60	17,670.14	9,082.49	137.47	140.72	-89.73	8,371.71	-1,453.53	1,269.77	991.60	278.17	4.565	
17,800.00	9,101.80	17,770.14	9,082.64	139.09	142.34	-89.73	8,471.71	-1,454.17	1,269.77	988.35	281.42	4.512	
17,900.00	9,102.01	17,870.14	9,082.79	140.72	143.97	-89.73	8,571.71	-1,454.81	1,269.76	985.10	284.67	4.461	
18,000.00	9,102.21	17,970.14	9,082.94	142.34	145.59	-89.73	8,671.71	-1,455.46	1,269.76	981.85	287.91	4.410	
18,100.00	9,102.42	18,070.14	9,083.10	143.96	147.22	-89.72	8,771.70	-1,456.10	1,269.76	978.60	291.16	4.361	
18,200.00	9,102.62	18,170.14	9,083.25	145.59	148.84	-89.72	8,871.70	-1,456.74	1,269.76	975.35	294.41	4.313	
18,300.00	9,102.83	18,270.14	9,083.40	147.22	150.47	-89.72	8,971.70	-1,457.39	1,269.76	972.09	297.67	4.266	
18,400.00	9,103.04	18,370.14	9,083.55	148.84	152.09	-89.72	9,071.70	-1,458.03	1,269.76	968.84	300.92	4.220	
18,500.00	9,103.24	18,470.14	9,083.70	150.47	153.72	-89.71	9,171.70	-1,458.68	1,269.76	965.59	304.17	4.175	
18,600.00	9,103.45	18,570.14	9,083.85	152.09	155.35	-89.71	9,271.69	-1,459.32	1,269.76	962.33	307.42	4.130	
18,700.00	9,103.65	18,670.14	9,084.00	153.72	156.97	-89.71	9,371.69	-1,459.96	1,269.76	959.08	310.68	4.087	
18,800.00	9,103.86	18,770.14	9,084.15	155.35	158.60	-89.71	9,471.69	-1,460.61	1,269.76	955.83	313.93	4.045	
18,900.00	9,104.06	18,870.14	9,084.31	156.97	160.23	-89.70	9,571.69	-1,461.25	1,269.75	952.57	317.19	4.003	
19,000.00	9,104.27	18,970.14	9,084.46	158.60	161.85	-89.70	9,671.69	-1,461.89	1,269.75	949.31	320.44	3.963	
19,100.00	9,104.47	19,070.14	9,084.61	160.23	163.48	-89.70	9,771.68	-1,462.54	1,269.75	946.06	323.70	3.923	
19,200.00	9,104.68	19,170.14	9,084.76	161.86	165.11	-89.70	9,871.68	-1,463.18	1,269.75	942.80	326.95	3.884	
19,300.00	9,104.88	19,270.14	9,084.91	163.48	166.74	-89.69	9,971.68	-1,463.82	1,269.75	939.54	330.21	3.845	
19,356.15	9,105.00	19,326.30	9,085.00	164.40	167.65	-89.69	10,027.83	-1,464.19	1,269.75	937.71	332.04	3.824 ES, SF	


LEAM Drilling Services

Anticollision Report

Company:	Devon Energy	Local Co-ordinate Reference:	Well Belloq 11-2 Fed State Com 524H
Project:	Eddy County, NM (NAD-83)	TVD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Reference Site:	Belloq 11-2 Fed State Com	MD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Belloq 11-2 Fed State Com 524H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	EDM 5000.1 Multi User Db
Reference Design:	Plan #2	Offset TVD Reference:	Offset Datum

Reference Depths are relative to 3488.9' GE + 23.5 @ 3512.40usft
Offset Depths are relative to Offset Datum
Central Meridian is 104° 19' 60.0000 W

Coordinates are relative to: Belloq 11-2 Fed State Com 524H
Coordinate System is US State Plane 1983, New Mexico Eastern Zone
Grid Convergence at Surface is: 0.32°




LEAM Drilling Services

Anticollision Report

Company:	Devon Energy	Local Co-ordinate Reference:	Well Belloq 11-2 Fed State Com 524H
Project:	Eddy County, NM (NAD-83)	TVD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Reference Site:	Belloq 11-2 Fed State Com	MD Reference:	3488.9' GE + 23.5 @ 3512.40usft
Site Error:	0.00 usft	North Reference:	Grid
Reference Well:	Belloq 11-2 Fed State Com 524H	Survey Calculation Method:	Minimum Curvature
Well Error:	0.00 usft	Output errors are at	2.00 sigma
Reference Wellbore	OH	Database:	EDM 5000.1 Multi User Db
Reference Design:	Plan #2	Offset TVD Reference:	Offset Datum

Reference Depths are relative to 3488.9' GE + 23.5 @ 3512.40usft
Offset Depths are relative to Offset Datum
Central Meridian is 104° 19' 60.0000 W

Coordinates are relative to: Belloq 11-2 Fed State Com 524H
Coordinate System is US State Plane 1983, New Mexico Eastern Zone
Grid Convergence at Surface is: 0.32°



Devon Energy – Belloq 11-2 Fed State Com 524H

1. Geologic Formations

TVD of target	9105	Pilot hole depth	N/A
MD at TD:	19328	Deepest expected fresh water:	

Basin

Formation	Depth (TVD) from KB	Water/Mineral Bearing/ Target Zone?	Hazards*
Rustler	739		
Base of Salt	4470		
Delaware	4507		
Leonard	8454		
1BSS	9462		
2BSS	9867		

*H2S, water flows, loss of circulation, abnormal pressures, etc.

Devon Energy – Belloq 11-2 Fed State Com 524H

2. Casing Program

Hole Size	Casing Interval		Csg. Size	Weight (PPF)	Grade	Conn.
	From	To				
17.5"	0	764	13.375"	48	H-40	STC
12.25"	0	6000	9.625"	40	J-55	BTC
8.75"	0	TD	5.5"	17	P-110	BTC
BLM Minimum Safety Factor				Collapse: 1.125	Burst: 1.00	Tension: 1.6 Dry 1.8 Wet

- All casing strings will be tested in accordance with Onshore Oil and Gas Order #2 III.B.1.h Must have table for contingency casing
- Rustler top will be validated via drilling parameters (i.e. reduction in ROP) and surface casing setting depth revised accordingly if needed.
- Variance is requested for collapse rating on intermediate casing. Operator will keep pipe full while running casing. No losses are expected in subsequent hole section.
- Int casing shoe will be selected based on drilling data, gamma, and flows experienced while drilling. Setting depth will be revised accordingly if needed.
- A variance is requested to waive the centralizer requirement for the intermediate and production casing strings if drilling conditions dictate

Devon Energy – Belloq 11-2 Fed State Com 524H

	Y or N
Is casing new? If used, attach certification as required in Onshore Order #1	Y
Does casing meet API specifications? If no, attach casing specification sheet.	Y
Is premium or uncommon casing planned? If yes attach casing specification sheet.	N
Does the above casing design meet or exceed BLM's minimum standards? If not provide justification (loading assumptions, casing design criteria).	Y
Will the intermediate pipe be kept at a minimum 1/3 fluid filled to avoid approaching the collapse pressure rating of the casing?	Y
Is well located within Capitan Reef?	N
If yes, does production casing cement tie back a minimum of 50' above the Reef?	
Is well within the designated 4 string boundary.	
Is well located in SOPA but not in R-111-P?	N
If yes, are the first 2 strings cemented to surface and 3 rd string cement tied back 500' into previous casing?	
Is well located in R-111-P and SOPA?	N
If yes, are the first three strings cemented to surface?	
Is 2 nd string set 100' to 600' below the base of salt?	
Is well located in high Cave/Karst?	N
If yes, are there two strings cemented to surface?	
(For 2 string wells) If yes, is there a contingency casing if lost circulation occurs?	
Is well located in critical Cave/Karst?	N
If yes, are there three strings cemented to surface?	

Devon Energy – Belloq 11-2 Fed State Com 524H

3. Cementing Program (3-String Primary Design)

Casing	# Sks	TOC	Wt. (lb/gal)	Yld (ft3/sack)	Slurry Description
Surface	798	Surf	13.2	1.33	Lead: Class C Cement + additives
Int	1115	Surf	9	1.94	Lead: Class C Cement + additives
	197	500' above shoe	13.2	1.33	Tail: Class H / C + additives
Int 1 Two Stage (optional) w/ DV @ ~4500	560	Surf	9	1.94	Stage 1 Lead: Class C Cement + additives
	196	500' above shoe	13.2	1.33	Stage 1 Tail: Class H / C + additives
	580	Surf	9	1.94	Stage 2 Lead: Class C Cement + additives
	196	500' above DV	13.2	1.33	Stage 2 Tail: Class H / C + additives
Int 1 Intermediate Squeeze	As Needed	Surf	13.2	1.33	Squeeze Lead: Class C Cement + additives
	1115	Surf	9	1.94	Lead: Class C Cement + additives
	197	500' above shoe	13.2	1.33	Tail: Class H / C + additives
Production	740	Surf	9	3.27	Lead: Class H / C + additives
	2264	KOP	13.2	1.33	Tail: Class H / C + additives

If a DV tool is ran the depth(s) will be adjusted based on hole conditions and cement volumes will be adjusted proportionally. Slurry weights will be adjusted based on estimated fracture gradient of the formation. DV tool will be set a minimum of 50 feet below previous casing and a minimum of 200 feet above current shoe. If cement is not returned to surface during the primary cement job on the surface casing string, a planned top job will be conducted immediately after completion of the primary job.

Casing String	% Excess
Surface	100%
Intermediate	50%
Production	10%

Devon Energy – Belloq 11-2 Fed State Com 524H

4. Pressure Control Equipment

BOP installed and tested before drilling which hole?	Size?	Min. Required WP	Type	✓	Tested to:
Int 1	13-5/8"	5M	Annular	X	50% of rated working pressure
			Blind Ram		5M
			Pipe Ram		
			Double Ram	X	
			Other*		
Production	13-5/8"	5M	Annular	X	50% of rated working pressure
			Blind Ram		5M
			Pipe Ram		
			Double Ram	X	
			Other *		
			Annular		
			Blind Ram		
			Pipe Ram		
			Double Ram		
			Other *		

Devon Energy – Belloq 11-2 Fed State Com 524H

5. Mud Program

Interval	Type	Weight (ppg)	Vis	Water Loss
Surface	FW	8.5 – 9.0	28-34	N/C
Intermediate	Brine	10 – 10.5	28-34	N/C
Production	WBM	8.5 – 9.0	28-34	N/C

Sufficient mud materials to maintain mud properties and meet minimum lost circulation and weight increase requirements will be kept on location at all times.

What will be used to monitor the loss or gain of fluid?	PVT/Pason/Visual Monitoring
---	-----------------------------

6. Logging and Testing Procedures

Logging, Coring and Testing.	
X	Will run GR/CNL from TD to surface (horizontal well – vertical portion of hole). Stated logs run will be in the Completion Report and submitted to the BLM.
	No Logs are planned based on well control or offset log information.
	Drill stem test? If yes, explain
	Coring? If yes, explain

Additional logs planned	Interval
Resistivity	
Density	
X CBL	Production casing
X Mud log	KOP to TD

7. Drilling Conditions

Condition	Specify what type and where?
BH Pressure at deepest TVD	4252 psi
Abnormal Temperature	No

Mitigation measure for abnormal conditions. Describe. Lost circulation material/sweeps/mud scavengers.

Hydrogen Sulfide (H2S) monitors will be installed prior to drilling out the surface shoe. If H2S is detected in concentrations greater than 100 ppm, the operator will comply with the provisions of Onshore Oil and Gas Order #6. If Hydrogen Sulfide is encountered, measured values and formations will be provided to the BLM.	
N	H2S is present
Y	H2S Plan attached

Devon Energy – Belloq 11-2 Fed State Com 524H

8. Other facets of operation

Is this a walking operation? Potentially

1. If operator elects, drilling rig will batch drill the surface holes and run/cement surface casing; walking the rig to next wells on the pad.
2. The drilling rig will then batch drill the intermediate sections and run/cement intermediate casing; the wellbore will be isolated with a blind flange and pressure gauge installed for monitoring the well before walking to the next well.
3. The drilling rig will then batch drill the production hole sections on the wells with OBM, run/cement production casing, and install TA caps or tubing heads for completions.

NOTE: During batch operations the drilling rig will be moved from well to well however, it will not be removed from the pad until all wells have production casing run/cemented.

Will be pre-setting casing? Potentially

1. Spudder rig will move in and drill surface hole.
 - a. Rig will utilize fresh water based mud to drill surface hole to TD. Solids control will be handled entirely on a closed loop basis.
2. After drilling the surface hole section, the spudder rig will run casing and cement following all of the applicable rules and regulations (OnShore Order 2, all COAs and NMOCD regulations).
3. The wellhead will be installed and tested once the surface casing is cut off and the WOC time has been reached.
4. A blind flange with the same pressure rating as the wellhead will be installed to seal the wellbore. Pressure will be monitored with a pressure gauge installed on the wellhead.
5. Spudder rig operations is expected to take 4-5 days per well on a multi well pad.
6. The NMOCD will be contacted and notified 24 hours prior to commencing spudder rig operations.
7. Drilling operations will be performed with the drilling rig. At that time an approved BOP stack will be nipped up and tested on the wellhead before drilling operations commences on each well.
 - a. The NMOCD will be contacted / notified 24 hours before the drilling rig moves back on to the pad with the pre-set surface casing.


Attachments

☒ Directional Plan

☐ Other, describe



Commitment Runs Deep



Design Plan
Operation and Maintenance Plan
Closure Plan

SENM - Closed Loop Systems
June 2010

I. Design Plan

Devon uses MI SWACO closed loop system (CLS). The MI SWACO CLS is designed to maintain drill solids at or below 5%. The equipment is arranged to progressively remove solids from the largest to the smallest size. Drilling fluids can thus be reused and savings is realized on mud and disposal costs. Dewatering may be required with the centrifuges to insure removal of ultra fine solids.

The drilling location is constructed to allow storm water to flow to a central sump normally the cellar. This insures no contamination leaves the drilling pad in the event of a spill. Storm water is reused in the mud system or stored in a reserve fluid tank farm until it can be reused. All lubricants, oils, or chemicals are removed immediately from the ground to prevent the contamination of storm water. An oil trap is normally installed on the sump if an oil spill occurs during a storm.

A tank farm is utilized to store drilling fluids including fresh water and brine fluids. The tank farm is constructed on a 20 ml plastic lined, bermed pad to prevent the contamination of the drilling site during a spill. Fluids from other sites may be stored in these tanks for processing by the solids control equipment and reused in the mud system. At the end of the well the fluids are transported from the tank farm to an adjoining well or to the next well for the rig.

Prior to installing a closed-loop system on site, the topsoil, if present, will be stripped and stockpiled for use as the final cover or fill at the time of closure.

Signs will be posted on the fence surrounding the closed-loop system unless the closed-loop system is located on a site where there is an existing well, that is operated by Devon.


II. Operations and Maintenance Plan

Primary Shakers: The primary shakers make the first removal of drill solids from the drilling mud as it leaves the well bore. The shakers are sized to handle maximum drilling rate at optimal screen size. The shakers normally remove solids down to 74 microns.

Mud Cleaner: The Mud Cleaner cleans the fluid after it leaves the shakers. A set of hydrocyclones are sized to handle 1.25 to 1.5 times the maximum circulating rate. This ensures all the fluid is being processed to an average cut point of 25 microns. The wet discharged is dewatered on a shaker equipped with ultra fine mesh screens and generally cut at 40 microns.



Closed Loop Schematic



Centrifuges: The centrifuges can be one or two in number depending on the well geometry or depth of well. The centrifuges are sized to maintain low gravity solids at 5% or below. They may or may not need a dewatering system to enhance the removal rates. The centrifuges can make a cut point of 8-10 microns depending on bowl speed, feed rate, solids loading and other factors.

The centrifuge system is designed to work on the active system and be flexible to process incoming fluids from other locations. This set-up is also dependant on well factors.

Dewatering System: The dewatering system is a chemical mixing and dosing system designed to enhance the solids removal of the centrifuge. Not commonly used in shallow wells. It may contain pH adjustment, coagulant mixing and dosing, and polymer mixing and dosing. Chemical flocculation binds ultra fine solids into a mass that is within the centrifuge operating design. The

dewatering system improves the centrifuge cut point to infinity or allows for the return of clear water or brine fluid. This ability allows for the ultimate control of low gravity solids.

Cuttings Boxes: Cuttings boxes are utilized to capture drill solids that are discarded from the solids control equipment. These boxes are set upon a rail system that allows for the removal and replacement of a full box of cuttings with an empty one. They are equipped with a cover that insures no product is spilled into the environment during the transportation phase.

Process Tank: (Optional) The process tank allows for the holding and process of fluids that are being transferred into the mud system. Additionally, during times of lost circulation the process tank may hold active fluids that are removed for additional treatment. It can further be used as a mixing tank during well control conditions.

Sump and Sump Pump: The sump is used to collect storm water and the pump is used to transfer this fluid to the active system or to the tank for to hold in reserve. It can also be used to collect fluids that may escape during spills. The location contains drainage ditches that allow the location fluids to drain to the sump.

Reserve Fluids (Tank Farm): A series of frac tanks are used to replace the reserve pit. These are steel tanks that are equipped with a manifold system and a transfer pump. These tanks can contain any number of fluids used during the drilling process. These can include fresh water, cut brine, and saturated salt fluid. The fluid can be from the active well or reclaimed fluid from other locations. A 20 ml liner and berm system is employed to ensure the fluids do not migrate to the environment during a spill.

If a leak develops, the appropriate division district office will be notified within 48 hours of the discovery and the leak will be addressed. Spill prevention is accomplished by maintaining pump packing, hoses, and pipe fittings to insure no leaks are occurring. During an upset condition the source of the spill is isolated and repaired as soon as it is discovered. Free liquid is removed by a diaphragm pump and returned to the mud system. Loose topsoil may be used to stabilize the spill and the contaminated soil is excavated and placed in the cuttings boxes. After the well is finished and the rig has moved, the entire location is scrapped and testing will be performed to determine if a release has occurred.

All trash is kept in a wire mesh enclosure and removed to an approved landfill when full. All spent motor oils are kept in separate containers and they are removed and sent to an approved recycling center. Any spilled lubricants, pipe

dope, or regulated chemicals are removed from soil and sent to landfills approved for these products.

These operations are monitored by Mi Swaco service technicians. Daily logs are maintained to ensure optimal equipment operation and maintenance. Screen and chemical use is logged to maintain inventory control. Fluid properties are monitored and recorded and drilling mud volumes are accounted for in the mud storage farm. This data is kept for end of well review to insure performance goals are met. Lessons learned are logged and used to help with continuous improvement.

A MI SWACO field supervisor manages from 3-5 wells. They are responsible for training personnel, supervising installations, and inspecting sites for compliance of MI SWACO safety and operational policy.

III. Closure Plan

A maximum 340' X 340' caliche pad is built per well. All of the trucks and steel tanks fit on this pad. All fluid cuttings go to the steel tanks to be hauled by various trucking companies to an agency approved disposal.

Devon Energy
APD VARIANCE DATA

OPERATOR NAME: Devon Energy

1. SUMMARY OF Variance:

Devon Energy respectfully requests approval for the following additions to the drilling plan:

1. Potential utilization of a spudder rig to pre-set surface casing.

2. Description of Operations

1. A spudder rig contractor may move in their rig to drill the surface hole section and pre-set surface casing on this well.
 - a. After drilling the surface hole section, the rig will run casing and cement following all of the applicable rules and regulations (OnShore Order 2, all COAs and NMOCD regulations).
 - b. Rig will utilize fresh water based mud to drill surface hole to TD.
2. The wellhead will be installed and tested once the surface casing is cut off and the WOC time has been reached.
3. A blind flange with the same pressure rating as the wellhead will be installed to seal the wellbore. Pressure will be monitored with needle valves installed on two wingvalves.
 - a. A means for intervention will be maintained while the drilling rig is not over the well.
4. The BLM will be contacted and notified 24 hours prior to commencing spudder rig operations.
5. Drilling operation will be performed with the big rig. At that time an approved BOP stack will be nipped up and tested on the wellhead before drilling operations commences on each well.
 - a. The BLM will be contacted / notified 24 hours before the big rig moves back on to the pad with the pre-set surface casing.
6. Devon Energy will have supervision on the rig to ensure compliance with all BLM and NMOCD regulations and to oversee operations.
7. Once the rig is removed, Devon Energy will secure the wellhead area by placing a guard rail around the cellar area.



U. S. Steel Tubular Products

9.625" 40.00lbs/ft (0.395" Wall) J55

1/24/2019 2:45:24 PM

MECHANICAL PROPERTIES	Pipe	BTC	LTC	STC	
Minimum Yield Strength	55,000	--	--	--	psi
Maximum Yield Strength	80,000	--	--	--	psi
Minimum Tensile Strength	75,000	--	--	--	psi

DIMENSIONS	Pipe	BTC	LTC	STC	
Outside Diameter	9.625	10.625	10.625	10.625	in.
Wall Thickness	0.395	--	--	--	in.
Inside Diameter	8.835	8.835	8.835	8.835	in.
Standard Drift	8.679	8.679	8.679	8.679	in.
Alternate Drift	8.750	8.750	8.750	8.750	in.
Nominal Linear Weight, T&C	40.00	--	--	--	lbs/ft
Plain End Weight	38.97	--	--	--	lbs/ft

PERFORMANCE	Pipe	BTC	LTC	STC	
Minimum Collapse Pressure	2,570	2,570	2,570	2,570	psi
Minimum Internal Yield Pressure	3,950	3,950	3,950	3,950	psi
Minimum Pipe Body Yield Strength	630	--	--	--	1,000 lbs
Joint Strength	--	714	520	452	1,000 lbs
Reference Length	--	11,898	8,665	7,529	ft


MAKE-UP DATA	Pipe	BTC	LTC	STC	
Make-Up Loss	--	4.81	4.75	3.38	in.
Minimum Make-Up Torque	--	--	3,900	3,390	ft-lbs
Maximum Make-Up Torque	--	--	6,500	5,650	ft-lbs

Legal Notice

All material contained in this publication is for general information only. This material should not therefore be used or relied upon for any specific application without independent competent professional examination and verification of accuracy, suitability and applicability. Anyone making use of this material does so at their own risk and assumes any and all liability resulting from such use. U. S. Steel disclaims any and all expressed or implied warranties of fitness for any general or particular application.

U. S. Steel Tubular Products
460 Wildwood Forest Drive, Suite 300S
Spring, Texas 77380

1-877-893-9461
connections@uss.com
www.usstubular.com





U. S. Steel Tubular Products

13.375" 48.00lbs/ft (0.330" Wall) H40

1/8/2019 12:38:52 PM

MECHANICAL PROPERTIES	Pipe	BTC	LTC	STC	
Minimum Yield Strength	40,000	--	--	--	psi
Maximum Yield Strength	80,000	--	--	--	psi
Minimum Tensile Strength	60,000	--	--	--	psi

DIMENSIONS	Pipe	BTC	LTC	STC	
Outside Diameter	13.375	--	--	14.375	in.
Wall Thickness	0.330	--	--	--	in.
Inside Diameter	12.715	--	--	12.715	in.
Standard Drift	12.559	12.559	--	12.559	in.
Alternate Drift	--	--	--	--	in.
Nominal Linear Weight, T&C	48.00	--	--	--	lbs/ft
Plain End Weight	46.02	--	--	--	lbs/ft

PERFORMANCE	Pipe	BTC	LTC	STC	
Minimum Collapse Pressure	740	740	--	740	psi
Minimum Internal Yield Pressure	1,730	1,730	--	1,730	psi
Minimum Pipe Body Yield Strength	541	--	--	--	1,000 lbs
Joint Strength	--	--	--	322	1,000 lbs
Reference Length	--	--	--	4,473	ft

MAKE-UP DATA	Pipe	BTC	LTC	STC	
Make-Up Loss	--	--	--	3.50	in.
Minimum Make-Up Torque	--	--	--	2,420	ft-lbs
Maximum Make-Up Torque	--	--	--	4,030	ft-lbs

Legal Notice

All material contained in this publication is for general information only. This material should not therefore be used or relied upon for any specific application without independent competent professional examination and verification of accuracy, suitability and applicability. Anyone making use of this material does so at their own risk and assumes any and all liability resulting from such use. U. S. Steel disclaims any and all expressed or implied warranties of fitness for any general or particular application.

U. S. Steel Tubular Products
460 Wildwood Forest Drive, Suite 300S
Spring, Texas 77380

1-877-893-9461
connections@uss.com
www.usstubular.com

A multibowl wellhead may be used. The BOP will be tested per Onshore Order #2 after installation on the surface casing which will cover testing requirements for a maximum of 30 days. If any seal subject to test pressure is broken the system must be tested.

Devon proposes using a multi-bowl wellhead assembly. This assembly will only be tested when installed on the surface casing. Minimum working pressure of the blowout preventer (BOP) and related equipment (BOPE) required for drilling below the surface casing shoe shall be 5000 (5M) psi.

- Wellhead will be installed by wellhead representatives.
- If the welding is performed by a third party, the wellhead representative will monitor the temperature to verify that it does not exceed the maximum temperature of the seal.
- Wellhead representative will install the test plug for the initial BOP test.
- Wellhead company will install a solid steel body pack-off to completely isolate the lower head after cementing intermediate casing. After installation of the pack-off, the pack-off and the lower flange will be tested to 5M, as shown on the attached schematic. Everything above the pack-off will not have been altered whatsoever from the initial nipple up. Therefore the BOP components will not be retested at that time.
- If the cement does not circulate and one inch operations would have been possible with a standard wellhead, the well head will be cut and top out operations will be conducted.
- Devon will pressure test all seals above and below the mandrel (but still above the casing) to full working pressure rating.
- Devon will test the casing to 0.22 psi/ft or 1500 psi, whichever is greater, as per Onshore Order #2.

After running the 13-3/8" surface casing, a 13-5/8" BOP/BOPE system with a minimum rating of 5M will be installed on the wellhead system and will undergo a 250 psi low pressure test followed by a 5,000 psi high pressure test. The 5,000 psi high and 250 psi low test will cover testing requirements a maximum of 30 days, as per Onshore Order #2. If the well is not complete within 30 days of this BOP test, another full BOP test will be conducted, as per Onshore Order #2.

After running the 9-5/8" intermediate casing with a mandrel hanger, the 13-5/8" BOP/BOPE system with a minimum rating of 5M will already be installed on the wellhead.

The pipe rams will be operated and checked each 24 hour period and each time the drill pipe is out of the hole. These tests will be logged in the daily driller's log. A 2" kill line and 3" choke line will be incorporated into the drilling spool below the ram BOP. In addition to the rams and annular preventer, additional BOP accessories include a kelly cock, floor safety valve, choke lines, and choke manifold rated at 5,000 psi WP.

Devon's proposed wellhead manufactures will be FMC Technologies, Cactus Wellhead, or Cameron.

Technical Specifications

Connection Type:	Size(O.D.):	Weight (Wall):	Grade:
DWC/C Casing standard	5-1/2 in	17.00 lb/ft (0.304 in)	P-110RY

	Material
P-110RY	Grade
110,000	Minimum Yield Strength (psi)
125,000	Minimum Ultimate Strength (psi)

	Pipe Dimensions
5.500	Nominal Pipe Body O.D. (in)
4.892	Nominal Pipe Body I.D.(in)
0.304	Nominal Wall Thickness (in)
17.00	Nominal Weight (lbs/ft)
16.89	Plain End Weight (lbs/ft)
4.962	Nominal Pipe Body Area (sq in)

	Pipe Body Performance Properties
546,000	Minimum Pipe Body Yield Strength (lbs)
7,480	Minimum Collapse Pressure (psi)
10,640	Minimum Internal Yield Pressure (psi)
9,700	Hydrostatic Test Pressure (psi)


	Connection Dimensions
6.050	Connection O.D. (in)
4.892	Connection I.D. (in)
4.767	Connection Drift Diameter (in)
4.13	Make-up Loss (in)
4.962	Critical Area (sq in)
100.0	Joint Efficiency (%)

	Connection Performance Properties
546,000	Joint Strength (lbs)
22,940	Reference String Length (ft) 1.4 Design Factor
568,000	API Joint Strength (lbs)
546,000	Compression Rating (lbs)
7,480	API Collapse Pressure Rating (psi)
10,640	API Internal Pressure Resistance (psi)
91.7	Maximum Uniaxial Bend Rating [degrees/100 ft]

	Appoximated Field End Torque Values
12,000	Minimum Final Torque (ft-lbs)
13,800	Maximum Final Torque (ft-lbs)
15,500	Connection Yield Torque (ft-lbs)



VAM-USA
4424 W. Sam Houston Pkwy. Suite 150
Houston, TX 77041
Phone: 713-479-3200
Fax: 713-479-3234
E-mail: VAMUSAsales@vam-usa.com




For detailed information on performance properties, refer to DWC Connection Data Notes on following page(s).

Connection specifications within the control of VAM-USA were correct as of the date printed. Specifications are subject to change without notice. Certain connection specifications are dependent on the mechanical properties of the pipe. Mechanical properties of mill proprietary pipe grades were obtained from mill publications and are subject to change. Properties of mill proprietary grades should be confirmed with the mill. Users are advised to obtain current connection specifications and verify pipe mechanical properties for each application.

11/13/2013 3:17:42 PM

**DWC Connection Data Notes:**

1. DWC connections are available with a seal ring (SR) option.
2. All standard DWC/C connections are interchangeable for a give pipe OD. DWC connections are interchangeable with DWC/C-SR connections of the same OD and wall.
3. Connection performance properties are based on nominal pipe body and connection dimensions.
4. DWC connection internal and external pressure resistance is calculated using the API rating for buttress connections. API Internal pressure resistance is calculated from formulas 31, 32, and 35 in the API Bulletin 5C3.
5. DWC joint strength is the minimum pipe body yield strength multiplied by the connection critical area.
6. API joint strength is for reference only. It is calculated from formulas 42 and 43 in the API Bulletin 5C3.
7. Bending efficiency is equal to the compression efficiency.
8. The torque values listed are recommended. The actual torque required may be affected by field conditions such as temperature, thread compound, speed of make-up, weather conditions, etc.
9. Connection yield torque is not to be exceeded.
10. Reference string length is calculated by dividing the joint strength by both the nominal weight in air and a design factor (DF) of 1.4. These values are offered for reference only and do not include load factors such as bending, buoyancy, temperature, load dynamics, etc.
11. DWC connections will accommodate API standard drift diameters.



Connection specifications within the control of VAM-USA were correct as of the date printed. Specifications are subject to change without notice. Certain connection specifications are dependent on the mechanical properties of the pipe. Mechanical properties of mill proprietary pipe grades were obtained from mill publications and are subject to change. Properties of mill proprietary grades should be confirmed with the mill. Users are advised to obtain current connection specifications and verify pipe mechanical properties for each application.

11/13/2013 3:17:42 PM

District I
1625 N. French Dr., Hobbs, NM 88240
District II
811 S. First St., Artesia, NM 88210
District III
1000 Rio Brazos Road, Aztec, NM 87410
District IV
1220 S. St. Francis Dr., Santa Fe, NM 87505

State of New Mexico
Energy, Minerals and Natural Resources Department
Oil Conservation Division
1220 South St. Francis Dr.
Santa Fe, NM 87505

Submit Original
to Appropriate
District Office

GAS CAPTURE PLAN

Date: 1/18/2019

☒ Original Devon & OGRID No.: Devon Energy Prod Co., LP (6137)
☐ Amended - Reason for Amendment: _____

This Gas Capture Plan outlines actions to be taken by the Devon to reduce well/production facility flaring/venting for new completion (new drill, recomple to new zone, re-frac) activity.

Note: Form C-129 must be submitted and approved prior to exceeding 60 days allowed by Rule (Subsection A of 19.15.18.12 NMAC).

Well(s)/Production Facility – Name of facility

The well(s) that will be located at the production facility are shown in the table below.

Well Name	API	Well Location (ULSTR)	Footages	Expected MCF/D	Flared or Vented	Comments
Belloq 11-2 Fed State Com 513H	N/A	Lot O, Sec 11, T23S, R 31E	500 FSL 2130 FEL			BELLOQ 11 CTB 2
Belloq 11-2 Fed State Com 514H	N/A	Lot P, Sec 11, T23S, R 31E	500 FSL 880 FEL			BELLOQ 11 CTB 2
Belloq 11-2 Fed State Com 523H	N/A	Lot O, Sec 11, T23S, R 31E	500 FSL 2160 FEL			BELLOQ 11 CTB 2
Belloq 11-2 Fed State Com 524H	N/A	Lot P, Sec 11, T23S, R 31E	500 FSL 910 FEL			BELLOQ 11 CTB 2

Gathering System and Pipeline Notification

Well(s) will be connected to a production facility after flowback operations are complete, if DCP system is in place. The gas produced from production facility is dedicated to DCP and will be connected to DCP low/high pressure gathering system located in Lea County, New Mexico. It will require 5500' of pipeline to connect the facility to low/high pressure gathering system. Devon provides (periodically) to DCP a drilling, completion and estimated first production date for wells that are scheduled to be drilled in the foreseeable future. In addition, Devon and DCP have periodic conference calls to discuss changes to drilling and completion schedules. Gas from these wells will be processed at DCP Processing Plant located in Sec.19, Twn. 19S, Rng. 32E, Eddy County, New Mexico. The actual flow of the gas will be based on compression operating parameters and gathering system pressures.

Flowback Strategy

After the fracture treatment/completion operations, well(s) will be produced to temporary production tanks and gas will be flared or vented. During flowback, the fluids and sand content will be monitored. When the produced fluids contain minimal sand, the wells will be turned to production facilities. Gas sales should start as soon as the wells start flowing through the production facilities, unless there are operational issues on DCP system at that time. Based on current information, it is Devon's belief the system can take this gas upon completion of the well(s).

Safety requirements during cleanout operations from the use of underbalanced air cleanout systems may necessitate that sand and non-pipeline quality gas be vented and/or flared rather than sold on a temporary basis.

Alternatives to Reduce Flaring

Below are alternatives considered from a conceptual standpoint to reduce the amount of gas flared.

- Power Generation – On lease

- Only a portion of gas is consumed operating the generator, remainder of gas will be flared
- Compressed Natural Gas – On lease
 - Gas flared would be minimal, but might be uneconomical to operate when gas volume declines
- NGL Removal – On lease
 - Plants are expensive, residue gas is still flared, and uneconomical to operate when gas volume declines



Fluid Technology

ContiTech Beattie Corp.
Website: www.contitechbeattie.com

Monday, June 14, 2010

RE: Drilling & Production Hoses
Lifting & Safety Equipment

To Helmerich & Payne,

A Continental ContiTech hose assembly can perform as intended and suitable for the application regardless of whether the hose is secured or unsecured in its configuration. As a manufacturer of High Pressure Hose Assemblies for use in Drilling & Production, we do offer the corresponding lifting and safety equipment, this has the added benefit of easing the lifting and handling of each hose assembly whilst affording hose longevity by ensuring correct handling methods and procedures as well as securing the hose in the unlikely event of a failure; but in no way does the lifting and safety equipment affect the performance of the hoses providing the hoses have been handled and installed correctly. It is good practice to use lifting & safety equipment but not mandatory.


Should you have any questions or require any additional information/clarifications then please do not hesitate to contact us.

ContiTech Beattie is part of the Continental AG Corporation and can offer the full support resources associated with a global organization.

Best regards,

Robin Hodgson
Sales Manager
ContiTech Beattie Corp

ContiTech Beattie Corp,
11535 Brittmoore Park Drive,
Houston, TX 77041
Phone: +1 (832) 327-0141
Fax: +1 (832) 327-0148
www.contitechbeattie.com



RIG 212



QUALITY DOCUMENT

PHOENIX RUBBER

INDUSTRIAL LTD.

6728 Szeged, Budapesti út 10. Hungary • H-6701 Szeged, P. O. Box 152
 Phone: (3662) 566-737 • Fax: (3662) 566-738

SALES & MARKETING: H-1092 Budapest, Ráday u. 42-44. Hungary • H-1440 Budapest, P. O. Box 26
 Phone: (361) 456-4200 • Fax: (361) 217-2972, 456-4273 • www.taurusemerge.hu

QUALITY CONTROL INSPECTION AND TEST CERTIFICATE				CERT. N°: 552	
PURCHASER: Phoenix Beattie Co.			P.O. N°: 1519FA-871		
PHOENIX RUBBER order N°: 170466		HOSE TYPE: 3" ID Choke and Kill Hose			
HOSE SERIAL N°: 34128		NOMINAL / ACTUAL LENGTH: 11,43 m			
W.P. 68,96 MPa 10000 psi		T.P. 103,4 MPa 15000 psi		Duration: 60 min.	
Pressure test with water at ambient temperature <div style="text-align: center;">See attachment. (1 page)</div>					
↑ 10 mm = 10 Min. → 10 mm = 25 MPa					
COUPLINGS					
Type	Serial N°		Quality	Heat N°	
3" coupling with 4 1/16" Flange end	720 719		AISI 4130	C7626	
			AISI 4130	47357	
API Spec 16 C Temperature rate: "B"					
All metal parts are flawless					
WE CERTIFY THAT THE ABOVE HOSE HAS BEEN MANUFACTURED IN ACCORDANCE WITH THE TERMS OF THE ORDER AND PRESSURE TESTED AS ABOVE WITH SATISFACTORY RESULT.					
Date:	Inspector		Quality Control		
29. April. 2002.			PHOENIX RUBBER Industrial Ltd. Hose Inspection and Pressure Testing PHOENIX RUBBER Q.C.		

40920-0-00015 NB0006

6	GN1	+0.000	PC	14:00		
	RD1	+0.000	PC	14:00		
	BL	+1041	SA	13:00		
7	GN1	+0.000	PC	13:40	40	
	RD1	+0.000	PC	13:40	60	
	BL	+1047	SA	13:10	80	
6	GN1	+0.000	PC	13:20		
	RD1	+0.000	PC	13:20		
	BL	+1050	SA	13:20		
5	GN1	+0.000	PC	13:00		
	RD1	+0.000	PC	13:00		
	BL	+1056	SA	13:00		
4						
3						
	PHOENIX 34123-12-32					
2						

GENEX RUBBER
Industrial Ltd.
Hose Inspection and
Certification Dept.

VERIFIED TRUE CO.
PHOENIX RUBBER CO.



APD ID: 10400038622

Submission Date: 01/31/2019

Highlighted data
reflects the most
recent changes

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11-2 FED STATE COM

Well Number: 524H

[Show Final Text](#)

Well Type: OIL WELL

Well Work Type: Drill

Section 1 - Existing Roads

Will existing roads be used? YES

Existing Road Map:

EX_RD_20190130091641.pdf

Existing Road Purpose: ACCESS,FLUID TRANSPORT

Row(s) Exist? NO

ROW ID(s)

ID:

Do the existing roads need to be improved? YES

Existing Road Improvement Description: Improve road to accommodate Drilling and Completion operations.

Existing Road Improvement Attachment:

Section 2 - New or Reconstructed Access Roads

Will new roads be needed? NO

Section 3 - Location of Existing Wells

Existing Wells Map? YES

Attach Well map:

BELLOQ_11_2_FED_STATE_COM_524H_OneMileBuffer_WA017267299_20190130091703.pdf

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11-2 FED STATE COM

Well Number: 524H

Section 4 - Location of Existing and/or Proposed Production Facilities

Submit or defer a Proposed Production Facilities plan? DEFER

Estimated Production Facilities description: Wells will go to Belloq 11 CTB 2 . Please refer to CTB plat.

Section 5 - Location and Types of Water Supply

Water Source Table

Water source type: OTHER

Describe type: null

Water source use type: STIMULATION

Source latitude:

Source longitude:

Source datum:

Water source permit type: OTHER

Water source transport method: PIPELINE

Source land ownership: FEDERAL

Source transportation land ownership: STATE

Water source volume (barrels): 230000

Source volume (acre-feet): 29.645412

Source volume (gal): 9660000

Water source and transportation map:

BELLOQ_11_2_FED_STATE_COM_524H__514H_water_x__map_20190130084312.PDF

Water source comments: The attached Water Transfer Map is a proposal only and the final route and documentation will be provided by a Devon contractor prior to installation. When available Devon will always follow existing disturbance.

New water well? NO

New Water Well Info

Well latitude:

Well Longitude:

Well datum:

Well target aquifer:

Est. depth to top of aquifer(ft):

Est thickness of aquifer:

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11-2 FED STATE COM

Well Number: 524H

Aquifer comments:

Aquifer documentation:

Well depth (ft):

Well casing type:

Well casing outside diameter (in.):

Well casing inside diameter (in.):

New water well casing:

Used casing source:

Drilling method:

Drill material:

Grout material:

Grout depth:

Casing length (ft.):

Casing top depth (ft.):

Well Production type:

Completion Method:

Water well additional information:

State appropriation permit:

Additional information attachment:

Section 6 - Construction Materials

Using any construction materials: YES

Construction Materials description: Dirt fill and caliche will be used to construct well pad. Map attached.

Construction Materials source location attachment:

BELLOQ_11__Caliche_Map_20190130084332.pdf

Section 7 - Methods for Handling Waste

Waste type: DRILLING

Waste content description: Water Based Cuttings

Amount of waste: 1985 barrels

Waste disposal frequency : Daily

Safe containment description: N/A

Safe containmant attachment:

Waste disposal type: HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** COMMERCIAL

Disposal type description:

Disposal location description: All cuttings will disposed of at R360, Sundance, or equivalent.

Waste type: COMPLETIONS/STIMULATION

Waste content description: Flow back water during completion operations.

Amount of waste: 3000 barrels

Waste disposal frequency : One Time Only

Safe containment description: N/A

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11-2 FED STATE COM

Well Number: 524H

Safe containmant attachment:

Waste disposal type: HAUL TO COMMERCIAL FACILITY **Disposal location ownership:** COMMERCIAL

Disposal type description:

Disposal location description: Various disposal locations in Lea and Eddy counties.

Waste type: FLOWBACK

Waste content description: Average produced BWPD over the flowback period (first 30 days of production).

Amount of waste: 2000 barrels

Waste disposal frequency : Daily

Safe containment description: N/A

Safe containmant attachment:

Waste disposal type: OFF-LEASE INJECTION **Disposal location ownership:** STATE

Disposal type description:

Disposal location description: Produced water during flowback will be disposed of at various disposals in Lea and Eddy County.

Waste type: PRODUCED WATER

Waste content description: Average produced BWPD over the first year of production

Amount of waste: 1000 barrels

Waste disposal frequency : Daily

Safe containment description: N/A

Safe containmant attachment:

Waste disposal type: OFF-LEASE INJECTION **Disposal location ownership:** PRIVATE

Disposal type description:

Disposal location description: Multiple methods for handling waste will be utilized. Via trucking, Dvn owned disposal system and or third party pipeline take away.

Reserve Pit

Reserve Pit being used? NO

Temporary disposal of produced water into reserve pit?

Reserve pit length (ft.) **Reserve pit width (ft.)**

Reserve pit depth (ft.) **Reserve pit volume (cu. yd.)**

Is at least 50% of the reserve pit in cut?

Reserve pit liner

Reserve pit liner specifications and installation description

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11-2 FED STATE COM

Well Number: 524H

Cuttings Area

Cuttings Area being used? NO

Are you storing cuttings on location? NO

Description of cuttings location

Cuttings area length (ft.)

Cuttings area width (ft.)

Cuttings area depth (ft.)

Cuttings area volume (cu. yd.)

Is at least 50% of the cuttings area in cut?

WCuttings area liner

Cuttings area liner specifications and installation description

Section 8 - Ancillary Facilities

Are you requesting any Ancillary Facilities?: NO

Ancillary Facilities attachment:

Comments:

Section 9 - Well Site Layout

Well Site Layout Diagram:

524H_RIG_LAYOUT_20190130091800.pdf

Comments:

Section 10 - Plans for Surface Reclamation

Type of disturbance: New Surface Disturbance

Multiple Well Pad Name: BELLOQ 11 PAD

Multiple Well Pad Number: 4

Recontouring attachment:

RECLAMATION_20190130091814.pdf

Drainage/Erosion control construction: All areas disturbed shall be reclaimed as early and as nearly as practicable to their original condition or their final land use and shall be maintained to control dust and minimize erosion to the extent practicable.

Drainage/Erosion control reclamation: Topsoils and subsoils shall be replaced to their original relative positions and contoured so as to achieve erosion control, long-term stability and preservation of surface water flow patterns. The disturbed area then shall be reseeded in the first favorable growing season.

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11-2 FED STATE COM

Well Number: 524H

Well pad proposed disturbance (acres): 4.76

Road proposed disturbance (acres): 0.978

Powerline proposed disturbance (acres): 0

Pipeline proposed disturbance (acres): 1.136

Other proposed disturbance (acres): 5.741

Total proposed disturbance: 12.615

Well pad interim reclamation (acres): 1.995

Road interim reclamation (acres): 0

Powerline interim reclamation (acres): 0

Pipeline interim reclamation (acres): 0

Other interim reclamation (acres): 0

Total interim reclamation: 1.995

Well pad long term disturbance (acres): 2.765

Road long term disturbance (acres): 0

Powerline long term disturbance (acres): 0

Pipeline long term disturbance (acres): 1.136

Other long term disturbance (acres): 5.741

Total long term disturbance: 9.642

Disturbance Comments:

Reconstruction method: Operator will use Best Management Practices "BMP" to mechanically recontour to obtain the desired outcome.

Topsoil redistribution: Topsoils shall be replaced to their original relative positions and contoured so as to achieve erosion control, long-term stability and preservation of surface water flow patterns.

Soil treatment: Topsoils shall be replaced to their original relative positions and contoured so as to achieve erosion control, long-term stability and preservation of surface water flow patterns.

Existing Vegetation at the well pad: Shinnery, yucca, grasses and mesquite.

Existing Vegetation at the well pad attachment:

Existing Vegetation Community at the road: Shinnery, yucca, grasses and mesquite.

Existing Vegetation Community at the road attachment:

Existing Vegetation Community at the pipeline: Shinnery, yucca, grasses and mesquite.

Existing Vegetation Community at the pipeline attachment:

Existing Vegetation Community at other disturbances: Shinnery, yucca, grasses and mesquite.

Existing Vegetation Community at other disturbances attachment:

Non native seed used? NO

Non native seed description:

Seedling transplant description:

Will seedlings be transplanted for this project? NO

Seedling transplant description attachment:

Will seed be harvested for use in site reclamation? NO

Seed harvest description:

Seed harvest description attachment:

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11-2 FED STATE COM

Well Number: 524H

Seed Management

Seed Table

Seed type:

Seed source:

Seed name:

Source name:

Source address:

Source phone:

Seed cultivar:

Seed use location:

PLS pounds per acre:

Proposed seeding season:

Seed Summary	
Seed Type	Pounds/Acre

Total pounds/Acre:

Seed reclamation attachment:

Operator Contact/Responsible Official Contact Info

First Name: JACOB

Last Name: OCHOA

Phone: (575)748-9934

Email: JACOB.OCHOA@DVN.COM

Seedbed prep:

Seed BMP:

Seed method:

Existing invasive species? NO

Existing invasive species treatment description:

Existing invasive species treatment attachment:

Weed treatment plan description: Maintain weeds on an as need basis.

Weed treatment plan attachment:

Monitoring plan description: Monitor as needed.

Monitoring plan attachment:

Success standards: N/A

Pit closure description: N/A

Pit closure attachment:

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11-2 FED STATE COM

Well Number: 524H

Section 11 - Surface Ownership

Disturbance type: PIPELINE

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Disturbance type: NEW ACCESS ROAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11-2 FED STATE COM

Well Number: 524H

USFS Forest/Grassland:

USFS Ranger District:

Disturbance type: EXISTING ACCESS ROAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Disturbance type: WELL PAD

Describe:

Surface Owner: BUREAU OF LAND MANAGEMENT

Other surface owner description:

BIA Local Office:

BOR Local Office:

COE Local Office:

DOD Local Office:

NPS Local Office:

State Local Office:

Military Local Office:

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11-2 FED STATE COM

Well Number: 524H

USFWS Local Office:

Other Local Office:

USFS Region:

USFS Forest/Grassland:

USFS Ranger District:

Section 12 - Other Information

Right of Way needed? NO

Use APD as ROW?

ROW Type(s):

ROW Applications

SUPO Additional Information:

Use a previously conducted onsite? YES

Previous Onsite information: 5-2017; Belloq 11 Fed State Com 223H

Other SUPO Attachment


AA000145292_BELLOQ_11_CTB_2_PAD_P_20190130084933.pdf

EL8031_BELLOQ_11_WELL_PAD_4_ELECTRIC_LINE_P_R1_20190130084936.pdf

7660157F_BELLOQ_11_PAD_4_CTB_2_FL_P_20190130084929.pdf

512H_524H_Pay.gov__Receipt_20190130121932.pdf

SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
AERIAL ACCESS ROUTE MAP



NOT TO SCALE
AERIAL PHOTO:
GOOGLE EARTH
NOV. 2017

DEVON ENERGY PRODUCTION COMPANY, L.P.
BELLOQ 11-2 FED STATE COM 524H
LOCATED 500 FT. FROM THE SOUTH LINE
AND 910 FT. FROM THE EAST LINE OF
SECTION 11, TOWNSHIP 23 SOUTH,
RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

DECEMBER 13, 2018

SURVEY NO. 6186B

MADRON SURVEYING, INC. 301 SOUTH CANAL (575) 234-3341 CARLSBAD, NEW MEXICO

PLAT
One Mile Radius Map



This map is for illustrative purposes only and is neither a legally recorded map nor a survey and is not intended to be used as one. Devon makes no warranty, representation, or guarantee of any kind regarding this map.

USA Contiguous Equidistant Conic
Datum: North American 1983
Created by: FME Server
Map is current as of 1/17/2019



0 0.3 1 inch = 0.44 miles

BELLOQ 11-2 FED STATE COM 524H
WA017267299


TOMB RAIDER 1-12 FED 61H
Nearest wellbore to SHL:

1565 ft.

TANKLESS FEDERAL COM 002H
Nearest wellbore to BHL:

508 ft.

- Unknown SHL
- Active SHL
- Inactive SHL
- × BHL



BELLOQ 11-2 FED STATE COM

524H, 514H



This map is for illustrative purposes only and is neither a legally recorded map nor survey and is not intended to be used as one. Devon makes no warranty, representation, or guarantee of any kind regarding this map.

WGS_1984_Web_Mercator_Auxiliary_Sphere

Prepared by: _User

Map is current as of: 17-May-2018



Miles

0 0.14 0.28 0.56 1:28,457

CROFT FW POND

DEVON 30 DAY, INSTALL DAYS PRIOR TO COMPLETION
DEVON WILL CONTACT BLM IF ADDITIONAL TIME IS NEEDED
DISTURBANCE: EXISTING
CONTENTS: TREATED WATER & FRESH WATER
TYPE OF TYPE: LAYFLAT
SIZE OF PIPE: 10" OR 12"
LENGTH OF PIPE: TW 6,816' & FW 15,971'

TODD 2 TW POND

BELLOQ 11-2 FED STATE COM 524H, 514H

1E = 3

23S = 31E = 2

23S = 31E = 1

23S = 32E = 16

23310114

15

Caliche Pit 23S 31E Section 1

Total 12,911.57 ft

6,332.82 ft

E = 10

23S = 31E = 11

23S = 31E = 12

23S = 32E = 7

Belloq 11


E = 15

23S = 31E = 13

23S = 31E = 13

23S = 32E = 18


Devon Energy - Well Pad Rig Location Layout Safety Equipment Location



BELLOQ 11 CTB 2

DEVON ENERGY PRODUCTION COMPANY, L.P.
IN THE SW/4 SE/4 & NW/4 SE/4 OF
SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

MAY 15, 2017



DESCRIPTION

A CERTAIN PIECE OR PARCEL OF LAND AND REAL ESTATE LYING IN THE SW/4 SE/4 & NW/4 SE/4 OF SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST N.M.P.M., EDDY COUNTY, NEW MEXICO.

BEGINNING AT THE SOUTHWEST CORNER OF THE PARCEL, WHENCE THE SOUTH QUARTER CORNER OF SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S11°12'43"W, A DISTANCE OF 841.35 FEET; THENCE N00°06'55"W A DISTANCE OF 500.06 FEET TO THE NORTHWEST CORNER OF THE PARCEL; THENCE N89°53'03"E A DISTANCE OF 500.08 FEET TO THE NORTHEAST CORNER OF THE PARCEL; THENCE S00°06'46"E A DISTANCE OF 500.06 FEET TO THE SOUTHEAST CORNER OF THE PARCEL; THENCE S89°53'02"W A DISTANCE OF 500.06 FEET TO THE SOUTHWEST CORNER OF THE PARCEL, TO THE POINT OF BEGINNING; CONTAINING 5.682 ACRES IN THE SW/4 SE/4 & 0.059 ACRES IN THE NW/4 SE/4 FOR A TOTAL OF 5.741 ACRES MORE OR LESS.

GENERAL NOTES

- 1.) THE INTENT OF THIS SURVEY IS TO ACQUIRE A BUSINESS LEASE FOR THE PURPOSE OF BUILDING A CENTRAL TANK BATTERY
- 2.) BASIS OF BEARING IS NEW MEXICO STATE PLANE EAST ZONE MODIFIED TO THE SURFACE (NAD83)

DRIVING DIRECTIONS: FROM STATE HIGHWAY 128 AND CR 798 (RED ROAD) GO NORTH ON CR 798 4.7 MILES, TURN LEFT (WEST) AT LEASE ROAD GO WEST 0.15 OF A MILE, ROAD BENDS RIGHT GO NORTHWEST 0.2 OF A MILE, TURN LEFT (SOUTHWEST) GO 0.4 OF A MILE, TURN LEFT (SOUTH) GO APPROX. 0.25 OF A MILE TO EXISTING PAD (BARCLAY 11N FED 14, AT EAST EDGE OF PAD IS ROAD LATH RED & WHITE FLAGGING, GO EAST APPROX. 328', TURN LEFT GO NORTH 675', TURN RIGHT GO EAST 370' TO THE NORTHWEST PAD CORNER.

SHEET: 1-3

SURVEYOR CERTIFICATE

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 15th DAY OF MAY 2017.

[Signature of Filmon F. Jaramillo]
FILMON F. JARAMILLO, PLS. #12797

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SURVEY NO. 5241


MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO (575) 234-3341

BELLOQ 11 CTB 2

DEVON ENERGY PRODUCTION COMPANY, L.P.
IN THE SW/4 SE/4 & NW/4 SE/4 OF
SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

MAY 15, 2017

QUAD MAP



SHEET: 2-3

SURVEY NO. 5241


MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
(575) 234-3341

BELLOQ 11 CTB 2

DEVON ENERGY PRODUCTION COMPANY, L.P.
IN THE SW/4 SE/4 & NW/4 SE/4 OF
SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO

MAY 15, 2017

AERIAL PHOTO




SHEET: 3-3

SURVEY NO. 5241

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
(575) 234-3341

PLAN VIEW



DEVON ENERGY PRODUCTION COMPANY, L.P.
 GRADING PLAN AND CROSS SECTIONS
FOR BELLOQ 11 CTB 2
 SECTION 11, TOWNSHIP 23 SOUTH,
 RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO

0 12 60 120 240
 SCALE 1" = 120'




CUT	FILL	NET
14524 CU. YD	20841 CU. YD	6317 CU. YD (FILL)

EARTHWORK QUANTITIES ARE ESTIMATED

MAY 15, 2017
 MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
 (575) 234-3341

SHEET 1-2
 SURVEY NO. 5241

CROSS SECTIONS



DEVON ENERGY PRODUCTION COMPANY, L.P.
 GRADING PLAN AND CROSS SECTIONS
FOR BELLOQ 11 CTB 2
 SECTION 11, TOWNSHIP 23 SOUTH,
 RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO

012 60 120 240
 SCALE 1" = 120' - 1" = 20' VER


MAY 15, 2017

MADRON SURVEYING, INC. 301 SOUTH CANAL CARLSBAD, NEW MEXICO
 (575) 234-3341


SHEET 2-2
 SURVEY NO. 5241

ACCESS ROAD PLAT
ACCESS ROAD TO THE BELLOQ 11 CTB 2

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
MAY 15, 2017



SEE NEXT SHEET (2-2) FOR DESCRIPTION



GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SHEET: 1-2

MADRON SURVEYING, INC.

SURVEYOR CERTIFICATE

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 12TH DAY OF MAY 2017

Filmon F. Jaramillo
FILMON F. JARAMILLO, PLS. #12797
MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SURVEY NO. 5241

CARLSBAD, NEW MEXICO

ACCESS ROAD PLAT
ACCESS ROAD TO THE BELLOQ 11 CTB 2

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF AN ACCESS ROAD CROSSING
SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
MAY 15, 2017

DESCRIPTION

A STRIP OF LAND 30 FEET WIDE CROSSING BUREAU OF LAND MANAGEMENT LAND IN SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.; EDDY COUNTY, STATE OF NEW MEXICO AND BEING 15 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

BEGINNING AT A POINT WITHIN THE SE/4 SW/4 OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE SOUTH QUARTER CORNER OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S18°03'46"E, A DISTANCE OF 667.28 FEET;

THENCE N00°00'07"W A DISTANCE OF 675.94 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;

THENCE N89°59'58"E A DISTANCE OF 369.51 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE SOUTH QUARTER CORNER OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S07°04'25"W, A DISTANCE OF 1320.38 FEET;

SAID STRIP OF LAND BEING 1045.45 FEET OR 63.36 RODS IN LENGTH, CONTAINING 0.720 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

SE/4 SW/4	876.91 L.F.	53.15 RODS	0.604 ACRES
SW/4 SE/4	168.54 L.F.	10.21 RODS	0.116 ACRES

SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO, THIS 22 DAY OF MAY 2017.


FILIMON F. JARAMILLO
MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

GENERAL NOTES

1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.

2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SHEET: 2-2



MADRON SURVEYING INC.  **SURVEY NO. 5241**
301 SOUTH CANAL
(575) 234-3341
CARLSBAD, NEW MEXICO

EXHIBIT "A"
PAGE 1 of 4
ELECTRIC LINE PLAT
SECTION 11, T23S-R31E, N.M.P.M.
EDDY COUNTY, NEW MEXICO




30' EASEMENT AREA = 0.401 ACRE(S)
582.52 FEET OR 35.30 RODS

SEE THE ATTACHED LEGAL DESCRIPTION

Note: All bearings recited herein are based on the New Mexico State Plane Coordinate System, NAD 83, New Mexico East Zone 3001, US Survey Feet, all distances are grid.

I, B.L. Laman, New Mexico PLS No. 22404, hereby certify this survey to reflect an actual survey made on the ground under my supervision. This survey meets the minimum standards for surveying in New Mexico.



B.L. Laman
Date Signed: 03-22-2018
Horizonrow, LLC
P.O. Box 548, Dry Creek, LA.
(903) 388-3045 70637
Employee of Horizonrow, LLC

HORIZON ROW LLC

Drawn for:

devon

Drawn by:
JEANNIE PERRY

Date: 03/12/2018

DEVON ENERGY PRODUCTION COMPANY, L.P.

BELLOQ 11 WELL PAD 4
ELECTRIC LINE

PROPOSED 30' EASEMENT
ON THE PROPERTY OF
BUREAU OF LAND MANAGEMENT
SECTION 11, T23S-R31E, N.M.P.M.

LINE NUMBER:
EL8031

WBS NUMBER:
CC-127671.01.FAC

SCALE:
1" = 1000'

REVISIONS:

SHEET:
1 OF 4

0 1000 2000



SECTION 11, T23S-R31E, N.M.P.M.,
EDDY COUNTY, NEW MEXICO

ELECTRIC LINE PLAT

LEGAL DESCRIPTION

FOR

DEVON ENERGY PRODUCTION COMPANY, L.P.

BUREAU OF LAND MANAGEMENT

30' EASEMENT DESCRIPTION:

BEING an easement thirty (30) feet in width lying fifteen (15) feet on the right side and fifteen (15) feet on the left side of the survey centerline described below, being out of Section 11, Township 23 South, Range 31 East, N.M.P.M., Eddy County, New Mexico, and being out of a parcel of land owned by the Bureau of Land Management. Said centerline of easement being more particularly described as follows:

Commencing from a 2" iron pipe w/ BC found for the southeast corner of Section 11, T23S-R31E, N.M.P.M., Eddy County, New Mexico;

Thence N 15°21'41" W, a distance of 908.75' to the **Point of Beginning** of this easement, having coordinates of Northing=478512.37 feet, Easting=724390.63 feet, and continuing the following courses;


Thence S 86°16'28" W, a distance of 379.72' to an angle point;

Thence S 01°15'09" E, a distance of 202.80' to the **Point of Ending**, having coordinates of Northing=478284.95 feet, Easting=724016.15 feet, from said point a 1" iron pipe w/ BC found for the south quarter corner of Section 11, T23S-R31E, N.M.P.M., Eddy County, New Mexico bears S 72°07'07" W a distance of 2129.90', covering a total of **582.52' or 35.30 rods** and having an area of **0.401 acres**.

NOTES:

Bearings, distances and coordinates shown herein are based on New Mexico State Plane Coordinate System, NAD 83, East Zone 3001, US Survey Feet, all distances are grid.

I, B.L. Laman, New Mexico PLS No. 22404, hereby certify this survey to reflect an actual survey made on the ground under my supervision. This survey meets the minimum standards for surveying in New Mexico.


B.L. Laman PLS 22404

Date Signed: 03/22/2018

Horizon Row, LLC

P.O. Box 548, Dry Creek, LA


(903) 388-3045 70637

Employee of Horizon Row, LLC



EXHIBIT "A"

PAGE 3 of 4.



QUAD MAP

SECTION 11, T23S-R31E, N.M.P.M.;
EDDY COUNTY, NEW MEXICO

HORIZON ROW LLC

DEVON ENERGY PRODUCTION CO., L.P.

PROPOSED 30' EASEMENT

Drawn by:
JEANNIE PERRY

Date: 03/12/2018

Drawn for:



LINE NUMBER:
EL8031

WBS NUMBER:
CC-127671.01.FAC


SCALE:
1" = 2000'

REVISIONS:

SHEET:
3 OF 4

EXHIBIT "A"

PAGE 4 of 4



AERIAL MAP

SECTION 11, T23S-R31E, N.M.P.M.;
EDDY COUNTY, NEW MEXICO

HORIZON ROW LLC

DEVON ENERGY PRODUCTION CO., L.P.

PROPOSED 30' EASEMENT

Drawn by:
JEANNIE PERRY

Date: 03/12/2018

Drawn for:




LINE NUMBER:
EL8031
WBS NUMBER:
CC-127671.01.FAC
SCALE:
1" = 2000'
REVISIONS:
SHEET:
4 OF 4


FLOWLINE PLAT

FOUR-8" FLOWLINES & ONE-8" GAS LIFT LINE BURIED IN THE SAME DITCH FROM BELLOQ 11 WELLPAD 4 (BELLOQ 11-2 FED STATE COM 524H, 514H, 223H, & 234H) TO BELLOQ 11 CTB 2

DEVON ENERGY PRODUCTION COMPANY, L.P.
 CENTERLINE SURVEY OF A PIPELINE CROSSING
 SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
 EDDY COUNTY, STATE OF NEW MEXICO
 JANUARY 9, 2019



SEE NEXT SHEET (2-4) FOR DESCRIPTION



GENERAL NOTES

- 1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.
- 2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SHEET: 1-4

MADRON SURVEYING, INC. CARLSBAD, NEW MEXICO

SURVEYOR CERTIFICATE

I, FILMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY. THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD,

NEW MEXICO THIS 10 DAY OF JANUARY 2019

FILMON F. JARAMILLO, PLS. 12797
 301 SOUTH CANAL
 CARLSBAD, NEW MEXICO 88220
 (575) 234-3341

MADRON SURVEYING, INC.
 301 SOUTH CANAL
 CARLSBAD, NEW MEXICO 88220
 Phone (575) 234-3341

SURVEY NO. 6834

FLOWLINE PLAT

FOUR-8" FLOWLINES & ONE-8" GAS LIFT LINE BURIED IN THE SAME DITCH FROM
BELLOQ 11 WELLPAD 4 (BELLOQ 11-2 FED STATE COM 524H, 514H, 223H, & 234H) TO BELLOQ 11 CTB 2

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF A PIPELINE CROSSING
SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
JANUARY 9, 2019

DESCRIPTION

A STRIP OF LAND 30 FEET WIDE CROSSING BUREAU OF LAND MANAGEMENT LAND IN SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., EDDY COUNTY, STATE OF NEW MEXICO AND BEING 15 FEET EACH SIDE OF THE FOLLOWING DESCRIBED CENTERLINE SURVEY:

BEGINNING AT A POINT WITHIN THE SE/4 SE/4 OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M., WHENCE THE SOUTHEAST CORNER OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S45°08'31"E, A DISTANCE OF 920.13 FEET;
THENCE N00°00'17"W A DISTANCE OF 108.80 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;
THENCE N89°59'52"W A DISTANCE OF 1477.21 FEET TO AN ANGLE POINT OF THE LINE HEREIN DESCRIBED;
THENCE N00°02'11"W A DISTANCE OF 63.13 FEET THE TERMINUS OF THIS CENTERLINE SURVEY, WHENCE THE SOUTH QUARTER CORNER OF SAID SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M. BEARS S31°51'49"W, A DISTANCE OF 972.90 FEET;

SAID STRIP OF LAND BEING 1649.14 FEET OR 99.95 RODS IN LENGTH, CONTAINING 1.136 ACRES MORE OR LESS AND BEING ALLOCATED BY FORTIES AS FOLLOWS:

SE/4 SE/4	781.57 L.F.	47.37 RODS	0.538 ACRES
SW/4 SE/4	867.57 L.F.	52.58 RODS	0.597 ACRES

GENERAL NOTES

1.) THE INTENT OF THIS ROUTE SURVEY IS TO ACQUIRE AN EASEMENT.

2.) BASIS OF BEARING AND DISTANCE IS NMSP EAST (NAD83) MODIFIED TO SURFACE COORDINATES. NAD 83 (FEET) AND NAVD 88 (FEET) COORDINATE SYSTEMS USED IN THE SURVEY.

SHEET: 2-4

MADRON SURVEYING, INC.

SURVEYOR CERTIFICATE

I, FILIMON F. JARAMILLO, A NEW MEXICO PROFESSIONAL SURVEYOR NO. 12797, HEREBY CERTIFY THAT I HAVE CONDUCTED AND AM RESPONSIBLE FOR THIS SURVEY, THAT THIS SURVEY IS TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF, AND THAT THIS SURVEY AND PLAT MEET THE MINIMUM STANDARDS FOR LAND SURVEYING IN THE STATE OF NEW MEXICO.

IN WITNESS WHEREOF, THIS CERTIFICATE IS EXECUTED AT CARLSBAD, NEW MEXICO THIS 12TH DAY OF JANUARY 2019

[Signature]
FILIMON F. JARAMILLO, PLS. #12797
301 SOUTH CANAL
(575) 234-3341

MADRON SURVEYING, INC.
301 SOUTH CANAL
CARLSBAD, NEW MEXICO 88220
Phone (575) 234-3341

SURVEY NO. 6834

CARLSBAD, NEW MEXICO

FLOWLINE PLAT

FOUR-8" FLOWLINES & ONE-8" GAS LIFT LINE BURIED IN THE SAME DITCH FROM
BELLOQ 11 WELLPAD 4 (BELLOQ 11-2 FED STATE COM 524H, 514H, 223H, & 234H) TO BELLOQ 11 CTB 2


DEVON ENERGY PRODUCTION COMPANY, L.P.

CENTERLINE SURVEY OF A PIPELINE CROSSING

SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.

EDDY COUNTY, STATE OF NEW MEXICO


JANUARY 9, 2019



FLOWLINE PLAT

FOUR-8" FLOWLINES & ONE-8" GAS LIFT LINE BURIED IN THE SAME DITCH FROM
BELLOQ 11 WELLPAD 4 (BELLOQ 11-2 FED STATE COM 524H, 514H, 223H, & 234H) TO BELLOQ 11 CTB 2

DEVON ENERGY PRODUCTION COMPANY, L.P.
CENTERLINE SURVEY OF A PIPELINE CROSSING
SECTION 11, TOWNSHIP 23 SOUTH, RANGE 31 EAST, N.M.P.M.
EDDY COUNTY, STATE OF NEW MEXICO
JANUARY 9, 2019



S11, T23S, R31E
 EDDY COUNTY, STATE OF NEW MEXICO
 BUREAU OF LAND MANAGEMENT LAND
 1649.14 L.F.
 99.95 RODS

OWNERSHIP



PLAN ON AERIAL

EASEMENT

STATIONING

PROFILE

LEGEND



PIPE SPECIFICATIONS AND TEST REQUIREMENTS		BILL OF MATERIAL		X-RAY REQUIREMENTS		RECORD		APPROVED FOR CONSTRUCTION	
FROM	TO	LN. FT.	O.D.	W.T.	GRADE	D.P.	TEST PRESS. MIN	TEST DUE HL	DATE
									1/11/19
									1/11/19

MADRON SURVEYING, INC. 201 NORTH CANAL CARLSBAD, NEW MEXICO
 (505) 234-5141

SHEET: 1-1

FOUR-8" FLOWLINES & ONE-8" GAS LIFT LINE BURIED IN THE SAME DITCH FROM BELLOO 11 WELLPAD 4 (BELLOO 11-2 FED STATE COM 524H, 514H, 223H, & 234H) TO BELLOO 11 CTB 2
 JANUARY 9, 2019

**DEVON ENERGY
 PRODUCTION
 COMPANY, L.P.**



Receipt

Tracking Information

Pay.gov Tracking ID: 26F3G8IJ

Agency Tracking ID: 75668973897

Form Name: Bureau of Land Management (BLM) Application for Permit to Drill (APD) Fee

Application Name: BLM Oil and Gas Online Payment

Payment Information

Payment Type: Bank account (ACH)

Payment Amount: \$20,100.00

Transaction Date: 01/30/2019 11:28:56 AM EST

Payment Date: 01/31/2019

Company: Devon Energy Production Company, L.P.

APD IDs: 10400038557, 10400038622

Lease Numbers: NMNM0404441, NMNM0404441

Well Numbers: 512H, 524H

Note: You will need your Pay.gov Tracking ID to complete your APD transaction in AFMSS II. Please ensure you write this number down upon completion of payment.

Account Information

Account Holder Name: Devon Energy Production Company, L.P.

Routing Number: 061000052

Account Number: *****9892



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

PWD Data Report

10/20/2019

APD ID: 10400038622

Submission Date: 01/31/2019

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11-2 FED STATE COM

Well Number: 524H

Well Type: OIL WELL

Well Work Type: Drill

Section 1 - General

Would you like to address long-term produced water disposal? NO

Section 2 - Lined Pits

Would you like to utilize Lined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Lined pit PWD on or off channel:

Lined pit PWD discharge volume (bbl/day):

Lined pit specifications:

Pit liner description:

Pit liner manufacturers information:

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal permit:

Lined pit precipitated solids disposal schedule:

Lined pit precipitated solids disposal schedule attachment:

Lined pit reclamation description:

Lined pit reclamation attachment:

Leak detection system description:

Leak detection system attachment:

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11-2 FED STATE COM

Well Number: 524H

Lined pit Monitor description:

Lined pit Monitor attachment:

Lined pit: do you have a reclamation bond for the pit?

Is the reclamation bond a rider under the BLM bond?

Lined pit bond number:

Lined pit bond amount:

Additional bond information attachment:

Section 3 - Unlined Pits

Would you like to utilize Unlined Pit PWD options? NO

Produced Water Disposal (PWD) Location:

PWD disturbance (acres):

PWD surface owner:

Unlined pit PWD on or off channel:

Unlined pit PWD discharge volume (bbl/day):

Unlined pit specifications:

Precipitated solids disposal:

Describe precipitated solids disposal:

Precipitated solids disposal permit:

Unlined pit precipitated solids disposal schedule:

Unlined pit precipitated solids disposal schedule attachment:

Unlined pit reclamation description:

Unlined pit reclamation attachment:

Unlined pit Monitor description:

Unlined pit Monitor attachment:

Do you propose to put the produced water to beneficial use?

Beneficial use user confirmation:

Estimated depth of the shallowest aquifer (feet):

Does the produced water have an annual average Total Dissolved Solids (TDS) concentration equal to or less than that of the existing water to be protected?

TDS lab results:

Geologic and hydrologic evidence:

State authorization:

Unlined Produced Water Pit Estimated percolation:

Unlined pit: do you have a reclamation bond for the pit?

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11-2 FED STATE COM

Well Number: 524H

Is the reclamation bond a rider under the BLM bond?

Unlined pit bond number:

Unlined pit bond amount:

Additional bond information attachment:

Section 4 - Injection

Would you like to utilize Injection PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Injection PWD discharge volume (bbl/day):

Injection well mineral owner:

Injection well type:

Injection well number:

Injection well name:

Assigned injection well API number?

Injection well API number:

Injection well new surface disturbance (acres):

Minerals protection information:

Mineral protection attachment:

Underground Injection Control (UIC) Permit?

UIC Permit attachment:

Section 5 - Surface Discharge

Would you like to utilize Surface Discharge PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Surface discharge PWD discharge volume (bbl/day):

Surface Discharge NPDES Permit?

Surface Discharge NPDES Permit attachment:

Surface Discharge site facilities information:

Surface discharge site facilities map:

Section 6 - Other

Would you like to utilize Other PWD options? NO

Produced Water Disposal (PWD) Location:

PWD surface owner:

PWD disturbance (acres):

Other PWD discharge volume (bbl/day):

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11-2 FED STATE COM

Well Number: 524H

Other PWD type description:

Other PWD type attachment:

Have other regulatory requirements been met?

Other regulatory requirements attachment:



U.S. Department of the Interior
BUREAU OF LAND MANAGEMENT

Bond Info Data Report

10/20/2019

APD ID: 10400038622

Submission Date: 01/31/2019

Operator Name: DEVON ENERGY PRODUCTION COMPANY LP

Well Name: BELLOQ 11-2 FED STATE COM

Well Number: 524H

Well Type: OIL WELL

Well Work Type: Drill

Highlighted data
reflects the most
recent changes

[Show Final Text](#)

Bond Information

Federal/Indian APD: FED

BLM Bond number: CO1104

BIA Bond number:

Do you have a reclamation bond? NO

Is the reclamation bond a rider under the BLM bond?

Is the reclamation bond BLM or Forest Service?

BLM reclamation bond number:

Forest Service reclamation bond number:

Forest Service reclamation bond attachment:

Reclamation bond number:

Reclamation bond amount:

Reclamation bond rider amount:

Additional reclamation bond information attachment: