
Submit I Copy To Appropriate District State of New Mexico	Form C-103
District I – (575) 393-6161 Energy, Minerals and Natural Resource District II – (575) 748-1283 District II – (575) 748-1283	WELL API NO.
811 S. First St., Artesia, NM 88210 District III – (505) 334-6178 MAR 1 1 2020 South St. Francis Dr.	S. Indicate Type of Lease STATE
District IV - (505) 476-3460	6. State Oil & Gas Lease No.
1220 S. St. Francis Dr., Santa EMNRD-OCDARTESIA 87505	
SUNDRY NOTICES AND REPORTS ON WELLS (DO NOT USE THIS FORM FOR PROPOSALS TO DRILL OR TO DEEPEN OR PLUG BACK TO A DIFFERENT RESERVOIR. USE "APPLICATION FOR PERMIT" (FORM C-101) FOR SUCH PROPOSALS.)	7. Lease Name or Unit Agreement Name Sweet Pea SWD
1. Type of Well: Oil Well 🗌 Gas Well 🛛 Other SWD	8. Well Number 001
2. Name of Operator TLT SWD, LLC	9. OGRID Number 287481
3. Address of Operator	10. Pool name or Wildcat
PO Box 1906, Hobbs, NM 88241	SWD; Bell Canyon- Cherry Canyon
4. Well Location Unit Letter_L: 1980feet from theSouth line and660feet from theWestline	
Section 2 Township 23S Range 31E NMPM Eddy County	
11. Elevation (Show whether DR, RKB, RT, GR, etc.) 3411	
12. Check Appropriate Box to Indicate Nature of Notice, Report or Other Data	
NOTICE OF INTENTION TO: SUBSEQUENT REPORT OF:	
PERFORM REMEDIAL WORK PLUG AND ABANDON REMEDIAL WORK	
PULL OR ALTER CASING I MULTIPLE COMPL CASING/CEMENT JOB	
OTHER: DTHER:	
13. Describe proposed or completed operations. (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work). SEE RULE 19.15.7.14 NMAC. For Multiple Completions: Attach wellbore diagram of proposed completion or recompletion.	
2.25.2020 - 3.5.2020	
Tested anchors. O.K. MIRU WSU.	
NU B.O.P. Bled well down in ½ pit. Released Arrowset pkr. TOH. LD 3 1/2 tbg. RU W.L. Ran gauge ring to 4555'. TOH. Ran 5 ½"	
CIBP. Set @ 4550'. PU 2 7/8" W.S. TIH to 4550'. Circ. Hole w/ 10" gelled brine. Spotted 25 sxs Class "C" cement on CIBP. (Job delayed due to weather & ND old tree). Next morning tagged top of cement above CIBP 4308'. PU pkr. TIH. RU W.L. Perf 4 spf @	
2100'. Spot 50 sxs Class "C" cement. Squeezed same. W.O.C. 4 hrs. Tagged TOC 1851'. TIH w/ perf gun. Perf 4 spf @ 750. Spotted 25	
sxs Class "C" cement. Squeezed. W.O.C. 4 hrs. Tagged TOC 497'. TOH to 150'. Pump 45 sxs Class "C" cement. Spot & attempt to	
squeeze. Circ. 25 sxs to surface. Released all equipment. Cleaned ½ pit. Moved out.	
Dry hole marker & clean up / re-hab per regulation within 90 days.	
Approved for plugging of well bore only.	
	Liability under bond is retained pending receive of C-10.3 (Subsequent Report of Well Placesias)
	which may be found at OCD Web Page under Forms, www.cammd.state.mm.us/ocd-
Spud Date: Rig Release Date:	
· · · · · · · · · · · · · · · · · · ·	
I hereby certify that the information above is true and complete to the best of my knowledge and belief.	
SIGNATURE LBCock PLON TITLE Agent	DATE3/7/2020
Type or print nameM.Y. Merchant E-mail address:mymerch@penrocoil.com PHONE:575-492-1236 For State Use Only	
APPROVED BY: MARCE TITLE Staff Mr. DATE 3/13/20	
Conditions of Approval (if any):	

,



.