

- 6) Junk drilling cable and other large items of junk will be removed from drill site by the drilling contractor under the supervision of Enserch Exploration, Inc. After the rig has moved out, the area will be cleaned up by a roustabout crew under the supervision of Enserch Exploration, Inc.

8. Ancillary Facilities.

- A. None

9. Well Site Layout.

- A. Cross section of drill site with approximate cuts and fills is shown on attached Exhibit No. 6.
- B. Location of mud pits, reserve pits, burn and trash pits, pipe racks, etc. are shown on attached Exhibit No. 7.
- C. Rig orientation, parking areas and access roads are shown on attached Exhibit No. 7.
- D. Reserve pit will be lined.

10. Plans for Restoration of Surface.

- A. The following agreements have been made with the surface owner upon completion of drilling and testing.
 - 1) The drilling location will be leveled and waste disposal pits backfilled upon completion of drilling and testing operations.
 - 2) None required by land owner.
 - 3) Pits will be fenced and maintained until they have dried and can be backfilled.
 - 4) Any oil on Reserve Pit will be removed.
 - 5) All of the area except the Reserve Pit will be leveled after the rig has moved out and testing operations have been completed. The pit will be allowed to dry, then it will be backfilled and leveled. It is anticipated that clean up will be completed by August, 1980.

11. Other Information.

- A. General Description.

- 1) Archaeology Report attached as Exhibit No. 8.