


8. After setting the 8-5/8" casing string and before drilling into the Abo formation, the blowout preventers and related control equipment shall be pressure tested to rated working pressures. Any equipment failing to test satisfactorily shall be repaired or replaced. This office should be notified in sufficient time for a representative to witness the tests.
9. Notify the Survey by telephone 24 hours prior to spudding well.
10. Cement behind the 13-3/8" casing must be circulated.
11. Please have anyone contacting the Survey in regard to this well to identify the well with all of the information required above for the well sign.

Sincerely yours,



George H. Stewart  
Acting District Engineer