

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil ☒ gas ☐ other ☐
well well
2. NAME OF OPERATOR
Yates Petroleum Corporation /
3. ADDRESS OF OPERATOR
207 South 4th St., Artesia, NM 88210
4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 990' FNL & 990' FEL
AT TOP PROD. INTERVAL:
AT TOTAL DEPTH:
16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

- | REQUEST FOR APPROVAL TO: | | SUBSEQUENT REPORT OF: |
|---------------------------|--------------------------|--------------------------|
| TEST WATER SHUT-OFF | <input type="checkbox"/> | <input type="checkbox"/> |
| FRACTURE TREAT | <input type="checkbox"/> | <input type="checkbox"/> |
| SHOOT OR ACIDIZE | <input type="checkbox"/> | <input type="checkbox"/> |
| REPAIR WELL | <input type="checkbox"/> | <input type="checkbox"/> |
| PULL OR ALTER CASING | <input type="checkbox"/> | <input type="checkbox"/> |
| MULTIPLE COMPLETE | <input type="checkbox"/> | <input type="checkbox"/> |
| CHANGE ZONES | <input type="checkbox"/> | <input type="checkbox"/> |
| ABANDON* | <input type="checkbox"/> | <input type="checkbox"/> |
| (other) Perforate & Treat | | |

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

TD 1100'- WIH w/Steel Strip gun & perforated 1022-1041' w/12 .50" holes. Set packer (Uni VI 4-1/2") at 986'. Acidized perforations 1022-1041' w/1500 gallons 15% regular acid & 15 ball sealers. Swab tested well. TOOH & set cement retainer at 1006'. Squeezed perforations 1022-1041' w/100 sacks Class C .4% CF-2 & 2% CaCl₂. TOOH. WIH w/Steel strip gun & perforated 948-966' w/15 .50" holes as follows: 948, 49, 50, 51, 52, 60, 61, 62, 63, 64, 65 & 66'. Acidized perforations 948-966' w/1500 gallons 15% regular acid using 15 ball sealers. Swabbed well down. Run rods & pump and set pumpjack.

5. LEASE
NM 27909
6. IF INDIAN, ALLOTTEE OR TRIBE NAME RECEIVED
7. UNIT AGREEMENT NAME
APR 23 1981
8. FARM OR LEASE NAME
Comanche PQ Federal O. C. D.
9. WELL NO.
1 ARTEZIA, OFFICE
10. FIELD OR WILDCAT NAME
Und. San Andres
11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA
Unit A, Sec. 27-T10S-R25E
12. COUNTY OR PARISH
Chaves
13. STATE
NM
14. API NO.
15. ELEVATIONS (SHOW DF, KDB, AND WD)
3536.1' GR


(NOTE: Report results of multiple completion or zone change on Form 9-330.)

Subsurface Safety Valve: Manu. and Type

18. I hereby certify that the foregoing is true and correct.

SIGNED Roger A. Chapman TITLE Engineering Secretary DATE 4-17-81

APPROVED BY
CONDITIONS OF APPROVAL, IF ANY:



This space for Federal or State office use)

TITLE

DATE

*See Instructions on Reverse Side

1000