

UNITED STATES  
DEPARTMENT OF THE INTERIOR  
BUREAU OF LAND MANAGEMENT

SUBMIT IN TRIPLI  
(Other instructions  
verse side)

Form approved.  
Budget Bureau No. 1004-0135  
Expires August 31, 1985

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.  
Use "APPLICATION FOR PERMIT—" for such proposals.)

1. OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/>		7. UNIT AGREEMENT NAME	
2. NAME OF OPERATOR Stevens Operating		8. FARM OR LEASE NAME Sand Creek Federal	
3. ADDRESS OF OPERATOR Post Office Box A, Roswell, NM 88202-9500		9. WELL NO. 1	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.) At surface Section 17, T.7S, R.37E 990' FNL, 660' FWL		10. FIELD AND POOL, OR WILDCAT Wildcat San Andres	
14. PERMIT NO.		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA Sec. 17-T7S-R27E	
15. ELEVATIONS (Show whether DF, RT, GR, etc.) 3934 GR		12. COUNTY OR PARISH Chaves	
		13. STATE NM	

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF	<input type="checkbox"/>	PULL OR ALTER CASING	<input type="checkbox"/>
FRACTURE TREAT	<input type="checkbox"/>	MULTIPLE COMPLETE	<input type="checkbox"/>
SHOOT OR ACIDIZE	<input type="checkbox"/>	ABANDON*	<input checked="" type="checkbox"/>
REPAIR WELL	<input type="checkbox"/>	CHANGE PLANE	<input type="checkbox"/>
(Other)	<input type="checkbox"/>		

SUBSEQUENT REPORT OF:

WATER SHUT-OFF	<input type="checkbox"/>	REPAIRING WELL	<input type="checkbox"/>
FRACTURE TREATMENT	<input type="checkbox"/>	ALTERING CASING	<input type="checkbox"/>
SHOOTING OR ACIDIZING	<input type="checkbox"/>	ABANDONMENT*	<input type="checkbox"/>
(Other)	<input type="checkbox"/>		

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)\*

Proposed Operations:

1. Set CIBP @ 1640'.
2. Dump 75x cement on top of CIBP.
3. turn hole over to mud (90 BBLs).
4. Lay in cement plug f/1100' - 1000' (30 sx).
5. Cut & pull 7" csg f/325'.
6. Lay in cement plug f/375' - 225' (50 sx).
7. Lay in cement f/50' - 0' (20 sx).

Data:

10-3/4" - 40# csg f/0-302'; cement circulated; 15" bit  
7-5/8" - 26# csg f/0-1799'; 175 sx cement; 10" bit  
TD 1799', PBTD 1787'; top perf 1741.5'



RECEIVED

DEC 08 1995

OIL CON. DIV.  
DIST. 2

18. I hereby certify that the foregoing is true and correct

SIGNED Billy Walker


TITLE Consultant

DATE 11/01/95

(This space for Federal or State office use)

APPROVED BY  
CONDITIONS OF APPROVAL, IF ANY:

TITLE



\*See Instructions on Reverse Side