

clsf

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT" for such proposals.)

1. OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER <input type="checkbox"/>	2. NAME OF OPERATOR Yates Petroleum Corporation ✓	3. ADDRESS OF OPERATOR 105 South 4th St., Artesia, NM 88210	4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.) At surface 1980' FNL & 660' FEL
14. PERMIT NO. API #30-005-62576	15. ELEVATIONS (Show whether DF, RT, GR, etc.) 3861' GR		

5. LEASE DESIGNATION AND SERIAL NO. NM 29211	6. IF INDIAN, ALLOTTEE OR TRIBE NAME	7. UNIT AGREEMENT NAME	8. FARM OR LEASE NAME Engwall RL Federal	9. WELL NO. 2	10. FIELD AND POOL, OR WILDCAT Pecos Slope Abo	11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA Unit H, Sec. 4-T9S-R26E	12. COUNTY OR PARISH Chaves	13. STATE NM
---	--------------------------------------	------------------------	---	------------------	---	---	--------------------------------	-----------------


16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:		SUBSEQUENT REPORT OF:	
TEST WATER SHUT-OFF <input type="checkbox"/>	PULL OR ALTER CASING <input type="checkbox"/>	WATER SHUT-OFF <input checked="" type="checkbox"/>	REPAIRING WELL <input type="checkbox"/>
FRACTURE TREAT <input type="checkbox"/>	MULTIPLE COMPLETION <input type="checkbox"/>	FRACTURE TREATMENT <input type="checkbox"/>	ALTERING CASING <input type="checkbox"/>
SHOOT OR ACIDIZE <input type="checkbox"/>	ABANDON* <input type="checkbox"/>	SHOOTING OR ACIDIZING <input type="checkbox"/>	ABANDONMENT* <input type="checkbox"/>
REPAIR WELL <input type="checkbox"/>	CHANGE PLANS <input type="checkbox"/>	(Other) <input type="checkbox"/>	

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*


Spudded 26" hole at 2:00 PM 12-30-87 with Frank's Rathole. Set 55' of 20" conductor pipe. Notified James Brasfield, BLM, Roswell, NM, of spud. Resumed drilling 12-1/4" hole 2:45 PM 1-1-88. Lost circulation 60'. Filled hole with Redi-mix. Ran 23 joints 8-5/8" 24# J-55 casing set 974'. Texas Pattern notched guide shoe set 974'. Insert float set 932'. Cemented w/450 sx Halliburton Lite w/1/2#sx Flocele + 10#/sx Gilsonite and 3% CaCl2 (yield 1.84, weight 12.8). Tailed in w/200 sx Class "C" with 2% CaCl2 (yield 1.32, weight 14.6). PD 1:45 PM 1-3-88. Bumped plug to 600 psi, released pressure and float held okay. Cement circulated 5 sacks. Drilled out 8:30 AM 1-4-88. WOC 18 hrs and 45 minutes. NU and tested to 1000 psi for 30 minutes, OK. Reduced hole to 7-7/8". Resumed drilling.



18. I hereby certify that the foregoing is true and correct

SIGNED [Signature] TITLE Production Supervisor DATE 1-5-88
(This space for Federal or State office use)

APPROVED BY _____ TITLE _____
CONDITIONS OF APPROVAL, IF ANY:



*See Instructions on Reverse Side