

8. TESTING, LOGGING AND CORING PROGRAM:

DST: Significant shows will be tested.

Logging: Neutron log will be run from surface to TD.  
Laterolog from 3000'± to TD.  
Other logs as determined by geologist.

9. ABNORMAL PRESSURES, TEMPERATURES OR HYDROGEN SULFIDE:

None anticipated

10. ANTICIPATED STARTING DATE: Drilling will commence prior to the January 31, 1993 lease expiration date. Drilling and completion operations should require about 30 days.

