

Operator Prairie State Mngt. Corp.
Well Sprague State #2
Unit E Section 30 Township 17 Range 28
API # 30-015-01621

TOPS

LAGERS ~
THINERS 487'

← 60' Surface Plug.

- * Contact OCD 24 hrs. prior to any work done.
- * Salt gel mud consisting of 10# brine with 25# of gel per barrel must be placed between each plug.
- * Install dry hole marker as per Rule 202.B.2
- * Plugs are to be set from point indicated up.
- * Plugs must not be less than 100' or 25 Sacks of cement, whichever is greater, unless specifically indicated.
- * Shoe and stub plugs will be 50' above and below shoe or stub and tagged.
- * Surface plug will be from 0' - 60'
- * Where plugs are required, cement must be placed inside and outside of all casing string(s) in the correct footage or sacks required, if no cement exists.
- * Plugs to be tagged will be indicated.

No Toe.
Mud Only.

5 5/8" @ 325'
mud
10" Hole.

← 275' Cement Plug Inside + Outside 8 5/8" csj. TAG



TD 549'

MS