

RE: CONTINUED DRILLING PROGNOSIS  
STABLEIN #8  
EDDY COUNTY, NEW MEXICO

---

XI. CASING AND TUBING PROGRAM: (CONTINUED)

B. Production: 4-1/2" K-55 9.5# ST&C casing will be run.

Cementing of production casing will be with Class "H" cement with 1/4# floccel, 3/4 of 1% CFR-2, 5# salt, 10# sand per sack, and Class "C" if the well is to be cemented above the Seven Rivers.

XII. SAFETY PROGRAM:

Blowout preventers will be used as well as close observation by Company personnel to assure the well is safely drilled.

XIII. THIRD PARTY SERVICES:

Surveying:	Jones & Company	and	John West Engineering
Dirtwork:	Jabo Rowland	and	Sweatt Construction
Cementing:	Halliburton	and	B. J.
Logging:	Dresser Atlas		
Drilling Mud:	Marrs	and	Magobar
Water Trucking:	I & W	and	C L M

XIV. LOG DISTRIBUTION:

2 - W. T. Patterson	GAOC Meadows Building	Dallas, Texas 75206
4 - L. N. Hawkins	GAOC P.O. Box 128	Loco Hills, N. M. 88255