

7. Maximum anticipated bottom hole pressure is 3300 psi at approximately 8500' based on nearby well data. Mud weight required to offset this pressure is 7.5 ppg. Maximum bottom hole temperature should approach 130°F. No sour gas is expected.
8. Anticipated starting date is April 21, 1980, with completion of drilling operations on May 20, 1980. Completion operations (perforating and stimulation) will follow the drilling operations as soon as a CU is available.