

After tripping up on surface pipe,
but before drilling out the cement
plug, the BOP's shall be tested to
the rated working pressure.

FREQUENCY

The BOP's shall be cycled
on every trip.

