

Operator SLX Resources Inc.  
 Well 30-01S-24123 'A' # 11  
 Unit C Section 13 Township 17 Range 27  
 API # 30-01S-24123

TOPS

|             |       |
|-------------|-------|
| Gate        | 116'  |
| TRivers     | 400'  |
| Bowers      | 650'  |
| Queen       | 874'  |
| Graburg     | 1324' |
| San Antonio | 1668' |

3 5/8" @ 442'  
CIRC

8 5/8" @ 800'  
CIRC

5 1/2" @ 2229'  
Loc est - 310'

- \* Contact OCD 24 hrs. prior to any work done.
- \* Salt gel mud consisting of 10# brine with 25# of gel per barrel must be placed between each plug.
- \* Install dry hole marker as per Rule 202.B.2
- \* Plugs are to be set from point indicated up.
- \* Plugs must not be less than 100' or 25 Sacks of cement, whichever is greater, unless specifically indicated.
- \* Shoe and stub plugs will be 50' above and below shoe or stub and tagged.
- \* Surface plug will be from 0' - 60'
- \* Where plugs are required, cement must be placed inside and outside of all casing string(s) in the correct footage or sacks required, if no cement exists.
- \* Plugs to be tagged will be indicated.