

9. Abnormal Conditions, Pressures, Temperatures and Potential Hazards:

No abnormal pressures, temperatures, or other potential hazards are anticipated.

Some minor hydrogen sulfide may be encountered. No major lost circulation zones have been reported in offsetting wells.

The maximum anticipated bottom hole pressure is approximately 1386 psi.  
(3257' x .433 psi/ft = 1386 psi)

The maximum anticipated bottom hole temperature is 90 degrees F.

10. Anticipated Starting Date and Duration of Operations:

Road and location work will not begin until approval has been received from the BLM. The anticipated spud date is November 20, 1999. Once commenced, the drilling operation should be complete in 10 days.