

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEYSUBMIT IN TRIPLICATE*
(Other instructions on reverse side)Form approved.
Budget Bureau No. 42-R1424.

5. LEASE DESIGNATION AND SERIAL NO.

LC-028793-C

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

UNIT AGREEMENT NAME

8. FARM OR LEASE NAME

Burch "C"

9. WELL NO.

27

10. FIELD AND POOL, OR WILDCAT

Grayburg-Jackson

11. SEC., T., R., M., OR BLK. AND
SURVEY OR AREA

Sec. 30, T 17-S, R 30-E

12. COUNTY OR PARISH 13. STATE

Eddy

New Mexico

1. OIL WELL ☒ GAS WELL ☐ OTHER ☐

RECEIVED

2. NAME OF OPERATOR

General American Oil Company of Texas

SEP 13 1972

3. ADDRESS OF OPERATOR

P. O. Box 416, Loco Hills, New Mexico 88255

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. See also space 17 below.)
At surfaceO. C. C.
ARTESIA, OFFICE

1980' FSL and 1980' FWL, Sec. 30, T-17S, R-30E.

14. PERMIT NO.

15. ELEVATIONS (Show whether DF, RT, GR, etc.)

3597' GL

16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF ☐FRACTURE TREAT ☐SHOOT OR ACIDIZE ☐REPAIR WELL ☐(Other) ☐PULL OR ALTER CASING ☐MULTIPLE COMPLETE ☐ABANDON* ☐CHANGE PLANS ☐

SUBSEQUENT REPORT OF:

WATER SHUT-OFF ☒FRACTURE TREATMENT ☒SHOOTING OR ACIDIZING ☐(Other) ☐REPAIRING WELL ☐ALTERING CASING ☐ABANDONMENT* ☐

(NOTE: Report results of multiple completion, Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

1. Well spudded at 11:30 a.m., 5-27-72.

2. Ran 494' KB of 8-5/8 20# casing as follows:

a. Volume of cement equalled 132 cubic feet (100 sacks).

b. Brand of cement was Southwestern Class C with 2% CaCl.

c. Approximate temperature of cement slurry was 69°F.

d. Formation temperature was 85°F.

e. After standing cemented for 9 hours compressive strength was 800#. Pressure tested to 400#. Tested OK.

f. Drilled out cement after standing cemented 12 hours.

3. Ran 3388' KB of 4-1/2" 9.5# casing and cemented with 350 sacks cement.

4. We perforated as follows: 2703'-2711', 2758'-2764', 2831'-2838', 2916'-2920', 2950'-2954', 3138'-3146', 3312'-3318', 3368'-3374.

5. Acidized from 3368' to 3374' with 3,000 gallons 15% acid.

Acidized from 3312' to 3318' with 3,000 gallons 15% acid.

Fraced from 3138' to 3146' with 30,000# sand and 30,000 gallons gelled water.

Fraced from 2916' to 2954' with 30,000# sand and 30,000 gallons gelled water.

Fraced from 2831' to 2838' with 20,000# sand and 20,000 gallons gelled water.

Acidized from 2754' to 2764' with 2,500 gallons 15% acid.

Fraced from 2703' to 2711' with 25,000# sand and 25,000 gallons gelled water.

18. I hereby certify that the foregoing is true and correct

SIGNED

W. E. Hatter

TITLE District Superintendent

DATE 8-29-72

(This space for Federal or State office use)


APPROVED BY

CONDITIONS OF APPROVAL, IF ANY:

TITLE

DATE

*See Instructions on Reverse Side



Instructions

General: This form is designed for submitting proposals to perform certain well operations, and reports of such operations when completed, as indicated, on Federal and Indian lands pursuant to applicable Federal law and regulations, and, if approved or accepted by any State, on all lands in such State, pursuant to applicable State law and regulations. Any necessary special instructions concerning the use of this form and the number of copies to be submitted, particularly with regard to local, area, or regional procedures and practices, either are shown below or will be issued by, or may be obtained from, the local Federal and/or State office.

Item 4: If there are no applicable State requirements, locations on Federal or Indian land should be described in accordance with Federal requirements. Consult local State or Federal office for specific instructions.

Item 17: Proposals to abandon a well and subsequent reports of abandonment should include such special information as is required by local Federal and/or State offices. In addition, such proposals and reports should include reasons for the abandonment; data on any former or present productive zones, or other zones with present significant fluid contents not sealed off by cement or otherwise; depths (top and bottom) and method of placement of cement plugs; mud or other material placed below, between and above plugs; amount, size, method of parting of any casing, liner or tubing pulled and the depth to top of any left in the hole; method of closing top of well; and date well site conditioned for final inspection looking to approval of the abandonment.