

UNITED STATES
DEPARTMENT OF THE INTERIOR
GEOLOGICAL SURVEY

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use Form 9-331-C for such proposals.)

1. oil well ☒ gas well ☐ other ☐

2. NAME OF OPERATOR ARCO Oil & Gas Company
Division of Atlantic Richfield Co.

3. ADDRESS OF OPERATOR
P. O. Box 1710, Hobbs, New Mexico 88240

4. LOCATION OF WELL (REPORT LOCATION CLEARLY. See space 17 below.)
AT SURFACE: 430' FSL & 2250' FEL, Unit "0"
AT TOP PROD. INTERVAL: as above
AT TOTAL DEPTH: as above

16. CHECK APPROPRIATE BOX TO INDICATE NATURE OF NOTICE,
REPORT, OR OTHER DATA

REQUEST FOR APPROVAL TO:		SUBSEQUENT
TEST WATER SHUT-OFF	<input type="checkbox"/>	<input type="checkbox"/>
FRACTURE TREAT	<input type="checkbox"/>	<input type="checkbox"/>
SHOOT OR ACIDIZE	<input type="checkbox"/>	<input type="checkbox"/>
REPAIR WELL	<input type="checkbox"/>	<input type="checkbox"/>
PULL OR ALTER CASING	<input type="checkbox"/>	<input type="checkbox"/>
MULTIPLE COMPLETE	<input type="checkbox"/>	<input type="checkbox"/>
CHANGE ZONES	<input type="checkbox"/>	<input type="checkbox"/>
ABANDON*	<input checked="" type="checkbox"/>	
(other)		

Grbg Jackson
only

5. LEASE LC-029435(b)	
6. IF INDIAN, ALLOTTEE OR TRIBE NAME	
7. UNIT AGREEMENT NAME	
8. FARM OR LEASE NAME J. L. Keel "B"	
9. WELL NO. 30	
10. FIELD OR WILDCAT NAME Grayburg Jackson QCSA	
11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA 6-17S-31E	
12. COUNTY OR PARISH Eddy	13. STATE N M
14. API NO. 30-015-21460	
15. ELEVATIONS (SHOW DF, KDB, AND WD) 3760.4' GR	

RECEIVED
JUL (NOV) 1981
Report results
change on Form

OIL & GAS
U.S. GEOLOGICAL SURVEY
ROSWELL, NEW MEXICO

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Propose to P&A the Grayburg Jackson, recomplete in Fren Seven Rivers in the following manner:

1. Rig up, install BOP, POH w/comp assy.
2. RIH w/pkr, set pkr @ 2850' & establish pump rate.
3. POH w/pkr, set cmt retr @ 2850'. Squeeze cmt perfs 2889-3170' w/ CI C cmt cont'g 2% CaCl₂ w/amt determined from pump rate. *

NOTE: Recompletion to Seven Rivers reported separately on Form 9-331-C.

Blowout Preventer Program Attached.

* Leave cement plug within $5\frac{1}{2}$ " casing from 3220' to 2839'

Subsurface Safety Valve: Manu. and Type _____ **Set @** _____ **Ft.**

18. I hereby certify that the foregoing is true and correct

SIGNED George Schmidt TITLE Dist. Drlg. Supt DATE 6/30/81

APPROVED AS AMENDED


(Orig. Sgd.) PETER W. CHESTER

APPROVED BY: Col. Dg. PETER W. CHESTER TITLE _____ DATE _____
CONDITIONS OF APPROVAL, IF ANY: _____

VAL IF ANY: JUL 9 1981

for JAMES A. GILLHAM
DISTRICT SUPERVISOR

*See Instructions on Reverse Side



ARCO Oil & Gas Company

Division of Atlantic Richfield Company

Blow Out Preventer Program

Lease Name J. L. Keel "B"

Well No. 30

Location 430' FSL & 2250' FEL Unit "O"
Sec 6-17S-31E, Eddy Co. N M

BOP to be tested before installed on well and will be maintained in good working condition during drilling. All wellhead fittings to be of sufficient pressure to operate in a safe manner.