

8. TESTING PROGRAM:

Possible DST's 6500' - TD as dictated by shows. Such tests, if necessary, will be conducted under prudent industry practice.

Open Hole Logs planned - Schlumberger

CNL/LD/GR/Cal	3000 - TD
DLL/MSFL	3000 - TD
BHC/GR	3000 - TD

GR log will be ran from surface to TD. Other logs and logging intervals at wellsite geologist's discretion.

9. POTENTIAL HAZARDS:

No H²S, abnormal temperatures or abnormal pressures are anticipated. Maximum mud weight is 10.2 ppg to lessen washouts in the salt, and 9.8 ppg cut brine to inhibit sloughing shale.

10. ESTIMATED STARTING DATE:

Anticipate starting operations as soon as possible, subject to approval of this permit.