Form 3160-3 (Decem Ser 1990)	TERARCHEN A	STATES WI ssien nterioi	SUBMIT IN TP—UICAT (See other instr. on reverse side)	E*	Form approved.	ely
	ANTE BUREAU OF LAN	ID MANAGEMENT		5. LEASE LC 0294	DESIGNATION AND SER	IAL NO.
	47 GO E	TO DRILL OR DEEPEN			IAN, ALLOTTEE OR TR	THE NAME
la TYPE OF WORK:	DRILL 🔀	DEEPEN 🖂		NA		
b TYPE OF WELL:	_	SINGLE	MULTIPLE [7.UNIT A NA	GREEMENT NAME	
2 NAME OF OPERAT	WELL Oulei	ZONE	ZONE	8. FARM O	R LEASE NAME, WELL	NO.
2 NAME OF OFFICE	DEVON ENERGY OPERA	TING CORPORATION	136025	WEST "	'A" #32 16	469
3. ADDRESS AND TE	LEPHONE NO.			9.API WE		
	20 N. BROADWAY, SUITE			30-0	215 - 283	, 24
	-	CTHODOX Subject	. RECEN	Visi	AND POOL, OR WILDOURG-JACKSON	IRUS-QN-GB-SA
At top proposed prod.	zone (SAME) LOCA	Tion: Like App			3-T17 S - R31 E	
	Unit	CG\ By State	10 10 2	1004		
	AND DIRECTION FROM NEAREST TOWN OR	POST OFFICE*	JAN DO	EDDY	TY OR PARISH	13. STATE NM
4 miles east & 4 mile	es north of Loco Hills, N.M.			2001	. 	NP.
15.DISTANCE FROM PROPO		16.NO. OF ACRES IN LEASE	OIF COM	. Di	17.NO. OF ACRES	ASSIGNED
PROPERTY OR LEASE L		639.56	DIST.	2	TO THIS WELL	
(Also to nearest drig, unit lin 18. DISTANCE FROM PROPO		19. PROPOSED DEPTH		(5)	20.ROTARY OR CAR	TE TOOLST
TO NEAREST WELL, DR	ILLING, COMPLETED,	4400			Rotary	ne 10013
OR APPLIED FOR, ON 21.ELEVATIONS (Show who		<u> </u>	***************************************	22.	APPROX. DATE WORK W	/ILL START+
3964' GR	,,,				uary 1, 1995	
23.		PROPOSED CASING AND CEN	MENTING PROGRAM		·	
SIZE OF HOLE	GRADE, SIZE OF CASING	WEIGHT PER FOOT	SETTING DEPTH	T	QUANTITY	OF CEMENT
12 1/4"	8 5/8" J-55	24.0#	600' CIRCULAT	E	165 sk lite cmt + 2	00 sk Class "C"
7 7/8"	5 1/2" J-55	15.5#	4400'		500 sk Class "C" 35	/65 + 500 sk Class
the Grayburg-Ja wellbore will be p outlined in the fo Drilling Program Exhibits #1/1-A = Exhibit #2 Exhibit #3/3-A = Exhibit #4 Exhibit #5 Exhibit #6 Exhibit #7 H2S Operating P	Blowout Prevention Equip Location and Elevation Pla Road Map and Topo Map Wells Within 1 Mile Radiu Production Facilities Plat Rotary Rig Layout Casing Designary	reial quantities of oil. If the Federal Regulations. Proposal is to deepen, give date in Federal Regulations. The undersiment terms, conducted of the restrictions conducted of the reof, as	he Grayburg-Jackson is grams to adhere to onsh grams to adhere to onsh gned accepts all applicalition, stipulations and concerning operations in the leased land or por lescribed below: C029426-A iption: Section 3-T17N-age: Nationwide No.: CO1151	and proper	OFC 09	al, the ons are Port ID-1 2-3-95 Auwher + API
This space for Fede	eral or State office use)		APPROVAL DATE		12/6/94	
CONDITIONS OF API	PROVAL, IF ANY: RIG. SGD.) RICHARD L.		MANAGER			-

State of New Mexico Ene , Minerals, and Natural Resources L artment Revised 02-10-94

Instructions on back

Submit to the Appropriate District Office State Lease — 4 copies Fee Lease — 3 copies

DISTRICT II P. O. Drawer DD Artesia, NM 88211-0719 OIL CONSERVATION DIVISION <u>DISTRICT III</u> 1000 Rio Brazos Rd. Aztec, NM 87410 P. O. Box 2088 Santa Fe, New Mexico 87504-2088

AMENDED REPORT

DISTRICT IV
P. O. Box 2088
Sonto Fe, NM 87507-2088 WELL LOCATION AND ACREAGE DEDICATION PLAT

1 API Number		² Pool Code	3 Po	ol Name	 				
30-015-2	8324	78509	1 G1	auburg-	Jackson; 7	RUS-QN	-6B-SA		
* Property Code G	* Well Number								
OGRID No. Operator Name DEVON ENERGY DPERATING COMPANY							* Elevation 3964	* Elevation 3964*	
	-	14	SURFACE	LOCATION					
UL or lot no. Section	Township 17 SOUTH	Range 31 EAST, N.M		Feet from the 2622'	North/South line NORTH	Feet from the 1330'	East/West line EAST	County EDDY	
	"BOTT	OM HOLE LO	CATION IF	DIFFERE	NT FROM SU	JRFACE			
UL or lot no. Section	Township	Range	Lot Ida	Feet from the	North/South line	Feet from the	East/West line	County	
12 Dedicated Acres 13 Je	oint or Infill	14 Consolidation C	ode 15 Order	No.	L				
		ELL BE ASSIGN OR A NON-ST				·			
			2	1622'	330'	I hereby cert contained here to the best of Signature Printed Name Randy Ja Title District Date 12/6/94 SURVEYOI I hereby colocation sho plotted from surveys mo my supervises of my Date of Survey OCTO Signature and Professionalise * B	R CERTIFICA ertify that the field notes of the deby me or the ision, and the and correct belief. LYNN EZNER D. 7920 RAND RASS.	ATTON The well lat was actual under to the	

MINIMUM BLOWOUT PREVENTER REQUIREMENTS

3,000 psi Working Pressure

3 MWP

STACK REQUIREMENTS

No.	liem		Min. I.D.	Min. Nominal
1	Flowline			
2	Fill up line			2*
3	Drilling nipple			
4	Annular preventer			
5	Two single or one dual hy operated rams	draulically		
62	Drilling spool with 2" min. 3" min choke line outlets	kill line and		
6b	2" min. kill line and 3" mi outlets in ram. (Alternate			
7	Valve	Gate 🗆 Plug 🗆	3-1/8"	
8	Gate valve—power opera	ted	3-1/8"	
9	Line to choke manifold			3"
10	Valves	Gate C Plug C	2-1/16"	
11	Check valve		2-1/16"	
12	Casing head			
13	Valve	Gate □ Plug □	1-13/16"	
14	Pressure gauge with nee	die valve		
15	Kill line to rig mud pump			2"

(a)
ANNULAR PREVENTER
BLIND RAMS PIPE RAMS
ORILLING POOL TO BE SPOOL
CASING READ (2)

EXHIBIT #1

CONFIGURATION

	OPTIONAL
16 Flanged valve	1-13/16"

CONTRACTOR'S OPTION TO FURNISH:

- All equipment and connections above bradenhead or casinghead. Working pressure of preventers to be 3,000 psi, minimum.
- Automatic accumulator (80 gallon, minimum) capable of closing BOP in 30 seconds or less and, holding them closed against full rated working pressure.
- 3.BOP controls, to be located near drillers position.
- 4. Kelly equipped with Kelly cock.
- Inside blowout prevventer or its equivalent on derrick floor at all times with proper threads to fit pipe being used.
- 6.Kelly saver-sub equipped with rubber casing protector at all times.
- 7.Plug type blowout preventer tester.
- Extra set pipe rams to fit drill pipe in use on location at all times.
- 9.Type RX ring gaskets in place of Type R.

MEC TO FURNISH:

- Bradenhead or casinghead and side valves.
- 2. Wear bushing, if required.

GENERAL NOTES:

- Deviations from this drawing may be made only with the express permission of MEC's Drifting Manager.
- 2.All connections, valves, fittings, piping, etc., subject to well or pump pressure must be flanged (sultable clamp connections acceptable) and have minimum working pressure equal to rated working pressure of preventers up through chore. Valves must be full opening and suitable for high pressure mud service.
- Controls to be of standard design and each marked, showing opening and closing position.
- 4.Chokes will be positioned so as not to hamper or delay changing of choke beans. Replaceable parts for adjustable choke, other bean sizes, retainers, and choke wrenches to be conveniently located for immediate use.
- All valves to be equipped with handwheels or handles ready for immediate use.
- 6. Choke lines must be sultably anchored.


- 7. Handwheels and extensions to be connected and ready for use.
- Valves adjacent to drilling spool to be kept open. Use outside valves except for emergency.
- All seamless steel control piping (3000 psi working pressure) to have flexible joints to avoid stress. Hoses will be permitted.
- Casinghead connections shall not be used except in case of emergency.
- 11.Do not use kill line for routine fill-up operations.

Attachment to Exhibit #1 NOTES REGARDING BLOWOUT PREVENTORS

Grayburg-Jackson Field Eddy County, New Mexico

- 1. Drilling nipple will be constructed so it can be removed mechanically without the aid of a welder. The minimum internal diameter will equal BOPE bore.
- 2. Wear ring will be properly installed in head.
- 3. Blowout preventor and all associated fittings will be in operable condition to withstand a minimum 3000 psi working pressure.
- 4. All fittings will be flanged.
- 5. A full bore safety valve tested to a minimum 3000 psi W.P. with proper thread connections will be available on the rotary rig floor at all times.
- 6. All choke lines will be anchored to prevent movement.
- 7. All BOP equipment will be equal to or larger in bore than the internal diameter of the last casing string.
- 8. Will maintain a kelly cock attached to the kelly.
- 9. Hand wheels and wrenches will be properly installed and tested for safe operation.
- 10. Hydraulic floor control for blowout preventor will be located as near in proximity to driller's controls as possible.
- All BOP equipment will meet API standards and include a minimum 40 gallon accumulator having two independent means of power to initiate closing operation.

3 MWP - 5 MWP - 10 MWP



			MINI	MUM REQL	HREMENTS	3				
		3,000 MWP		5,000 MWP			10,000 MWP			
No.		I.D.	NOMINAL	RATING	1.D.	NOMINAL	RATING	1.D.	NOMINAL	RATING
1	Line from drilling spool		3-	3,000		3.	5,000		3.	10,000
2	Cross 3"x3"x3"x2"			3,000			5,000			
_	Cross 3"x3"x3"x3"									10,000
3	Valves ⁽¹⁾ Gate □ Plug □(2)	3-1/8"		3,000	3-1/8"		5,000	3-1/8"		10,000
4	Valve Gate □ Plug □(2)	1-13/16*		3,000	1-13/16*		5,000	1-13/16"		10,000
4a	Valves(1)	2-1/16"		3,000	2-1/16"		5,000	3-1/8"		10,000
5	Pressure Gauge			3,000			5,000			10,000
6	Valves Gate □ Plug □(2)	3-1/8"		3,000	3-1/8"		5,000	3-1/8"		10,000
7	Adjustable Choke(3)	2"		3,000	2.		5.000	2.	1	10,000
8	Adjustable Choke	1-		3,000	1"		5,000	5.		10,000
9	Line		3-	3,000	1	3-	5,000		3-	10,000
10	Line		2"	3,000		2.	5,000		3*	10,000
11	Valves Gate □ Plug □(2)	3-1/8"		3,000	3-1/8"		5,000	3-1/8"		10,000
12	Lines	1	3.	1,000		3-	1,000		3-	2,000
13	Lines		3.	1,000		3*	1,000	·	3"	2,000
14	Remote reading compound standpipe pressure gauge			3,000			5,000			10,000
15	Gas Separator		2'x5'			2'x5'			2'x5'	
16	Line		4*	1,000		4*	1,000		4"	2,000
17	Valves Plug (2)	3-1/8"		3,000	3-1/8"		5,000	3-1/8"		10,000

- (1) Only one required in Class 3M.
- (2) Gate valves only shall be used for Class 10M.
- (3) Remote operated hydraulic choke required on 5,000 psi and 10,000 psi for drilling.

EQUIPMENT SPECIFICATIONS AND INSTALLATION INSTRUCTIONS

- 1. All connections in choke manifold shall be welded, studded, flanged or Cameron clamp of comparable rating.
- 2. All flanges shall be API 6B or 6BX and ring gaskets shall be API RX or BX. Use only BX for 10 MWP.
- 3. All lines shall be securely anchored.
- 4. Chokes shall be equipped with tungsten carbide seats and needles, and replacements shall be available.
- Choke manifold pressure and standpipe pressure gauges shall be available at the choke manifold to assist in regulating chokes. As an alternate with automatic chokes, a choke manifold pressure gauge shall be located on the rig floor in conjunction with the standpipe pressure gauge.
- Line from drilling spool to choke manifold should be as straight as possible. Lines downstream from chokes shall make turns by large bends or 90° bends using bull plugged tees.
- 7. Discharge lines from chokes, choke bypass and from top of gas separator should vent as far as practical from the well.