



CEMENT TESTING REPORT

File No.: _____ Report Date: _____
Operator: Texaco Requested By: _____
Lease No: Tex Mack II Fed #1 Service Point: ANM/HNN
Location: Feld, NM Type of Job: Surface

Test Conditions:

Depth: _____ ft., Temp Grad _____, BHST: 90 °F, BHCT: 85 °F
Properties: Density (ppg) Yield (cu ft/sk) Mix Water (gal/sk) Total Liquid (gal/sk) Water Source Cement Source
System No. 1 13.5 1.74 9.11 9.11 Loc C
System No. 2 14.8 1.32 6.32 6.32 Loc C
System No. 3 _____
System No. 4 _____

Cement System Compositions:

System No. 1 C + 47.520 + 27.51
System No. 2 C + 27.51
System No. 3 _____
System No. 4 _____

Thickening Time Results

Rheology Results

SYSTEM	HR:MIN	BC	300	200	100	60	30	6	3	PV or n'	Ty or k'	RHEOLOGICAL MODEL	I.O.D.
No. 1	3:40	70	36	31	27	22	17	14	12				
No. 2	2:10	70	40	36	31	26	20	17	14				
No. 3													
No. 4													

Compressive Strengths - psi

SYSTEM	TEMP.	6 HR.	12 HR.	24 HR.
No. 1	90 °F	250	500	800
No. 1	°F			
No. 2	90 °F	600	1400	2000
No. 2	°F			
No. 3	°F			
No. 3	°F			
No. 4	°F			
No. 4	°F			

FLUID LOSS

FREE WATER

SYSTEM	°F, _____ psi	°F
	mL/30 min	mL
No. 1		
No. 2		
No. 3		
No. 4		

Remarks: Previous Data

Chemist: _____