

Injection shall be through the one authorized water injection well which shall be equipped with 2 3/8-inch plastic-lined tubing set in a packer at approximately 1100 feet. The casing-tubing annulus shall be loaded with an inert fluid and equipped with a pressure gauge at the surface to facilitate detection of leakage in the casing, tubing, or packer.