

Injection is to be through the 30 water level water injection wells each of which shall be equipped with a packer, said packers to be set within 100 feet of the water level. The casing-tubing annulus in each well shall be filled with a cement-inhibiting fluid and shall be fitted with a pressure gauge to facilitate detection of leakage in the tubing, casing or packer.