

6. Mud Program: See Form 9-331C and attached mud program by Adobe Drilling Mud.
7. Auxiliary Equipment: Blowout Preventer, Inside Blowout Preventer, Kelly cock.
8. Testing, logging and coring programs: Drill stem testing as warranted.  
Mud logging from 8500' to TD.
9. No abnormal pressures or temperatures are anticipated.
10. Anticipated starting date: As soon as possible (no later than  
January 6, 1979)