

ATTACHMENT TO FORM C-101  
NEW MEXICO OIL CONSERVATION COMMISSION  
SOL WEST III  
TURKEY TRACK WELL NO. 1

BOP EQUIPMENT AND CASING TESTING

SURFACE CASING: 13 3/8" O.D.

- BOP: One 12", 3000 psig Hydrill preventor.
- TESTING: 1. Before drilling shoe pressure casing to 1000 psig for thirty minutes with rig pump - 50 psig pressure drop acceptable.
2. After drilling shoe and five feet of new hole, pressure test to 250 psig for 30 minutes with rig pump.

INTERMEDIATE CASING: 8 5/8" O.D.

- BOP: One 10", 5000 psig Type "LWS" Double Shaffer.  
One 10", 5000 psig Hydrill GK.
- TESTING: 1. Before drilling float, pressure casing with rig pump to 2000 psig for 30 minutes - 50 psig pressure drop acceptable.
2. After drilling shoe and five feet of new hole, pressure test to 1500 psig for 30 minutes with rig pump.