

6. SOURCE OF CONSTRUCTION MATERIALS

- A. Caliche for construction of the drilling pad and resurfacing of the existing access road, will be obtained from Sec 13 T-18S R-31E

7. METHODS OF HANDLING WASTE DISPOSAL.

- A. Drill cuttings will be disposed of in the reserve pit.
- B. Drilling fluids will be allowed to evaporate in the reserve pits until the pit is dry.
- C. Water produced during operations will be disposed of in the reserve pit. Oil produced during operations will be stored in tanks until sold.
- D. Current laws and regulation pertaining to the disposal of human waste will be complied with.
- E. Trash, waste paper, garbage and junk will be buried in a separate trash pit and covered with a minimum of 24 inches of dirt. All waste material will be contained to prevent scattering by the wind.
- F. All trash and debris will be buried or removed from the wellsite within 30 days after finishing drilling and/or completion operations.

8. ANCILLARY FACILITIES.

- A. None required.

9. WELLSITE LAYOUT.

- A. Exhibit D shows the relative location and dimensions of the well pad, reserve pit and major rig components.
- B. Leveling will be required to construct the location. The ground surface at the wellsite is 6-8 feet tall on the west side of location. The sand dunes will be leveled and pushed to east side of wellsite to level location and covered with 6 inches of compacted caliche.

10. PLANS FOR RESTORATION OF THE SURFACE.

- A. After finishing drilling and/or completions operations, all equipment and other material not needed for further operations will be removed. Pits will be filled and the location will be cleaned of all trash and junk to leave the wellsite in as aesthetically pleasing a condition as possible.
- B. Any unguarded pits containing fluids will be fenced until they have been filled.
- C. If the proposed well is nonproductive, all rehabilitation and/or vegetation requirements of the Bureau of Land Management and the United States Geological Survey will be complied with and will be accomplished as expeditiously as possible. All pits will be filled and leveled within 90 days after abandonment.