

8 5/8" casing installation: 10"-3M BOP stack to be installed and tested by Yellow Jacket, Inc. to 3,000 psi before drilling the 8 5/8" casing shoe by Yellow Jacket, Inc. The BOP stack to consist of an annular BOP, blind ram BOP and one pipe ram BOP.

11. See Form 9-331C.

12. A. DST Program: None

B. Core: None

C. Mud Logging: None

D. Wire Line Logs:

The following suite of logs will be run in both of the listed intervals:

GR/CNL/FDC/Cal

TD-500' (GR/CNL to surf)

13. No abnormal pressures anticipated with bottom hole pressures at TD expected to be 1600 psi. Bottom hole temperature 90° F. No Hydrogen Sulfide expected in this know drilling area. No crooked hole or abnormal deviation problems.

14. Anticipated starting date to spud - on or before 12-10-86 Anticipated drilling time expected to be 8 days from surface to TD.