

1. (A) Pressure control equipment to be used.

1 - 5000# WP Cameron Iron Works double type "U" Blowout preventor with pipe rams and blind rams.

(B) Pressure ratings (or API series).

1 - 1500 series - 5000# WP.

(C) Testing procedures and frequency.

BOP will be tested at installation point as indicated on Application for Permit to Drill (Form 3160-3)

(D) Schematic Diagram.

See attached Exhibit "C"

2. Mud Program

Type and Characteristics

0 - 650' 8.5-8.8 Native  
650 - 2500' 10.0 Brine Water  
2500 - 9000' 8.4 Fresh water  
9000 - 9500' 8.4-10.0 Gel/starch

Quantities and types of weighting material to be maintained

500 sacks barite on location.