

1. (A) Pressure control equipment to be used.
1 - 5000# WP Cameron Iron Works double type "U" Blowout preventor with pipe rams and blind rams.

- (B) Pressure ratings (or API series).

1 - 1500 series - 5000# WP

- (C) Testing procedures and frequency.

BOP will be tested at installation point as indicated on Application for Permit to Drill.

- (D) Schematic Diagram.

See attached Exhibit "C"

2. Mud Program

Type and Characteristics

| | |
|-------------|---------------------|
| 0 - 650' | 8.5-8.8 Native |
| 650'-2500' | 10.0 brine water |
| 2500'-9000' | 8.4 fresh water |
| 9000'-9100' | 8.4-10.0 gel/starch |

Quantities and types of weighting material to be maintained

500 sacks barite on location.