

8. TESTING PROGRAM:

Possible DST's 6500' - TD as dictated by shows. Such tests, if necessary, will be conducted under prudent industry practice.

Open Hole Logs planned - Schlumberger

DIL/MSFL/GR	500 - TD
CNL/LDT/GR/CAL	500 - TD
DIPMETER	8500 - TD

GR log will be ran from surface to TD. Other logs and logging intervals at wellsite geologist's discretion.

9. POTENTIAL HAZARDS:

No H²S, abnormal temperatures or abnormal pressures are anticipated.

10. ESTIMATED STARTING DATE:

Anticipate starting operations as soon as possible, subject to approval of this permit.