- 7. Auxiliary Equipment: Kelly Cock; pit level indicators and flow sensor equipment; sub with full-opening valve on floor, drill pipe connection.
- 8. Testing, Logging and Coring Program:

Samples: 10' from surface casing to TD

DST's: None

Coring: None

Logging: CNL/LDT, TD to Casing with CNL to surface; DLL/MSFL TD to casing, Sonic log TD to casing

9. No abnormal pressures or temperatures are anticipated. No $\rm H_2S$ is anticipated during the drilling of this well.

10. Anticipated starting date: As soon as possible after approval.