

9. **Anticipated Abnormal Temperature, Pressure, or Hazards**

Possible lost circulation at +975' in anhydrite section. Seepage and lost circulation is expected starting in the Queen Formation and continuing through the Glorietta (720'-3870').

10. **Anticipated Starting Date and Duration of Operations**

Pending favorable weather and permit approval, construction work on this location is planned to begin in January, 1997. Construction work will require 4 days, move-in and rig up rotary tools, 1 day, drill and complete, 21 days. It is planned to spud the well in February, 1997.