

ENRON OIL & GAS COMPANY
STW "25" ST. COM. NO. 1
PROCEDURE TO COMPLETE IN MISSISSIPPIAN
PAGE 2



7. Swab fluid level down to 8,000'. RD pulling unit.
8. RU Baker-Atlas, crane truck. Install 2-1/8" 5,000 psig lubricator and grease equipment. RIH w/2-1/8" Predator expendable bar carrier w/gamma ray, loaded 4 SPF and with 0° phasing, decentralized, and shoot the following interval, depths being from Baker-Atlas Z-Density Neutron log run 12/31/98:

11,192' - 11,202'; 44 holes, 10' total

9. Unload tubing and flow test Morrow.
10. Evaluate for frac treatment.

<i>Tools & Services:</i>	HES	Shawn Flesher	Midland	915/686-4506
<i>Stimulation Services:</i>	HES	John Brown	Midland	915/686-4520
<i>Cased Hole Services:</i>	Baker-Atlas	John Welge	Hobbs	505/392-7593

Hal Crabb, III

02/02/99

c:\my documents\completion procedures 1999\stw 25 state com. no. 1 complete in morrow stage ii.doc