



**Beach State 25 No. 1
Beach Prospect
Eddy County, New Mexico**

Drilling Prognosis

Surface:

- Drill 17 1/2" hole to $\pm 300'$
- Run 13 3/8", 48 ppf, J-55, ST&C casing
- Circulate cement to surface

Intermediate:

- Drill 12 1/4" hole to 2400'
- Run 9 5/8" 36 ppf, J-55, ST&C casing
- Circulate cement to surface

Production:

- Drill 8 1/2" hole to 10,450'
- Run 4 1/2", 11.6, N-80, LT&C casing
- Circulate cement in a single stage to 7200'

Projected Mud Up Depth: $\pm 8000'$ (Cut Brine/Drispac/X-C Polymer)

Projected Time: Drilling Time 36 days

Logs: CNL/LDT – (Intermediate hole & Production hole)
DLL/MSFL – (Intermediate hole & Production hole)

Drill Stem Tests: None

Cores: None

Mud Loggers: 5000' to TD (Two man unit)