

30-015-05507

OGRIN 24164

PROP 28621

POOI 56439

Injection is to be through the casing of the four authorized water injection wells, with the injection water continuously treated to prevent corrosion and coupon corrosion tests conducted as prescribed by the order. Furthermore, casing of each well shall be pressure-tested to a minimum of 2000 psi for at least 30 minutes prior to conversion to water injection. If pressure shall fail to satisfactorily hold for this period of time, adequate remedial measures shall be taken and a satisfactory casing test completed prior to placing the well on injection. The Artesia district office of the Commission shall be notified of the date and hour pressure tests are to be conducted.

The above casing tests, water treatment, and continuous coupon survey may be dispensed with if injection wells are equipped with tubing and packers immediately above the pay.

L-4300

5-31-72

