FOSTER - FEDERAL WELL NO. 1

MUD PROGRAM

Surface:

0 - 500' Fresh water gel/lime slurry.

Intermediate:

500 - 2100' Fresh water with LCM for seepage if required.

Production:

2100' - TD

Fresh water to 7500'. At 7500' mud up with low solids, non-dispersed fresh water system. Weight and viscosity will be adjusted to contain the formation fluids.

The water loss will be decreased to 5 cc or less before drilling the Morrow.

•

