

INITIAL INSTALLATION TEST OF BLOWOUT PREVENTER AND CHOKE MANIFOLD SYSTEM
FOR INSTALLATION AS SHOWN ON FIGURE NO. 10 (Cont'd)

17. Keep both inside bradenhead valves closed while drilling to prevent plugging by cuttings. Keep both outside bradenhead valves and choke manifold valves open.
18. Reconnect kill line.
19. Enter results of test on tour sheet.