

Application For Drilling

Phoenix Resources Company - Gardner Draw Unit Well No. 4

Page 2.

7. The rig will be equipped with safety devices such as kelly cock, drill pipe float, full opening stabbing valve, inside drill pipe BOP, etc. Operational tests will be run weekly and results noted on tour sheets.
8. One Density Laterolog and one Density Neutron Log will be run at total depth.
9. No abnormal pressures or temperatures or potential hazards are expected to be encountered.
10. Anticipated starting date is July 31, 1978, with completion of operations expected to be on or about August 31, 1978.