

8. Abnormal Conditions, Pressures, Temperatures & Potential Hazards:

The entire re-entry should be conducted incased hole.

No abnormal pressure or temperatures are anticipated. The estimated bottom hole temperature (BHT) at TD is 94° F. and estimated maximum bottom hole pressure (BHP) is 1200 psig. No H2S or other hazardous gases or fluids should be encountered during the re-entry. H2S warning signs, flags and safety monitors will be used at all times.

9. Anticipated Starting Date and Duration of Operations:

Road and location work will not begin until approval has been received from the BLM. The anticipated spud date is March 1, 1998. Once commenced, the drilling operation should be finished in approximately 3 days. If the well is productive, an additional 30 days will be required for completion and testing before a decision is made to install permanent facilities.