

FAX TRANSMITTAL

of pages

ROSWell DISTRICT COPY

TO Gary Gaudley FROM Linda D
 DESTINATION RDD-Blm PHONE # CRA
 FAX # _____ FAX # _____
 NSN 7540-01-217-7352 5003-101 GENERAL SERVICES ADMINISTRATION

Budget Bureau No. (U.S. G.S.)
 Expires: March 31, 1993

5. Lease Designation and Serial No.

LC-029392B

6. If Indian, Allottee or Tribe Name

7. If Unit or CA, Agreement Designation

8. Well Name and No.

Hinkle B-26 #6

9. AM Well No.

30-015-23381

10. Field and Pool, or Exploratory Area

Shugart

11. County or Parish, State

Eddy Co., NM

SUBMIT IN TRIPLICATE

1. Type of Well

☐ Oil Well ☐ Gas Well ☒ Other

Unsuccessful Penrose Sand Completion

2. Name of Operator

Nadel and Gussman

3. Address and Telephone No.

3200 First National Tower, Tulsa, OK 74103

4. Location of Well (Footage, Sec., T., R., M., or Survey Description)

1977 FSL 860 FWL
 Sec. 26-18S-31E

12. CHECK APPROPRIATE BOX(S) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☒ Initial Notice☒ Subsequent Report☐ Final Abandonment Notice

TYPE OF ACTION

☒ Abandonment☐ Recore/Completion☐ Plugging Back☐ Casing Repair☐ Altering Casing☐ Other☐ Change of Plans☐ New Construction☐ Non-Routine Fracturing☐ Water Shut-Off☐ Conversion to Injection☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recore/Completion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated dates of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

NOTE: Proposed procedure as approved verbally by Mr. Adam Salamch on 8/29/96.

1. Notify local BLM office in Carlsbad of work being started.
2. Set CIBP @ 3750, TIH w/tbg., spot 50 ft. cmt. on top of plug, circ. hole w/drilling mud.
3. Spot cmt. plug 750-850 ft., let plug set, tag same.
4. Spot surface plug of cement from 50 ft. to surface.
5. Submit 3160 to verify well plugged as proposed, final report on well.

14. I hereby certify that the foregoing is true and correct

Signed Adam SalamchTitle EngineerDate 8/29/96

(This space for Federal or State office use)

Approved by APLTitle State EngineerDate 9/17/96

- SEE ATTACHED -

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See instruction on Reverse Side

NADEL AND GUSSMAN PERMIAN

Hinkle B-26 #6

1977' FSL & 860' FWL, Unit L, Sec 26, 18S, 37E, Eddy County, NM

API # 30-015-23381


Elev. 3652', KB = 3669.5'

Current Status - P&A 8-30-96

16", 65#, H-40 @ 800'
900 sx, circulated
20" hole

Casing cut @ 4455'
10-3/4", 51#, K-55 @ 4798'
3600 sx, cement circulated
14-3/4" hole

7-5/8", 26/29#, N80/S95 @ 12,005'
2000 sx, TOC @ surface
9-1/2" Hole



Cement Plug: 0 - 50' w/ 10 sx

Cement Plug: 650' - 850' w/ 45 sx

CIBP @ 3750' w/ 10 sx cement

Penrose Perfs: 3800' - 3892'
@ 2-4 SPF

Cement Plug: 4400' - 4500' w/ 25 sx

CIBP @ 10,400' w/ 35' cement
Strawn Perfs: 10,424' - 10,605'

CIBP @ 10,840 w/ 35' cement
Atoka Perfs: 10,942' - 10,948'

CIBP @ 11,350' w/ 35' cement

Morrow Perfs: 11,396' - 11,537'

Cement Plug

Cement Plug

TD @ 13,101'