

7. AUXILIARY EQUIPMENT: Drill string safety valve.
8. TESTING, LOGGING AND CORING PROGRAMS:
 - DST's: As warranted.
 - Coring: None planned.
 - Logging: A Compensated Neutron/Formation Density Log w/Gamma Ray and a Dual Laterolog/Micro-Spherically Focused Log.
9. ABNORMAL PRESSURES, TEMPERATURES OR GASES: None anticipated.
10. ANTICIPATED DATES:
 - Road and pad construction: October 1, 1981.
 - Spud well: October 7, 1981
 - Duration of drilling & testing: 35 - 65 days.