

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

SUBMIT IN 1
(Other instructions on re-
verse side)

Form approved.
Budget Bureau No. 1004-0135
Expires August 31, 1985

SUNDRY NOTICES AND REPORTS ON WELLS

(Do not use this form for proposals to drill or to deepen or plug back to a different reservoir.
Use "APPLICATION FOR PERMIT—" for such proposals.)

RECEIVED

1. OIL WELL ☒ GAS WELL ☐ OTHER ☐

2. NAME OF OPERATOR

Conoco Inc.

3. ADDRESS OF OPERATOR

P.O. Box 460 - Hobbs, New Mexico 88240

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.
See also space 17 below.)
At surface

810' FSL & 875' FWL - - Unit Letter M

14. PERMIT NO.

30-015-25310

15. ELEVATIONS (Show whether DF, RT, GR, etc.)

16.

Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data

NOTICE OF INTENTION TO:

TEST WATER SHUT-OFF

FRACTURE TREAT

SHOOT OR ACIDIZE

REPAIR WELL

(Other)

PULL OR ALTER CASING

MULTIPLE COMPLETE

ABANDON*

CHANGE PLANS

SUBSEQUENT REPORT OF:

WATER SHUT-OFF

FRACTURE TREATMENT

SHOOTING OR ACIDIZING

(Other)

REPAIRING WELL

ALTERING CASING

ABANDONMENT*

(NOTE: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)

1. MIRR. Kill well if necessary with 10 ppg mud.
2. RIH w/open end tbg to 1309' tag CIBP. Pump 24 bbls 10 ppg mud & 5 sxs class "H" cement. Displace w/5 bbls 10 ppg mud. This plug caps the CIBP w/ 35' of cement.
3. Pull up to 450' w/tbg. Pump 13 sxs class "H" cement. Displace w/ 1.5 bbl 10 ppg mud. This plug extends 50' above & 50' below surface csq shoe at 400'.
4. Pull up 50' w/tbg. Pump 7 sxs class "H" cement & fill csq to surface. POOH w/tbg. This plug is the 50' surface plug.
5. Cut off csq. install P & A marker.

18. I hereby certify that the foregoing is true and correct

SIGNED

William W. Baker

TITLE Administrative Supervisor

DATE

May 31, 1989

(This space for Federal or State office use)

APPROVED BY (ORIG. SGD.) DAVID R. GLASS

CHIEF, MINERAL RESOURCES

DATE


6-15-89

CONDITIONS OF APPROVAL, IF ANY:

*See Instructions on Reverse Side

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

BLM-Charlottesville, VA




AFTER P & A

LOCATION:

ELEVATION : 3330
ZERO : 15' AGL

810' FSL & 875' FWL
SECTION 34, T19S, R29E
EDDY COUNTY, NM



TOC: SURFACE;

50' SURFACE CEMENT CAP

10:57 5X CLASS H2

10	PPL	MUD
----	-----	-----

SURFACE CASING:

8 5/8" C/L, J-55, 24" @ 400'
CMTD W/ 250 SX CLASS C
CIRC TO SURFACE

TOC: 350'; 100' CEMENT

PLUG EXTENDING 50'
ABOVE AND 50' BELOW
SURFACE

13 SK CLASS H

10	PPG MUD
----	---------

TOC: 1274-35

FT CEMENT CAP
ON CIBP

53X CLASS H-71

HALLIBURTON 5 1/2" "E-Z DRILL" CIBP
@ 1309'

YATES PERKS: 1340' - 1384'

2. SQUEEZED W/ 50% CLASS C

YATES PERFS: 1398' - 1422'

2 SQUEEZED W/PO SK CLASS C

YATES PERFS: 1445' - 1508'

PRODUCTION CASING:

5 1/2 CK, T-55 5.5" @ 1750'
CMTD. W/650 SK CLASS C
CIRC TO SURFACE

PBTD: 701

ORIGINAL TD: 1750